

UM Addendum Format

ADDENDUM #1

DATE: 1/12/2022

Page 1 of 1

TO CONTRACT DOCUMENTS ENTITLED:

PROJECT MANUAL FOR:

General Site – Replace Water Mains at Alton and Green Buildings

PROJECT NUMBER:

CP220061

ADVERTISEMENT DATE:

12/16/2021

PREPARED FOR:

The Curators of the University of Missouri

CONSULTANT:

Crockett Engineering Consultants

1000 W. Nifong Blvd., Bldg. 1

Columbia, Missouri

573-447-0292

Drawings and Specifications for the above noted project and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

QUESTIONS AND ANSWER:

1. The patching detail shows a 2" Asphalt Cap. Is this required or can we do a full depth concrete patch?

1a. The Asphalt topping was requested by MU to match the existing asphalt parking area.

2. There is a discrepancy between the notes and the detail for the sidewalks. The detail shows a 6" sidewalk on 4" base but note #1 below says 4" sidewalk on 4" base. Please clarify what is correct.

2a. Note 1 is incorrect. It should indicate 6" thickness to match the dimension on the detail.

3. The existing ramp that is getting torn out at the sleep disorder building is exposed aggregate ramp. Does the new ramp have to be exposed aggregate as well or can the ramp be normal concrete construction?

3a. Medium broom finish concrete for this ramp is acceptable.

4. Just clarifying that the rock excavation quantity of 190 CY is to be included in the base bid? Or is this just a unit price based on the anticipation of hitting 190 CY of rock?

4a. 190 CY of rock excavation should be included in the base bid. A unit price per CY of rock excavation needs to be identified.

SPECIFICATION CHANGES:

1. None

DRAWING CHANGES:

1. Legend labels have been added to the plan view on CE 4.

2. Clarification of the sidewalk pavement thickness within "Note 1" on the "Typical Private Sidewalk" detail on CE 5.

END OF ADDENDUM #1