ADDENDUM #2 DATE: 09.22.2022

TO CONTRACT DOCUMENTS ENTITLED:

PROJECT MANUAL FOR:	CP221951 UMPB Ground Floor Renovation
ADVERTISEMENT DATE:	08.29.2022
PREPARED FOR:	The Curators of the University of Missouri
CONSULTANTS:	CP221951 bc DESIGN GROUP 12101 110th Street, Suite 100 Overland Park, KS 66210 913.232.2123 x 809

Drawings and Specifications for the above noted project and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

CLARIFICATIONS, QUESTIONS, ANSWERS:

- 1. If there is underslab plumbing run near a column then will spread footings be a problem?
 - a. Underslab piping conflicts have been addressed in this addendum, see attached drawings.
- Sheet E100 low voltage responsibility matrix. The telecom and the CATV call out for the outlet faceplates and terminations to be Furnished and Installed by the contractor. Typically these are by the owner here at MU. Please review and clarify if the notes are correct, or will need to be corrected in an addendum.
 - a. Low Voltage responsibility matrix has been revised for this addendum.
- 3. Also, sound masking is listed as Alternate #7, but I don't see it referenced anywhere else on the drawings, and there are no alternates shown on the bid form. Is there any sound masking on this project?
 - a. No. This note has been removed from sheet E100 for this addendum.
- 4. Please compare the Horton Automatic operator pricing vs Stanley Magic Force Operator pricing and install for comparison.
 - a. The Stanley Magic Force Operator is an approved substitution for the Horton Automatic Operator.
- 5. I have had several contractors wanting to bid CertainTeed Ceilings for the above project. Our direct alternate to ACT 1: Armstrong Ultima 1910 is Symphony M75.
 - a. The CertainTeed Symphony M75 ceiling is an approved substitution for the Armstrong Ultima 1910 ceiling.

CP221951 DRAWINGS:

1. A100 – Detail 1 – All previous keynote 1s and associated locations with under slab piping have been removed. New under slab piping has been located throughout existing Corridor C0102 and branches into Office 0102B, Open Office 0102, Office 0102F, Conference Room 0104, and Staff Lounge 0103. New working of under slab piping in part of Open Office 0106.

- 2. A100 Detail 4 Chase behind toilet in toilet room 0102N has been elongated into Echo room 0102M to accommodate plumbing piping. Added dimension of chase.
- 3. A100 Demo Plan Notes Added a hatch to show under slab piping.

ATTACHMENTS:

- 1. Ross and Baruzzini Narrative
- **2.** A100, E100, P100, P101, P400, and P500

ISSUED BY:

Jackie Dinkins bc**DESIGN**GROUP

END OF ADDENDUM #2





CP221951 UPMB Addendum # 2

PROJECT:	UPMB Ground Floor Renovations
PROJECT NO:	MUHC – CP221951, R&B - 1202.0011414.000
DATE:	September 22, 2022
BY:	Tori Gillespie
RE:	Addendum #2
DWG REF:	See below
SPEC REF:	See below
CC:	Central File
SPEC REF:	See below

The following additions, revisions and modifications are hereby made part of the contract documents, which shall be amended accordingly. Acknowledge receipt of addenda on bid form. Failure of your acknowledgement of receipt of this addendum may result in rejection of your offer.

INSTRUCTIONS

ELECTRICAL

- 1. E100
 - a. REVISE the low voltage responsibility matrix


PLUMBING

- 1. P100
 - a. REVISE routing of sanitary/waste piping & saw cutting to coordinate with structural footings.
 - b. ADD waste piping for new wall cleanout locations.
- 2. P101
 - a. REVISE sanitary & vent piping for water closet (model was changed to a wall hung unit).
 - b. ADD waste piping for new wall cleanout locations.
 - c. REMOVE two previous wall cleanout locations.
 - d. REVISE waste piping for a sink and lavatory to be routed in wall before dropping below slab to coordinate around structural footings.
- 3. P400

- a. REVISE Sanitary/Vent isometric drawing to include changes from P100 and P101.
- 4. P500
 - a. REVISE water closet (WC-1) model to be a wall-hung unit so that the sanitary piping can be routed above grade before dropping once it clears structural footing. A horizontal style standard fixture wall carrier is to be used.
 - b. ADD detail "Water Hammer Arrestor Schematic."

SIGNED: Tori Gillespie, Chris Philipp







ELECTRICAL NEW WORK FLOOR PLAN

GENERAL NOTES

- 1. REFER TO SHEET E000 FOR ELECTRICAL GENERAL NOTES.
- 2. CIRCUIT NUMBERS ARE FOR REFERENCE AND ARE SHOWN FOR LOADING PURPOSES ONLY. CONTRACTOR TO USE CIRCUITS MADE SPARE FROM DEMOLITION AND AVAILABLE SPARE CIRCUIT BREAKERS IN PANEL NBB AND IF NECESSAY PANEL NBA. CONTRACTOR MAY CONNECT NEW RECEPTACLES TO EXISTING CIRCUITS ALREADY IN ROOMS SO LONG AS THERE ARE NO MORE THAN (8) RECEPTACLES ON A SINGLE CIRCUIT. DEVICES SHOWN ON DEDICATED CIRCUITS TO REMAIN ON DEDICATED CIRCUITS.
- 3. ALL ELECTRICAL CIRCUITS SHOWN ARE CONNECTED TO PANEL NBB UNLESS OTHERWISE NOTED.

KEYED NOTES

- 1. PROVIDE NEW TAMPER RESISTANT RECEPTACLE IN EXISTING DEVICE BOX AND NEW COVER PLATE. CONNECT TO EXISTING WIRING.
- 2. REMOVE (2) 20A-1P CIRCUIT BREAKERS AND PROVIDE (1) NEW 20A-2P CIRCUIT BREAKER FOR TREADMILL. FIELD VERIFY EXACT CIRCUIT NUMBERS BASED ON CIRCUITS MADE SPARE FROM DEMOLITION. MATCH EXISTING MANUFACTERER AND AIC RATING.
- 3. PROVIDE EZ PATH SERIES 22 FIRE RATED PATHWAY ABOVE DOOR FOR LOW VOLTAGE CABLES.


LEGEND:	CONTRACTOR P.E.	is a		
F: FURNISHED I: INSTALLED	ONSIBIL	No IS		
GENERAL LOW VOLTAGE ITEMS		2	12	1
LOW VOLTAGE RACKS		F,I		
RACK CABLE MANAGEMENT		F,I		-
CONDUIT SLEEVES		.,.	F,I	
GROUNDING AND BONDING (GROUND BARS, CONDUCTORS, TERMINA	TIONS ETC.)		F,I	
CABLE PATHWAYS, CABLE TRAY, LADDER TRAY			F,I	
LADDER RACK			F,I	-
FIRESTOPPING FOR LOW VOLTAGE SYSTEMS			F,I	-
FIRE RATED PATHWAYS			F,I	-
EQUIPMENT, CABLE, AND OUTLET FACEPLATE LABELING		F	1,1	-
CORE DRILLING FLOOR/WALL SLEEVES			F,I	-
			Г,І	
TELECOMMUNICATIONS SYSTEMS				
FIBER SERVICE AND HORIZONTAL DISTRIBUTION FROM HOSPITAL		F,I		-
FIBER SWITCH AND TERMINATIONS		F,I		-
EQUIPMENT (SERVERS, SWITCHES, PDU, ETC.)		F,I		-
TELECOM ROOM LADDER RACK		F,I		-
PATCH PANELS		F,I		
PATCH CABLES		F,I		
HORIZONTAL CABLING AND TERMINATIONS		F		
BACKBOXES AND CONDUITS		\sim	F	
OUTLET FACEPLATES AND TERMINATIONS	{	F,I		$\dot{\mathcal{Y}}_{2}$
WIRELESS ACCESS POINTS		F ,I		
COMMUNITY ACCESS TELEVISION SYSTEM (CATV)				
CABLE DISTRIBUTION (BETWEEN TELECOM ROOMS)		F,I		
AMPLIFIERS AND SPLITTERS		F,I		
EQUIPMENT: HEAD-END ELECTRONICS		F,I		
HORIZONTAL CABLING AND TERMINATIONS		F	1	
BACKBOXES AND CONDUITS		\sim	E,t	
OUTLET FACEPLATES AND TERMINATIONS	{	F,I		BA
ACCESS CONTROL				
HEAD-END EQUIPMENT		F	1	1
BACKBOXES AND CONDUITS			F,I	
DEVICES (CARD READERS, KEYPADS, ETC.)		F,I		
INTERCONNECTION WIRING AND TERMINATIONS		F		-
VIDEO SURVEILLANCE				
HEAD-END EQUIPMENT (HARDWARE, SOFTWARE, DISPLAYS, ETC.)		F		
CAMERAS AND SUPPORTS		F,I		-
HORIZONTAL WIRING AND TERMINATIONS		F,i F		-
BACKBOXES AND CONDUITS		•	F,I	-
			, ı ,ı	1
				-
HEAD-END EQUIPMENT, UPS, AND PROGRAMMING		F	 .	-
HORIZONTAL CABLING AND TERMINATIONS		F	1	
BACKBOXES AND CONDUITS			F,I	-
DEVICES		F,I		-
INTERCONNECTION WIRING AND TERMINATIONS TO PERIPHERALS		F,I		1
PUBLIC ADDRESS SYSTEM				1
HEAD-END EQUIPMENT		F,I		
HORIZONTAL CABLING AND TERMINATIONS		F	1	
BACKBOXES AND CONDUITS			F,I	
SREAKERS	\sim		\square	h
] J
				1
				1 √
				1 2
				1 1


THE PARTY RESPONSIBLE FOR INSTALLING THE RESPECTIVE EQUIPMENT SHALL ALSO BE RESPONSIBLE FOR CONNECTING, PROGRAMMING AND TESTING THE SYSTEM, UNLESS OTHERWISE SPECIFICALLY NOTED. CONTRACTOR TO COORDINATED TESTING WITH ALL THIRD PARTY VENDORS.


ITEMS INDICATED AS FURNISHED AND/OR INSTALLED BY THE OWNER MAY BE PROVIDED BY A THIRD-PARTY VENDOR. CONTRACTOR IS REQUIRED TO COORDINATE ALL INSTALLATIONS.

ALL LINE VOLTAGE RECEPTACLE AND HARD-WIRED CONNECTIONS WILL BE PROVIDED BY THE CONTRACTOR. FIRESTOPPING TO BE PROVIDED BY A SINGLE ENTITY. REFER TO DIVISION 07 SPECIFICATIONS FOR REQUIREMENTS.


$2 \log voltage responsibility matrix$













KEYPLAN

NORTH

—AREA OF WORK









PLUMBING - GROUND FLOOR PLAN

KEYED NOTES

#


. SEE "CALIBRATED BALANCING VALVE" DETAIL ON SHEET P500 FOR MORE INFORMATION.









—AREA OF WORK












FLOOR CLEANOUT



3 SENSOR OPERATED FAUCET

PLUMBING FIXTURE SCHEDULE													
PLAN MARK	DESCRIPTION	MANUFACTURER	MODEL	ТКІМ	DRAIN / TRAP	SUPPLIES	CARRIER	HOT WATER	COLD WATER	TEMPERED WATER	SANITARY / WASTE	VENT	NOTES
L-1	WALL HUNG LAVATORY	AMERICAN STANDARD	LUCERNE 0355.012	CHICAGO FAUCETS MODEL 116.606.AB.1; 0.5GPM SENSORED FAUCET; BATTERY POWERED.	GRID DRAIN/CHROME PLATED P-TRAP	CHICAGO FAUCET LOOSE KEY ANGLE STOPS AND RISERS	JAY R. SMITH	1/2"	1/2"	-	2"		INSULATE SUPPLY AND WASTE PIPING WITH TRUBRO #102 WHITE INSULATION KIT WITH #105 OFFSET DRAIN INSULATION KIT. 0.5 GPM NON-AERATED OUTLET. PROVIDE WITH ASSE 1070 THERMOSTATIC MIXING VALVE.
SK-1	SINGLE BOWL STAINLESS STEEL SINK (EXAM ROOMS)	ELKAY	DLR191910PD	CHICAGO FAUCETS MODEL 201-AGN8AE36-317AB; 1.5GPM MANUAL FAUCET	GRID DRAIN/CHROME PLATED P-TRAP	CHICAGO FAUCET LOOSE KEY ANGLE STOPS AND RISERS	-	1/2"	1/2"	-	2"		PROVIDE WITH ASSE 1070 THERMOSTATIC MIXING VALVE.
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	SINGLE BOWL STAINLESS	ELKAT		SYMMONS S-23-2-W-1 5 MANUAL	GRID DRAUNCHROMERLATED P-IDAP	CHICAGO FAUCET LOOSE KEY		1/2"		$\sim$	$\sim$	$\frown$	PROVIDE WITH ASSE 1079 THERMOSTATIC MIXING VALVE
WC-1	WALL MOUNT/OUTLET WATER CLOSET (ADA)	AMERICAN STANDARD	AFWALL MILLENNIUM FLOWISE 3351.101	SLOAN ROYAL 111 SFSM-1.6 SENSOR FLUSHOMETER; BATTERY POWERED.	INTEGRAL	-	JAY R. SMITH STANDARD HORIZONTAL STYLE	-	1 1/4"	-	4"	2"	MOUNTED AT ADA HEIGHT.
$\overline{\mathbf{x}}$								$\mathcal{T}$			$\overline{\mathcal{A}}$	ス	







### SECTION THRU HANGER

REFER TO SPECS FOR INSULATION AND HANGER SUPPORTS.

2 INSULATED PIPE HANGER SUPPORT







 $5_{\text{NONE}}^{\text{CALIBRATED BALANCING VALVE}}$ 

