
PROJECT MANUAL FOR: CLINICAL SUPPORT AND EDUCATION BUILDING - SIM CENTER RENOVATION
PROJECT NUMBER: CP242241
AT UNIVERSITY OF MISSOURI COLUMBIA, MISSOURI
FOR:
THE CURATORS OF THE UNIVERSITY OF MISSOURI
PREPARED BY:
INTERNATIONAL ARCHITECTS ATELIER 912 BROADWAY BLVD., SUITE 300 KANSAS CITY, MO 64105


DATE:

FEBRUARY 27, 2024

I hereby certify that these Architectural Drawings and/or Specifications have been prepared by me, or under my supervision. I further certify that to the best of my knowledge these Drawings and/or Specifications are as required by and in compliance with Building Codes of the University



I hereby certify that these Mechanical, Electrical and Plumbing Drawings and/or Specifications have been prepared by me, or under my supervision. I further certify that to the best of my knowledge these Drawings and/or Specifications are as required by and in compliance with Building Codes of the University of Missouri.



PROJECT MANUAL FOR:

CLINICAL SUPPORT AND EDUCATION BUILDING - SIM CENTER RENOVATION

PROJECT NUMBER:

CP242241

TABLE OF CONTENTS

<u>TITLE</u>		PAGE
DIVISION 1	GENERAL	REQUIREMENTS
	Advertisement for Bids	
1.A	Bid for Lump Sum Contract	1.A 1-4
1.B	Bidder's Statement of Qualifications	BSQ/1-2
1.B.2	Supplier Diversity Compliance Evaluation	SD 1-2
1.B.3	Application for Waiver	SD 3-4
1.B.4	Affidavit for Affirmative Action	SD 5-6
1.B.5	Certifying Supplier Diversity Agencies	SD 7
1.B.6	Newspapers for Outreach to Diverse Suppliers	SD 8
1.B.7	Affidavit of Supplier Diversity Participation	SD 9
1.C	Information for Bidders	IFB/1-5
1.D	General Conditions	GC/1-39
1.E	Special Conditions	SC 1-10
1.E.1	Scheduling Specification	SS 1-3
1.E.4	Shop Drawing and Submittal Log	SDSL 1-14
1.E.5	Operating Instructions and Service Manual Log	OMML 1-3
1.E.6	Closeout Log	CLOSL 1-2
1.E.7	Commissioning Plan	COM 1
1.F	Index of Drawings	INDEX 1
1.G	Prevailing Wage Rates	PW 1

DIVISION 2 SITE WORK

024119 Selective Demolition

DIVISION 3 CONCRETE (NOT USED)

<u>DIVISION 4</u> <u>MASONRY (NOT USED)</u>

<u>DIVISION 5</u> <u>METALS (NOT USED)</u>

<u>DIVISION 6</u> <u>WOOD AND PLASTICS</u>

061000 Rough Carpentry

064023 Interior Architectural Woodwork

DIVISION 7 THERMAL AND MOISTURE PROTECTION

079200 Joint Sealants

DIVISION 8 DOORS, WINDOWS & GLASS

081213 Hollow Metal Frames 081416 Flush Wood Doors 087100 Door Hardware

088000 Glazing

DIVISION 9 FINISHES

092216 Non-structural Metal Framing

092900 Gypsum Board

095113 Acoustical Panel Ceiling

096513 Resilient Base and Accessories

096516 Resilient Sheet Flooring

096813 Tile Carpeting 099123 Interior Painting

DIVISION 10 SPECIALTIES

102600 Wall and Door Protection

<u>DIVISION 11</u> <u>EQUIPMENT (NOT USED)</u>

DIVISION 12 FURNISHINGS

122413 Roller Window Shades

DIVISION 13 SPECIAL CONSTRUCTION (NOT USED)

<u>DIVISION 14</u> <u>CONVEYING SYSTEMS (NOT USED)</u>

DIVISION 21 FIRE SUPPRESSION

210500 Common Work Results for Fire Suppression

211313 Wet-Pipe Sprinkler Systems

DIVISION 22 PLUMBING

220500 Common Work Results for Plumbing

220523	General-Duty Valves for Plumbing Piping
220529	Hangers and Supports for Plumbing Piping and Equipment
220553	Identification for Plumbing Piping and Equipment
220700	Plumbing Insulation
221116	Domestic Water Piping
221316	Sanitary Waste and Vent Piping
226113	Compressed-Air Piping for Laboratory and Healthcare Facilities
226213	Vacuum Piping for Laboratory and Healthcare Facilities
226313	Gas Piping for Laboratory and Healthcare Facilities
DIVICION 22	HVAC
DIVISION 23	HVAC
230500	Common Work Results for HVAC
230523	General-Duty Valves for HVAC
230529	Hangers and Supports for HVAC
230553	Identification for HVAC Piping and Equipment
230593	Testing, Adjusting, and Balancing for HVAC
230700	HVAC Insulation
230900	Control Systems
232113	Hydronic Piping
233113	Metal Ducts
233300	Air Duct Accessories
233600	Air Terminal Units
233713	Diffusers, Registers, and Grilles
DIVISION 26	ELECTRICAL
260500	Common Work Results for Electrical
260505	Electrical Testing
260519	Low-Voltage Electrical Power Conductors and Cables
260526	Grounding and Bonding for Electrical Systems
260529	
200327	Hangers and Slipports for Electrical Systems
260533	Hangers and Supports for Electrical Systems
260533 260553	Raceways and Boxes for Electrical Systems
260553	Raceways and Boxes for Electrical Systems Identification for Electrical Systems
	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard
260553 260573	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis
260553 260573 260923	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices
260553 260573 260923 262726	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices
260553 260573 260923	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices
260553 260573 260923 262726 265100	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting
260553 260573 260923 262726 265100 DIVISION 27	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting COMMUNICATIONS
260553 260573 260923 262726 265100 DIVISION 27 270500	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting COMMUNICATIONS Common Work Results for Communications
260553 260573 260923 262726 265100 DIVISION 27	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting COMMUNICATIONS
260553 260573 260923 262726 265100 DIVISION 27 270500 271500	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting COMMUNICATIONS Common Work Results for Communications Communications Horizontal Cabling
260553 260573 260923 262726 265100 DIVISION 27 270500 271500 DIVISION 28	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting COMMUNICATIONS Common Work Results for Communications Communications Horizontal Cabling ELECTRONIC SAFETY AND SECURITY
260553 260573 260923 262726 265100 DIVISION 27 270500 271500 DIVISION 28 280500	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting COMMUNICATIONS Common Work Results for Communications Communications Horizontal Cabling ELECTRONIC SAFETY AND SECURITY Common Work Results for Safety and Security
260553 260573 260923 262726 265100 DIVISION 27 270500 271500 DIVISION 28	Raceways and Boxes for Electrical Systems Identification for Electrical Systems Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis Lighting Control Devices Wiring Devices Interior Lighting COMMUNICATIONS Common Work Results for Communications Communications Horizontal Cabling ELECTRONIC SAFETY AND SECURITY

END OF SECTION

PLANNING DESIGN & CONSTRUCTION

900 E. Stadium, Ste. 130 Columbia, Missouri 65211 Telephone: (573) 882-6800

ADVERTISEMENT FOR BIDS

Sealed bids for:

CLINICAL SUPPORT AND EDUCATION BUILDING – SIM CENTER RENOVATION UNIVERSITY OF MISSOURI COLUMBIA, MISSOURI

PROJECT NUMBER: CP242241 CONSTRUCTION ESTIMATE: \$370,000 - \$430,000

will be received by the Curators of the University of Missouri, Owner, at Planning, Design & Construction, Room L100 (Front Reception Desk), General Services Building, University of Missouri, Columbia, Missouri 65211, until 1:30 p.m., C.T., March 27, 2024 and then immediately opened and publicly read aloud.

Drawings, specifications, and other related contract information may be obtained at http://operations-webapps.missouri.edu/pdc/adsite/ad.html. Electronic bid sets are available at no cost and may be printed as desired by the plan holders. No paper copies will be issued. If paper copies are desired, it is the responsibility of the user to print the files or have them printed.

Questions regarding the scope of work should be directed to Majid Amirahmadi with International Architects Atelier at (816) 471-6522 or majid@i-a-a.com. Questions regarding commercial conditions should be directed to Heather Brown at (573) 884-6322 or brownheat@missouri.edu.

A prebid meeting will be held at 1:00 p.m., C.T., March 13, 2024 in the General Services Bldg., Room 194B, followed by a site walk-through.

A Diversity Participation goal of 10% Combined MBE, WBE, DBE, Veteran Owned Business and 3% SDVE has been established for this contract.

The Owner reserves the right to waive informalities in bids and to reject any and all bids.

Individuals with special needs as addressed by the Americans with Disabilities Act may contact (573) 882-6800.

Advertisement Date: February 28, 2024

SECTION 1.A

BID FOR LUMP SUM CONTRACT

Date:	
BID OF	ed "Bidder") a corporation* organized and existing under laws of the State of
a partnership* c	consisting of
an individual* t	rading as,
a joint venture*	consisting of
*Insert Corpora	tion(s), partnership or individual, as applicable.
Room Univer Colum 1. and S SUPPO dated I familia and lab Contra includi require	sociate Vice Chancellor – Facilities L100, General Services Building rsity of Missouri – Columbia lbia, MO 65211 Bidder, in compliance with invitation for bids for construction work in accordance with Drawing pecifications prepared by INTERNATIONAL ARCHITECTS ATELIER, entitled "CLINICAL DRT AND EDUCATION BUILDING – SIM CENTER RENOVATION", project number CP242241, FEBRUARY 27, 2024 having examined Contract Documents and site of proposed work, and bein are with all conditions pertaining to construction of proposed project, including availability of material poor, hereby proposes to furnish all labor, materials and supplies to construct project in accordance wit act Documents, within time set forth herein at prices stated below. Prices shall cover all expenses ing taxes not covered by the University of Missouri's tax exemption status, incurred in performing wor and under Contract documents, of which this Bid is a part.
Bidder	acknowledges receipt of following addenda:
Adden	dum NoDated
Adden	dum NoDated
Adden	dum No Dated
Adden	dum NoDated
2. betwee	In following Bid(s), amount(s) shall be written in both words and figures. In case of discrepancy on words and figures, words shall govern.
3.	BID PRICING a. Base Bid: The Bidder agrees to furnish all labor, materials, tools, and equipment required to renovate a portio of the simulation center on the sixth floor of the Clinical Support and Education Building; all a indicated on the Drawings and described in these Specifications for sum of:
	DOLLARS (\$).

4. PROJECT COMPLETION

- a. Contract Period Contract period begins on the day the Contractor receives unsigned Contract, Performance Bond, Payment Bond, and "Instructions for Execution of Contract, Bonds, and Insurance Certificates." Bidder agrees to complete project within one hundred twenty-five (125) calendar days from receipt of aforementioned documents. Fifteen (15) calendar days have been allocated in construction schedule for receiving aforementioned documents from Bidder.
- b. Commencement Contractor agrees to commence work on this project after the "Notice to Proceed" is issued by the Owner. "Notice to Proceed" will be issued within seven (7) calendar days after Owner receives properly prepared and executed Contract documents listed in paragraph 4.a. above.
- 5. SUBCONTRACTOR LIST (NOT USED)

6. SUPPLIER DIVERSITY PARTICIPATION GOALS

- a. The Contractor shall have as a combined goal, subcontracting with Minority Business Enterprise (MBE), Women Business Enterprise (WBE), Disadvantage Business Enterprise (DBE), and/or Veteran Owned Business of ten percent (10%), and with Service Disabled Veteran Owned Business (SDVE) of three percent (3%); of awarded contract price for work to be performed.
- b. Requests for waiver of this goal shall be submitted on the attached Application For Waiver form. A determination by the Director of Facilities Planning & Development, UM, that a good faith effort has not been made by Contractor to achieve above stated goal may result in rejection of bid.

c.	The Undersigned proposes to perform work with following Supplier Diversity participation
level:	

MBE, WBE, DBE, and/or VETERAN PERC	ENTAGE PARTICIPATION:			(%	5
SDVE PERCENTAGE PARTICIPATION:	percent (<u>%</u>	<u> </u>		

d. A Supplier Diversity Compliance Evaluation form shall be submitted with this bid for each diverse subcontractor to be used on this project.

7. BIDDER'S ACKNOWLEDGMENTS

- a. Bidder declares that he has had an opportunity to examine the site of the work and he has examined Contract Documents therefore; that he has carefully prepared his bid upon the basis thereof; that he has carefully examined and checked bid, materials, equipment and labor required thereunder, cost thereof, and his figures therefore. Bidder hereby states that amount, or amounts, set forth in bid is, or are, correct and that no mistake or error has occurred in bid or in Bidder's computations upon which this bid is based. Bidder agrees that he will make no claim for reformation, modifications, revisions or correction of bid after scheduled closing time for receipt of bids.
- b. Bidder agrees that bid shall not be withdrawn for a period of sixty (60) days after scheduled closing time for receipt of bids.
- c. Bidder understands that Owner reserves right to reject any or all bids and to waive any informalities in bidding.
- d. Accompanying the bid is a bid bond, or a certified check or a cashier's check payable without

condition to "The Curators of the University of Missouri" which is an amount at least equal to five percent (5%) of amount of largest possible total bid herein submitted, including consideration of Alternates.

- e. Accompanying the bid is a Bidder's Statement of Qualifications. Failure of Bidder to submit the Bidder's Statement of Qualifications with the bid may cause the bid to be rejected. Owner does not maintain Bidder's Statements of Qualifications on file.
- f. It is understood and agreed that bid security of two (2) lowest and responsive Bidders will be retained until Contract has been executed and an acceptable Performance Bond and Payment Bond has been furnished. It is understood and agreed that if the bid is accepted and the undersigned fails to execute the Contract and furnish acceptable Performance/Payment Bond as required by Contract Documents, accompanying bid security will be realized upon or retained by Owner. Otherwise, the bid security will be returned to the undersigned.

8. BIDDER'S CERTIFICATE

Bidder hereby certifies:

- a. His bid is genuine and is not made in interest of or on behalf of any undisclosed person, firm or corporation, and is not submitted in conformity with any agreement or rules of any group, association or corporation.
- b. He has not directly or indirectly induced or solicited any other bidder to put in a false or sham bid.
- c. He has not solicited or induced any person, firm or corporation to refrain from bidding.
- d. He has not sought by collusion or otherwise to obtain for himself any advantage over any other Bidder or over Owner.
- e. He will not discriminate against any employee or applicant for employment because of race, color, religion, sex or national origin in connection with performance of work.
- f. By virtue of policy of the Board of Curators, and by virtue of statutory authority, a preference will be given to materials, products, supplies, provisions and all other articles produced, manufactured, mined or grown within the State of Missouri. By virtue of policy of the Board of Curators, preference will also be given to all Missouri firms, corporations, or individuals, all as more fully set forth in "Information For Bidders."

9. BIDDER'S SIGNATURE

Note: All signatures shall be original; not copies, photocopies, stamped, etc.

Authorized Signature	Date
Printed Name	Title
Company Name	
Mailing Address	
City, State, Zip	
Phone No.	Federal Employer ID No.
Fax No.	E-Mail Address
Circle one: Individual Partnership C	orporation Joint Venture
If a corporation, incorporated under the laws of the Sta	ate of
Licensed to do business in the State of Missouri?	_yesno

(Each Bidder shall complete bid form by manually signing on the proper signature line above and supplying required information called for in connection with the signature. Information is necessary for proper preparation of the Contract, Performance Bond and Payment Bond. Each Bidder shall supply information called for in accompanying "Bidder's Statement of Qualifications.")

END OF SECTION

UNIVERSITY OF MISSOURI BIDDER'S STATEMENT OF QUALIFICATIONS

Submit with Bid for Lump Sum Contract in separate envelope appropriately labeled. Attach additional sheet if necessary.

		<u> </u>			
Address					
Number of years in busine types of organization.	ss If not under	er present fir	m name, list p	orevious firm nar	mes and
List contracts on hand (con Project & Address	mplete the following s Owner/Owner's Representative	schedule, inc Phone Number	lude telephone Architect	e number). Amount of your Contract	Percent Complet
General character of work	performed by your co	ompany perso	onnel.		
List important projects cor including approximate cos Project & Address			a type simila	Amount of you	
Other experience qualifying	ng you for the work no	ow bid.			
Other experience qualifyin	ng you for the work no	ow bid.			

BSQ/1 9/2016 Revision

	(c)	• •		owned by a minority?	
	(d)	Yes No Is fifty percent or more of yo		owned by a woman?	
	(4)	Yes No		•	
	(e)	Is fifty percent or more of yo		wned by a service disable	ed veteran?
	(f)	Yes No Is fifty percent or more of yo		aunad hu a vataran?	
	(f)	Yes No		owned by a veterall?	
	(g)	Is your company a Disadvar		s Enterprise?	
		Yes No		-	
0	11			1-111	and Hairmaite of Missessi
9.		ve you or your company been an enterprise pour some some some some some some some some	suspended or o	iedarred from working at	any University of Missouri
	•		(If the ans	wer is "yes", give details.)	
10.				een started against you or	your company alleging violation
	of a	ny wage and hour regulations			
		Yes No	(II the ans	wer is yes, give details.	•
11.	Wot	rkers Compensation Experience	ce Modificatio	n Rates (last 3 vrs):	/ /
11.					
	Inci	dence Rates (last 3 years):	/ /		
10	T :4	. h l			
12.	List	banking references.			
13.	(a)	Do you have a current confi	dential financi	al statement on file with (Owner?
13.	(u)	Yes No	(If not, and	d if desired, Bidder may s	ubmit such statement with bid, in
			a separate s	ealed and labeled envelop	e.)
	(b)	If not, upon request will you		l confidential financial sta	tement within three (3) days?
		Yes No			
Dated at			this	day of	20
Dated at				uu	20
			Name of Or	ganization	
			Signature		
			D. 1. 137		
			Printed Nar	ne	
			Title of Per	son Signing	

END OF SECTION

SUPPLIER DIVERSITY COMPLIANCE EVALUATION FORM

This form shall be completed by Bidders and submitted with the Bidder's Statement of Qualifications form for \underline{each} diverse firm who will function as a subcontractor on the contract.

The undersigned submits the following data with respect to this firm's assurance to meet the goal for Supplier Diversity participation.

Project:
Name of General Contractor:
Name of Diverse Firm:
Address:
Phone No.: Fax No.:
Status (check one) MBE WBE Veteran Service Disabled Veteran DBE
Describe the subcontract work to be performed. (List Base Bid work and any Alternate work separately):
Base Bid:
Dollar amount of contract to be subcontracted to the Diverse firm:
Base Bid:
Alternate(s), (Identify separately):
Is the proposed subcontractor listed in the Directory of M/W/DBE Vendors, Directory of Serviced Disable Veterans and/or the Directory of Veterans maintained by the State of Missouri?
Yes No

			r by any of the following: federal government overnment agencies, Minority and/or WBE
	Yes	No	If yes, please provide details and attach a copy of the certification.
	Does the proposed subcontra Diverse and meeting the 51%	ctor have a signed document to owned and committed require	from their attorney certifying the Supplier as a rement?
	Yes	No	If yes, please attach letter.
Signature:			
Name:			
Title:			
Date:			

APPLICATION FOR WAIVER

This form shall be completed and submitted with the Bidder's Statement of Qualifications. Firms wishing to be considered for award are required to demonstrate that a good faith effort has been made to include diverse suppliers. This form will be used to evaluate the extent to which a good faith effort has been made. The undersigned submits the following data with respect to the firm's efforts to meet the goal for Supplier Diversity Participation.

List pre-or	d conferences your firm attended where Supplier Diversity requirements were discussed.
	vertising efforts undertaken by your firm which were intended to recruit potential diverse subcontract ects of this project. Provide names of newspapers, dates of advertisements and copies of ads that were
Note speci	ic efforts to contact in writing those diverse suppliers capable of and likely to participate as subcontra ject.
Describe s performing	eps taken by your firm to divide work into areas in which diverse suppliers/contractors would be capa.
What efformames, add given to di	
What efformames, add given to di	ts were taken to negotiate with prospective diverse suppliers/contractors for specific sub-bids? Include resses, and telephone numbers of diverse suppliers/contractors contacted, a description of the informativerse suppliers/contractors regarding plans and specifications for the assigned work, and a statement a

Describ	e the follow-up contacts with diverse suppliers/contractors made by your firm after the initial solicitation
	e the efforts made by your firm to provide interested diverse suppliers/contractors with sufficiently detaition about the plans, specifications and requirements of the contract.
Describ	e your firm's efforts to locate diverse suppliers/contractors.
	n the above stated good faith efforts made to include supplier diversity, the bidder hereby requests that t supplier diversity percentage goal be waived and that the percentage goal for this project be set at
	lersigned hereby certifies, having read the answers contained in the foregoing Application for Waiver, the and correct to the best of his/her knowledge, information and belief.
Signatu	re
Name_	
Title	
Compar	ny

AFFIDAVIT

	entify and explain the operation of	correct and include an material
provide through the prime coinformation regarding actual changes, if any, of the projection and files of the name	ame of firm) as well as the ownership their ontractor or directly to the Contracting O I work performed on the project, the payrect, the foregoing arrangements and to perfed firm. Any material misrepresentation reded and for initiating action under federal	Officer current, complete and accurate ment therefore and any proposed rmit the audit and examination of books, will be grounds for terminating any
	nformation submitted, you must inform t	leted on the contract covered by this regulation, the Director of Facilities Planning and
Signature		
Name		
Title		
Corporate Seal (where appropriate) Date		
State of		
County of		
On this	day of	
		to me personally known, who, being
duly sworn, did execute the foregoing	affidavit, and did state that he or she was	s properly authorized by (name of firm)
	_to execute the affidavit and did so as hi	is or her own free act and deed.
(Seal)		
Notary Public		
Commission expires		

AFFIDAVIT FOR AFFIRMATIVE ACTION

State of Missouri)	99	
County of)	SS.	
	1	CC) C	first being duly sworn on his/her oath
states: that he/she is the (se			and as such (sole proprietor, partner, or officer) is
duly outhorized to make the			artnership, corporation); that under the contract
known as "	is affidavit off behalf	or said (sole proprietorship, pa	arthership, corporation), that under the contract
Project No.	less than 50 per	sons in the aggregate will be	employed and therefore, the applicable Affirmative
Action requirements as set	forth in the "Nondisc	rimination in Employment Eq	ual Opportunity," Supplemental Special
Conditions, and Article 13			
Subscribed and sworn befo	re me this	day of	, 19 .
My commission expires			, 19

CERTIFYING SUPPLIER DIVERSITYAGENCIES

Diverse firms are defined in General Conditions Articles 1.1.7 and those businesses must be certified as disadvantaged by an approved agency. The Bidder is responsible for obtaining information regarding the certification status of a firm. A list of certified firms may be obtained by contacting the agencies listed below. Any firm listed as disadvantaged by any of the following agencies will be classified as a diverse firm by the Owner.

St. Louis Development Corporation 1520 Market St., Ste. 2000 St. Louis, MO 63103 P: 314.982.1400 W: www.stlouis-mo.gov/sldc/

Bi-State Development 211 N. Broadway, Ste. 700 St. Louis, MO 63102 P: 314.982.1400

W: www.metrostlouis.dbesystem.com

St. Louis Minority Business Council 211 N. Broadway, Ste. 1300 St. Louis, MO 63102 P: 314.231.5555 W: www.slmbc.org

U.S. Small Business Administration - St. Louis, MO 8(a) Contractors, Minority Small Business 1222 Spruce Street, Suite 10.103 St. Louis, MO 63101

P: 314.539.6600 W: www.sba.gov

Lambert St. Louis International Airport Business Diversity Development Office 11495 Navaid Bridgeton, MO 63044 P: 314-426-8111 W: www.flystl.com/business/business-diversitydevelopment-1/directories

City of Kansas City, Missouri Human Relations Department, MBE/WBE Division 4th Floor, City Hall 414 E. 12th Street Kansas City, MO 64106 P: 816.513.1836 W: kcmohrd.mwdbe.com/?TN=kcmohrd

Mid-States Minority Supplier Development Council 505 N. 7th Street, Ste. 1820 St. Louis, MO 63101 P: 314.278.5616 W: midstatesdc.org

U.S. Small Business Administration - Kansas City, MO 8(a) Contractors, Minority Small Business 1000 Walnut, Suite 500 Kansas City, MO 64106 P: 816.426.4900 W: kcmohrd.mwdbe.com/?TN=kcmohrd

Missouri Department of Transportation Division of Construction 1617 Missouri Blvd. P.O. Box 270 Jefferson City, MO 65102 P: 573.526.2978

W: www.modot.org/mrcc-directory

Illinois Department of Transportation MBE/WBE Certification Section 2300 Dirksen Parkway Springfield, IL 62764

217/782-5490; 217/785-1524 (Fax)

W: webapps.dot.illinois.gov/UCP/ExternalSearch

State of Missouri OA Office of Equal Opportunity 301 W. High St. HSC Rm 870-B Jefferson City, MO 65101

P: 877.259.2963

W: oa.mo.gov/sites/default/files/sdvelisting.pdf

W: oeo.mo.gov/

Minority Newspapers

Dos Mundos Bilingual Newspaper 902A Southwest Blvd. Kansas City, MO 64108 816-221-4747 www.dosmundos.com

Kansas City Hispanic News 2918 Southwest Blvd. Kansas City, MO 64108 816/472-5246 www.kchispanicnews.com

The Kansas City Globe 615 E. 29th Street Kansas City, MO 64109 816-531-5253 www.thekcglobe.com/about_us.php

St. Louis American 4144 Lindell St. Louis, MO 63108 314-533-8000 www.stlamerican.com

St. Louis Chinese American News 1766 Burns Ave, Suite 201 St. Louis, MO 63132 314-432-3858 www.scannews.com

St. Louis Business Journal 815 Olive St., Suite 100 St. Louis, MO 63101 314-421-6200 www.bizjournal.com/stlouis

Kansas City Business Journal 1100 Main Street, Suite 210 Kansas City, MO 64105 816-421-5900 www.bizjournals.com/kansascity

AFFIDAVIT OF SUPPLIER DIVERSITY PARTICIPATION

The apparent low Bidder shall complete and submit this form within 48 hours of bid opening for each Diverse firm that will participate on the contract. 1. Diverse Firm: Contact Name: ____ E-Mail: Phone No.: Status (check one) MBE WBE Veteran Service Disabled Veteran DBE If MBE, Certified as (circle one): 1) Black American 2) Hispanic American 3) Native American 4) Asian American 2. Is the proposed diverse firm certified by an approved agency [see IFB article 15]? Yes \square No \square [attach copy of certification authorization from agency] Certification Number: 3. Diverse firm scope work and bid/contract dollar amount of participation (List Base Bid and Alternate work separately). The final Dollar amount will be determined at substantial completion: Bid/Contract Amount Scope of Work Final Dollar Amount Base Bid Alternate #1 Alternate #2 Alternate #3 Alternate #4 Alternate #5 Alternate #6 The undersigned certifies that the information contained herein (i.e. Scope of Work and Bid/Contract Amount) is true and correct to the best of their knowledge, information and belief. General Contractor: Diverse Firm: Signature: Signature: Name: Name:

Title: Title: Date: Date: The undersigned certifies that the information contained herein (i.e. Scope of Work and Final Dollar Amount) is true and correct to the best of their knowledge, information and belief. If the Final Dollar Amount is different than the Bid/Contract Amount, then attach justification for the difference. Contractor: _ Diverse Firm: Signature: Signature: Name: Name: Title: Title: Date: Date:

University of Missouri

INFORMATION FOR BIDDERS

1.	Contract Documents	FB/1
2.	Bidder's Obligation	FB/1
3.	Interpretation of Documents	FB/1
4.	Bids	FB/1
	Modification and Withdrawal of Bids	
6.	Signing of Bids	FB/2
7.	Bid Security	FB/2
8.	Bidder's Statement of Qualifications	FB/2
	Award of Contract	
10.	Contract Execution	FB/2
11.	Contract Security	FB/3
12.	Time of Completion	FB/3
13.	Number of Contract Documents	FB/3
14.	Missouri Products and Missouri Firms	FB/3
15.	Supplier Diversity	FB/3
16.	List of Subcontractors	FB/5

1. Contract Documents

1.1 Drawings, specifications, and other contract documents, pursuant to work, which is to be done, may be obtained shown in the Advertisement for Bids and Special Conditions.

2. Bidder Obligations

- 2.1 Before submitting bids, each bidder shall carefully examine the drawings and specifications and related contract documents, visit site of work, and fully inform themselves as to all existing conditions, facilities, restrictions, and other matters which can affect the work or the cost thereof.
- 2.2 Each bidder shall include in their bid the cost of all work and materials required to complete the contract in a first-class manner as hereinafter specified.
- 2.3 Failure or omission of any bidder to receive or examine any form, instrument, addendum, or other document, or to visit the site and acquaint themselves with existing conditions, shall in no way relieve them from any obligation with respect to their bid or contract, and no extra compensation will be allowed by reason of anything or matter concerning which bidder should have fully informed themselves prior to bidding.
- 2.4 Submission of bids shall be deemed acceptance of the above obligations and each and every obligation required to be performed by all of the contract documents in the event the bid is accepted.

3. Interpretation of Documents

- **3.1** If any prospective bidder is in doubt as to the true meaning of any part of the drawings and specifications or contract documents, they shall submit a written request to the Architect for an interpretation.
- **3.2** Requests for such interpretations shall be delivered to the Architect at least one (1) week prior to time for receipt of bids.
- 3.3 Bids shall be based only on interpretations issued in the form of addenda mailed to each person who is on the

Architect's record as having received a set of the contract documents.

Page No.

4. Bids

- **4.1** Bids shall be received separately or in combination as shown in and required by the Bid for Lump Sum contract. Bids will be completed so as to include insertion of amounts for alternate bids, unit prices and cost accounting data.
- **4.2** Bidders shall apportion each base bid between various phases of the work, as stipulated in the Bid for Lump Sum contract. All work shall be done as defined in the specifications and as indicated on the drawings.
- 4.3 Bids shall be presented in sealed envelopes which shall be plainly marked "Bids for (indicate name of project from cover sheet)" and mailed or delivered to the building and room number specified in the Advertisement for Bids. Bidders shall be responsible for actual delivery of bids during business hours, and it shall not be sufficient to show that a bid was mailed in time to be received before scheduled closing time for receipt of bids, nor shall it be sufficient to show that a bid was somewhere in a university facility.
- 4.4 The bidder's price shall include all federal sales, excise, and similar taxes, which may be lawfully assessed in connection with their performance of work and purchase of materials to be incorporated in the work. City & State taxes shall not be included as defined within Article 3.16 of the General Conditions for Construction Contract included in the contract documents.
- **4.5** Bids shall be submitted on a single bid form, furnished by the Owner or Architect. Do not remove the bid form from the specifications.
- **4.6** No bidder shall stipulate in their bid any conditions not contained in the bid form.
- **4.7** The Owner reserves the right to waive informalities in bids and to reject any or all bids.

5. Modification and Withdrawal of Bids

- 5.1 The bidder may withdraw their bid at any time before the scheduled closing time for receipt of bids, but no bidder may withdraw their bid after the scheduled closing time for receipt of bids.
- 5.2 Only telegrams, letters and other written requests for modifications or correction of previously submitted bids, contained in a sealed envelope which is plainly marked "Modification of Bid on (name of project on cover sheet)," which are addressed in the same manner as bids, and are received by Owner before the scheduled closing time for receipt of bids will be accepted and bids corrected in accordance with such written requests.

6. Signing of Bids

- **6.1** Bids which are signed for a partnership shall be **manually** signed in the firm name by at least one partner, or in the firm name by Attorney-in-Fact. If signed by Attorney-in-Fact there should be attached to the bid, a Power of Attorney evidencing authority to sign the bid dated the same date as the bid and executed by all partners of the firm.
- **6.2** Bids that are signed for a corporation shall have the correct corporate name thereon and the signature of an authorized officer of the corporation manually written below corporate name. Title of office held by the person signing for the corporation shall appear below the signature of the officer.
- **6.3** Bids that are signed by an individual doing business under a firm name, shall be manually signed in the name of the individual doing business under the proper firm name and style.
- **6.4** Bids that are signed under joint venture shall be manually signed by officers of the firms having authority to sign for their firm.

7. Bid Security

- 7.1 Each bid shall be accompanied by a bid bond, certified check, or cashier's check, acceptable to and payable without condition to The Curators of the University of Missouri, in an amount at least equal to five percent (5%) of bidder's bid including additive alternates.
- 7.2 Bid security is required as a guarantee that bidder will enter into a written contract and furnish a performance bond within the time and in form as specified in these specifications; and if successful bidder fails to do so, the bid security will be realized upon or retained by the Owner. The apparent low bidder shall notify the Owner in writing within 48 hours (2 workdays) of the bid opening of any circumstance that may affect the bid security including, but not limited to, a bidding error. This notification will not guarantee release of the bidder's security and/or the bidder from the Bidder's Obligations.
- **7.3** If a bid bond is given as a bid security, the amount of the bond may be stated as an amount equal to at least five percent (5%) of the bid, including additive alternates, described in the bid. The bid bond shall be executed by the bidder and a responsible surety licensed in the State of Missouri with a Best's rating of no less than A-/XI.

- 7.4 It is specifically understood that the bid security is a guarantee and shall not be considered as liquidated damages for failure of bidder to execute and deliver their contract and performance bond, nor limit or fix bidder's liability to Owner for any damages sustained because of failure to execute and deliver the required contract and performance bond.
- 7.5 Bid security of the two (2) lowest and responsive Bidders will be retained by the Owner until a contract has been executed and an acceptable bond has been furnished, as required hereby, when such bid security will be returned. Surety bid bonds of all other bidders will be destroyed and all other alternative forms of bid bonds will be returned to them within ten (10) days after Owner has determined the two (2) lowest and responsive bids.

8. Bidder's Statement of Qualifications

- **8.1** Each bidder submitting a bid shall present evidence of their experience, qualifications, financial responsibility and ability to carry out the terms of the contract by completing and submitting with their bid the schedule of information set forth in the form furnished in the bid form.
- **8.2** Such information, a single copy required in a separate sealed envelope, will be treated as confidential information by the Owner, within the meaning of Missouri Statue 610.010.
- **8.3** Bids not accompanied with current Bidder's Statement of Qualifications may be rejected.

9. Award of Contract

- **9.1** The Owner reserves the right to let other contracts in connection with the work, including, but not by way of limitation, contracts for furnishing and installation of furniture, equipment, machines, appliances, and other apparatus.
- 9.2 In awarding the contract, the Owner may take into consideration the bidder's, and their subcontractor's, ability to handle promptly the additional work, skill, facilities, capacity, experience, ability, responsibility, previous work, financial standing of bidder, and the bidder's ability to provide the required bonds and insurance; quality, efficiency and construction of equipment proposed to be furnished; period of time within which equipment is proposed to be furnished and delivered; success in achieving the specified Supplier Diversity goal, or demonstrating a good faith effort as described in Article 15; necessity of prompt and efficient completion of work herein described, and the bidder's status as suspended or debarred. Inability of any bidder to meet the requirements mentioned above may be cause for rejection of their bid.

10. Contract Execution

- 10.1 The Contractor shall submit within fifteen (15) days from receipt of notice, the documents required in Article 9 of the General Conditions for Construction Contract included in the contract documents.
- 10.2 No bids will be considered binding upon the Owner until the documents listed above have been furnished. Failure of Contractor to execute and submit these documents within the time period specified will be treated, at the option of the

Owner, as a breach of the bidder's bid security under Article 7 and the Owner shall be under no further obligation to Bidder.

11. Contract Security

- 11.1 When the Contract sum exceeds \$50,000, the Contractor shall procure and furnish a Performance bond and a Payment bond in the form prepared by Owner. Each bond shall be in the amount equal to one hundred percent (100%) of the contract sum, as well as adjustments to the Contract Sum. The Performance Bond shall secure and guarantee Contractor's faithful performance of this Contract, including but not limited to Contractor's obligation to correct defects after final payment has been made as required by the Contract Documents. The Payment Bond shall secure and guarantee payment of all persons performing labor on the Project under this Contract and furnishing materials in connection with this Contract. These Bonds shall be in effect through the duration of the Contract plus the Guaranty Period as required by the Contract Documents.
- 11.2 The bonds required hereunder shall be meet all requirements of Article 11 of the General Conditions for Construction Contract included in the contract documents.
- 11.3 If the surety of any bond furnished by Contractor is declared bankrupt or becomes insolvent or its right to conduct business in the State of Missouri is terminated, or it ceases to meet the requirements of this Article 11, Contractor shall within ten (10) days substitute another bond and surety, both of which must be acceptable to Owner. If Contractor fails to make such substitution, Owner may procure such required bonds on behalf of Contractor at Contractor's expense.

12. Time of Completion

12.1 Contractors shall agree to commence work within five (5) days of the date "Notice to Proceed" is received from the Owner, and the entire work shall be completed by the completion date specified or within the number of consecutive calendar days stated in the Special Conditions. The duration of the construction period, when specified in consecutive calendar days, shall begin when the contractor receives notice requesting the documents required in Article 9 of the General Conditions for Construction Contract included in the contract documents.

13. Number of Contract Documents

- **13.1** The Owner will furnish the Contractor a copy of the executed contract and performance bond.
- 13.2 The Owner will furnish the Contractor the number of copies of complete sets of drawings and specifications for the work, as well as clarification and change order drawings pertaining to change orders required during construction as set forth in the Special Conditions.

14. Missouri Products and Missouri Firms

14.1 The Curators of the University of Missouri have adopted a policy which is binding upon all employees and departments of the University of Missouri, and which by contract, shall be binding upon independent contractors and subcontractors with the University of Missouri whereby all other things being equal, and when the same can be secured without additional cost over foreign products, or products of other states, a preference shall be granted in all construction, repair and purchase contracts, to all products, commodities,

materials, supplies, and articles mined, grown, produced, andmanufactured in marketable quantity and quality in the Stateof Missouri, and to all firms, corporations or individuals doing business as Missouri firms, corporations, or individuals. Each bidder submitting a bid agrees to comply with and be bound by the foregoing policy.

15. SUPPLIER DIVERSITY

15.1 Award of Contract

The Supplier Diversity participation goal for this project is stated on the Bid for Lump Sum Contract Form, and the Owner will take into consideration the bidder's success in achieving the Supplier Diversity participation goal in awarding the contract. Inability of any bidder to meet this requirement may be cause for rejection of their bid.

A 3-point Service-Disabled Veteran Enterprises (SDVE) bonus preference shall apply to this contract. The 3 bonus points can be obtained by a certified, Missouri based SDVE performing a commercially useful function, (as defined in Article 1 of the General Conditions of the Contract for Construction) either by submitting a bid directly to the Owner, or through the utilization of certified SDVE subcontractors and/or suppliers, whose participation provides atleast 3% of the total bid amount. A firm does not perform a commercially useful function if its role is limited to that of an extra participant in a transaction, contract, or project through which funds are passed in order to obtain the appearance of SDVE participation. In determining whether a firm is such an extra participant, the Owner will examine similar transactions, particularly those in which SDVEs do not participate. The 3point bonus preference shall be calculated and applied by reducing the bid amount of the eligible bidder by three (3) percent of the apparent low responsive bidder's bid. Based on this calculation, if the eligible bidder's resulting total bid valuation is less than the apparent low responsive bidder's bid, the eligible bid becomes the apparent low responsive bid. This reduction is for evaluation purposes only and will have no impact on the actual amount(s) of the eligible bidder's bid or the amount(s) of any contract awarded. The submitted bid form must include a minimum of 3% SDVE participation to obtain the three (3) point bonus. For every SDVE firm utilized, a completed AFFIDAVIT OF SUPPLIER DIVERSITY PARTICIPATION form shall be submitted to the Owner within 24 hours of the receipt of bids. Failure to do so may be grounds for rejection of the SDVE bonus preference.

15.2 List of Supplier Diversity Firms

- **15.2.1** The bidder shall submit as part of their bid a list of diverse firms performing as contractor, subcontractors, and/or suppliers. The list shall specify the single designated diverse firm name and address. If acceptance or non-acceptance of alternates will affect the designation of a subcontractor, provide information for each affected category.
- **15.2.2** Failure to include a complete list of diverse firms may be grounds for rejection of the bid.
- **15.2.3** The list of diverse firms shall be submitted in addition to any other listing of subcontractors required in the Bid for Lump Sum Contract Form.

15.3 Supplier Diversity Percentage Goal

The bidder shall have a minimum goal of subcontracting with diverse contractors, subcontractors, and suppliers, the percent

of contract price stated in the Supplier Diversity goal paragraph of the Bid for Lump Sum Contract Form.

15.4 Supplier Diversity Percent Goal Computation

- 15.4.1 The total dollar value of the work granted to the diverse firms by the successful bidder is counted towards the applicable goal of the entire contract, unless otherwise noted below.
- 15.4.2 The bidder may count toward the Supplier Diversity goal only expenditures to diverse firms that perform a commercially useful function in the work of a contract. A diverse firm is considered to perform a commercially useful function when it is responsible for executing a distinct element of the work and carrying out its responsibilities by actually performing, managing and supervising the work involved. A bidder that is a certified diverse firm may count as 100% of the contract towards the Supplier Diversity goal. For projects with separate MBE, SDVE, and WBE/Veteran/DBE goals, a MBE firm bidding as the prime bidder is expected to obtain the required SDVE, and WBE/Veteran/ DBE participation; a WBE or Veteran or DBE firm bidding as the prime bidder is expected to obtain the required MBE and SDVE participation and a SDVE firm bidding as the prime bidder is expected to obtain the required MBE, and WBE/Veteran/ DBE participation.
- **15.4.3** When a MBE, WBE, Veteran Business Enterprise, DBE, or SDVE performs work as a participant in a joint venture, only the portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work of the contract that the MBE, WBE, Veteran Business Enterprise, DBE, or SDVE performs with its own forces shall count toward the MBE, WBE, Veteran Business Enterprise, DBE, or SDVE individual contract percentages.
- **15.4.4** The bidder may count toward its Supplier Diversity goal expenditures for materials and supplies obtained from diverse suppliers and manufacturers, provided the diverse firm assumes the actual and contractual responsibility for the provision of the materials and supplies.
- **15.4.4.1** The bidder may count its entire expenditure to a diverse manufacturer. A manufacturer shall be defined as an individual or firm that produces goods from raw materials or substantially alters them before resale.
- **15.4.4.2** The bidder may count its entire expenditure to diverse suppliers that are not manufacturers provided the diverse supplier performs a commercially useful function as defined above in the supply process.
- **15.4.4.3** The bidder may count 25% of its entire expenditures to diverse firms that do not meet the definition of a subcontractor, a manufacturer, nor a supplier. Such diverse firms may arrange for, expedite, or procure portions of the work but are not actively engaged in the business of performing, manufacturing, or supplying that work.
- **15.4.5** The bidder may count toward the Supplier Diversity goal that portion of the total dollar value of the work awarded to a certified joint venture equal to the percentage of the ownership and control of the diverse partner in the joint venture.

- 15.5 Certification by Bidder of Diverse Firms
- **15.5.1.** The bidder shall submit with its bid the information requested in the "Supplier Diversity Compliance Evaluation Form" for every diverse firm the bidder intends to award work to on the contract.
- **15.5.2.** Diverse firms are defined in Article 1 (Supplier Diversity Definitions) of the General Conditions of the Contract for Construction included in the contract documents, and as those businesses certified as disadvantaged by an approved agency. The bidder is responsible for obtaining information regarding the certification status of a firm. A list of certified firms may be obtained by contacting the agencies listed in the proposal form document "Supplier Diversity Certifying Agencies." Any firm listed as disadvantaged by any of the identified agencies will be classified as a diverse firm by the Owner.
- **15.5.3.** Bidders are urged to encourage their prospective diverse contractors, subcontractors, joint venture participants, team partners, and suppliers who are not currently certified to obtain certification from one of the approved agencies.

15.6 Supplier Diversity Participation Waiver

- The bidder is required to make a good faith effort to 15.6.1 locate and contract with diverse firms. If a bidder has made a good faith effort to secure the required diverse firms and has failed, the bidder shall submit with the bid, the information requested in "Application for Supplier Diversity Participation Waiver." The Contracting Officer will review the bidder's actions as set forth in the bidder's "Application for Waiver" and any other factors deemed relevant by the Contracting Officer to determine if a good faith effort has been made to meet the applicable percentage goal. If the bidder is judged not to have made a good faith effort, the bid may be rejected. Bidders who demonstrate that they have made a good faith effort to include Supplier Diversity participation may be awarded the contract regardless of the percent of Supplier Diversity participation, provided the bid is otherwise acceptable and is determined to be the best bid.
- **15.6.2** To determine good faith effort of the bidder, the Contracting Officer may evaluate factors including, but not limited to, the following:
- **15.6.2.1** The bidder's attendance at pre-proposal meetings scheduled to inform bidders and diverse firms of contracting and subcontracting opportunities and responsibilities associated with Supplier Diversity participation.
- **15.6.2.2** The bidder's advertisements in general circulation trade association, and diverse (minority) focused media concerning subcontracting opportunities.
- **15.6.2.3** The bidder's written notice to specific diverse firms that their services were being solicited in sufficient time to allow for their effective participation.
- **15.6.2.4** The bidder's follow-up attempts to the initial solicitation(s) to determine with certainty whether diverse firms were interested.
- **15.6.2.5** The bidder's efforts to divide the work into packages suitable for subcontracting to diverse firms.

- **15.6.2.6** The bidder's efforts to provide interested diverse firms with sufficiently detailed information about the drawings, specific actions and requirements of the contract, and clear scopes of work for the firms to bid on.
- 15.6.2.7 The bidder's efforts to solicit for specific subbids from diverse firms in good faith. Documentation should include names, addresses, and telephone numbers of firms contacted a description of all information provided the diverse firms, and an explanation as to why agreements were not reached.
- **15.6.2.8** The bidder's efforts to locate diverse firms not on the directory list and assist diverse firms in becoming certified as such.
- **15.6.2.9** The bidder's initiatives to encourage and develop participation by diverse firms.
- **15.6.2.10** The bidder's efforts to help diverse firms overcome legal or other barriers impeding the participation of diverse firms in the construction contract.
- **15.6.2.11** The availability of diverse firms and the adequacy of the bidder's efforts to increase the participation of such business provided by the persons and organizations consulted by the bidder.

15.7 Submittal of Forms

15.7.1 The bidder will include the Supplier Diversity Compliance Evaluation Form(s), or the Application for Waiver and other form(s) as required above in the envelope containing the "Bidder's Statement of Qualifications", see Article 8.

15.8 Additional Bid/Proposer Information

- **15.8.1** The Contracting Officer reserves the right to request additional information regarding Supplier Diversity participation and supporting documentation from the apparent low bidder. The bidder shall respond in writing to the Contracting Officer within 24 hours (1 workday) of arequest.
- **15.8.2** The Contracting Officer reserves the right to request additional information after the bidder has responded to prior 24-hour requests. This information may include follow up and/or clarification of the information previously submitted.
- 15.8.3 The Owner reserves the right to consider additional diverse subcontractor and supplier participation submitted by the bidder after bids are opened under the provisions within these contract documents that describe the Owner's right to accept or reject subcontractors including, but not limited to, Article 16 below. The Owner may elect to waive the good faith effort requirement if such additional participation achieves the Supplier Diversity goal.

15.8.4 The Bidder shall provide the Owner information related to the Supplier Diversity participation included in the bidder's proposal, including, but is not limited to, the complete Application for Waiver, evidence of diverse certification of participating firms, dollar amount of participation of diverse firms, information supporting a good faith effort as described in Article 15.6 above, and a list of all diverse firms that submitted bids to the Bidder with the diverse firm's price and the name and the price of the firm awarded the scope of work bid by the diverse firm.

16. List of Subcontractors

- 16.1 If a list of subcontractors is required on the Bid for Lump Sum Contract Form, the bidders shall list the name, city and state of the firm(s) which will accomplish that portion of the contract requested in the space provided. This list is separate from both the list of diverse firms required in Article 15.2, and the complete list of subcontractors required in Article 10.1 of this document. Should the bidder choose to perform any of the listed portions of the work with its own forces, the bidder shall enter its own name, city and state in the space provided. If acceptance or non-acceptance of alternates will affect the designation of a subcontractor, the bidder shall provide that information on the bid form.
- 16.2 Failure of the bidder to supply the list of subcontractors required or the listing of more than one subcontractor for any category without designating the portion of the work to be performed by each, shall be grounds for the rejection of the bid. The bidder can petition the Owner to change a listed subcontractor within 48 hours of the bid opening. The Owner reserves the right to make the final determination on a petition to change a subcontractor. The Owner will consider factors such as clerical and mathematical bidding errors, listed subcontractor's inability to perform the work for the bid used, etc. Any request to change a listed subcontractor shall include at a minimum, contractor's bid sheet showing tabulation of the bid; all subcontractor bids with documentation of the time they were received by the contractor; and a letter from the listed subcontractor on their letterhead stating why they cannot perform the work if applicable. The Owner reserves the right to ask for additional information.
- 16.3 Upon award of the contract, the requirements of Article 10 of this document and Article 5 of the General Conditions of the Contract for Construction included in the contract documents will apply.

University of Missouri

General Conditions

of the

Contract

for

Construction

December 2021 Edition



TABLE OF ARTICLES

		PAGE
1.	GENERAL PROVISIONS	GC/1
1 1	D ' D C '.'	CC/1
	Basic Definitions	
1.2	Required Provisions Deemed Inserted	GC/3
1.5	Required 1 Tovisions Decined inserted.	
2.	OWNER	GC/4
2.1	Information and Services Required of the Owner	GC/4
2.2	Owner's Right to Stop the Work	GC/4
	Owner's Right to Carry Out the Work	
2.4	Extent of Owner Rights	
3.	CONTRACTOR	GC/5
3 1	Contractor's Warranty	GC/5
	Compliance with Laws, Regulations, Permits, Codes, and Inspections	
	Anti-Kickback	
3.4	Supervision and Construction Procedures	GC/6
	Use of Site	
	Review of Contract Documents and Field Conditions by Contractor	
	Cleaning and Removal.	
	Cutting and Patching	
	Indemnification.	
	0 Patents	
	1 Delegated Design	
	2 Materials, Labor, and Workmanship	
	3 Approved Equal	
	4Shop Drawings, Product Data and Samples	
	5Record Drawings	
	6Operating Instructions and Service Manual	
	7Taxes	
	8Contractor's Construction Schedules	
4.	ADMINISTRATION OF THE CONTRACT	GC/14
11	Rights of the Owner	CC/14
	Rights of the Architect	
	Review of the Work	
	Claims	
	Claims for Concealed or Unknown Conditions	
	Claim for Additional Cost	
	Claims for Additional Time	
	Resolution of Claims and Disputes	
	Administrative Review	
5.	SUBCONTRACTORS	GC/17
	Award of Subcontracts	
	Subcontractual Relations	
5.3	Contingent Assignment of Subcontract	GC/18
6.	SEPARATE CONTRACTS AND COOPERATION	GC/18
7.	CHANGES IN THE WORK	GC/19
	7.1 Change Orders	
	7.2 Construction Change Directive	
	7.3 Overhead and Profit	
	7.4 Extended General Conditions	
	7.5 Emergency Work	

8. TIME	GC/21
8.1 Progress and Completion	GC/21
8.2 Delay in Completion	
8.3 Liquidated Damages	
6.3 Elquidated Dalliages	
9. PAYMENTS AND COMPLETION	GC/22
9.1 Commencement, Prosecution and Completion	GC/22
9.2 Contract Sum	
9.3 Schedule of Values	GC/24
9.4 Applications for Payment	GC/24
9.5 Approval for Payment	
9.6 Decisions to Withhold Approval	
9.7 Progress Payments	
9.8 Failure of Payment	
9.9 Substantial Completion	
9.10Partial Occupancy or Use	
9.11Final Completion and Final Payment	
10. PROTECTION OF PERSONS AND PROPERTY	GC/27
10.1 Safety Precautions and Programs	GC/27
10.2Safety of Persons and Property	
11. INSURANCE & BONDS	GC/28
11.1Insurance	GC/28
11.2Commercial General Liability	
11.3Licensed for Use Vehicle Liability	GC/29
11.4Workers' Compensation Insurance	
11.5Liability Insurance General Requirements	
11.6Builder's Risk Insurance	
11.7Bonds	
12. UNCOVERING AND CORRECTION OF THE WORK	GC/32
12.1Uncovering of the Work	GC/32
12.2Correction of the Work	
12.3 Acceptance of Nonconforming Work	
13. MISCELLANEOUS PROVISIONS	GC/33
13.1 Written Notice	
13.2Rights and Remedies	
13.3 Tests and Inspections	
13.4Nondiscrimination in Employment Equal Opportunity	
13.5 Supplier Diversity Goal Program	
13.7Records	
13.8Codes and Standards.	
13.9General Provisions.	
13.10Certification.	
14. TERMINATION OR SUSPENSION OF THE CONTRACT	GC/38
14.1 Termination by Owner for Cause	CC/29
14.1 Termination by Owner for Cause	
14.3 Owner's Termination for Convenience	
1 5 it is a reminimuon for Convenience	

ARTICLE 1 GENERAL PROVISIONS

1.1 Basic Definitions

As used in the Contract Documents, the following terms shall have the meanings and refer to the parties designated in these definitions.

1.1.1 Owner

The Curators of the University of Missouri. The Owner may act through its Board of Curators or any duly authorized committee or representative thereof.

1.1.2 Contracting Officer

The Contracting Officer is the duly authorized representative of the Owner with the authority to execute contracts. Communications to the Contracting Officer shall be forwarded via the Owner's Representative.

1.1.3 Owner's Representative

The Owner's Representative is authorized by the Owner as the administrator of the Contract and will represent the Owner during the progress of the Work. Communications from the Architect to the Contractor and from the Contractor to the Architect shall be through the Owner's Representative, unless otherwise indicated in the Contract Documents.

1.1.4 Architect

When the term "Architect" is used herein, it shall refer to the Architect or the Engineer specified and defined in the Contract for Construction or its duly authorized representative. Communications to the Architect shall be forwarded to the address shown in the Contract for Construction.

1.1.5 Owner's Authorized Agent

When the term "Owner's Authorized Agent" is used herein, it shall refer to an employee or agency acting on the behalf of the Owner's Representative to perform duties related to code inspections, testing, operational systems check, certification or accreditation inspections, or other specialized work.

1.1.6 Contractor

The Contractor is the person or entity with whom the Owner has entered into the Contract for Construction. The term "Contractor" means the Contractor or the Contractor's authorized representative.

1.1.7 Subcontractor and Lower-tier Subcontractor

A Subcontractor is a person or organization who has a contract with the Contractor to perform any of the Work. The term "Subcontractor" is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or its authorized representative. The term "Subcontractor" also is applicable to those furnishing materials to be incorporated in the Work whether work performed is at the Owner's site or off site, or both. A lower-tier Subcontractor is a person or organization who has a contract with a Subcontractor or another lower-tier

Subcontractor to perform any of the Work at the site. Nothing contained in the Contract Documents shall create contractual relationships between the Owner or the Architect and any Subcontractor or lower-tier Subcontractor of any tier.

1.1.8 Supplier Diversity Definitions

Businesses that fall into the Supplier Diversity classification shall mean an approved certified business concern which is at least fifty-one percent (51%) owned and controlled by one (1) or more diverse suppliers as described below.

.1 Minority Business Enterprises (MBE)

Minority Business Enterprise [MBE] shall mean an approved certified business concern which is at least fifty-one percent (51%) owned and controlled by one (1) or more minorities as defined below or, in the case of any publicly-owned business, in which at least fifty-one percent (51%) of the stock of which is owned by one (1) or more minorities as defined below, and whose management and daily business operations are controlled by one (1) or more minorities as defined herein.

- .1.1 "African Americans", which includes persons having origins in any of the black racial groups of Africa.
- .1.2 "Hispanic Americans", which includes persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish culture or origin, regardless of race.
- .1.3 "Native Americans", which includes persons of American Indian, Eskimo, Aleut, or Native Hawaiian origin.
- .1.4 "Asian-Pacific Americans", which includes persons whose origins are from Japan, China, Taiwan, Korea, Vietnam, Laos, Cambodia, the Philippines, Samoa, Guam, the U.S. Trust Territories of the Pacific, or the Northern Marinas.
- .1.5 "Asian-Indian Americans", which includes persons whose origins are from India, Pakistan, or Bangladesh.

.2 Women Business Enterprise (WBE)

Women Business Enterprise [WBE] shall mean an approved certified business concern which is at least fifty-one percent (51%) owned and controlled by one (1) or more women or, in the case of any publicly owned business, in which at least fifty-one percent (51%) of the stock of which is owned by one (1) or more women, and whose management and daily business operations are controlled by one (1) or more women.

.3 Veteran Owned Business

Veteran Owned Business shall mean an approved certified business concern which is at least fifty-one percent (51%) owned and controlled by one (1) or more Veterans or, in the case of any publicly owned business, in which at least fifty-one percent (51%) of the stock of which is owned by one (1) or more Veterans, and whose management and daily business operations are controlled by one (1) or more Veterans. Veterans must be certified by the appropriate federal agency responsible for veterans' affairs.

.4 Service-Disabled Veteran Enterprise (SDVE)

Service-Disabled Veteran Enterprise (SDVE) shall mean a business certified by the State of Missouri Office of Administration as a Service-Disabled Veteran Enterprise, which is at least fifty-one percent (51%) owned and controlled by one (1) or more Serviced-Disabled Veterans or, in the case of any publicly-owned business, in which at least fifty-one percent (51%) of the stock of which is owned by one (1) or more Service-Disabled Veterans, and whose management and daily business operations are controlled by one (1) or more Serviced-Disabled Veterans.

.5 Disadvantaged Business Enterprise (DBE)

A Disadvantaged Business Enterprise (DBE) is a forprofit small business concern where a socially and economically disadvantaged individual owns at least 51% interest and also controls management and daily business operations. These firms can and also be referred to as Small Disadvantaged Businesses (SDB). Eligibility requirements for certification are stated in 49 CFR (Code of Federal Regulations), part 26, Subpart D.

U.S. citizens that are African Americans, Hispanics, Native Americans, Asian-Pacific and Subcontinent Asian Americans, and women are presumed to be socially and economically disadvantaged. Also recognized as DBE's are Historically Black Colleges and Universities (HBCU) and small businesses located in Federal HUB Zones.

To be regarded as economically disadvantaged, an individual must have a personal net worth that does not exceed \$1.32 million. To be seen as a small business, a firm must meet Small Business Administration (SBA) size criteria (500 employees or less) and have average annual gross receipts not to exceed \$22.41 million. To be considered a DBE/SDB, a small business owned and controlled by socially and/or economically disadvantaged individuals must receive DBE certification from one of the recognized Missouri state agencies to be recognized in this classification.

1.1.9 Work

Work shall mean supervision, labor, equipment, tools, material, supplies, incidentals operations and activities required by the Contract Documents or reasonably inferable by Contractor therefrom as necessary to produce the results intended by the Contract Documents in a safe, expeditious, orderly, and workmanlike manner, and in the best manner known to each respective trade.

1.1.10 Approved

The terms "approved", "equal to", "directed", "required", "ordered", "designated", "acceptable", "compliant", "satisfactory", and similar words or phrases will be understood to have reference to action on the part of the Architect and/or the Owner's Representative.

1.1.11 Contract Documents

The Contract Documents consist of (1) the executed Contract for Construction, (2) these General Conditions of

the Contract for Construction, (3) any Supplemental Conditions or Special Conditions identified in the Contract for Construction, (4) the Specifications identified in the Contract for Construction, (5) the Drawings identified in the Contract for Construction, (6) Addenda issued prior to the receipt of bids, (7) Contractor's bid addressed to Owner, including Contractor's completed Qualification Statement, (8) Contractor's Performance Bond and Contractor's Payment Bond, (9) Notice to Proceed, (10) and any other exhibits and/or post bid adjustments identified in the Contract for Construction, (11) Advertisement for Bid, (12) Information for Bidders, and (13) Change Orders issued after execution of the Contract. All other documents and technical reports and information are not Contract Documents, including without limitation, Shop Drawings, and Submittals.

1.1.12 Contract

The Contract Documents form the Contract and are the exclusive statement of agreement between the parties. The Contract represents the entire and integrated agreement between the parties hereto and supersedes prior representations or agreements, either written or oral. The Contract Documents shall not be construed to create a contractual relationship of any kind between the Owner and a Subcontractor or any lower-tier Subcontractor.

1.1.13 Change Order

The Contract may be amended or modified without invalidating the Contract, only by a Change Order, subject to the limitations in Article 7 and elsewhere in the Contract Documents. A Change Order is a written instrument signed by the Owner and the Contractor stating their agreement to a change in the Work, the amount of the adjustment to the Contract Sum, if any, and the extent of the adjustment to the Contract Time, if any. Agreement to any Change Order shall constitute a final settlement of all matters relating to the change in the work which is the subject of the Change Order, including, but not limited to, all direct and indirect costs associated with such change and any and all adjustments of the Contract sum, time and schedule.

1.1.14 Substantial Completion

The terms "Substantial Completion" or "substantially complete" as used herein shall be construed to mean the completion of the entire Work, including all submittals required under the Contract Documents, except minor items which in the opinion of the Architect, and/or the Owner's Representative will not interfere with the complete and satisfactory use of the facilities for the purposes intended.

1.1.15 Final Completion

The date when all punch list items are completed, including all closeout submittals and approval by the Architect is given to the Owner in writing.

1.1.16 Supplemental and Special Conditions

The terms "Supplemental Conditions" or "Special Conditions" shall mean the part of the Contract Documents

which amend, supplement, delete from, or add to these General Conditions.

1.1.17 Day

The term "day" as used in the Contract Documents shall mean calendar day unless otherwise specifically defined.

1.1.18 Knowledge.

The terms "knowledge," "recognize" and "discover" their respective derivatives and similar terms in the Contract Documents, as used in reference to the Contractor, shall be interpreted to mean that which the Contractor knows or should know, recognizes, or should recognize and discovers or should discover in exercising the care, skill, and diligence of a diligent and prudent contractor familiar with the work. Analogously, the expression "reasonably inferable" and similar terms in the Contract Documents shall be interpreted to mean reasonably inferable by a diligent and prudent contractor familiar with the work.

1.1.19 Punch List

"Punch List" means the list of items, prepared in connection with the inspection(s) of the Project by the Owner's Representative or Architect in connection with Substantial Completion of the Work or a portion of the Work, which the Owner's Representative or Architect has designated as remaining to be performed, completed, or corrected before the Work will be accepted by the Owner.

1.1.20 Public Works Contracting Minimum Wage

The public works contracting minimum wage shall be equal to one hundred twenty percent of the average hourly wage in a particular locality, as determined by the Missouri economic research and information center within the department of economic development, or any successor agency.

1.1.21 Force Majeure

An event or circumstance that could not have been reasonably anticipated and is out of the control of both the Owner and the Contractor.

1.2 Specifications and Drawings

1.2.1 The Specifications are that portion of the Contract Documents consisting of the written requirements for materials, equipment, construction system, standards and workmanship and performance of related services for the Work identified in the Contract for Construction. Specifications are separated into titled divisions for convenience of reference only. Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade. Such separation will not operate to make the Owner or the Architect an arbiter of labor disputes or work agreements.

- **1.2.2** The drawings herein referred to, consist of drawings prepared by the Architect and are enumerated in the Contract Documents.
- 1.2.3 Drawings are intended to show general arrangements, design, and dimensions of work and are partly diagrammatic. Dimensions shall not be determined by scale or rule. If figured dimensions are lacking, they shall be supplied by the Architect on the Contractor's written request to the Owner's Representative.
- 1.2.4 The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complimentary, and what is required by one shall be as binding as if required by all; performance by the Contractor shall by required only to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the intended results.
- In the event of inconsistencies within or between parts of the Contract Documents, or between the Contract Documents and applicable standards, codes and ordinances, the Contractor shall (1) provide the better quality or greater quantity of Work or (2) comply with the more stringent requirement; either or both in accordance with the Owner's Representative's interpretation. On the Drawings, given dimensions shall take precedence over scaled measurements and large-scale drawings over small scale drawings. Before ordering any materials or doing any Work, the Contractor and each Subcontractor shall verify measurements at the Work site and shall be responsible for the correctness of such measurements. Any difference which may be found shall be submitted to the Owner's Representative and Architect for resolution before proceeding with the Work. If a minor change in the Work is found necessary due to actual field conditions, the Contractor shall submit detailed drawings of such departure for the approval by the Owner's Representative and Architect before making the change.
- 1.2.6 Data in the Contract Documents concerning lot size, ground elevations, present obstructions on or near the site, locations and depths of sewers, conduits, pipes, wires, etc., position of sidewalks, curbs, pavements, etc., and nature of ground and subsurface conditions have been obtained from sources the Architect believes reliable, but the Architect and Owner do not represent or warrant that this information is accurate or complete. The Contractor shall verify such data to the extent possible through normal construction procedures, including but not limited to contacting utility owners and by prospecting.
- **1.2.7** Only work included in the Contract Documents is authorized, and the Contractor shall do no work other than that described therein.
- **1.2.8** Execution of the Contract by the Contractor is a representation that the Contractor has visited the site, become familiar with local conditions under which the Work is to be

performed and correlated personal observations with requirements of the Contract Documents. Contractor represents that it has performed its own investigation and examination of the Work site and its surroundings and satisfied itself before entering into this Contract as to:

- .1 conditions bearing upon transportation, disposal, handling, and storage of materials;
- .2 the availability of labor, materials, equipment, water, electrical power, utilities and roads;
- .3 uncertainties of weather, river stages, flooding and similar characteristics of the site:
- .4 conditions bearing upon security and protection of material, equipment, and Work in progress;
- .5 the form and nature of the Work site, including the surface and sub-surface conditions;
- .6 the extent and nature of Work and materials necessary for the execution of the Work and the remedying of any defects therein; and
- .7 the means of access to the site and the accommodations it may require and, in general, shall be deemed to have obtained all information as to risks, contingencies and other circumstances.
- .8 the ability to complete work without disruption to normal campus activities, except as specifically allowed in the contract documents.

The Owner assumes no responsibility or liability for the physical condition or safety of the Work site or any improvements located on the Work site. The Contractor shall be solely responsible for providing a safe place for the performance of the Work. The Owner shall not be required to make any adjustment in either the Contract Sum or Contract Time concerning any failure by the Contractor or any Subcontractor to comply with the requirements of this Paragraph.

1.2.9 Drawings, specifications, and copies thereof furnished by the Owner are and shall remain the Owner's property. They are not to be used on another project and, with the exception of one contract set for each party to the Contract, shall be returned to the Owner's Representative on request, at the completion of the Work.

1.3 Required Provisions Deemed Inserted

Each and every provision of law and clause required by law to be inserted in this Contract shall be deemed to be inserted herein, and the Contract shall be read and enforced as though it were included herein; and if through mistake or otherwise any such provision is not inserted, or is not correctly inserted, then upon the written application of either party the Contract shall forthwith be physically amended to make such insertion or correction.

ARTICLE 2 OWNER

2.1 Information and Services Required of Owner

- **2.1.1** Permits and fees are the responsibility of the Contractor under the Contract Documents, unless specifically stated in the contract documents that the Owner will secure and pay for specific necessary approvals, easements, assessments, and charges required for construction, use or occupancy of permanent structures, or for permanent changes in existing facilities.
- **2.1.2** When requested in writing by the Contractor, information or services under the Owner's control, which are reasonably necessary to perform the Work, will be furnished by the Owner with reasonable promptness to avoid delay in the orderly progress of the Work.

2.2 Owner's Right to Stop the Work

2.2.1 If the Contractor fails to correct Work which is not in strict accordance with the requirements of the Contract Documents or fails to carry out Work in strict accordance with the Contract Documents, the Owner's Representative may order the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of the Owner to stop the Work will not give rise to a duty on the part of the Owner to exercise this right for the benefit of the Contractor or any other person or entity. Owner's lifting of Stop Work Order shall not prejudice Owner's right to enforce any provision of this Contract.

2.3 Owner's Right to Carry Out the Work

- 2.3.1 If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a seven (7) day period after receipt of a written notice from the Owner to correct such default or neglect, the Owner may, without prejudice to other remedies the Owner may have, correct such default or neglect. In such case, an appropriate Change Order shall be issued deducting from payments then or thereafter due the Contractor the cost of correcting such deficiencies, including compensation for the Architect's additional services and expenses made necessary by such default or neglect. If payments then or thereafter due the Contractor are not sufficient to cover such amounts, the Contractor shall pay the difference to Owner. However, such notice shall be waived in the event of an emergency with the potential for property damage or the endangerment of students, faculty, staff, the public or construction personnel, at the sole discretion of the Owner.
- **2.3.2** In the event the Contractor has not satisfactorily completed all items on the Punch List within thirty (30) days of its receipt, the Owner reserves the right to complete the Punch List without further notice to the Contractor or its surety. In such case, Owner shall be entitled to deduct from payments then or thereafter due the Contractor the cost of completing the Punch List items, including compensation for the Architect's additional services. If payments then or

thereafter due Contractor are not sufficient to cover such amounts, the Contractor shall pay the difference to Owner.

2.4 Extent of Owner Rights

- **2.4.1** The rights stated in this Article 2 and elsewhere in the Contract Documents are cumulative and not in limitation of any rights of the Owner (1) granted in the Contract Documents, (2) at law or (3) in equity.
- **2.4.2** In no event shall the Owner have control over, charge of, or any responsibility for construction means, methods, techniques, sequences or procedures or for safety precautions and programs in connection with the Work, notwithstanding any of the rights and authority granted the Owner in the Contract Documents.

ARTICLE 3 CONTRACTOR

3.1 Contractor's Warranty

- The Contractor warrants all equipment and 3.1.1 materials furnished, and work performed, under this Contract, against defective materials and workmanship for a period of twelve months after acceptance as provided in this Contract, unless a longer period is specified, regardless of whether the same were furnished or performed by the Contractor or any Subcontractors of any tier. Upon written notice from the Owner of any breech of warranty during the applicable warranty period due to defective material or workmanship, the affected part or parts thereof shall be repaired or replaced by the Contractor at no cost to the Owner. Should the Contractor fail or refuse to make the necessary repairs, replacements, and tests when requested by the Owner, the Owner may perform, or cause the necessary work and tests to be performed, at the Contractor's expense, or exercise the Owner's rights under Article 14.
- **3.1.2** Should one or more defects mentioned above appear within the specified period, the Owner shall have the right to continue to use or operate the defective part or apparatus until the Contractor makes repairs or replacements or until such time as it can be taken out of service without loss or inconvenience to the Owner.
- **3.1.3** The above warranties are not intended as a limitation but are in addition to all other express warranties set forth in this Contract and such other warranties as are implied by law, custom, and usage of trade. The Contractor, and its surety or sureties, if any, shall be liable for the satisfaction and full performance of the warranties set forth herein.
- **3.1.4** Neither the final payment nor any provision in the Contract Documents nor partial or entire occupancy of the premises by the Owner, nor expiration of warranty stated herein, will constitute an acceptance of Work not

done in accordance with the Contract Documents or relieve the Contractor of liability in respect to any responsibility for non-conforming work. The Contractor shall immediately remedy any defects in the Work and pay for any damage to other Work resulting therefrom upon written notice from the Owner. Should the Contractor fail or refuse to remedy the non-conforming work, the Owner may perform, or cause to be performed the work necessary to bring the work into conformance with the Contract Documents at the Contractor's expense.

The Contractor agrees to defend, indemnify, and save harmless The Curators of the University of Missouri, their Officers, Agents, Employees and Volunteers, from and against all loss or expense from any injury or damages to property of others suffered or incurred on account of any breech of the aforesaid obligations and covenants. The Contractor agrees to investigate, handle, respond to and provide defense for and defend against any such liability, claims, and demands at the sole expense of the Contractor, or at the option of the University, agrees to pay to or reimburse the University for the defense costs incurred by the University in connection with any such liability claims, or demands. The parties hereto understand and agree that the University is relying on and does not waive or intend to waive by any provision of this Contract, any monetary limitations or any other rights, immunities, and protections provided by the State of Missouri, as from time to time amended, or otherwise available to the University, or its officers, employees, agents or volunteers.

3.2 Compliance with Laws, Regulations, Permits, Codes, and Inspections

- **3.2.1** The Contractor shall, without additional expense to the Owner, comply with all applicable laws, ordinances, rules, permit requirements, codes, statutes, and regulations (collectively referred to as "Laws").
- **3.2.2** Since the Owner is an instrumentality of the State of Missouri, municipal, or political subdivision, ordinances, zoning ordinances, and other like ordinances are not applicable to construction on the Owner's property, and the Contractor will not be required to submit plans and specifications to any municipal or political subdivision authority to obtain construction permits or any other licenses or permits from or submit to, inspection by any municipality or political subdivision relating to the construction on the Owner's property, unless required by the Owner in these Contract Documents or otherwise in writing.
- **3.2.3** All fees, permits, inspections, or licenses required by municipality or political subdivision for operation on property not belonging to the Owner, shall be obtained by and paid for by the Contractor. The Contractor, of its own expense, is responsible to ensure that all inspections required by said permits or licenses on property, easements, or utilities not belonging to the Owner are conducted as required therein. All connection charges, assessments or transportation fees as may be imposed by any utility company or others are

included in the Contract Sum and shall be the Contractor's responsibility, as stated in 2.1.1 above.

3.2.4 If the Contractor has knowledge that any Contract Documents are at variance with any Laws, including Americans with Disabilities Act – Standards for Accessible Design, ordinances, rules, regulations, or codes applying to the Work, Contractor shall promptly notify the Architect and the Owner's Representative, in writing, and any necessary changes will be adjusted as provided in the Contract Documents. However, it is not the Contractor's primary responsibility to ascertain that the Contract Documents are in accordance with applicable Laws, unless such Laws bear upon performance of the Work.

3.3 Anti-Kickback

- **3.3.1** No member or delegate to Congress, or resident commissioner, shall be admitted to any share or part of this Contract or to any benefit that may arise therefrom, but this provision shall not be construed to extend to this Contract if made with a corporation for its general benefit.
- **3.3.2** No official of the Owner who is authorized in such capacity and on behalf of the Owner to negotiate, make, accept or approve, or to take part in negotiating, making, accepting, or approving any architectural, engineering, inspection, construction, or material supply contract or any Subcontract of any tier in connection with the construction of the Work shall have a financial interest in this Contract or in any part thereof, any material supply contract, Subcontract of any tier, insurance contract, or any other contract pertaining to the Work.

3.4 Supervision and Construction Procedures

- 3.4.1 The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for and have control over construction means, methods, techniques, sequences, and procedures and for coordinating all portions of the Work under the Contract. The Contractor shall supply sufficient and competent supervision and personnel, and sufficient material, plant, and equipment to prosecute the Work with diligence to ensure completion thereof within the time specified in the Contract Documents, and shall pay when due any laborer, Subcontractor of any tier, or supplier.
- **3.4.2** The Contractor, if an individual, shall give the Work an adequate amount of personal supervision, and if a partnership or corporation or joint venture the Work shall be given an adequate amount of personal supervision by a partner or executive officer, as determined by the Owner's Representative.
- **3.4.3** The Contractor and each of its Subcontractors of any tier shall submit to the Owner such schedules of quantities and costs, progress schedules in accordance

- with 3.17.2 of this document, payrolls, reports, estimates, records, and other data as the Owner may request concerning Work performed or to be performed under the Contract.
- **3.4.4** The Contractor shall be represented at the site by a competent superintendent from the beginning of the Work until its final acceptance, whenever contract work is being performed, unless otherwise permitted in writing by the Owner's Representative. The superintendent for the Contractor shall exercise general supervision over the Work and such superintendent shall have decision making authority of the Contractor. Communications given to the superintendent shall be binding as if given to the Contractor. The superintendent shall not be changed by the contractor without approval from the Owner's Representative.
- **3.4.5** The Contractor shall establish and maintain a permanent benchmark to which access may be had during progress of the Work, and Contractor shall establish all lines and levels, and shall be responsible for the correctness of such. Contractor shall be fully responsible for all layout work for the proper location of Work in strict accordance with the Contract Documents.
- **3.4.6** The Contractor shall establish and be responsible for wall and partition locations. If applicable, separate contractors shall be entitled to rely upon these locations and for setting their sleeves, openings, or chases.
- **3.4.7** The Contractor's scheduled outage/tie-in plan, time, and date for any utilities is subject to approval by the Owner's Representative. Communication with the appropriate entity and planning for any scheduled outage/tie-in of utilities shall be the responsibility of the Contractor. Failure of Contractor to comply with the provisions of this Paragraph shall cause Contractor to forfeit any right to an adjustment of the Contract Sum or Contract Time for any postponement, rescheduling or other delays ordered by Owner in connection with such Work. The Contractor shall follow the following procedures for all utility outages/tie-ins or disruption of any building system:
- .1 All shutting of valves, switches, etc., shall be by the Owner's personnel.
- .2 Contractor shall submit its preliminary outage/tie-in schedule with its baseline schedule.
- .3 The Contractor shall request an outage/tie-in meeting at least two weeks before the outage/tie-in is required.
- .4 The Owner's Representative will schedule an outage/tie-in meeting at least one week prior to the outage/tie-in.
- **3.4.8** The Contractor shall coordinate all Work so there shall be no prolonged interruption of existing utilities, systems, and equipment of Owner. Any existing plumbing, heating, ventilating, air conditioning, or electrical disconnection necessary, which affect portions of this construction or building or any other building, must be scheduled with the Owner's Representative to avoid any

disruption of operation within the building under construction or other buildings or utilities. In no case shall utilities be left disconnected at the end of a workday or over a weekend. Any interruption of utilities, either intentionally or accidentally, shall not relieve the Contractor from repairing and restoring the utility to normal service. Repairs and restoration shall be made before the workers responsible for the repair and restoration leave the job.

- **3.4.9** The Contractor shall be responsible for repair of damage to property on or off the project occurring during construction of project, and all such repairs shall be made to meet code requirements or to the satisfaction of the Owner's Representative if code is not applicable.
- **3.4.10** The Contractor shall be responsible for all shoring required to protect its work or adjacent property and shall pay for any damage caused by failure to shore or by improper shoring or by failure to give proper notice. Shoring shall be removed only after completion of permanent supports.
- **3.4.11** The Contractor shall maintain at his own cost and expense, adequate, safe and sufficient walkways, platforms, scaffolds, ladders, hoists and all necessary, proper, and adequate equipment, apparatus, and appliances useful in carrying on the Work and which are necessary to make the place of Work safe and free from avoidable danger for students, faculty, staff, the public and construction personnel, and as may be required by safety provisions of applicable laws, ordinances, rules regulations and building and construction codes.
- **3.4.12** During the performance of the Work, the Contractor shall be responsible for providing and maintaining warning signs, lights, signal devices, barricades, guard rails, fences, and other devices appropriately located on site which shall give proper and understandable warning to all persons of danger of entry onto land, structure, or equipment, within the limits of the Contractor's work area.
- **3.4.13** The Contractor shall pump, bail, or otherwise keep any general excavations free of water. The Contractor shall keep all areas free of water before, during and after concrete placement. The Contractor shall be responsible for protection, including weather protection, and proper maintenance of all equipment and materials installed, or to be installed by him.
- **3.4.14** The Contractor shall be responsible for care of the Work and must protect same from damage of defacement until acceptance by the Owner. All damaged or defaced Work shall be repaired or replaced to the Owner's satisfaction, without cost to the Owner.
- **3.4.15** When requested by the Owner's Representative, the Contractor, at no extra charge, shall provide scaffolds

- or ladders in place as may be required by the Architect or the Owner for examination or inspection of Work in progress or completed.
- **3.4.16** The Contractor shall be responsible to the Owner for acts and omissions of the Contractor's employees, Subcontractors of any tier and their agents and employees, and any entity or other persons performing portions of the Work.
- **3.4.17** The Contractor shall not be relieved of its obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Owner's Representative or Architect in their administration of the Contract, or by tests, inspections or approvals required or performed by persons other than the Contractor.
- **3.4.18** The Contractor shall be responsible for inspection of portions of the Work already performed under this Contract to determine that such portions are compliant and in proper condition to receive subsequent Work.

3.5 Use of Site

- **3.5.1** The Contractor shall limit operations and storage of material to the area within the Work limit lines shown on Drawings, except as necessary to connect to exiting utilities, shall not encroach on neighboring property, and shall exercise caution to prevent damage to existing structures.
- **3.5.2** Only materials and equipment, which are to be used directly in the Work, shall be brought to and stored on the Work site by the Contractor. After equipment is no longer required for the Work, it shall be promptly removed from the Work site. Protection of construction materials and equipment stored at the Work site from weather, theft, damage and all other adversity is solely the responsibility of the Contractor.
- **3.5.3** No project signs shall be erected without the written approval of the Owner's Representative.
- 3.5.4 The Contractor shall ensure that the Work is at all times performed in a manner that affords reasonable access, both vehicular and pedestrian, to the site of the Work and all adjacent areas. Particular attention shall be paid to access for emergency vehicles, including fire trucks. Wherever there is the possibility of interfering with normal emergency vehicle operations, Contractor shall obtain permission from both campus and municipal emergency response entities prior to limiting any access. The Work shall be performed, to the fullest extent reasonably possible, in such a manner that public areas adjacent to the site of the Work shall be free from all debris, building materials and equipment likely to cause hazardous conditions. Without limitation of any other provision of the Contract Documents, Contractor shall not interfere with the occupancy or beneficial use of (1) any areas and buildings adjacent to the site of the Work or (2) the Work in the event of partial occupancy. Contractor shall assume full responsibility for any damage to the property

comprising the Work or to the owner or occupant of any adjacent land or areas resulting from the performance of the Work.

- The Contractor shall not permit any workers to 3.5.5 use any existing facilities at the Work site, including, without limitation, lavatories, toilets, entrances, and parking areas other than those designated by Owner. The Contractor, Subcontractors of any tier, suppliers and employees shall comply with instructions or regulations of the Owner's Representative governing access to, operation of, and conduct while in or on the premises and shall perform all Work required under the Contract Documents in such a manner as not to unreasonably interrupt or interfere with the conduct of Owner's operations. Any request for Work, a suspension of Work or any other request or directive received by the Contractor from occupants of existing buildings shall be referred to the Owner's Representative for determination.
- **3.5.6** The Contractor and the Subcontractor of any tier shall have its' name, acceptable abbreviation or recognizable logo and the name of the city and state of the mailing address of the principal office of the company, on each motor vehicle and motorized self-propelled piece of equipment which is used in connection with the project. The signs are required on such vehicles during the time the Contractor is working on the project.

3.6 Review of Contract Documents and Field Conditions by Contractor

- 3.6.1 The Contractor shall carefully study and compare the Contract Documents with each other and with information furnished by the Architect and Owner and shall at once report in writing to the Architect and Owner's Representative any errors, inconsistencies or omissions discovered. If the Contractor performs any construction activity which it knows or should have known involves a recognized error, inconsistency, or omission in the Contract Documents without such written notice to the Architect and Owner's Representative, the Contractor shall assume appropriate responsibility for such performance and shall bear an appropriate amount of the attributable costs for correction.
- 3.6.2 The Contractor shall take field measurements and verify field conditions and shall carefully compare such field measurements and conditions and other information known to the Contractor with the Contract Documents before commencing activities. Errors, inconsistencies, or omissions discovered shall be reported in writing to the Architect and Owner's Representative within twenty-four (24) hours. During the progress of work, Contractor shall verify all field measurements prior to fabrication of building components or equipment and proceed with the fabrication to meet field conditions. Contractor shall consult all Contract Documents to determine the exact location of all work and verify spatial relationships of all work. Any question concerning said

location or spatial relationships shall be submitted to the Owner's Representative. Specific locations for equipment, pipelines, ductwork and other such items of work, where not dimensioned on plans, shall be determined in consultation with Owner's Representative and Architect. Contractor shall be responsible for the proper fitting of the Work in place.

- **3.6.3** The Contractor shall provide, at the proper time, such material as required for support of the Work. If openings or chases are required, whether shown on Drawings or not, the Contractor shall see they are properly constructed. If required openings or chases are omitted, the Contractor shall cut them at the Contractors own expense, but only as directed by the Architect, through the Owner Representative.
- **3.6.4** Should the Contract Documents fail to particularly describe materials or goods to be used, it shall be the duty of the Contractor to inquire of the Architect and the Owner's Representative what is to be used and to supply it at the Contractor's expense, or else thereafter replace it to the Owner's Representative's satisfaction. At a minimum, the Contractor shall provide the quality of materials as generally specified throughout the Contract Documents.

3.7 Cleaning and Removal

3.7.1 The Contractor shall keep the Work site and surrounding areas free from accumulation of waste materials, rubbish, debris, and dirt resulting from the Work and shall clean the Work site and surrounding areas as requested by the Architect and the Owner's Representative, including mowing of grass greater than 6 inches high. The Contractor shall be responsible for the cost of clean up and removal of debris from premises. The building and premises shall be kept clean, safe, in a workmanlike manner, and in compliance with OSHA standards and code at all times. At completion of the Work, the Contractor shall remove from and about the Work site tools, construction equipment, machinery, fencing, and surplus materials. Further, at the completion of the work, all dirt, stains, and smudges shall be removed from every part of the building, all glass in doors and windows shall be washed, and entire Work shall be left broom clean in a finished state ready for occupancy. The Contractor shall advise his Subcontractors of any tier of this provision, and the Contractor shall be fully responsible for leaving the premises in a finished state ready for use to the satisfaction of the Owner's Representative. If the Contractor fails to comply with the provisions of this paragraph, the Owner may do so, and the cost thereof shall be charged to the Contractor.

3.8 Cutting and Patching

- **3.8.1** The Contractor shall be responsible for cutting, fitting, or patching required to complete the Work or to make its parts fit together properly.
- **3.8.2** The Contractor shall not damage or endanger a portion of the Work or fully or partially completed construction of the Owner or separate contractors by cutting, patching, or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter

such construction by the Owner or a separate contractor except with written consent of the Owner and of such separate contractor; such consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold from the Owner or a separate contractor the Contractor's consent to cutting or otherwise altering the Work.

3.8.3 If the Work involves renovation and/or alteration of existing improvements, Contractor acknowledges that cutting and patching of the Work is essential for the Work to be successfully completed. Contractor shall perform any cutting, altering, patching, and/or fitting of the Work necessary for the Work and the existing improvements to be fully integrated and to present the visual appearance of an entire, completed, and unified project. In performing any Work which requires cutting or patching, Contractor shall use its best efforts to protect and preserve the visual appearance and aesthetics of the Work to the reasonable satisfaction of both the Owner's Representative and Architect.

3.9 Indemnification

3.9.1 To the fullest extent permitted by law, the Contractor shall defend, indemnify, and hold harmless the Owner, the Architect, Architect's consultants, and the agents, employees, representatives, insurers and reinsurers of any of the foregoing (hereafter collectively referred to as the "Indemnitees") from and against claims, damages (including loss of use of the Work itself), punitive damages, penalties and civil fines unless expressly prohibited by law, losses and expenses, including, but not limited to, attorneys' fees, arising out of or resulting from performance of the Work to the extent caused in whole or in part by negligent acts or omissions or other fault of Contractor, a Subcontractor of any tier, or anyone directly or indirectly employed by them or anyone for whose acts they may be liable, regardless of whether or not such claim, damage, loss, or expense is caused in part by the negligent acts or omissions or other fault of a party indemnified hereunder. The Contractor's obligations hereunder are in addition to and shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that the Owner may possess. If one or more of the Indemnitees demand performance by the Contractor of obligations under this paragraph or other provisions of the Contract Documents and if Contractor refuses to assume or perform, or delays in assuming or performing Contractor's obligations, Contractor shall pay each Indemnitee who has made such demand its respective attorneys' fees, costs, and other expenses incurred in enforcing this provision. The defense and indemnity required herein shall be a binding obligation upon Contractor whether or not an Indemnitee has made such demand. Even if a defense is successful to a claim or demand for which Contractor is obligated to indemnify the Indemnitees from under this Paragraph, Contractor shall remain liable for all costs of defense.

- 3.9.2 The indemnity obligations of Contractor under this Section 3.9 shall survive termination of this Contract or final payment thereunder. In the event of any claim or demand made against any party which is entitled to be indemnified hereunder, the Owner may in its sole discretion reserve, return or apply any monies due or to become due the Contractor under the Contract for the purpose of resolving such claims; provided, however, that the Owner may release such funds if the Contractor provides the Owner with reasonable assurance of protection of the Owner's interests. The Owner shall in its sole discretion determine if such assurances are reasonable. Owner reserves the right to control the defense and settlement of any claim, action or proceeding which Contractor has an obligation to indemnify the Indemnitees against under Paragraph 3.9.1.
- **3.9.3** In claims against any person or entity indemnified under this Section 3.9 by an employee of the Contractor, a Subcontractor of any tier, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, the indemnification obligation under this Section 3.9 shall not be limited by a limitation on amount or type of damages, compensation or benefits payable by or for the Contractor or a Subcontractor of any tier under workers' or workmen's compensation acts, disability benefit acts or other employee benefit acts.
- **3.9.4** The obligations of the Contractor under Paragraph 3.9.1 shall not extend to the liability of the Architect, his agents or employees, arising out of the preparation and approval of maps, drawings, opinions, reports, surveys, Change Orders, designs, or Specifications.

3.10 Patents

3.10.1 The Contractor shall hold and save harmless the Owner and its officers, agents, servants, and employees from liability of any nature or kind, including cost and expense, for, or on account of, any patented or otherwise protected invention, process, article, or appliance manufactured or used in the performance of the Contract, including its use by the Owner, unless otherwise specifically stipulated in the Contract Documents.

3.10.2 If the Contractor uses any design, device, or material covered by letters patent or copyright, he shall provide for such use by suitable agreement with the Owner of such patented or copyrighted design, device, or material. It is mutually agreed and understood, without exception, that the Contract Sum include, and the Contractor shall pay all royalties, license fees or costs arising from the use of such design, device, or material in any way involved in the Work. The Contractor and/or sureties shall indemnify and save harmless the Owner from any and all claims for infringement by reason of the use of such patented or copyrighted design, device, or material or any trademark or copyright in connection with Work agreed to be performed under this Contract and shall indemnify the Owner for any cost, expense, or damage it may be obligated to pay by reason of

such infringement at any time during the prosecution of the Work or after completion of the Work.

3.11 Delegated Design

3.11.1 If the Contract Documents specify the Contractor is responsible for the design of any work as part of the project, then the Contractor shall procure all design services and certifications necessary to complete the Work as specified, from a design professional licensed in the State of Missouri. The signature and seal of that design professional shall appear on all drawings, calculations, specifications, certifications, shop drawings, and other submittals related to the Work. The design professional shall maintain insurance as required per Article 11.

3.12 Materials, Labor, and Workmanship

- **3.12.1** Materials and equipment incorporated into the Work shall strictly conform to the Contract Documents and representations and approved Samples provided by Contractor and shall be of the most suitable grade of their respective kinds for their respective uses and shall be fit and sufficient for the purpose intended, merchantable, of good new material and workmanship, and free from defect. Workmanship shall be in accordance with the highest standard in the industry and free from defect in strict accordance with the Contract Documents.
- **3.12.2** Materials and fixtures shall be new and of latest design unless otherwise specified and shall provide the most efficient operating and maintenance costs to the Owner. All Work shall be performed by competent workers and shall be of best quality.
- **3.12.3** The Contractor shall carefully examine the Contract Documents and shall be responsible for the proper fitting of his material, equipment, and apparatus into the building.
- **3.12.4** The Contractor shall base his bid only on the Contract Documents.
- **3.12.5** Materials and workmanship shall be subject to inspection, examination, and testing by the Architect and the Owner's Representative at any and all times during manufacture, installation, and construction of any of them, at places where such manufacture, installation, or construction is performed.
- **3.12.6** The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Contract. The Contractor shall not permit employment of unfit persons or persons not skilled in tasks assigned to them.
- **3.12.7** Unless otherwise specifically noted, the Contractor shall provide and pay for supervision, labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other

facilities and services necessary for the proper execution and completion of the Work.

3.12.8 Substitutions

- **3.12.8.1** A substitution is a Contractor proposal of an alternate product or method in lieu of what has been specified or shown in the Contract Documents, which is not an "or equal" as set forth in Section 3.12.1.
- **3.12.8.2** Contractor may make a proposal to the Architect and the Owner's Representative to use substitute products or methods as set forth herein, but the Architect's and the Owner's Representative's decision concerning acceptance of a substitute shall be final. The Contractor must do so in writing and setting forth the following:
- Full explanation of the proposed substitution and submittal of all supporting data including technical information, catalog cuts, warranties, test results, installation instructions, operating procedures, and other like information necessary for a complete evaluation of the substitution.
- .2 Reasons the substitution is advantageous and necessary, including the benefits to the Owner and the Work in the event the substitution is acceptable.
- .3 The adjustment, if any, in the Contract Sum, in the event the substitution is acceptable.
- .4 The adjustment, if any, in the time of completion of the Contract and the construction schedule in the event the substitution is acceptable.
- .5 An affidavit stating that (a) the proposed substitution conforms to and meets all of the Contract Document requirements and is code compliant, except as specifically disclosed and set forth in the affidavit and (b) the Contractor accepts the warranty and correction obligations in connection with the proposed substitution as if originally specified by the Architect. Proposals for substitutions shall be submitted to the Architect and Owner's Representative in sufficient time to allow the Architect and Owner's Representative no less than ten (10) working days for review. substitution will be considered or allowed without the Contractor's submittal of complete substantiating data and information as stated herein.
- **3.12.8.3** Substitutions may be rejected without explanation at the Owner's sole discretion and will be considered only under one or more of the following conditions:
- Required for compliance with interpretation of code requirements or insurance regulations then existing;
- .2 Unavailability of specified products, through no fault of the Contractor:
- .3 Material delivered fails to comply with the Contract Documents;
- .4 Subsequent information discloses inability of specified products to perform properly or to fit in designated space;

- .5 Manufacturer/fabricator refuses to certify or guarantee performance of specified product as required; or
- .6 When in the judgment of the Owner or the Architect, a substitution would be substantially to the Owner's best interests, in terms of cost, time, or other considerations.
- **3.12.8.4** Whether or not any proposed substitution is accepted by the Owner or the Architect, the Contractor shall reimburse the Owner for any fees charged by the Architect or other consultants for evaluating each proposed substitution.

3.13 Approved Equal

- 3.13.1 Whenever in the Contract Documents any article, appliance, device, or material is designated by the name of a manufacturer, vendor, or by any proprietary or trade name, the words "or approved equal," shall automatically follow and shall be implied unless specifically indicated otherwise. The standard products of manufacturers other than those specified will be accepted when, prior to the ordering or use thereof, it is proven to the satisfaction of the Owner's Representative and the Architect they are equal in design, appearance, spare parts availability, strength, durability, usefulness, serviceability, operation cost, maintenance cost, and convenience for the purpose intended. Any general listings of approved manufacturers in any Contract Document shall be for informational purposes only and it shall be the Contractor's sole responsibility to ensure that any proposed "or equal" complies with the requirements of the Contract Documents and is code compliant.
- 3.13.2 The Contractor shall submit to Architect and Owner's Representative a written and full description of the proposed "or equal" including all supporting data, including technical information, catalog cuts, warranties, test results, installation instructions, operating procedures, and similar information demonstrating that the proposed "or equal" strictly complies with the Contract Documents. The Architect or Owner's Representative shall take appropriate action with respect to the submission of a proposed "or equal" item. If Contractor fails to submit proposed "or equals" as set forth herein, it shall waive any right to supply such items. The Contract Sum and Contract Time shall not be adjusted as a result of any failure by Contractor to submit proposed "or equals" as provided for herein. All documents submitted in connection with preparing an "or equal" shall be clearly and obviously marked as a proposed "or equal" submission.
- **3.13.3** No approvals or action taken by the Architect or Owner's Representative shall relieve Contractor from its obligation to ensure that an "or equal" article, appliance, devise, or material strictly complies with the requirements of the Contract Documents. Contractor shall not propose "or equal" items in connection with Shop Drawings or

other Submittals, and Contractor acknowledges and agrees that no approvals or action taken by the Architect or Owner's Representative with respect to Shop Drawings or other Submittals shall constitute approval of any "or equal" item or relieve Contractor from its sole and exclusive responsibility. Any changes required in the details and dimensions indicated in the Contract Documents for the incorporation or installation of any "or equal" item supplied by the Contractor shall be properly made and approved by the Architect at the expense of the Contractor. No 'or equal' items will be permitted for components of or extensions to existing systems when, in the opinion of the Architect, the named manufacturer must be provided in order to ensure compatibility with the existing systems, including, but not limited to, mechanical systems, electrical systems, fire alarms, smoke detectors, etc. No action will be taken by the Architect with respect to proposed "or equal" items prior to receipt of bids, unless otherwise noted in the Special Conditions.

3.14 Shop Drawings, Product Data, Samples, and Coordination Drawings/BIM Models

- **3.14.1** Shop Drawings are drawings, diagrams, schedules, and other data specifically prepared for the Work by the Contractor or a Subcontractor, sub-subcontractor, manufacturer, supplier, or distributor to illustrate some portion of the Work.
- **3.14.2** Product Data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams and other information furnished by the Contractor to illustrate materials or equipment for some portion of the Work.
- **3.14.3** Samples are physical samples which illustrate materials, equipment or workmanship and establish standards by which the Work will be judged.
- **3.14.4** Coordination Drawings are drawings for the integration of the Work, including work first shown in detail on shop drawings or product data. Coordination drawings show sequencing and relationship of separate units of work which must interface in a restricted manner to fit in the space provided, or function as indicated. Coordination Drawings are the responsibility of the contractor and are submitted for informational purposes. The Special Conditions will state whether coordination drawings are required. BIM models may be used for coordination in lieu of coordination drawings at the contractor's discretion, unless required in the Special Conditions. The final coordination drawings/BIM Model will not change the contract documents, unless approved by a fully executed change order describing the specific modifications that are being made to the contract documents.
- **3.14.5** Shop Drawings, Coordination Drawings/BIM Models, Product Data, Samples and similar submittals (collectively referred to as "Submittals") are not Contract Documents. The purpose of their submittal is to demonstrate for those portions of the Work for which submittals are

required the way the Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents.

- **3.14.6** The Contractor shall schedule submittal of Shop Drawings and Product Data to the Architect so that no delays will result in delivery of materials and equipment, advising the Architect of priority for checking of Shop Drawings and Product Data, but a minimum of two weeks shall be provided for this purpose. Because time is of the essence in this contract, unless noted otherwise in the Special Conditions or Technical Specifications, all submittals, shop drawings and samples must be submitted as required to maintain the contractor's plan for proceeding but must be submitted within 90 days of the Notice to Proceed. If Contractor believes that this milestone is unreasonable for any submittal, Contractor shall request an extension of this milestone, within 60 days of Notice to Proceed, for each submittal that cannot meet the milestone. The request shall contain a reasonable explanation as to why the 90-day milestone is unrealistic, and shall specify a date on which the submittal will be provided, for approval by the Owner's Representative. Failure of the Contractor to comply with this section may result in delays in the submittal approval process and/or charges for expediting approval, both of which will be the responsibility of the Contractor.
- **3.14.7** The Contractor, at its own expense, shall submit Samples required by the Contract Documents with reasonable promptness as to cause no delay in the Work or the activities of separate contractors and no later than twenty (20) days before materials are required to be ordered for scheduled delivery to the Work site. Samples shall be labeled to designate material or products represented, grade, place of origin, name of producer, name of Contractor and the name and number of the Owner's project. Ouantities of Samples shall be twice the number required for testing so that Architect can return one set of Materials delivered before receipt of the Samples. Architect's approval may be rejected by Architect and in such event, Contractor shall immediately remove all such materials from the Work site. When requested by Architect or Owner's Representative, samples of finished masonry and field applied paints and finishes shall be located as directed and shall include sample panels built at the site of approximately twenty (20) square feet each.
- **3.14.8** The Contractor shall perform no portion of the Work requiring submittal and review of Shop Drawings, Product Data, Samples, or similar submittals until the respective submittal has been approved by the Architect. Such Work shall be in accordance with approved submittals.
- **3.14.9** By approving and submitting Shop Drawings, Product Data, Samples and similar submittals, the Contractor represents such Submittals strictly comply with the requirements of the Contract Documents and that the

Contractor has determined and verified field measurements and field construction criteria related thereto, that materials are fit for their intended use and that the fabrication, shipping, handling, storage, assembly and installation of all materials, systems and equipment are in accordance with best practices in the industry and are in strict compliance with any applicable requirements of the Contract Documents. Contractor shall also coordinate each Submittal with other Submittals.

- **3.14.10** Contractor shall be responsible for the correctness and accuracy of the dimensions, measurements and other information contained in the Submittals.
- **3.14.11** Each Submittal will bear a stamp or specific indication that the Submittal complies with the Contract Documents and Contractor has satisfied its obligations under the Contract Documents with respect to Contractor's review and approval of that Submittal. Each Submittal shall bear the signature of the representative of Contractor who approved the Submittal, together with the Contractor's name, Owner's name, number of the Project, and the item name and specification section number.
- **3.14.12** The Contractor shall not be relieved of responsibility for deviations from requirements of the Contract Documents by the Architect's approval of Shop Drawings, Product Data, Samples, or similar submittals. The Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or similar submittals by the Architect's approval thereof. Specifically, but not by way of limitation, Contractor acknowledges that Architect's approval of Shop Drawings shall not relieve Contractor for responsibility for errors and omissions in the Shop Drawings since Contractor is responsible for the correctness of dimensions, details and the design of adequate connections and details contained in the Shop Drawings.
- **3.14.13** The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples or similar submittals, to revisions other than those requested by the Architect on previous Submittals.
- **3.14.14** The Contractor represents and warrants that all Shop Drawings shall be prepared by persons and entities possessing expertise and experience in the trade for which the Shop Drawing is prepared and, if required by the Architect or applicable Laws, by a licensed engineer or other design professional.

3.15 Record Drawings

3.15.1 The Contractor shall maintain a set of Record Drawings on site in good condition and shall use colored pencils to mark up said set with "record information" in a legible manner to show: (1) bidding addendums, (2) executed change orders, (3) deviations from the Drawings made during construction; (4) details in the Work not previously shown; (5) changes to existing conditions or existing conditions found to differ from those shown on any existing drawings; (6) the actual installed position of equipment, piping, conduits, light switches, electric fixtures, circuiting, ducts, dampers, access

panels, control valves, drains, openings, and stub-outs; and (7) such other information as either Owner or Architect may reasonably request. The prints for Record Drawing use will be a set of "blue line" prints provided by Architect to Contractor at the start of construction. Upon Substantial Completion of the Work, Contractor shall deliver all Record Drawings to Owner and Architect for approval. If not approved, Contractor shall make the revisions requested by Architect or Owner's Representative. Final payment and any retainage shall not be due and owing to Contractor until the final Record Drawings marked by Contractor as required above are delivered to Owner.

3.16 Operating Instructions and Service Manuals

- **3.16.1** The Contractor shall submit four (4) volumes of operating instructions and service manuals to the Architect before completing 50% of the adjusted contract amount. Payments beyond 50% of the adjusted contract amount may be withheld until all operating instructions and service manuals are received. The operating instructions and service manuals shall contain:
- .1 Start-up and Shutdown Procedures: Provide a step-by-step write up of all major equipment. When manufacturer's printed start-up, trouble shooting and shut-down procedures are available, they may be incorporated into the operating manual for reference.
- .2 Operating Instructions: Written operating instructions shall be included for the efficient and safe operation of all equipment.
- .3 Equipment List: List of all major equipment as installed shall include model number, capacities, flow rate, and name-plate data.
- .4 Service Instructions: The Contractor shall be required to provide the following information for all pieces of equipment.
 - (a) Recommended spare parts including catalog number and name of local suppliers or factory representative.
 - **(b)** Belt sizes, types, and lengths.
 - (c) Wiring diagrams.
- .5 Manufacturer's Certificate of Warranty: Manufacturer's certificates of warranty shall be obtained for all major equipment. Warranty shall be obtained for at least one year from the date of Substantial Completion. Where longer period is required by the Contract Documents, the longer period shall govern.
- .6 Parts catalogs: For each piece of equipment furnished, a parts catalog or similar document shall be provided which identifies the components by number for replacement ordering.

3.16.2 Submission

.1 Manuals shall be bound into volumes of standard 8 1/2" x 11" hard binders. Large drawings too bulky to be folded into 8 1/2" x 11" shall be separately bound or folded and in brown

- envelopes, cross-referenced and indexed with the manuals.
- .2 The manuals shall identify the Owner's project name, project number, and include the name and address of the Contractor and major Subcontractors of any tier who were involved with the activity described in that particular manual.

3.17 Taxes

- **3.17.1** The Contractor shall pay all applicable sales, consumer, use, and similar taxes for the Work which are legally enacted when the bids are received, whether or not yet effective or scheduled to go into effect. However, certain purchases by the Contractor of materials incorporated in or consumed in the Work are exempt from certain sales tax pursuant to RSMo § 144.062. The Contractor shall be issued a Project Tax Exemption Certificate for this Work to obtain the benefits of RSMo § 144.062.
- 3.17.2 The Contractor shall furnish this certificate to all subcontractors, and any person or entity purchasing materials for the Work shall present such certificate to all material suppliers as authorization to purchase, on behalf of the Owner, all tangible personal property and materials to be incorporated into or consumed in the Work and no other on a tax-exempt basis. Such suppliers shall provide to the purchasing party invoices bearing the name of the exempt entity and the project identification number. Nothing in this section shall be deemed to exempt from any sales or similar tax the purchase of any construction machinery, equipment or tools used in construction, repairing or remodeling facilities for the Owner. All invoices for all personal property and materials purchased under a Project Tax Exemption Certificate shall be retained by the Contractor for a period of five years and shall be subject to audit by the Director of Revenue.
- 3.17.3 Any excess resalable tangible personal property or materials which were purchased for the project under this Project Tax Exemption Certificate but which were not incorporated into or consumed in the Work shall either be returned to the supplier for credit or the appropriate sales or use tax on such excess property or materials shall be reported on a return and paid by such purchasing party not later than the due date of the purchasing party's Missouri sales or use tax return following the month in which it was determined that the materials were not used in the Work.
- **3.17.4** If it is determined that sales tax is owed by the Contractor on property and materials due to the failure of the Owner to revise the certificate expiration date to cover the applicable date of purchase, Owner shall be liable for the tax owed.
- 3.17.5 The Owner shall not be responsible for any tax liability due to Contractor's neglect to make timely orders, payments, etc. or Contractor's misuse of the Project Tax Exemption Certificate. Contractor represents that the Project Tax Exemption Certificate shall be used in accordance with RSMo § 144.062 and the terms of the Project Tax Exemption

Certificate. Contractor shall indemnify the Owner for any loss or expense, including but not limited to, reasonable attorneys' fees, arising out of Contractor's use of the Project Tax Exemption Certificate.

3.18 Contractor's Construction Schedules

- **3.18.1** The Contractor, within fifteen (15) days after the issuance of the Notice to Proceed, shall prepare and submit for the Owner's and Architect's information Contractor's construction schedule for the Work and shall set forth interim dates for completion of various components of the Work and Work Milestone Dates as defined herein. The schedule shall not exceed time limits current under the Contract Documents, shall be revised on a monthly basis or as requested by the Owner's Representative as required by the conditions of the Work, and shall provide for expeditious and practicable execution of the Work. The Contractor shall conform to the most recent schedule.
- **3.18.2** The construction schedule shall be in a detailed format satisfactory to the Owner's Representative and the Architect and in accordance with the detailed schedule requirements set forth in this document and the Special Conditions. If the Owner's Representative or Architect has a reasonable objection to the schedule submitted by Contractor, the construction schedule shall be promptly revised by the Contractor. The Contractor shall monitor the progress of the Work for conformance with the requirements of the construction schedule and shall promptly advise the Owner of any delays or potential delays.
- **3.18.3** As time is of the essence to this contract, the University expects that the Contractor will take all necessary steps to ensure that the project construction schedule shall be prepared in accordance with the specific requirements of the Special Conditions to this contract. At a minimum, contractor shall comply with the following:
- .1 The schedule shall be prepared using Primavera P3, Oracle P6, Microsoft Project or other software acceptable to the Owner's Representative.
- .2 The schedule shall be prepared and maintained in CPM format, in accordance with Construction CPM Scheduling, published by the Associated General Contractors of American (AGC).
- .3 Prior to submittal to the Owner's Representative for review, Contractor shall obtain full buy-in to the schedule from all major subcontractors, in writing if so, requested by Owner's Representative.
- .4 Schedule shall be updated, in accordance with Construction CPM Scheduling, published by the AGC, on a monthly basis at minimum, prior to, and submitted with, the monthly pay application or as requested by the Owner's Representative.
- .5 Along with the update the Contractor shall submit a narrative report addressing all changes, delays and impacts, including weather to the schedule

- during the last month, and explain how the end date has been impacted by same.
- .6 The submission of the updated schedule certifies that all delays and impacts that have occurred on or to the project during the previous month have been factored into the update and are fully integrated into the schedule and the projected completion date.

Failure to comply with any of these requirements will be considered a material breach of this contract. See Special Conditions for detailed scheduling requirements.

3.18.4 In the event the Owner's Representative or Architect determines that the performance of the Work, as of a Milestone Date, has not progressed or reached the level of completion required by the Contract Documents, the Owner shall have the right to order the Contractor to take corrective measures necessary to expedite the progress of construction, including, without limitation, (1) working additional shifts or overtime, (2) supplying additional manpower, equipment, facilities, (3) expediting delivery of materials, and (4) other similar measures (hereinafter referred to collectively as Extraordinary Measures). Such Extraordinary Measures shall continue until the progress of the Work complies with the stage of completion required by the Contract Documents. The Owner's right to require Extraordinary Measures is solely for the purpose of ensuring the Contractor's compliance with the construction schedule. The Contractor shall not be entitled to an adjustment in the Contract Sum concerning Extraordinary Measures required by the Owner under or pursuant to this Paragraph 3.17.3. The Owner may exercise the rights furnished the Owner under or pursuant to this Paragraph 3.17.3 as frequently as the Owner deems necessary to ensure that the Contractor's performance of the Work will comply with any Milestone Date or completion date set forth in the Contract Documents.

ARTICLE 4 ADMINISTRATION OF THE CONTRACT

4.1 Rights of the Owner

- **4.1.1** The Owner's Representative will administer the Construction Contract. The Architect will assist the Owner's Representative with the administration of the Contract as indicated in these Contract Documents.
- **4.1.2** If, in the judgment of the Owner's Representative, it becomes necessary to accelerate the work, the Contractor, when directed by the Owner's Representative in writing, shall cease work at any point and transfer its workers to such point or points and execute such portions of the work as may be required to enable others to hasten and properly engage and carry out the work, all as directed by the Owner's Representative. The additional cost of accelerating the work, if any, will be borne by the Owner, unless the Contractor's work progress is behind schedule as shown on the most recent progress schedule.

- **4.1.3** If the Contractor refuses, for any reason, to proceed with what the Owner believes to be contract work, the Owner may issue a Construction Directive, directing the Contractor to proceed. Contractor shall be obligated to promptly proceed with this work. If Contractor feels that it is entitled to additional compensation for this work, it may file a claim for additional compensation and/or time, in accordance with 4.4 of this Document.
- **4.1.4** The Owner's Representative, may, by written notice, require a Contractor to remove from involvement with the Work, any of Contractor's personnel or the personnel of its Subcontractors of any tier whom the Owner's Representative may deem abusive, incompetent, careless, or a hindrance to proper and timely execution of the Work. The Contractor shall comply with such notice promptly, but without detriment to the Work or its progress.
- **4.1.5** The Owner's Representative will schedule Work status meetings that shall be attended by representatives of the Contractor and appropriate Subcontractors of any tier. Material suppliers shall attend status meetings if required by the Owner's Representative. These meetings shall include preconstruction meetings.
- **4.1.6** The Owner does not allow smoking on university property.

4.2 Rights of the Architect

4.2.1 The Architect will interpret requirements of the Contract Documents with respect to the quality, quantity, and other technical requirements of the Work itself within a reasonable time after written request of the Contractor. Contractor shall provide Owner's Representative a copy of such written request.

4.3 Review of the Work

- **4.3.1** The Architect, the Owner's Representative, and the Owner's Authorized Agent shall, at all times, have access to the Work; and the Contractor shall provide proper and safe facilities for such access.
- **4.3.2** The Owner's Representative shall have authority to reject Work that does not strictly comply with the requirements of the Contract Documents. Whenever the Owner's Representative considers it necessary or advisable for implementation of the intent of the Contract Documents, Owner's Representative shall have the authority to require additional inspection or testing of the Work, whether or not such Work is fabricated, installed, or completed.
- **4.3.3** The fact that the Architect or the Owner's Representative observed, or failed to observe, faulty Work, or Work done which is not in accordance with the Contract Documents, regardless of whether or not the Owner has released final payment, shall not relieve the

Contractor from responsibility for all damages and additional costs of the Owner as a result of defective or faulty Work.

4.4 Claims

- **4.4.1** A Claim is a demand or assertion by Contractor seeking, as a matter of right, adjustment or interpretation of Contract terms, payment of money, extension of time or any other relief with respect to the terms of the Contract. The term "Claim(s)" also includes demands and assertions of Contractor arising out of or relating to the Contract Documents, including Claims based upon breach of contract, mistake, misrepresentation, or other cause for Contract Modification or recision. Claims must be made by written notice. Contractor shall have the responsibility to substantiate Claims.
- Claims by Contractor must be made promptly, and no later than within fourteen (14) days after occurrence of the event giving rise to such Claim. Claims must be made by written notice. Such notice shall include a detailed statement setting forth all reasons for the Claim and the amount of additional money and additional time claimed by Contractor. The notice of Claims shall also strictly comply with all other provisions of the Contract Documents. Contractor shall not be entitled to rely upon any grounds or basis for additional money on additional time not specifically set forth in the notice of Claim. All Claims not made in the manner provided herein shall be deemed waived and of no effect. Contractor shall furnish the Owner and Architect such timely written notice of any Claim provided for herein, including, without limitation, those in connection with alleged concealed or unknown conditions, and shall cooperate with the Owner and Architect in any effort to mitigate the alleged or potential damages, delay or other adverse consequences arising out of the condition which is the cause of such a Claim.
- **4.4.3** Pending final resolution of a Claim, the Contractor shall proceed diligently with performance of the Contract and the Owner shall continue to make payments that are not in dispute in accordance with the Contract Documents.

4.5 Claims for Concealed or Unknown Conditions

4.5.1 If conditions are encountered at the site which are (1) subsurface or otherwise concealed physical conditions which differ materially from those indicated in the Contract Documents, or (2) unknown physical conditions of an unusual nature, which differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents, then notice by the Contractor shall be given to the Owner's Representative promptly before conditions are disturbed, and in no event later than three (3) days after first observance of the conditions. The Owner's Representative will promptly investigate such conditions. If such conditions differ materially, as provided for above and cause an increase or decrease in the Contractor's cost, or time, required for performance of the Work, an equitable adjustment in the Contract sum or Contract Time, or both, shall be made, subject to the provisions and restrictions set for herein. If the Owner's Representative determines that the conditions at the site are not materially different from those indicated in the Contract Documents, and that no change in the terms of the Contract is justified, the Owner's Representative will so notify the Contractor in writing. If the Contractor disputes the finding of the Owner's Representative that no change in the terms of the Contract terms is justified, Contractor shall proceed with the Work, taking whatever steps are necessary to overcome or correct such conditions so that Contractor can proceed in a timely manner. The Contractor may have the right to file a Claim in accordance with the Contract Documents.

4.5.2 It is expressly agreed that no adjustment in the Contract Time or Contract Sum shall be permitted, however, in connection with a concealed or unknown condition which does not differ materially from those conditions disclosed or which reasonably should have been disclosed by the Contractor's (1) prior inspections, tests, reviews and preconstruction investigations for the Project, or (2) inspections, tests, reviews and preconstruction inspections which the Contractor had the opportunity to make or should have performed in connection with the Project.

4.6 Claim for Additional Cost

4.6.1 If the Contractor makes a Claim for an increase in the Contract Sum, written notice as provided herein shall be given before proceeding to execute the Work. In addition to all other requirements for notice of a Claim, said notice shall detail and itemize the amount of all Claims and shall contain sufficient data to permit evaluation of same by Owner.

4.7 Claims for Additional Time

- **4.7.1** If the Contractor makes a Claim for an increase in the Contract Time, written notice as provided herein shall be given. In addition to other requirements for notice of a Claim, Contractor shall include an estimate of the probable effect of delay upon the progress of the Work, utilizing a CPM Time Impact Schedule Analysis, (TIA) as defined in the AGC Scheduling Manual. In the case of a continuing delay, only one Claim is necessary.
- .1 Time extensions will be considered for excusable delays only. That is, delays that are beyond the control and/or contractual responsibility of the Contractor.
- **4.7.2** If weather days are the basis for a Claim for additional time, such Claim shall be documented by the Contractor by data acceptable to the Owner's Representative substantiating that weather conditions for the period of time in question, had an adverse effect on the critical path of the scheduled construction. Weather days shall be defined as days on which critical path work cannot proceed due to weather conditions (including but not limited to rain, snow, etc.), in excess of the number of days shown on the Anticipated Weather Day schedule in the Special Conditions. To be considered a weather day,

at least four working hours must be lost due to the weather conditions on a critical path scope item for that day.-Weather days and Anticipated weather days listed in the Special Conditions shall only apply to Monday through Friday. A weather day claim cannot be made for Saturdays, Sundays, New Year's Day, Martin Luther King Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the day after Thanksgiving Day and Christmas Day, unless that specific day was approved in writing for work by the Owner's Representative.

- .1 The Contractor must have fulfilled its contract obligations with respect to temporary facilities and protection of its work, and worker protection for hot and cold weather per OSHA guidelines.
- .2 If the contract obligations have been satisfied, the Owner will review requests for non-compensable time extensions for critical path activities as follows:
 - If the Contractor cannot work on a critical path activity due to adverse weather, after implementing all reasonable temporary weather protection, the Contractor will so notify the Owner's Representative. Each week, the Contractor will notify the Owner's Representative of the number of adverse weather days that it believes it has experienced in the previous week. As provided in the contract, until such time as the weather days acknowledged by the Owner's Representative exceed the number of days of adverse weather contemplated in the Special Conditions, no request for extension of the contract completion time will be considered.
 - .2.2 If the Contractor has accumulated in excess of the number of adverse weather days contemplated in the Special Conditions due to the stoppage of work on critical path activities due to adverse weather, the Owner will consider a time extension request from the Contractor that is submitted in accordance with the contract requirements. The Owner will provide a change order extending the time for contract completion or direct acceleration of the work in accordance with the contract terms and conditions to recover the time lost due to adverse weather in excess of the number of adverse weather working days contemplated in the Special Conditions.
- **4.7.3** A Force Majeure event or circumstance shall not be the basis of a claim by the Contractor seeking an adjustment in the Contract amount for costs or expenses of any type. With the exception of weather delays which are administered under this Article 4, and not withstanding other requirements of the Contract, all Force Majeure events resulting in a delay

to the critical path of the project shall be administered as provided in Article 8.

4.7.4 The Owner will consider and evaluate requests for time extensions due to changes or other events beyond the control of the Contractor on a monthly basis only, with the submission of the Contractor's updated schedule, in conjunction with the monthly application for payment.

4.8 Resolution of Claims and Disputes

- **4.8.1** The Owner's Representative will review Claims and take one or more of the following preliminary actions within ten days of receipt of a Claim: (1) request additional supporting data from the Contractor, (2) reject the Claim in whole or in part, (3) approve the Claim, or (4) suggest a compromise.
- **4.8.2** If a Claim has not been resolved, the Contractor shall, within ten days after the Owner's Representative's preliminary response, take one or more of the following actions: (1) submit additional supporting data requested, (2) modify the initial Claim, or (3) notify the Owner's Representative that the initial Claim stands.
- **4.8.3** If a Claim has not been resolved after consideration of the foregoing and of further information presented by the Contractor, the Contractor has the right to seek administrative review as set forth in Section 4.9. However, Owner's Representative's decisions on matters relating to aesthetics will be final.

4.9 Administrative Review

- **4.9.1** Claims not resolved pursuant to the procedures set forth in the Contract Documents except with respect to Owner's Representative's decision on matters relating to aesthetic effect, and except for claims which have been waived by the making or acceptance of final payment, or the Contractor's acceptance of payments in full for changes in work may be submitted to administrative review as provided in this section. All requests for administrative review shall be made in writing.
- Upon written request from the Contractor, the Owner's Review Administrator authorized by the Campus Contracting Officer will convene a review meeting between the Contractor and Owner's Representative's within fifteen (15) days of receipt of such written request. The Contractor and Owner's Representative will be allowed to present written documentation with respect to the claim(s) before or during the meeting. The Contractor and Owner's Representative will be allowed to present the testimony of any knowledgeable person regarding the claim at the review meeting. The Owner's Review Administrator will issue a written summary of the review meeting and decision to resolve the Claim within fifteen (15) days. If the Contractor is in agreement with the decision the Contractor shall notify the Owner's Review Administrator in writing within five (5) days, and

appropriate documentation will be signed by the parties to resolve the Claim.

- 4.9.3 If the Contractor is not in agreement with the proposal of the Owner's Review Administrator as to the resolution of the claim, the Contractor may file a written appeal with the UM System Contracting Officer, [in care of the Director of Facilities Planning and Development, University of Missouri, 109 Old Alumni Centers, University of Missouri, Columbia, Missouri 65211] within fifteen (15) days after receipt of the Owner's Review Administrator's proposal. The UM System Contracting Officer will call a meeting of the Contractor, the Owner's Representative, and the Owner's Review Administrator by written notice, within thirty (30) days after receipt of the Contractor's written appeal. The Owner's Review Administrator shall provide the UM System Contracting Officer with a copy of the written decision and summary of the review meeting, the Contractor's corrections or comments regarding the summary of the review meeting, and any written documentation presented by the Contractor and the Owner's Representative at the initial review meeting. The parties may present further documentation and/or present the testimony of any knowledgeable person regarding the claim at the meeting called by the UM System Contracting Officer.
- The UM System Contracting Officer will issue a written decision to resolve the claim within fifteen (15) days after the meeting. If the Contractor is in agreement with the UM System Contracting Officer's proposal, the Contractor shall notify the UM System Contracting Officer in writing within five (5) days, and the Contractor and the Owner shall sign appropriate documents. The issuance of the UM System Contracting Officer's written proposal shall conclude the administrative review process even if the Contractor is not in agreement. However, proposals and any opinions expressed in such proposals issued under this section will not be binding on the Contractor nor will the decisions or any opinions expressed be admissible in any legal actions arising from the Claim and will not be deemed to remove any right or remedy of the Contractor as may otherwise exist by virtue of Contract Documents or law. Contractor and Owner agree that the Missouri Circuit Court for the County where the Work is located shall have exclusive jurisdiction to determine all issues between them. Contractor agrees not to file any complaint, petition, lawsuit or legal proceeding against Owner except with such Missouri Circuit Court.

ARTICLE 5 SUBCONTRACTORS

5.1 Award of Subcontracts

5.1.1 Pursuant to Article 9, the Contractor shall furnish the Owner and the Architect, in writing, with the name, and trade for each Subcontractor and the names of all persons or entities proposed as manufacturers of products, materials and equipment identified in the Contract Documents and where applicable, the name of the installing contractor. The

Owner's Representative will reply to the Contractor in writing if the Owner has reasonable objection to any such proposed person or entity. The Contractor shall not contract with a proposed person or entity to whom the Owner has made reasonable and timely objection.

- **5.1.2** The Contractor may request to change a subcontractor. Any such request shall be made in writing to the Owner's Representative. The Contractor shall not change a Subcontractor, person, or entity previously disclosed if the Owner makes reasonable objection to such change.
- **5.1.3** The Contractor shall be responsible to the Owner for acts, defaults, and omissions of its Subcontractors of any tier.

5.2 Subcontractual Relations

- 5.2.1 By appropriate agreement, written where legally required for validity, the Contractor shall require each Subcontractor of any tier, to the extent of the Work to be performed by the Subcontractor of any tier, to be bound to the Contractor by terms of the Contract Documents and to assume toward the Contractor all the obligations and responsibilities which the Contractor, by these Documents, assumes toward the Owner and the Architect. Each subcontract agreement of any tier shall preserve and protect the rights of the Owner and the Architect under the Contract Documents with respect to the Work to be performed by the Subcontractor of any tier so that subcontracting thereof will not prejudice such rights and shall allow to the Subcontractor of any tier, unless specifically provided otherwise in the subcontract agreement, the benefit of all rights, remedies, and redress against the Contractor that the Contractor, by the Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with its sub-subcontractors. The Contractor shall make available to each proposed Subcontractor of any tier, prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor of any tier shall be bound Subcontractors of any tier shall similarly make copies of applicable portions of such documents available to their respective proposed Subcontractors of any tier.
- 5.2.2 All agreements between the Contractor and a Subcontractor or supplier shall contain provisions whereby Subcontractor or supplier waives all rights against the Owner, contractor, Owner's representative, Architect and all other additional insureds for all losses and damages caused by, arising out of, or resulting from any of the perils covered by property or builders risk insurance coverage required of the Contractor in the Contract Documents. If Contractor fails to include said provisions in all subcontracts, Contractor shall indemnify, defend and hold all the above entities harmless in the event of any legal action by Subcontractor or supplier. If insureds on any such policies require separate waiver

forms to be signed by any Subcontractors of any tier or suppliers, Contractor shall obtain the same.

5.3 Contingent Assignment of Subcontract

5.3.1 No assignment by the Contractor of any amount or any part of the Contract or of the funds to be received thereunder will be recognized unless such assignment has had the written approval of the Owner, and the surety has been given due notice of such assignment and has furnished written consent hereto. In addition to the usual recitals in assignment Contracts, the following language must be set forth: "it is agreed that the funds to be paid to the assignee under this assignment are subject to performance by the Contractor of the contract and to claims and to liens for services rendered or materials supplied for the performance of the Work called for in said contract in favor of all persons, firms or corporations rendering such services or supplying such materials.

ARTICLE 6 SEPARATE CONTRACTS AND COOPERATION

- **6.1** The Owner reserves the right to let other contracts in connection with the Work.
- 6.2 It shall be the duty of each Contractor to whom Work may be awarded, as well as all Subcontractors of any tier employed by them, to communicate immediately with each other in order to schedule Work, locate storage facilities, etc., in a manner that will permit all Contractors to work in harmony in order that Work may be completed in the manner and within the time specified in the Contract Documents.
- **6.3** No Contractor shall delay another Contractor by neglecting to perform his work at the proper time. Each Contractor shall be required to coordinate his work with other Contractors to afford others reasonable opportunity for execution of their work. Any costs caused by defective, noncompliant, or ill-timed work, including actual damages and liquidated damages for delay, if applicable, shall be borne by the Contractor responsible therefor.
- 6.4 Each Contractor shall be responsible for damage to Owner's or other Contractor's property done by him or persons in his employ, through his or their fault or negligence. If any Contractor shall cause damage to any other Contractor, the Contractor causing such damage shall upon notice of any claim, settle with such Contractor.
- 6.5 The Contractor shall not claim from the Owner money damages or extra compensation under this Contract when delayed in initiating or completing his performance hereunder, when the delay is caused by labor disputes, acts of God, or the failure of any other Contractor to complete his performance under any Contract with the Owner, where any such cause is beyond the Owner's reasonable control.

- **6.6** Progress schedule of the Contractor for the Work shall be submitted to other Contractors as necessary to permit coordinating their progress schedules.
- **6.7** If Contractors or Subcontractors of any tier refuse to cooperate with the instructions and reasonable requests of other contractors performing work for the Owner under separate contract, in the overall coordinating of the Work, the Owner's Representative may take such appropriate action and issue such instructions as in his judgement may be required to avoid unnecessary and unwarranted delay.

ARTICLE 7 CHANGES IN THE WORK

7.1 CHANGE ORDERS

- **7.1.1** A change order is a written instrument prepared by the Owner and signed by the Owner and Contractor formalizing their agreement on the following:
- .1 a change in the Work
- .2 the amount of an adjustment, if any, in the Contract amount
- .3 an adjustment, if any, in the Contract time
- **7.1.2** The Owner may at any time, order additions, deletions, or revisions in the Work by a Change Order or a Construction Change Directive. Such Change Order or Construction Change Directive shall not invalidate the Contract and requires no notice to the surety. Upon receipt of any such document, or written authorization from the Owner's Representative directing the Contractor to proceed pending receipt of the document, Contractor shall promptly proceed with the Work involved in accordance with the terms set forth therein.
- **7.1.3** Until such time as the change order is formalized and signed by both the Owner and the Contractor it shall be considered a Change Order Request.
- **7.1.4** The amount of adjustment in the contract price for authorized Change Orders will be agreed upon before such Change Orders becomes effective and will be determined as follows:
- .1 By a lump sum proposal from the Contractor and the Subcontractors of any tier, including overhead and profit.
- .2 By a time and material basis with or without a specified maximum. The Contractor shall submit to the Owner's Representative itemized time and material sheets depicting labor, materials, equipment utilized in completing the Work on a daily basis for the Owner's Representative approval. If this pricing option is utilized, the Contractor may be required to submit weekly reports summarizing costs to

- date on time and material change orders not yet finalized.
- .3 By unit prices contained in the Contractor's original bid and incorporated in the Construction Contract or subsequently agreed upon. Such unit prices contained in the Contractor's original proposal are understood to include the Contractor's overhead and profit. If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are so changed in a proposed Change Order that application of such unit prices to quantities of the Work proposed will cause substantial inequity to the Owner or to the Contractor, the applicable unit prices shall be equitably adjusted.
- **7.1.5** The Contractor shall submit all fully documented change order requests with corresponding back-up documentation within the time requested by the Owner but no later than fourteen (14) working days following 1.) the Owner's request for change order pricing in the case of a lump sum; or 2.) the completion of unit price or time and material work.
- **7.1.6** The Contractor shall submit change order requests in sufficient detail to allow evaluation by the Owner. Such requests shall be fully itemized by units of labor, material and equipment and overhead and profit. Such breakdowns shall be itemized as follows:
- The Contractor's proposal shall include .1 Labor: breakdowns by labor, by trade, indicating number of hours and cost per hour for each Subcontractor as Such breakdowns shall only include applicable. employees in the direct employ of Contractor or Subcontractors in the performance of the Work. Such employees shall only include laborers at the site, mechanics, craftsmen and foremen. Payroll cost shall include base rate salaries and wages plus the cost of fringe benefits required by agreement or custom and social security contributions, unemployment, payroll taxes and workers' or workmen's compensation insurance and other customary and legally required taxes paid by the Contractor or Subcontractors. Any item or expense outside of these categories is not allowed. The expense of performing Work after regular working hours, on Saturdays, Sundays or legal holidays shall not be included in the above, unless approved in writing and in advance by Owner.
- .2 Material, supplies, consumables and equipment to be incorporated into the Work at actual invoice cost to the Contractor or Subcontractors; breakdowns showing all material, installed equipment and consumables fully itemized with number of units installed and cost per unit extended. Any singular item or items in aggregate greater than one thousand dollars (\$1,000) in cost shall be supported with supplier invoices at the request of the Owner's Representative. Normal hand tools are not compensable.
- .3 Equipment: Breakdown for required equipment shall itemize (at a minimum) delivery / pick-up charge, hourly

rate and hours used. Operator hours and rate shall not be included in the equipment breakdown. Contractor must use the most cost-effective equipment available in the area and should not exceed the rates listed in the Rental Rate Blue Book for Construction Equipment (Blue Book). Contractor shall submit documentation for the Blue Book to support the rate being requested.

7.2 Construction Change Directive

- **7.2.1** A construction change directive is a written order prepared and signed by the Owner, issued with supporting documents prepared by the Architect (if applicable), directing a change in the Work prior to agreement on adjustment of the Contract amount or Contract time, or both. A Construction Change Directive shall be used in the absence of complete agreement between the Owner and Contractor on the terms of a change order. If the Construction Change Directive allows an adjustment of the contract amount or time, such adjustment amount shall be based on one of the following methods:
- .1 A lump sum agreement, properly itemized and supported by substantiating documents of sufficient detail to allow evaluation.
- .2 By unit prices contained in the Contractor's original proposal and incorporated in the Construction Contract or subsequently agreed upon.
- .3 A method agreed to by both the Owner and the contractor with a mutually agreeable fee for overhead and profit.
- .4 In the absence of an agreement between the Owner and the Contractor on the method of establishing an adjustment of the contract amount, the Owner, with the assistance of the architect, shall determine the adjustment amount on the basis of expenditures by the Contractor for labor, materials, equipment, and other costs consistent with other provisions of the Contract. The contractor shall keep and submit to the Owner an itemized accounting of all cost components, either expended or saved, while performing the Work covered under the Construction Change Directive.
 - **7.2.2** Upon receipt of a Construction Change Directive, Contractor shall promptly proceed with the change in the Work involved and advise Owner of Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum, Contract Time, or both.
 - **7.2.3** A Construction Change Directive signed by Contractor indicates the agreement of the Contractor therewith, including adjustment in Contract Sum and Contract Time or the method for determining them. Such agreement shall be effective immediately and shall be recorded as a Change Order.

7.3 Overhead and Profit

- **7.3.1** Overhead and Profit on Change Orders shall be applied as follows:
- .1 The overhead and profit charged by the Contractor and Subcontractors shall be considered to include. but not limited to, job site office and clerical expense, normal hand tools, incidental job supervision, field supervision, payroll costs and other compensation for project manager, officers, general executives, principals, managers, estimators. attorneys, auditors, accountants, purchasing and contracting agents, expediters, timekeepers, and other personnel employed whether at the site or in principal or a branch office for general superintendent and administration of the Work.
- .2 The percentages for overhead and profit charged on Change Orders shall be negotiated and may vary according to the nature, extent, and complexity of the Work involved but in no case shall exceed the following:
 - 15% To the Contractor or the Subcontractor of any tier for Work performed with their respective forces or materials purchased
 - 5% To the Contractor on Work performed by other than his forces
 - 5% To first tier Subcontractor on Work performed by his Subcontractor
- .3 The Contractor will be allowed to add 2% for the cost of bonding and insurance to their cost of work. This 2% shall be allowed on the total cost of the added work, including overhead and profit.
- .4 Not more than three mark-ups, not to exceed individual maximums shown above, shall be allowed regardless of the number of tier subcontractors. Overhead and profit shall be shown separately for each subcontractor of any tier and the Contractor.
- .5 On proposals covering both increases and decreases in the amount of the Contract, the application of overhead and profit shall be on the net change in direct cost for the Contractor or Subcontractor of any tier performing the Work.
- .6 The percentages for overhead and profit credit to the Owner on Change Orders that are strictly decreases in the quantity of work or materials shall be negotiated and may vary according to the nature, extent, and complexity of the Work involved, but shall not be less than the following:

Overhead and Profit

- 7.5% Credit to the Owner from the Contractor or Subcontractor of any tier for Work performed with their respective forces or materials purchased
- 2.5% Credit to the Owner from the Contractor on Work performed by other than his forces
- 2.5% Credit to the Owner from the first tier Subcontractor on Work performed by his Subcontractor of any tier

7.4 Extended General Conditions

- **7.4.1** The Contractor acknowledges that the percentage mark-up allowed on change orders for overhead and profit cover the Contractor's cost of administering and executing the Work, inclusive of change orders that increase the contract time. Contractor further acknowledges that no compensation beyond the specified mark-up percentages for extended overhead shall be due or payable as a result of an increase in the Contract Time.
- **7.4.2** The Owner may reimburse the Contractor for extended overhead if an extension of the Contract Time is granted by the Owner, in accordance with Article 4.7.1 and the Owner determines that the extension of the Contract Time creates an inequitable condition for the Contractor. If these conditions are determined by the Owner to exist, the Contractor may be reimbursed by unit prices contained in the Contractor's original bid and incorporated in the Construction Contract or by unit prices subsequently agreed upon.
- **7.4.3** If unit prices are subsequently agreed upon, the Contractor's compensation shall be limited as follows:
- .1 For the portion of the direct payroll cost of the Contractor's project manager expended in completing the Work and the direct payroll cost of other onsite administrative staff not included in Article 7.3.1. Direct payroll cost shall include base rate salaries and wages plus the cost of fringe benefits required by agreement or custom and social security contributions, unemployment, payroll taxes and workers' or workmen's compensation insurance and other customary and legally required taxes paid by the Contractor;
- .2 Cost of Contractor's temporary office, including temporary office utilities expense;
- .3 Cost of temporary utilities required in the performance of the work;
- .4 Profit not to exceed 5% of the total extended overhead direct costs;
- **7.4.4** All costs not falling into one of these categories and costs of the Contractors staff not employed onsite are not allowed.

7.5 Emergency Work

7.5.1 If, during the course of the Work, the Owner has need to engage the Contractor in emergency work, whether related to the Work or not, the Contractor shall immediately proceed with the emergency work as directed by the Owner under the applicable provisions of the contract. In so doing, Contractor agrees that all provisions of the contract remain in full force and effect and the schedule for the Work is not impacted in any way unless explicitly agreed to in writing by the Owner.

ARTICLE 8 TIME

8.1 Progress and Completion

- **8.1.1** Contractor acknowledges and agrees that time is of the essence of this Contract
- **8.1.2** Contract Time is the period of time set forth in the Contract for Construction required for Substantial Completion and Final Completion of the entire Work or portions of the Work as defined in the Contract Documents. Time limits stated in the Contract Documents are of the essence of the Contract. The Contract Time may only be changed by a Change Order. By executing the Contract, the Contractor confirms that the Contract Time is a sufficient period for performing the Work in its entirety.
- **8.1.3** The Contractor shall not knowingly, except by agreement or instruction of the Owner in writing, prematurely commence operations on the site or elsewhere prior to the effective date of insurance and bonds required by Article 11 to be furnished by the Contractor.
- **8.1.4** The Contractor shall proceed expeditiously and diligently with adequate forces and shall achieve Substantial Completion and Final Completion within the time specified in the Contract Documents.

8.2 Delay in Completion

- **8.2.1** The Contractor shall be liable for all of the Owner's damages for delay in achieving Substantial Completion and/or Final Completion of the entire Work or portions of Work as set forth in the Contract Documents within the Contract Time unless liquidated damages are specifically provided for in the Contract Documents. If liquidated damages are specifically provided for in the Contract for Construction, Contractor shall be liable for such liquidated damages as set forth in Paragraph 8.3
- 8.2.2 All time limits stated in the Contract are of the essence of the Contract. However, if the Contractor is delayed at any time in the progress of the Work by any act or neglect of the Owner or by the Owner's Representative, by changes ordered in the Work, Force Majeure including but not limited to war, armed conflict, riot, civil commotion or disorder, act of terrorism or sabotage; epidemic, pandemic, outbreaks of infectious disease or any other public health crisis, including quarantine or other employee restrictions, compliance with any law or governmental order, rule, regulation or direction, curfew restriction, act of God or natural disaster such as earthquake, volcanic activity, landslide, tidal wave, tsunami, flood, damage or destruction by lightning, drought; explosion, fire, destruction of machines, equipment, prolonged break-down of transport, telecommunication or electric current; general labor disturbance such as but not limited to boycott, strike and lock-out, occupation of factories and premises, or any other causes beyond the Contractor's reasonable control which the Owner's Representative determines may justify

delay then, upon submission of the Time Impact Schedule Analysis (TIA) justifying the delay called out in Section 4.7 of these General Conditions, the Contract Time may be extended for a reasonable time to the extent such delay will prevent Contractor from achieving Substantial Completion and/or Final Completion within the Contract Time and if performance of the Work is not, was not or would not have been delayed by any other cause for which the Contractor is not entitled to an extension of the Contract Time under the Contract Documents. It shall be a condition precedent to any adjustment of the Contract Time that Contractor provide the Owner's Representative with written notice of the cause of delay within seven (7) days from the occurrence of the event or condition which caused the claimed delay. If a Force Majeure is approved by the Owner as the basis for a delay claim, an adjustment in the contract time to the extent the Force Majeure impacts the schedule is the only remedy. No increase in the contract sum for any reason shall be allowed due to a Force Majeure.

- **8.2.3** The Contractor further acknowledges and agrees that adjustments in the Contract Time will be permitted for a delay only to the extent such delay (1) is not caused, or could not have been anticipated, by the Contractor, (2) could not be limited or avoided by the Contractor's timely notice to the Owner of the delay, (3) prevents Contractor from completing its Work by the Contract Time, and (4) is of a duration not less than one (1) day. Delays attributable to and within the control of a Subcontractor or supplier shall not justify an extension of the Contract Time.
- 8.2.4 Notwithstanding anything to the contrary in the Contract Documents, except as otherwise noted in these General Conditions, an extension in the Contract Time, to the extent permitted under this Article, shall be the sole remedy of the Contractor for any (1) delay in the commencement, prosecution or completion of the Work, (2) hindrance or obstruction in the performance of the Work, (3) loss of productivity, or (4) other claims due to or caused by any events beyond the control of both the Owner and Contractor defined herein as Force Majeure. In no event shall the Contractor be entitled to any compensation or recovery of any damages or any portion of damages resulting from delays caused by or within the control of Contractor or by acts or omissions of Contractor or its Subcontractors of any tier or delays beyond the control of both Owner and Contractor. If the Contractor contends that delay, hindrance, obstruction or other adverse condition results from acts or omissions of the Owner, the Owner's Representative or the Architect, Contractor shall provide written notice to the Owner within seven (7) calendar days of the event giving rise to such claim. Contractor shall only be entitled to an adjustment in the Contract Sum to the extent that such acts or omissions continue after the Contractor's written notice to the Owner of such acts or omissions, but in no case shall Force Majeure be the basis of an increase in the Contract sum. The Owner's exercise of any of its rights or remedies under the Contract

Documents (including, without limitation, ordering changes in the Work, or directing suspension, rescheduling or correction of the Work) regardless of the extent or frequency of the Owner's exercise of such rights or remedies, shall not be the basis of any Claim for an increase in the Contract Sum or Contract Time. In the event Contractor is entitled to an adjustment in the Contract Sum for any delay, hindrance, obstruction or other adverse condition caused by the acts or omissions of the Owner, the Owner's Representative or the Architect, Contractor shall only be entitled to its actual direct costs caused thereby and Contractor shall not be entitled to and waives any right to special, indirect, or consequential damages including loss of profits, loss of savings or revenues, loss of anticipated profits, labor inefficiencies, idle equipment, home office overhead, and similar type of damages.

8.2.5 If the Contractor submits a progress report or any construction schedule indicating, or otherwise expressing an intention to achieve completion of the Work prior to any completion date required by the Contract Documents or expiration of the Contract Time, no liability of the Owner to the Contractor for any failure of the Contractor to so complete the Work shall be created or implied. Further, the Contractor acknowledges and agrees that even if Contractor intends or is able to complete the Work prior to the Contract Time, it shall assert no Claim and the Owner shall not be liable to Contractor for any failure of the Contractor, regardless of the cause of the failure, to complete the Work prior to the Contract Time.

8.3 Liquidated Damages

- **8.3.1** If Liquidated Damages are prescribed on the Bid Form and Special Conditions in the Contract Documents, the Owner may deduct from the Contract Sum and retain as Liquidated Damages, and not as penalty or forfeiture, the sum stipulated in the Contract Documents for each calendar day after the date specified for completion of the Work that the entire Work is not substantially complete and/or finally complete.
- **8.3.2** The Owner's Representative shall establish the date of Substantial completion and the date of Final Completion of the Work which shall be conclusive and binding on the Owner and Contractor for the purpose of determining whether or not Liquidated Damages shall be assessed under terms hereof and the sum total amount due.
- **8.3.3** Liquidated Damages or any matter related thereto shall not relieve the Contractor or his surety of any responsibility or obligation under this Contract.

ARTICLE 9 PAYMENTS AND COMPLETION

9.1 Commencement, Prosecution, and Completion

9.1.1 The Contractor shall commence Work within five (5) days upon the date of a "Notice to Proceed" from the Owner or the date fixed in the Notice to Proceed. Contractor shall prosecute the Work with faithfulness and diligence, and the

Contractor shall complete the Work within the Contract Time set forth in the Contract Documents.

- **9.1.2** The Owner will prepare and forward three (3) copies of the Contract and Performance Bond to the bidder to whom the contract for the Work is awarded and such bidder shall return two (2) properly executed prescribed copies of the Contract and Bond to the Owner.
- 9.1.3 The construction period, when specified in consecutive calendar days, shall begin when the Contractor receives notice requesting the instruments listed in below. Before the Owner will issue Notice to Proceed to permit the Contractor to begin Work, the Owner shall have received the following instruments, properly executed as described in the Contract Documents. The documents below shall have been received by the Owner within fifteen (15) days after receipt of request for documents:
- .1 Contract
- .2 Bond (See Article 11)
- .3 Insurance (See Article 11)
- .4 List of Subcontractors of any tier
- .5 Affirmative Action Plan (see Article 13.4)
- **9.1.4** In the event Contractor fails to provide Owner such documents, Contractor may not enter upon the site of the Work until such documents are provided. The date the Contractor is required to commence and complete the Work shall not be affected by the Owner denying Contractor access to the site as a result of Contractor's failure to provide such documents and Contractor shall not be entitled to an adjustment of the Contract Time or Contract sum as a result of its failure to comply with the provisions of this Paragraph
- 9.1.5 Contracts executed by partnerships shall be signed by all general partners of the partnership. Contracts signed by corporations shall be signed by the President or Vice President and the Secretary or Assistant Secretary. In case the Assistant Secretary or Vice President signs, it shall be so indicated by writing the word "Asst." or "Vice" in front of the words "Secretary" and "President". The corporate seal of the corporation shall be affixed. For all other types of entities, the Contractor and the person signing the Contract on behalf of Contractor represent and warrant that the person signing the Contract has the legal authority to bind Contractor to the Contract.
- 9.1.6 Any successful bidder which is a corporation organized in a state other than Missouri or any bidder doing business in the State of Missouri under a fictitious name shall furnish, at no cost to the Owner, no later than the time at which the executed Contract for Construction, the Payment Bond, and the Performance Bond are returned, a properly certified copy of its current Certificate of Authority and License to do business in the State of Missouri. No contract will be executed by the

Owner until such certificate is furnished by the bidder, unless there already is on file with the Owner a current certificate, in which event, no additional certificate will be required during the period of time for which such current certificate remains in effect.

- **9.1.7** Within fifteen (15) calendar days of the issuance of a Notice to Proceed, the Contractor shall submit one (1) signed copy of the following instruments. No payment will be processed until all of these instruments are received and approved by the Owner's Representative.
- .1 Reproducible progress and payment schedule
- .2 Contractor's Schedule of Values
- .3 List of material suppliers
- .4 Itemized breakdown of all labor rates for each classification. Overhead and profit shall not be included. Payroll cost shall include base rate salaries and wages plus the cost of fringe benefits required by agreement or custom and social security contributions, unemployment, payroll taxes and workers' or workmen's compensation insurance and other customary and legally required taxes paid by the Contractor or Subcontractors. Any item or expense outside of these categories is not allowed. The expense of performing Work after regular working hours, on Saturdays, Sundays or legal holidays shall not be included in the above, unless approved in writing and in advance by Owner.
- .5 Itemized breakdown of anticipated equipment rates (breakout operator rate). Overhead and profit shall not be included. Breakdown for required equipment shall itemize (at a minimum) delivery/ pick-up charge, hourly rate and hours used. Operator hours and rate shall not be included in the equipment breakdown. Contractor must use the most cost-effective equipment available in the area and should not exceed the rates listed in the Rental Rate Blue Book for Construction Equipment (Blue Book). Contractor shall submit documentation for the Blue Book to support the rate being requested.
- **9.1.8** The Contractor shall be paid electronically using the Owner's web-based payment program with a direct electronic transfer from the Owner's account into the Contractor's account. The Contractor must submit the following information to the Owner's Representative:
- .1 Bank Transit Number for the Contractor's bank into which the electronic deposit will be made.
- .2 Bank Account Number for the Contractor's account into which the electronic deposit will be made.
- .3 Contractor's E-Mail address so that formal notification of the deposit by the Owner can be provided.

9.2 Contract Sum

9.2.1 The Owner shall compensate Contractor for all Work described herein, and in the Contract Documents the Contract

Sum set forth in the Contract for Construction, subject to additions and deletions as provided hereunder.

9.3 Schedule of Values

- **9.3.1** Within fifteen (15) days after receipt of the Notice to Proceed, the Contractor shall submit to the Owner's Representative a schedule of values allocated to various portions of the Work, prepared in such form and supported by such data to substantiate its accuracy as the Owner's Representative may require. This schedule, unless objected to by the Owner's Representative, shall be used as a basis for reviewing the Contractor's Applications for Payment. The values set forth in such schedule may, at the Owner's option be used in any manner as fixing a basis for additions to or deletions from the Contract Sum.
- **9.3.2** The progress and payment schedule of values shall show the following:
- .1 Enough detail as necessary to adequately evaluate the actual percent complete of any line item on a monthly basis, as determined by the Owner's Representative.
- .2 Line items, when being performed by a subcontractor or material supplier, shall correlate directly back to the subcontract or purchase order amount if requested by the Owner's Representative.

9.4 Applications for Payment

- **9.4.1** The Contractor shall submit monthly to the Owner's Representative and the Architect an itemized Application for Payment for operations completed in accordance with the Schedule of Values. Such application shall be supported by such data substantiating the Contractor's right to payment as the Owner's Representative or Architect may require, such as copies of requisitions from Subcontractors and material suppliers, and reflecting retainage as provided for herein.
- **9.4.2** Such applications shall not include requests for payment of amounts the Contractor does not intend to pay to a Subcontractor or material supplier
- **9.4.3** Progress payments shall be made on account of materials and equipment delivered to the site and incorporated in the Work. No payments will be made for materials and equipment stored at the Project site but not yet incorporated into the Work except as provided in Paragraph 9.4.4.
- **9.4.4** If approved in writing and in advance by Owner, progress payments may be made on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. Owner may in its sole discretion refuse to grant approval for payments for materials and equipment stored at the Project site but not yet incorporated in the Work. Any approval by Owner for payment for materials and equipment delivered and suitably stored at the site, or stored offsite as noted below,

for subsequent incorporation in the Work shall be conditioned upon Contractor's demonstrating that such materials and equipment are adequately protected from weather, damage, vandalism and theft and that such materials and equipment have been inventoried and stored in accordance with procedures established by or approved by the Owner. Nothing in this clause shall imply or create any liability on the part of the Owner for the Contractor's inventory and storage procedures or for any loss or damage to material, equipment or supplies stored on the site, whether incorporated into the work or not. In the event any such loss or damage occurs, the Contractor remains solely responsible for all costs associated with replacement of the affected materials, supplies and equipment including labor and incidental costs, and shall have no claim against the Owner for such loss.

No allowance shall be made in the project pay requests for materials not delivered to the site of the work and incorporated into the work, except as noted below. For the purposes of this Article, Offsite is defined as any location not owned or leased by the Owner. Contractor shall submit a list of materials that they are requesting payment for offsite storage within 60 days of Notice to Proceed.

- 1 Items considered to be major items of considerable magnitude, if suitably stored, may be allowed in project pay requests on the basis of ninety percent (90%) of invoices
- .2 Determination of acceptable "major items of considerable magnitude" and "suitably stored" shall be made by the Owner's Representative.
- .3 Aggregate quantities of materials not considered unique to this project will not be considered for offsite storage payment.
- .4 Contractor shall submit to the Owner's Representative a list of the material for which application for payment for offsite storage is anticipated no less than forty-five days prior to the submission of the applicable pay request. The list shall include a material description, applicable division, quantity, and discounts offered to the Owner for early payment. Contractor shall also submit the location the material will be stored and the method of protection
- .5 The storage facility shall be subject to approval by the Owner's representative, shall be located within an acceptable distance of the project sites as established by the Owner's Representative and all materials for the Owner's project must be stored separately from all other items within the storage facility and shall be labeled and stored in the name of The Curators of the University of Missouri.
- .6 The Owner's representative shall be provided a minimum of two weeks' notice to visit the storage facility and inspect the stored material prior to submission of the pay request.
- .7 Upon favorable inspection by the Owner's Representative, the Contractor shall, at the Owner's option, submit a Bill of Sale and Bailment Agreement on forms provided by the Owner's

- Representative, transferring title of the material or equipment to The Curators of the University of Missouri.
- **.8** An invoice provided by the supplier shall be included with the applicable pay request.
- .9 The contractor shall remain fully responsible for all items, until acceptance of the project by the Owner.
- .10 The contractor shall reimburse all costs incurred by the Owner in inspecting and verifying all material stored offsite, including mileage, airfare, meals, lodging and time, charged at a reasonable hourly rate.
- .11 The Contractor shall furnish and maintain insurance covering the replacement cost of the material stored offsite against all losses and shall furnish proof of coverage with the application for payment for material stored offsite.
- .12 The Contractor is responsible for all costs related to storage and handling of material stored offsite unless otherwise directed by the Owner's Representative.
- **9.4.5** The Application for Payment shall constitute a representation by the Contractor to the Owner that the Work has progressed to the point indicated; the quality of the Work covered by the Application for Payment is in accordance with the Contract Documents; and the Contractor is entitled to payment in the amount requested.
- 9.4.6 The Contractor will be reimbursed for ninety-five percent (95%) of the value of all labor furnished and material installed and computed in the same manner, less all previous payments made. On projects where a bond is not required, the contractor will be reimbursed for ninety percent (90%) of the value of all labor furnished and material installed and computed in the same manner, less all previous payments made

9.5 Approval for Payment

9.5.1 The Owner's Representative will, within fifteen (15) days after receipt of the Contractor's Application for Payment, either approve Contractor's Application for Payment for such amount as the Owner's Representative determines is properly due or notify the Contractor of the Owner's Representative's reasons for withholding certification in whole or in part as provided in Section 9.6.

9.6 Decisions to Withhold Approval

9.6.1 The Owner's Representative may decide not to certify payment and may withhold approval in whole or in part, to the extent reasonably necessary to protect the Owner. If the Owner's Representative is unable to approve payment in the amount of the Application, the Owner's Representative will notify the Contractor as provided in Paragraph 9.5.1. If the Contractor and Owner's Representative cannot agree on a revised amount, the

Owner's Representative will promptly issue approval for payment for the amount for which the Owner's Representative is able to determine is due Contractor. The Owner's Representative may also decide not to approve payment or, because of subsequently discovered evidence or subsequent observations, may nullify the whole or a part of approval for payment previously issued, to such extent as may be necessary in the Owner's Representative opinion to protect the Owner from loss because of:

- .1 defective or non-compliant Work not remedied, or damage to completed Work;
- .2 failure to supply sufficient skilled workers or suitable materials:
- .3 third party claims filed or reasonable evidence indicating probable filing of such claims;
- .4 failure of the Contractor to make payments properly to Subcontractors or for labor, materials or equipment, Owner may, at its sole option issue joint checks to subcontractors who have presented evidence that it has not been paid in accordance with the Contract;
- .5 reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum:
- **.6** damage to the Owner or another contractor;
- .7 reasonable evidence that the Work will not be completed within the Contract Time or an unsatisfactory rate of progress made by Contractor;
- **.8** Contractor's failure to comply with applicable Laws;
- .9 Contractor's or Subcontractor's failure to comply with contract Prevailing Wage requirements; or
- .10 Contractor's failure to carry out the Work in strict accordance with the Contract Documents.
- **9.6.2** When the above reasons for withholding approval are removed, approval will be made for amounts previously withheld.

9.7 Progress Payments

- **9.7.1** Based upon Applications for Payment submitted to the Owner by the Contractor and approvals issued by the Owner's Representative, the Owner shall make progress payments on account of the Contract Sum to the Contractor as provided below and elsewhere in the Contract Documents.
- **9.7.2** The period covered by each Application for Payment shall be one (1) calendar month.
- **9.7.3** The Owner shall make payment to Contractor for amounts due and approved by Owner's Representative not later than thirty (30) days after the Owner approves a properly detailed Application for Payment which is in compliance with the Contract Documents. The Owner shall not have the obligation to process or pay such Application for Payment until it receives an Application for Payment satisfying such requirements.
- **9.7.4** Based on the Schedule of Values submitted by Contractor, Applications for Payment submitted by Contractor

shall indicate the actual percentage of completion of each portion of Contractor's Work as of the end of the period covered by the Application for Payment.

- 9.7.5 The Contractor shall promptly pay each Subcontractor and Supplier, upon receipt of payment from the Owner, out of the amount paid to the Contractor on account of such Subcontractor's or supplier's portion of the Work, the amount to which said Subcontractor or supplier is entitled, reflecting percentages actually retained from payments to the Contractor on account of each Subcontractor's or supplier's portion of the Work, in full compliance with state statute. The Contractor shall, by appropriate agreement with each Subcontractor or supplier, require each Subcontractor or supplier to make payments to Sub-subcontractors in similar manner.
- **9.7.6** Neither the Owner nor Architect shall have an obligation to pay or to see to the payment of money to a Subcontractor of any tier nor a laborer or employee of Contractor except to the extent required by law. Retainage provided for by the Contract Documents are to be retained and held for the sole protection of Owner, and no other person, firm or corporation shall have any claim or right whatsoever thereto.
- **9.7.7** An approval for payment by Owner's Representative, a progress payment, or partial or entire use or occupancy of the Project by the Owner shall not constitute acceptance of Work not in accordance with the Contract Documents.

9.8 Failure of Payment

9.8.1 If the Owner is entitled to reimbursement or payment from the Contractor under or pursuant to the Contract Documents, such payment by Contractor shall be made promptly upon demand by the Owner. Notwithstanding anything contained in the Contract Documents to the contrary, if the Contractor fails to promptly make any payment due the Owner, or the Owner incurs any costs and expenses to cure any default of the Contractor or to correct defective Work, the Owner shall have an absolute right to offset such amount against the Contract Sum and may, in the Owner's sole discretion, elect either to: (1) deduct an amount equal to that to which the Owner is entitled from any payment then or thereafter due the Contractor from the Owner, or (2) issue a written notice to the Contractor reducing the Contract Sum by an amount equal to that to which the Owner is entitled.

9.9 Substantial Completion

- **9.9.1** Substantial Completion is the stage in the progress of the Work as defined in Paragraph 1.1.14 as certified by the Owner.
- **9.9.2** When the Contractor considers the Work, or a portion thereof which the Owner agrees to accept separately, is substantially complete, the Contractor shall notify the Owner and the Architect. The Owner's

Representative will make an inspection to determine whether the Work or designated portion thereof is substantially complete. If the Owner's Representative's inspection discloses any item which is not in accordance with the requirements of the Contract Documents, the Contractor shall complete or correct such item upon notification by the Owner's Representative. The Contractor shall then submit a request for another inspection by the Owner's Representative to determine Substantial Completion. When the Work or designated portion thereof is substantially complete, the Owner will issue a Certificate of Substantial Completion. Substantial Completion shall transfer from the Contractor to the Owner responsibilities for security, maintenance, heat, utilities, damage to the Work and insurance. In no event shall Contractor have more than thirty (30) days to complete all items on the Punch List and achieve Final Completion. Warranties required by the Contract Documents shall commence on the date of Substantial Completion or as agreed otherwise.

9.9.3 At the date of Substantial Completion, the Contractor may apply for, and if approved by Owner's Representative, the Owner, subject to the provisions herein, shall increase total payments to one hundred percent (100%) of the Contract Sum less one hundred fifty percent (150%) of the value of any incomplete Work and unsettled claims, as determined by the Owner's Representative.

9.10 Partial Occupancy or Use

- **9.10.1** The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, security, maintenance, heat, utilities, damage to the Work and insurance. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by the Owner's Representative.
- **9.10.2** Immediately before such partial occupancy or use, the Owner, and Contractor shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work. Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

9.11 Final Completion and Final Payment

9.11.1 Upon receipt of written notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Owner's Representative and the Architect will promptly make such inspection and, when the Owner's Representative and Architect find the Work acceptable under the Contract Documents and the Contract fully performed, the Owner's Representative will promptly issue a final approval for payment; otherwise, Owner's

Representative will return Contractor's Final Application for Payment to Contractor, indicating in writing the reasons for refusing to recommend final payment, in which case Contractor shall make the necessary corrections and resubmit the Application. Submission of a Final Application for Payment shall constitute a further representation that conditions listed in Paragraph 9.11.2 as precedent to the Contractor's being entitled to final payment have been fulfilled. All warranties and guarantees required under or pursuant to the Contract Documents shall be assembled and delivered by the Contractor to the Owner's Representative as part of the final Application for Payment. The final approval for payment will not be issued by the Owner's Representative until all warranties and guarantees have been received and accepted by the Owner.

- **9.11.2** The Owner will request the Contractor to submit the application for final payment along with a manually signed notarized letter on the Contractor's letterhead certifying that:
- .1 Labor costs, prevailing wage rates, fringe benefits and material costs have been paid.
- .2 Subcontractors of any tier and manufacturers furnishing materials and labor for the project have fully completed their Work and have been paid in full.
- .3 The project has been fully completed in accordance with the Contract Documents as modified by Change Orders.
- .4 The acceptance by Contractor of its Final Payment, by check or electronic transfer, shall be and operate as a release of all claims of Contractor against Owner for all things done or furnished or relating to the Work and for every act or alleged neglect of Owner arising out of the Work.
- **9.11.3** Final Payment constituting the entire unpaid balance due shall be paid by the Owner to the Contractor within thirty (30) days after Owner's receipt of Contractor's Final Application for Payment which satisfies all the requirements of the Contract Documents and Owner's receipt of all information and documents set forth in Section 9.11.
- **9.11.4** No payment under this Contract, including but not limited to final payment, shall constitute acceptance by Owner of any Work or act not in accordance with the requirements of the Contract Documents.
- **9.11.5** No recourse shall be had against any member of the Board of Curators, or officer thereof, for any payment under the Contract or any claim based thereon.

ARTICLE 10 PROTECTION OF PERSONS AND PROPERTY

10.1 Safety Precautions and Programs

- **10.1.1** The Contractor shall at all times conduct operations under this Contract in a manner to avoid the risk of bodily harm to persons or risk of damage to any property. The Contractor shall promptly take precautions which are necessary and adequate against conditions created during the progress of the Contractor's activities hereunder which involve a risk of bodily harm to persons or a risk of damage to property. The Contractor shall continuously inspect Work, materials, and equipment to discover and determine any such conditions and shall be solely responsible for discovery, determination, and correction of any such conditions. The Contractor shall comply with applicable safety laws, standards, codes, and regulations in the jurisdiction where the Work is being performed, specifically, but without limiting the generality of the foregoing, with rules regulations, and standards adopted pursuant to the Williams-Steiger Occupational Safety and Health Act of 1970 and applicable amendments.
- **10.1.2** All contractors, subcontractors and workers on this project are subject to the Construction Safety Training provisions 292.675 RSMo.
- 10.1.3 In the event the Contractor encounters on the site, material reasonably believed to be asbestos, polychlorinated biphenyl (PCB), lead, mercury, or other material known to be hazardous, which has not been rendered harmless, the Contractor shall immediately stop Work in the area affected and report the condition to the Owner's Representative and the Architect in writing. The Work in the affected area shall not thereafter be resumed except by written agreement of the Owner's Representative and Contractor if in fact the material is asbestos or polychlorinated biphenyl (PCB) and has not been rendered harmless. The Work in the affected area shall be resumed in the absence of asbestos or polychlorinated biphenyl (PCB), or when it has been rendered harmless by written agreement of the Owner's Representative and the Contractor. "Rendered Harmless" shall mean that levels of such materials are less than any applicable exposure standards, including but limited to OSHA regulations.

10.2 Safety Of Persons and Property

- **10.2.1** The Contractor shall take reasonable precautions for safety of, and shall provide protection to prevent damage, injury, or loss to:
- students, faculty, staff, the public, construction personnel, and other persons who may be affected thereby;
- .2 the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody, or control of the Contractor or the Contractor's Subcontractors of any tier; and
- .3 other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures, and utilities not designated for removal, relocation, or replacement in the course of construction.

- **10.2.2** The Contractor shall give notices and comply with applicable laws, standards, codes, ordinances, rules, regulations, and lawful orders of public authorities bearing on safety of persons or property or their protection from damage, injury, or loss.
- 10.2.3 The Contractor shall erect and maintain, as required by existing conditions and performance of the Contract, safeguards for safety and protection, including, but not limited to, posting danger signs and other warnings against hazards, promulgating safety regulations, and notifying owners and users of adjacent sites and utilities.
- **10.2.4** When use or storage of explosives or other hazardous materials or equipment or unusual methods are necessary for execution of the Work, the Contractor shall exercise the highest degree of care and carry on such activities under supervision of properly qualified personnel.
- 10.2.5 The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property insurance required by the Contract Documents) to property referred to in Article 10 caused in whole or in part by the Contractor, a Subcontractor of any tier, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable, and for which the Contractor is responsible under Article 10, except damage or loss attributable solely to acts or omissions of Owner or the Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's other obligations stated elsewhere in the Contract.
- 10.2.6 The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents, and the maintaining, enforcing and supervising of safety precautions and programs. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the Owner's Representative and Architect. The Contractor shall hold regularly scheduled safety meetings to instruct Contractor personnel on safety practices, accident avoidance and prevention, and the Project Safety Program. The Contractor shall furnish safety equipment and enforce the use of such equipment by its employees and its subcontractors of any tier.
- **10.2.7** The Contractor shall not load or permit any part of the construction or site to be loaded so as to endanger its safety.
- **10.2.8** The Contractor shall promptly report in writing to the Owner all accidents arising out of or in connection with

the Work which cause death, lost time injury, personal injury, or property damage, giving full details and statements of any witnesses. In addition, if death, serious personal injuries, or serious property damages are caused, the accident shall be reported immediately.

10.2.9 The Contractor shall promptly notify in writing to the Owner of any claims for injury or damage to personal property related to the work, either by or against the Contractor.

ARTICLE 11 INSURANCE & BONDS

11.1 Insurance

- 11.1.1 Contractor shall secure from the date of the Contract for Construction and maintain for such periods of time as set forth below, insurance of such types and in such amounts specified below, to protect Contractor, Owner and others against all hazards or risks of loss described below. The form of such insurance together with carriers thereof, in each case, shall be approved by Owner, but, regardless of such approval, it shall be the responsibility of Contractor to maintain the insurance coverages set forth herein.
- **11.1.2** The contractor shall not be allowed on the Owners property without proof of the insurance coverages set forth herein

11.2 Commercial General Liability

- 11.2.1 Contractor shall secure and maintain from the date of the Contract and for a period of at least five (5) years from the date of Final Completion of the entire Work Commercial General Liability insurance ("CGL") with a combined single limit of not less than \$2,000,000 per occurrence, \$5,000,000 general aggregate, \$5,000,000 products and completed operations aggregate and \$1,000,000 personal injury and advertising injury. General Aggregate should apply per project. An umbrella policy may be used to satisfy these limits. If the General Aggregate is not on a per project basis, the contractor shall provide an additional \$2,000,000 general aggregate.
- 11.2.2 CGL insurance shall be written on a comprehensive form and shall cover claims and liability in connection with or resulting from the Contractor's operations and activities under the Contract, for personal injuries, occupational sickness, disease, death or damage to property of others, including loss of use resulting therefrom, arising out of any operations or activities of the Contractor, its agents, or any Subcontractors of any tier or by anyone directly or indirectly employed by either of them.
- 11.2.3 CGL insurance shall include premises, operations, independent contractors, products-completed operations, personal injury and advertising injury and liability assumed under an insured contract (including the tort liability of another assumed in a business contract) coverages. In particular, and not by way of any limitation, the CGL

insurance shall cover the Contractor's indemnity obligations contained in the Contract Documents.

- **11.2.4** There shall be no endorsement or modification of the CGL policy limiting the scope of coverage for liability arising from blasting, explosion, collapse, or underground property damage.
- 11.2.5 "The officers, employees, and agents of The Curators of the University of Missouri" shall be endorsed as an "additional insured" under the CGL policy. The additional insured status must be conveyed by using the ISO CG 2 10 (2004) edition or equivalent and the ISO CG 20 37 (2004) edition. The policy shall be endorsed to be primary coverage and any other insurance carried by the Owner shall be excess only and will not contribute with Contractors' insurance. To confirm, the Endorsement should accompany the insurance certificate.
- **11.2.6** Contractor waives all rights against Owner and its agents, officers, representatives, and employees for recovery of damages to the extent those damages are covered by the CGL policy required hereunder.

11.3 Licensed for Use Vehicle Liability

- 11.3.1 Contractor shall secure and maintain from the date of the Contract for Construction until the date of Final Completion of the entire Work, insurance, to be on comprehensive form, which shall protect Contractor against any and all claims for all injuries and all damage to property arising from the use of automobiles, trucks and motorized vehicles, in connection with the performance of Work under this Contract, and shall cover the operation on or off the site of the Work of all motor vehicles licensed for highway use whether they are owned, non-owned or hired. Such insurance shall include contractual liability coverage and shall provide coverage on the basis of the date of any accident. The liability limits under such policy shall not be less than \$2,000,000 combined single limit for bodily injury and property damage per accident.
- 11.3.2 Contractor waives all rights against Owner and its agents, officers, directors, and employees for recovery of damages to the extent such damages are covered by the automobile liability insurance required hereunder.

11.4 Workers' Compensation Insurance

11.4.1 Contractor shall purchase and maintain workers' compensation insurance and employers' liability insurance which shall protect Contractor from claims for injury, sickness, disease or death of Contractor's employees or statutory employees. The insurance policies required hereunder shall include an "all states" or "other states" endorsement. In case any Work is sublet, Contractor shall require any Subcontractor of any tier to provide the insurance coverages required under this Section 11.4.

11.4.2 Contractor's workers' compensation insurance coverage shall be in compliance with all applicable Laws, including the statutes of the State of Missouri. Contractor's employers' liability coverage limits shall not be less than \$1,000,000 each accident for bodily injury by accident or \$1,000,000 each employee for bodily injury by disease.

11.5 Liability Insurance General/Other Requirements

- 11.5.1 Any Consultant/Contractor providing professional design services as part of the contract shall be required to provide and maintain, from the date of this Contract and for a period of ten (10) years after the date of Final Completion, Professional Liability insurance to cover any claims, including but not limited to errors, omissions, and negligence, which may arise from the Design and related Services performed by the Consultant. The minimum limits such Policy shall be \$1,000,000.00 occurrence/\$1,000,000.00 aggregate. The insurance afforded by the policy shall meet the requirements of this Section 11.2 and Section 11.5 relating to CGL Policies, and without limiting the foregoing, shall be extended to cover the liability of "The officers, employees, and agents of The Curators of the University of Missouri", who shall be named as additional insureds therein, and this liability is assumed in writing by the Contractor's Consultant under the written Subcontract described herein. All insurance coverages procured by Contractor shall be provided by agencies and insurance companies acceptable to and approved by Owner. Any insurance coverage shall be provided by insurance companies that are duly licensed to conduct business in the State of Missouri as an admitted carrier. The form and content of all insurance coverage provided by Contractor are subject to the approval of Owner. All required insurance coverages shall be obtained and paid for by Contractor. Any approval of the form, content or insurance company by Owner shall not relieve the Contractor from the obligation to provide the coverages required herein.
- 11.5.2 All insurance coverage procured by the Contractor shall be provided by insurance companies having policyholder ratings no lower than "A-" and financial ratings not lower than "XI" in the Best's Insurance Guide, latest edition in effect as of the date of the Contract, and subsequently in effect at the time of renewal of any policies required by the Contract Documents. Insurance coverages required hereunder shall not be subject to a deductible amount on a per-claim basis of more than \$10,000.00 and shall not be subject to a per-occurrence deductible of more than \$25,000.00. Insurance procured by Contractor covering the additional insureds shall be primary insurance and any insurance maintained by Owner shall be excess insurance.
- 11.5.3 All insurance required hereunder shall provide that the insurer's cost of providing the insureds a defense and appeal, including attorneys' fees, shall be supplementary and shall not be included as part of the policy limits but shall remain the insurer's separate responsibility. Contractor shall cause its insurance carriers to waive all rights of subrogation,

except for Workers' Compensation, against the Owner and its officers, employees and agents.

- 11.5.4 The Contractor shall furnish the Owner with certificates, Additional Insured endorsements, policies, or binders which indicate the Contractor and/or the Owner and other Contractors (where required) are covered by the required insurance showing type, amount, class of operations covered, effective dates and dates of expiration of policies prior to commencement of the work. Contractor is required to maintain coverages as stated and required to notify the University of a Carrier Change or cancellation within 2 business days. The University reserves the right to request a copy of the policy. Contractor fails to provide, procure, and deliver acceptable policies of insurance or satisfactory certificates or other evidence thereof, the Owner may obtain such insurance at the cost and expense of the Contractor without notice to the Contractor.
- 11.5.5 With respect to all insurance coverages required to remain in force and affect after final payment, Contractor shall provide Owner additional certificates, policies and binders evidencing continuation of such insurance coverages along with Contractor's application for final payment and shall provide certificates, policies and binders thereafter as requested by Owner.
- **11.5.6** The maintenance in full current force and effect of such forms and amounts of insurance and bonds required by the Contract Documents shall be a condition precedent to Contractor's exercise or enforcement of any rights under the Contract Documents.
- 11.5.7 Failure of Owner to demand certificates, policies and binders evidencing insurance coverages required by the Contract Documents, approval by Owner of such certificates, policies and binders or failure of Owner to identify a deficiency from evidence that is provided by Contractor shall not be construed as a waiver of Contractor's obligations to maintain the insurance required by the Contract Documents.
- **11.5.8** The Owner shall have the right to terminate the Contract if Contractor fails to maintain the insurance required by the Contract Documents.
- 11.5.9 If Contractor fails to maintain the insurance required by the Contract Document, Owner shall have the right, but not the obligation, to purchase said insurance at Contractor's expense. If Owner is damaged by Contractor's failure to maintain the insurance required by the Contract Documents, Contractor shall bear all reasonable costs properly attributable to such failure.
- 11.5.10 By requiring the insurance set forth herein and in the Contract Documents, Owner does not represent or warrant that coverage and limits will necessarily be adequate to protect Contractor, and such coverages and

limits shall not be deemed as a limitation on Contractor's liability under the indemnities granted to Owner in the Contract Documents.

- **11.5.11** If Contractor's liability policies do not contain a standard separation of insureds provision, such policies shall be endorsed to provide cross-liability coverage.
- 11.5.12 If a part of the Work hereunder is to be subcontracted, the Contractor shall: (1) cover any and all Subcontractors in its insurance policies; (2) require each Subcontractor to secure insurance which will protect said Subcontractor and supplier against all applicable hazards or risks of loss designated in accordance with Article 11 hereunder; and (3) require each Subcontractor or supplier to assist in every manner possible in the reporting and investigation of any accident, and upon request, to cooperate with any insurance carrier in the handling of any claim by securing and giving evidence and obtaining the attendance of witnesses as required by any claim or suit.
- 11.5.13 It is understood and agreed that the insurance coverages required by the provisions of this Article 11 are required in the public interest and that the Owner does not assume any liability for acts of Contractor or Subcontractors of any tier or their employees in the performance of the Contract or Work.

11.6 Builder's Risk Insurance

- 11.6.1 The Contractor shall purchase and maintain, in a company or companies lawfully authorized to do business in the State of Missouri, as an admitted carrier, builder's risk insurance on the entire Work. Such insurance shall be written on a completed value form for the entire Work. The insurance shall apply on a replacement cost basis.
- 11.6.2 The insurance as required herein shall name as insureds the Owner, Contractor, and all Subcontractors of any tier. The insurance policy shall contain a provision that the insurance will not be canceled, allowed to expire or materially changed until at least thirty (30) days prior written notice has been given to Owner.
- 11.6.3 The insurance as required herein shall cover the entire Work, including reasonable compensation for Architect's services and expenses made necessary by an insured loss. Insured property shall include portions of the Work located away from the site (including all offsite stored materials) but intended for use at the site and shall also cover portions of the Work in transit, including ocean transit. The policy shall include as insured property scaffolding, falsework, and temporary buildings located at the site. The policy shall cover the cost of removing debris, including demolition as may be made legally necessary by the operation of any law, ordinance, or regulation.
- 11.6.4 The insurance required herein shall be on an all risk form and shall be written to cover all risks of physical loss or damage to the insured party and shall insure at least against the perils of fire and extended coverage, theft, vandalism,

malicious mischief, collapse, lightening, earthquake, flood, frost, water damage, windstorm and freezing.

- 11.6.5 If there are any deductibles applicable to the insurance required herein, Contractor shall pay any part of any loss not covered because of the operation of such deductibles.
- **11.6.6** The insurance as required herein shall be maintained in effect until the earliest of the following dates:
- .1 the date which all persons and organization who are insureds under the policy agree in writing that it shall be terminated;
- .2 the date on which final payment of this Contract has been made by Owner to Contractor; or
- .3 the date on which the insurable interests in the property of all insureds other than the Owner have ceased.
- 11.6.7 The Owner and Contractor waive all rights against (1) each other and any of their subcontractors of any tier, suppliers, agents and employees, each of the other, (2) the Architect and Architect's consultants, and (3) separate contractors described in Article 6, if any, and any of their subcontractors of any tier, suppliers, agents and employees, for damages caused by fire or other perils to the extent covered by property insurance obtained pursuant to this Section 11.7 or other insurance applicable to the Work, except such rights as they have to proceeds of such insurance. The Owner or Contractor, as appropriate, shall require of the Architect, Architect's consultants, separate contractors described in Article 6, if any, and the subcontractors of any tier, suppliers, agents, and employees of any of them, by appropriate agreements, written where legally required for validity, similar waivers each in favor of other parties enumerated herein. The policies shall provide such waivers of subrogation by endorsement or otherwise. A waiver of subrogation shall be effective as to a person or entity even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, did not pay the insurance premium directly or indirectly, was at fault or was negligent in causing the loss and whether or not the person or entity had an interest in the property damaged.
- 11.6.8 A loss insured under Contractor's property insurance shall be adjusted by the Owner in good faith and made payable to the Owner for the insureds, subject to requirements of the Contract Documents. The Contractor shall pay Subcontractors of any tier their just shares of insurance proceeds received by the Contractor, and by appropriate agreements, written where legally required for validity, shall require Subcontractors of any tier to make payments to their Sub-subcontractors in similar manner.

11.7 Bonds

11.7.1 When the Contract sum exceeds Fifty Thousand Dollars (\$50,000), the Contractor shall procure and

furnish a Performance Bond and a Payment Bond in the form prepared by the Owner, each in an amount equal to one hundred percent (100%) of the Contract Sum, as well as adjustments to the Contract Sum. The Performance Bond shall secure and guarantee Contractor's faithful performance of this Contract, including but not limited to Contractor's obligation to correct defects after final payment has been made as required by the Contract Documents. The Payment Bond shall secure and guarantee payment of all persons performing labor on the Project under this Contract and furnishing materials in connection with this Contract. These Bonds shall be in effect through the duration of the Contract plus the Guaranty Period as required by the Contract Documents.

- 11.7.2 The bonds required hereunder shall be executed by a responsible surety licensed in the State of Missouri, with a Best's rating of no less than A-/XI. The Contractor shall require the attorney in fact who executes the required bonds on behalf of the surety to affix thereto a certified and current copy of this power of attorney indicating the monetary limit of such power.
- 11.7.3 If the surety of any bond furnished by Contractor is declared bankrupt or becomes insolvent or its right to conduct business in the State of Missouri is terminated, or it ceases to meet the requirements of this paragraph, Contractor shall within ten (10) days substitute another bond and surety, both of which must be acceptable to Owner. If Contractor fails to make such substitution, Owner may procure such required bonds on behalf of Contractor at Contractor's expense.
- 11.7.4 Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds to such person or entity.
- 11.7.5 The Contractor shall keep the surety informed of the progress of the Work, and, where necessary, obtain the surety's consent to or waiver of: (1) notice of changes in the Work; (2) request for reduction or release of retention; (3) request for final payment; and (4) any other material required by the surety. The Owner shall be notified by the Contractor, in writing, of all communications with the surety, as it relates to items one through four. The Owner may, in the Owner's sole discretion, inform surety of the progress of the Work, any defects in the Work, or any defaults of Contractor under the Contract Documents and obtain consents as necessary to protect the Owner's rights, interest, privileges and benefits under and pursuant to any bond issued in connection with the Work.
- 11.7.6 Contractor shall indemnify and hold harmless the Owner and any agents, employees, representative or member of the Board of Curators from and against any claims, expenses, losses, costs, including reasonable attorneys' fees, as a result of any failure of Contractor to procure the bonds required herein.

ARTICLE 12 UNCOVERING AND CORRECTION OF THE WORK

12.1 Uncovering of the Work

- **12.1.1** If a portion of the Work is covered contrary to the Architect's request or to requirements specifically expressed in the Contract Documents, it shall, if required in writing by the Architect or the Owner's Representative, be uncovered for the Architect's observation and be replaced at the Contractor's expense without change in the Contract Time.
- 12.1.2 If a portion of the Work has been covered which the Architect or the Owner's Representative has not specifically requested to observe, prior to its being covered, the Architect or the Owner's Representative may request to see such Work, and it shall be uncovered by the Contractor. If such Work is in accordance with the Contract Documents, costs of uncovering and replacement shall, by appropriate Change Order, be charged to the Owner. If such Work is not in accordance with the Contract Documents, the Contractor shall pay such costs unless the condition was caused by the Owner or a separate contractor in which event the Owner will be responsible for payment of such costs.

12.2 Correction of the Work

12.2.1 The Architect or Owner's Representative shall have the right to reject Work not in strict compliance with the requirements of the Contract Documents. Contractor shall promptly correct Work rejected by the Architect or the Owner's Representative for failing to conform to the requirements of the Contract Documents, whether observed before or after final completion and whether or not fabricated, installed, or completed. If Work has been rejected by Architect or Owner's Representative, the Architect or Owner's Representative shall have the right to require the Contractor to remove it from the Project site and replace it with Work that strictly conforms to the requirements of the Contract Documents regardless, if such removal and replacement results in "economic waste." Contractor shall pay all claims, costs, losses and damages caused by or resulting from the correction, removal or replacement of defective, or noncompliant Work, including but not limited to, all costs of repair or replacement of Work of others. The Contractor shall bear costs of correcting, removing and replacing such rejected Work, including additional testing and inspections and compensation for the Architect's services and expenses made necessary thereby. If prior to the date of final payment, the Contractor, a Subcontractor, or anyone for whom either is responsible uses or damages any portion of the Work, including, without limitation, mechanical, electrical, plumbing, and other building systems, machinery, equipment or other mechanical device, the Contractor shall cause such item to be restored to "like new" condition at no expense to the Owner.

- 12.2.2 If, within twelve (12) months after the date of Final Completion of the Work or designated portion thereof, or after the date for commencement of warranties, or by terms of an applicable special warranty required by the Contract Documents, any of the Work is found not to be in strict accordance with the requirements of the Contract Documents, the Contractor shall correct or remove and replace such defective Work, at the Owner's discretion. Such twelve (12) month period is referred to as the "Guarantee Period." The obligations under this Paragraph 12.2.2 shall cover any repairs, removal, and replacement to any part of the Work or other property caused by the defective Work.
- **12.2.3** The Contractor shall remove from the site portions of the Work which are not in accordance with the requirements of the Contract Documents and are neither corrected by the Contractor nor accepted by the Owner.
- **12.2.4** If the Contractor fails to correct nonconforming Work within a reasonable time, the Owner may correct or remove it and replace such nonconforming Work. If the Contractor does not proceed with correction of such nonconforming Work within a reasonable time fixed by written notice from the Owner, the Owner may take action to correct or remove the nonconforming work at the contractor's expense.
- **12.2.5** The Contractor shall bear the cost of correcting destroyed or damaged Work or property, whether completed or partially completed, of the Owner or of others caused by the Contractor's correction or removal of Work which is not in accordance with the requirements of the Contract Documents.
- **12.2.6** Nothing contained in Article 12 shall be construed to establish a period of limitation with respect to other obligations that the Contractor might have under the Contract Establishment of the twelve (12) month Documents. Guarantee Period as described in Article 12 relates only to the specific obligation of the Contractor to correct, remove or replace the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish the Contractor's liability with respect to the Contractor's obligations under the Contract Documents. The requirements of Article 12 are in addition to and not in limitation of any of the other requirements of the Contract for warranties or conformance of the Work to the requirements of the Contract Documents.

12.3 Acceptance of Nonconforming Work

12.3.1 The Owner may accept Work which is not in accordance with the Contract Documents, instead of requiring its removal and correction, in its sole discretion. In Such case the Contract Sum will be adjusted as appropriate and equitable. Such adjustment shall be made whether or not final payment has been made. Nothing contained herein shall impose any obligation upon the Owner to accept nonconforming or defective Work.

ARTICLE 13 MISCELLANEOUS PROVISIONS

13.1 Written Notice

13.1.1 All notices required to be given by the contractor under the terms of this Contract shall be made in writing. Written notice when served by the Owner will be deemed to have been duly served if delivered in person to the individual or a member of the firm or entity or to an office of the corporation for which it was intended, or if delivered at or sent to the last business address known to the party giving notice.

13.2 Rights and Remedies

- **13.2.1** Duties and obligations imposed by the Contract Documents, and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.
- 13.2.2 No action or failure to act by the Owner, the Architect, or the Owner's Representative will constitute a waiver of a right or duty afforded to the Owner under the Contract Documents, nor will such action or failure to act constitute approval of or acquiescence in a breach thereunder, except as may be specifically agreed in writing.
- **13.2.3** The terms of this Contract and all representations. indemnifications. warranties and guarantees made in, required by, or given in accordance with the Contract Documents, as well as all continuing obligations indicated in the Contract Documents, will survive final payment, completion and acceptance of the Work and termination or completion of the Work and shall remain in effect so long as the Owner is entitled to protection of its rights under applicable law.
- **13.2.4** Contractor shall carry out the Work and adhere to the current construction schedule during all disputes or disagreements with the Owner. No Work shall be delayed or postponed pending resolution of any disputes or disagreements except as the Owner and Contractor may otherwise agree to in writing.

13.3 Tests and Inspections

13.3.1 Tests, inspections, and approvals of portions of the Work required by the Contract Documents or by laws, ordinances, rules, codes, or regulations shall be made at an appropriate time. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections and approvals with an independent testing laboratory, the Owner's Authorized Agent, or entity acceptable to the Owner, and the Contractor shall bear related costs of tests, inspections, and approvals as required in the Contract Documents. The Contractor shall give the Architect, Owner's Representative, and the Owner's Authorized Agent timely notice of when and where tests and inspections are to be made so the

Architect, the Owner's Representative and/or the Owner's Authorized Agent may observe procedures or perform the necessary tests or inspections.

- 13.3.2 If the Architect, Owner's Representative, or the Owner's Authorized Agent determine that portions of the Work require additional testing, inspection or approval not included in the Contract Documents, or required by law, the Architect, or the Owner's Representative will instruct the Contractor to make arrangements for such additional testing, inspection, or approval by an entity acceptable to the Owner's Representative and the Contractor shall give timely notice to the Architect, the Owner's Representative or the Owner's Authorized Agent, of when and where tests and inspections are to be made so the Architect, Owner's Representative and/or the Owner's Authorized Agent , so may choose that the tests or inspections can be performed or observed. The Owner will bear such costs except as provided elsewhere in Article 13.
- 13.3.3 If such procedures for testing, inspection, or approval under Article 13 reveal failure of the portions of the Work to comply with requirements established by the Contract Documents, the Contractor shall bear all costs made necessary by such failure including those of repeated procedures and compensation for the Architect's and Owner's Authorized Agent's services and expenses.
- **13.3.4** Required certificates of testing, inspection, or approval shall, unless otherwise required by the Contract Documents, be secured by the Contractor, and promptly delivered to the Owner's Representative and Architect.
- 13.3.5 Contractor shall take all necessary actions to ensure that all tests or inspections conducted pursuant to the Contract Documents shall be made promptly to avoid unreasonable delay in the Work.
- 13.3.6 Contractor shall arrange for and pay for all costs of all testing required by the Contract Documents or any applicable Laws for materials to be tested or certified at or on the place or premises of the source of the material to be supplied. The Owner shall have the right to require testing of all materials at the place of the source of the material to be supplied if not required by the Contract Documents or any applicable Laws. The Owner shall bear the costs of such tests and inspections not required by the Contract Documents or by applicable Laws unless prior defective Work provides Architect or Owner with a reasonable belief that additional defective Work may be found, in which case Contractor shall be responsible for all costs of tests and inspections ordered by the Owner or Architect, whether or not such tests or inspection reveals that Work is in compliance with the Contract Documents.

13.4 Nondiscrimination in Employment Equal Opportunity

13.4.1 The University serves from time to time as a contractor for the United States government. Accordingly, the provider of goods and/or services shall comply with

federal laws, rules and regulations applicable to subcontractors of government contracts including those relating to equal employment opportunity and affirmative action in the employment of minorities (Executive Order 11246), women (Executive Order 11375), persons with disabilities (29 USC 706) and Executive Order 11758, and certain veterans (38 USC 4212 formerly [2012]) contracting with business concerns with small disadvantaged business concerns (Publication L. 95-507). Contract clauses required by the Government in such circumstances are incorporated herein by reference.

13.5 Supplier Diversity Goal Program

- **13.5.1** The Contractor shall subcontract with diverse firms no less than the amount pledged in the Contractor's Bid and/or the amount accepted by the Owner.
- 13.5.2 If the Contractor must remove any diverse subcontractor of any tier, the Contractor shall replace the diverse subcontractor of any tier with another diverse subcontractor(s) of equal dollar value to the diverse supplier removed. The Contractor shall immediately notify the Owner's Representative in writing of the Contractor's intent to remove any, and the Contractor's plan to maintain subcontracts with diverse firms of no less than amount pledged in the Contractor's Bid and/or the amount accepted by the Owner. All changes of diverse subcontractor of any tier shall be approved by the Director of Facilities Planning & Development.
- 13.5.3 If the Contractor fails to meet or maintain the contractor's Supplier Diversity subcontracting pledge, the Contractor shall immediately notify in writing the Owner's Representative, and the Director of Facilities Planning & Development. Such notice shall include a description of the Contractor's good faith effort to comply with their Supplier Diversity subcontracting pledge.
- 13.5.4 If the Director of Facilities Planning & Development finds the Contractor has failed to comply in good faith with the Owner's Supplier Diversity goal program, the Director may take appropriate action, including but not limited to, declaring the Contractor ineligible to participate in any contracts with the Owner for a period not to exceed six (6) months, and/or directing that the Contractor's actions be declared a material breach of the Contract and that the Contract be terminated.
- 13.5.5 The Contractor and his subcontractors shall develop, implement, maintain, and submit in writing to the Director of Facilities Planning & Development, an affirmative action program if at least fifty (50) persons in the aggregate are employed under this contract. If less than fifty (50) persons in the aggregate are to be employed under this contract, the Contractor shall submit, in lieu of the written affirmative action program, a properly executed "Affidavit for Affirmative Action" in the form as included in the Contract Documents. For the purpose of this section, an "Affirmative Action Program"

means positive actions to influence all employment practices (including, but not limited to, recruiting, hiring, promoting, and training) in providing equal employment opportunity regardless of race, color, sex, national origin, religion, age (where the person affected is between 40 and 70), disabled and Vietnam-era veteran status, and handicapped otherwise qualified status. Such affirmative action program shall include:

- .1 A written policy statement committing the total organization to affirmative action and assigning management responsibilities and procedures for evaluation and dissemination.
- .2 The identification of a person designated to handle affirmative action.
- .3 The establishment of non-discriminatory selection standards, objective measures to analyze recruitment, an upward mobility system, a wage and salary structure, and standards applicable to lay-off, recall, discharge, demotion, and discipline.
- .4 The exclusion of discrimination from collective bargaining agreements.
- .5 Performance of an internal audit of the reporting system to monitor execution and to provide for future planning.
- 13.5.6 In the enforcement of this non-discrimination requirement, the Owner may use any reasonable procedures available, including but not limited to: requests, reports, site visits, and inspection of relevant documents of Contractors and Subcontractors of any tier. The contractor shall submit a final Affidavit of Supplier Diversity Participation for each diverse firm at the end of the project stating the actual amount paid to the diverse firm.

13.6 Wage Rates (If the contract amount is less than \$75,000, the requirements of this section will not apply. Any contract adjustments that increase the contract above \$75,000 will be subject to this section.)

13.6.1 The Contractor shall pay workers employed in the execution of this contract in full each week and not less than the predetermined wage rates and overtime for work of a similar character that have been made a part of this Contract. These rates are determined by the University of Missouri Director of Facilities Planning and Development. The rates are based on wage rates published in the Annual Wage Orders of the Missouri Department of Labor and Industrial Relations (MDLIR). The Contractor is to use MDLIR 8 CSR 30-3.020; .030; .040, .060 in determining the appropriate occupational titles and rates for workers used in the execution of this contract. All determinations and/or interpretations regarding wage rates and classification of workers will be made by the office of the University of Missouri Director of Facilities Planning and Development. The Contractor is responsible for the payment of the aggregate of the Basic Hourly Rate and the Total Fringe Benefits to the workers on the project. Fringe benefit payments may be made to the worker in cash, or irrevocably made by a Contractor or Subcontractor to a trustee or to a third person pursuant to a fund, plan or program, or pursuant to an enforceable

commitment, or any combination thereof, to carry out a financially responsible plan or program which was communicated in writing to the workmen affected, for medical or hospital care, pensions on retirement or death, compensation for injuries or illness resulting from occupational activity, or insurance to provide any of the foregoing, for unemployment benefits, life insurance, disability and sickness insurance, accident insurance, for vacation and holiday pay, for defraying costs of apprenticeship or other similar programs, or for other bona fide fringe benefits, but only where the Contractor or Subcontractor is not required by other federal or state law to provide any of the benefits as referenced in §290.210(5) RSMo 1994. Pay for travel, mileage, meals, bonuses, or other expenses are not fringe benefits and cannot be considered part of the workers wage rate. The Contractor shall not make any deductions for food, sleeping accommodations, transportation, use of small tools, uniforms, or anything of any kind or description, unless the Contractor and employee enter into an agreement in writing at the beginning of the worker's term of employment, and such agreement is approved by the Owner. In the event the contract contains more than one wage determination the Contractor shall comply with both.

13.6.2 The Contractor shall submit to the Owner with the Contractor's periodic pay request, certified payroll records for labor performed by the Contractor and Subcontractors of any tier. The Contractor shall submit all required certified payroll information records electronically in pdf format using the Owner's web-based payment program. The certified payroll forms shall contain the name, address, personal identification number, and occupational title of the workers as well as the hours they work each day. The Owner's acceptance of certified payroll records does not in any way relieve the Contractor of any responsibility for the payment of prevailing wages to workers on the project. The Contractor shall also maintain copies of the certified payroll records. The Owner may, at any time, request copies of, and/or inspect all of the Contractor's payroll records for the Work to verify compliance. The Contractor shall furnish the Owner copies of payroll records within 10 days of the Owner's written request. The Contractor shall provide copies of workers I-9 forms within 24 hours of written notice. (If applicable, and required by Owner, the Contractor will demonstrate that the Contractor is enrolled and participating in a federal work authorization program with respect to the employees working in connection with this project.) Such payroll records shall be maintained in accordance with Article 13.7.1 and shall be available for inspection for two (2) years after final completion of the Work. The contractor further agrees, in the event the records are not presented as requested, he will abide by any decision made by the Owner regarding underpayment of wages to workers and amounts owed them as well as liquidated damages for underpayment of wages. Falsification of the certified payroll records may result in the debarment of the contractor or subcontractor from future work with the University.

- **13.6.3** The acquisition of products or services is subject to the supplier's conformance to the rules and regulations of the President's Committee on Equal Employment Opportunity (41 CFR, Ch. 60).
- 13.6.4 The Contractor shall comply with the Copeland Regulations of the Secretary of Labor (29 CFR, Part 3), which are incorporated herein by reference. In addition, the Weekly Statement of Compliance required by these Regulations shall also contain a statement that the applicable fringe benefits paid are equal to or greater than those set forth in the minimum wage decision.
- 13.6.5 Contractor acknowledges that violation of the requirements of Article 13.6 result in additional costs to Owner, including, but not limited to, cost of construction delays, of additional work for Owner's staff and legal expense. The cost of Contractor's violation of the provisions of Article 13.6 would be and is difficult to determine and establish. In the event that Contractor fails to comply with the provisions of this Article 13.6, Owner shall be entitled to retain or recover from the Contractor, as liquidated damages and not as a penalty, the sum of Fifty Dollars (\$50.00) per day per individual who is paid less than the applicable prevailing wage, to approximate the investigative cost resulting to the Owner for such violations. To approximate the delay costs, Owner shall be entitled to retain or recover from the Contractor, as liquidated damages and not as a penalty, the sum of One Hundred Dollars (\$100.00) per day for each day the Contract cannot be closed out and final payment made because of Contractor's failure to comply with the provisions of this Article 13.6. Such liquidated damages shall be collected regardless of whether the Work has been completed. The liquidated damages and other amounts set forth in this Article 13.6 shall be in addition to all other liquidated damages the Owner may be entitled as set forth in the Contract Documents.
- 13.6.6 The Owner may deduct liquidated damages described Article 13 and the amounts set forth in Article 13 from any unpaid amounts then or thereafter due the Contractor under the Contract. Any liquidated damages not so deducted from any unpaid amounts due the Contractor shall be payable to the Owner at the demand of the Owner.
- **13.6.7** The Contractor shall specifically incorporate the obligations of Article 13 into the subcontracts, supply agreements and purchase orders for the Work and require the same of any Subcontractors of any tier.
- 13.6.8 Contractor acknowledges and recognizes that a material factor in its selection by the Owner is the Contractor's willingness to undertake and comply with the requirements of this Article 13.6. If Contractor fails to comply with the provisions of this Article 13.6, Owner may, in its sole discretion, immediately terminate the Contract

upon written notice. The rights and remedies of Owner provided herein shall not be exclusive and are in addition to other rights and remedies provided by law or under this Contract.

13.6.9 Only such workers who are individually registered in a bona fide apprenticeship program approved by the U.S. Department of Labor, Office of Apprenticeship can be paid less than the journeyperson rate of pay. "Entry Level Workers; must be registered apprentices. The apprenticeship ratio will be one to one with a journeyperson of the same classification. Any worker not registered as an apprentice per this section will be paid as a journeyperson.

13.6.10 The Contractor shall post the wage rates for the contract in a conspicuous place at the field office on the project. On projects where there is no field office the Contractor may post the wage rates at their local office, as long as they provide a copy of the wage rates to a worker upon request. The wage rates shall be kept in a clearly legible condition for the duration of the project.

13.6.11 Neither the Contractor, nor any Subcontractor of any tier, nor any person hired by them or acting on their behalf, shall request or demand that workers pay back, return, donate, contribute, or give any part, or all, of said workers wages, salary, or any thing of value, upon the statement, representation or understanding that failure to comply with such request or demand will prevent such worker from procuring or retaining employment. The exception being to an agent or representative of a duly constituted labor organization acting in the collection of dues or assessments of such organization.

13.6.12 No contractor or subcontractor may directly or indirectly receive a wage subsidy, bid supplement, or rebate for employment on this project if such wage subsidy, bid supplement, or rebate has the effect of reducing the wage rate paid by the employer on a given occupational title below the prevailing wage rate as provided in contract. In the event a wage subsidy, bid supplement, or rebate is provided or received, the entity receiving such subsidy, supplement, or rebate shall report the date and amount of such subsidy, supplement, or rebate to the University within thirty days of receipt of payment. This disclosure report shall be a matter of public record. Any employer not in compliance with this Article shall owe to the University double the dollar amount per hour that the wage subsidy, bid supplement, or rebate has reduced the wage rate paid by the employer below the prevailing wage rate for each hour that work was performed.

13.6.13 Time and one-half overtime will be paid on all hours over 10 hours per day or 40 hours per week. The wage rate is the total of the "Basic Hourly Rate" plus "Total Fringe Benefits" or the "public works contracting minimum wage". For all work performed on a Sunday or

Holiday, not less than twice the prevailing hourly rate of pay or public works contracting minimum wage will apply. Holidays are as follows: January first, the last Monday in May, July fourth, the first Monday in September, November 11, the fourth Thursday in November, December twenty-fifth. If any holiday falls on a Sunday, the following Monday shall be considered a holiday.

13.7 Records

13.7.1 The Owner, or any parties it deems necessary, shall have access to and the right to examine any accounting or other records of the Contractor involving transactions and Work related to this Contract for five (5) years after final payment or five (5) years after the final resolution of any on going disputes at the time of final payment. All records shall be maintained in accordance with generally accepted accounting procedures, consistently applied. Subcontractors of any tier shall be required by Contractor to maintain records and to permit audits as required of Contractor herein.

13.8 Codes and Standards

13.8.1 The Work shall be performed to comply with the International Code Council (ICC) Codes, and the codes and standards noted below. The latest editions and supplements of these Codes and Standards in effect on the date of the execution of the Contract for Construction shall be applicable unless otherwise designated in the Contract Documents. Codes and standards required by accreditation agencies will also be used unless the ICC requirements are more stringent. In the event that special design features and/or construction systems are not covered in the ICC codes, the applicable edition of the National Fire Protection Association (NFPA) family of standards and/or the NFPA 101 Life Safety Code shall be used.

- .1 ICC International Building Code and reference standards
- .2 ICC International Plumbing Code
- .3 ICC International Mechanical Code
- .4 ICC International Fire Code
- .5 ICC International Fuel Gas Code
- .6 NFPA 70 National Electric Code (NEC)
- Americans with Disabilities Act Standards for Accessible Design.
- .8 American National Standard Safety Code for Elevators, Dumbwaiters, Escalators, and Moving Walks as published by the American Society of Mechanical Engineers (ASME), American National Standards Institute (ANSI) A17.1
- .9 NFPA 101 Life Safety Code (as noted above)
- .10 American Concrete Institute (ACI)
- .11 American National Standards Institute (ANSI)
- .12 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
- .13 American Refrigeration Institute (ARI)
- .14 American Society for Testing and Materials (ASTM)
- .15 Missouri Standard Specification for Highway Construction, Missouri State Highway Commission

- .16 National Electrical Manufacturers Association (NEMA)
- .17 Underwriter's Laboratories, Inc. (UL), Federal Specifications
- .18 Williams Steiger Occupational Safety and Health Act of 1970 (OSHA)

13.9 General Provisions

- 13.9.1 Any specific requirement in this Contract that the responsibilities or obligations of the Contractor also apply to a Subcontractor is added for emphasis and are also hereby deemed to include a Subcontractor of any tier. The omission of a reference to a Subcontractor in connection with any of the Contractor's responsibilities or obligations shall not be construed to diminish, abrogate or limit any responsibilities or obligations of a Subcontractor of any tier under the Contract Documents or the applicable subcontract.
- 13.9.2 This Contract shall be interpreted, construed, enforced, and regulated under and by the laws of the State of Missouri. Whenever possible, each provision of this Contract shall be interpreted in a manner as to be effective and valid under applicable law. If, however, any provision of this Contract, or a portion thereof, is prohibited by law or found invalid under any law, only such provision or portion thereof shall be ineffective, without invalidating or affecting the remaining provisions of this Contract or valid portions of such provision, which are hereby deemed severable. Contractor and Owner further agree that in the event any provision of this Contract, or a portion thereof, is prohibited by law or found invalid under any law, this Contract shall be reformed to replace such prohibited or invalid provision or portion thereof with a valid and enforceable provision which comes as close as possible to expressing the intention of the prohibited or invalid provision.
- 13.9.3 Contractor and Owner each agree that the State of Missouri Circuit Court for the County where the Project is located shall have exclusive jurisdiction to resolve all Claims and any issue and disputes between Contractor and Owner. Contractor agrees that it shall not file any petition, complaint, lawsuit or legal proceeding against Owner in any other court other than the State of Missouri Circuit Court for the County where the Project is located.
- 13.9.4 Owner's total liability to Contractor and anyone claiming by, through, or under Contractor for any Claim, cost, loss, expense, or damage caused in part by the fault of Owner and in part by the fault of Contractor or any other entity or individual shall not exceed the percentage share that Owner's fault bears to the total fault of Owner, Contractor and all other entities and individuals as determined on the basis of comparative fault principles.
- **13.9.5** Contractor agrees that Owner shall not be liable to Contractor for any special, indirect, incidental, or consequential damage whatsoever, whether caused by

- Owner's negligence, fault, errors or omissions, strict liability, breach of contract, breach of warranty or other cause or causes whatsoever. Such special, indirect, incidental or consequential damages include, but are not limited to loss of profits, loss of savings or revenue, loss of anticipated profits, labor inefficiencies, idle equipment, home office overhead, and similar types of damages.
- **13.9.6** Nothing contained in this Contract, or the Contract Documents shall create any contractual relationship with or cause of action in favor of a third party against the Owner.
- **13.9.7** No member or officer of the Board of Curators of the University incurs or assumes any individual or personal liability under the Contract or by reason of the default of the Owner in the performance of any terms thereof. Contractor releases and discharges all members or officers of the Board of Curators of the University from any liability as a condition of and as consideration for the award of the Contract to Contractor.
- 13.9.8 The Contractor hereby binds itself, its partners, successors, assigns and legal representatives to the Owner in respect to covenants, agreements and obligations contained in the Contract Documents. Contractor shall not assign the Contract or proceeds hereof without written consent of the Owner. If Contractor attempts to make such an assignment without such consent, it shall be void and confer no rights on third parties, and Contractor shall nevertheless remain legally responsible for all obligations under the Contract. Owner's consent to any assignment is conditioned upon Contractor entering into a written assignment which contains the following language: "it is agreed that the funds to be paid to the assignee under this assignment are subject to performance by the Contractor and to claims and to liens for services rendered or materials supplied for the performance of the Work required in said Contract in favor of all persons, firms, corporations rendering such services or supplying such materials."

13.10 Certification

- **13.10.1** The contractor certifies to the best of its knowledge and belief that it and its principals are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency in accordance with Executive Order 12549 (2/18/86).
- **13.10.2** If this contract is for \$100,000 or more, and if the Contractor is a company with ten (10) or more employees, then Contractor certifies that it, and any company affiliated with it, does not boycott Israel, and will not boycott Israel during the term of this Contract. In this paragraph, the terms "company" and "boycott Israel" shall have the meanings described in Section 34.600 of the Missouri Revised Statutes.

ARTICLE 14 TERMINATION OR SUSPENSION OF THE CONTRACT

14.1 Termination by Owner for Cause

- **14.1.1** In addition to other rights and remedies granted to Owner under the Contract Documents and by law, the Owner may terminate the Contract if the Contractor:
- .1 refuses or fails to supply enough properly skilled workers, superintendents, foremen, or managers;
- .2 refuses or fails to supply sufficient or proper materials:
- .3 fails to make payment to Subcontractors for materials or labor in accordance with the respective agreements between the Contractor and the Subcontractors;
- .4 disregards laws, ordinances, rules, codes, regulations or orders of an authority having iurisdiction:
- .5 disregards the authority of the Owner's Representative, Architect, or Owner's Authorized Agent;
- breaches any warranty or representations made by the Contractor under or pursuant to the Contract Documents;
- .7 fails to furnish the Owner with assurances satisfactory to the Owner evidencing the Contractor's ability to complete the Work in compliance with all the requirements of the Contract Documents:
- .8 fails after commencement of the Work to proceed continuously with the construction and completion of the Work for more than ten (10) days, except as permitted under the Contract Documents:
- .9 fails to maintain a satisfactory rate of progress with the Work or fails to comply with approved progress schedules; or
- .10 violates in any substantial way any provisions of the Contract Documents.
- **14.1.2** When any of the above reasons exist, the Owner may, without prejudice to any other rights or remedies of the Owner, terminate this Contract by delivering a written notice of termination to Contractor and Contractor's surety, and may:
- .1 take possession of the site and of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
- .2 accept assignment of subcontracts pursuant to Paragraph 5.3; and
- finish the Work by whatever reasonable method the Owner may deem expedient, including turning the Work over to the surety.
- **14.1.3** The Contractor, in the event of a termination under Section 14.1, shall not be entitled to receive any further payments under the Contract until the Work is completed in its entirety. Then, if the unpaid balance

under the Contract shall exceed all expenses of the Owner in finishing the Work, including additional compensation for the Architects services and expenses made necessary thereby, such excess will be paid to the Contractor; but, if such expenses of Owner to finish the Work shall exceed the unpaid balance, the Contractor and its surety shall be liable for, and shall pay the difference and any damages to the Owner. The obligation of the Contractor and its surety for payment of said amounts shall survive termination of the Contract.

- **14.1.4** In exercising the Owner's right to secure completion of the Work under any of the provisions hereof, the Owner shall have the right to exercise the Owner's sole discretion as to the manner, methods, and reasonableness of costs of completing the Work.
- **14.1.5** The rights of the Owner to terminate pursuant to Article 14.1 will be cumulative and not exclusive and shall be in addition to any other remedy provided by law or the Contract Documents.
- **14.1.6** Should the Contractor fail to achieve Final Completion of the Work within thirty (30) calendar days following the date of Substantial Completion, the Owner may exercise its rights under Article 14.1.

14.2 Suspension by the Owner for Convenience

- **14.2.1** The Owner may, without cause, order the Contractor in writing to suspend, delay, or interrupt the Work in whole or in part for such period of time as the Owner may determine.
- 14.2.2 An adjustment will be made to the Contract Sum for increases in the cost of performance of the Contract caused by suspension, delay or interruption. However, in the event of a suspension under this Article 14.2, Contractor hereby waives and forfeits any claims for payment of any special, indirect, incidental or consequential damages such as lost profits, loss of savings or revenue, loss of anticipated profits, idle labor or equipment, home office overhead, and similar type damages. No adjustment will be made to the extent:
- that performance is, was, or would have been so suspended, delayed or interrupted by another cause for which the Contractor in whole or in part is responsible, or
- .2 that an equitable adjustment is made or denied under another provision of this Contract.

14.3 Owner's Termination for Convenience

- **14.3.1** The Owner may, at any time, terminate the Contract in whole or in part for the Owner's convenience and without cause. Termination by the Owner under this Paragraph shall be by a notice of termination delivered to the Contractor specifying the extent of termination and the effective date.
- **14.3.2** Upon receipt of a notice of termination for convenience, the Contractor shall immediately, in accordance with instructions from the Owner, proceed with performance

of the following duties regardless of delay in determining or adjusting amounts due under this Paragraph:

- .1 cease operation as specified in the notice;
- .2 place no further orders and enter into no further subcontracts for materials, labor, services or facilities except as necessary to complete Work not terminated;
- .3 terminate all subcontracts and orders to the extent they relate to the Work terminated;
- .4 proceed to complete the performance of Work not terminated; and
- .5 take actions that may be necessary, or that the Owner may direct, for the protection and preservation of the terminated Work.
- 14.3.3 Upon such termination, the Contractor shall recover as its sole remedy payment for Work properly performed in connection with the terminated portion of the Work prior to the effective date of termination and for items properly and timely fabricated off the Project site, delivered and stored in accordance with the Owner's instructions and for all Owner approved claims, costs, losses and damages incurred in settlement of terminated contracts with Subcontractors and suppliers. The Contractor hereby waives and forfeits all other claims for payment and damages, including, without limitation, anticipated profits, consequential damages and other economic losses.
- **14.3.4** The Owner shall be credited for (1) payments previously made to the Contractor for the terminated portion of the Work, (2) claims which the Owner has against the Contractor under the Contract and (3) the value of the materials, supplies, equipment, or other items that are to be disposed of by the Contractor that are part of the Contract Sum.
- **14.3.5** Upon determination by a court that termination of Contractor or its successor in interest pursuant to Paragraph 14.1 was wrongful, such termination will be deemed converted to a termination for convenience pursuant to Paragraph 14.3, and Contractor's sole and exclusive remedy for wrongful termination is limited to recovery of the payments permitted for termination for convenience as set forth in Paragraph 14.3.

SECTION 1.E SPECIAL CONDITIONS

1. DEFINITIONS

a. "Drawings"

Drawings referred to in and accompanying Project Manual consist of Drawings prepared by and bearing name of below defined Architect, bearing FEBRUARY 27, 2024 - CLINICAL SUPPORT AND EDUCATION BUILDING - SIM CENTER RENOVATION

b. Architect

International Architects Atelier 912 Broadway Blvd., Suite 300 Kansas City, MO 64105 P: 816-471-6522

c. Mechanical & Plumbing & Electrical Engineer IMEG Corp.
1600 Baltimore, Suite 300
Kansas City, MO 64108
P: 816-842-8437

d. Other Definitions: See Article 1., General Conditions.

2. SPECIAL SCHEDULING REQUIREMENTS (NOT USED)

3. SCOPE OF WORK

- a. The Contractor shall furnish all labor, materials, tools, equipment necessary for, and incidental to, construction of this project as indicated on Drawings and specified herein.
- b. Work shall include everything requisite and necessary to finish work properly, notwithstanding that every item of labor or materials or accessories required to make project complete may not be specifically mentioned.
- c. General Description of Work:
 - (1) Project consists of generally of the renovation of a portion of the 6th Floor of the Clinical Support & Education Building.
 - (2) Demolition shall consist of removal of flooring, ceiling, walls, doors and mechanical and electrical items within the work area.
 - (3) Architectural work shall consist of new flooring and ceiling finishes. New walls, doors, replacement of some exterior glazing.

- (4) Mechanical work shall consist of changes to ductwork and piping within the work area.
- (5) Electrical work shall consist of new lighting, power, data, and fire alarm within the work area.

4. LOCATION

Work shall be performed under this Contract on campus of the University of Missouri - Columbia, at the Clinical Support and Education Building on the sixth floor.

5. NUMBER OF CONSTRUCTION DOCUMENTS

- a. The Owner's Representative will furnish the Contractor a copy of executed Contract. Electronic copies of the Drawings and Specifications can be accessed from the Owner's projex4 website.
- b. Additional sets may be obtained from the architect at cost of reproduction.
- c. The Owner will furnish electronic copies of explanatory and changed Drawings at no cost to Contractor as issued during project.
- d. The Owner will provide electronic data files to the Contractor for their convenience and use in progressing the Work and the preparation of shop drawings or other submittal requirements required for construction of the referenced project. The electronic data files shall reflect Construction Documents and Bid Addenda only. These files will be transmitted subject to the following terms and conditions:
 - (1) The Owner makes no representation as to the compatibility of these files with the Contractor's hardware or software.
 - (2) Data contained on these electronic files shall not be used by the Contractor or anyone else for any purpose other than as a convenience in progressing the Work or in the preparation of shop drawings or other required submittals for the referenced project. Any other use or reuse by the Contractor or by others will be at their own sole risk and without liability or legal exposure to Owner. The Contractor agrees to make no claim and hereby waive, to the fullest extent permitted by law, any claim or cause of action of any nature against the Owner and its consultants, contractors, agents, employees, and representatives that may arise out of or in connection with the use of the electronic files transmitted.
 - (3) Furthermore, the Contractor shall, to the fullest extent permitted by law, indemnify and hold harmless the Owner and its consultants, contractors, agents, employees, and representatives, against all damages, liabilities or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.
 - (4) These electronic files are not contract documents. Differences may exist between these electronic files and corresponding hard-copy construction documents. The Owner makes no representation regarding the accuracy or completeness of the electronic files you receive. In the event that a conflict arises between the signed or sealed hard-copy construction documents prepared by the Consultant and the electronic files, the signed and sealed hard-copy construction documents shall govern. The Contractor is responsible for determining if any conflict exists. By

- use of these electronic files, the Contractor is not relieved of their duty to fully comply with the contract documents.
- (5) Because information presented on the electronic files can be modified, unintentionally or otherwise, the Owner reserves the right to remove all indications of ownership and/or involvement from each electronic display.
- (6) Under no circumstances shall delivery of the electronic files be deemed a sale by the Owner and no warranties are made, either expressed or implied, of merchantability and fitness for any particular purpose. In no event shall the Owner be liable for any loss of profit, or any consequential damages as a result of use or reuse of these electronic files.

6. SUBMITTALS

- a. The Contractor shall submit for approval to the Architect, equipment lists and Shop Drawings, as expediently as possible. Failure of the Contractor to submit Shop Drawings in a timely manner will result in the Owner holding back Contractor payments. (See General Conditions)
- b. The material and equipment lists shall be submitted and approved before any material or equipment is purchased and shall be corrected to as-built conditions before the completion of the project.
- c. The Contractor shall submit electronic versions of all required Shop Drawings, material and equipment lists. The Contractor shall upload all Shop Drawings to a secure information sharing website determined by the Owner notifying the Owner and Consultant that these shop drawings are available for review. Each submittal shall have the General Contractors digital stamp affixed to the first page signifying their review and acceptance. Review comments, approvals, and rejections will be posted on this same site with notification to the contractor. Submittals requiring a professional seal shall be submitted hard copy with a manual seal affixed.
 - (1) The Contractor shall identify each submittal item with the following:
 - (a) Project Title and Location
 - (b) Project Number
 - (c) Supplier's Name
 - (d) Manufacturer's Name
 - (e) Contract Specification Section and Article Number
 - (f) Contract Drawing Number
 - (g) Acrobat file name: Spec Section_Times Submitted-Spec Title: 033000 _01-Cast In Place Concrete.pdf
 - (2) Reference the accompanying Shop Drawing and Submittal Log at the end of this section (1.E.3) for required submittal information.
- d. The Contractor shall submit to the Architect four (4) bound, and one (1) electronic, copies of all required Operating Instructions and Service Manuals for the Architect's and the Owner's sole use prior to completing 50% of the adjusted contract. Payments beyond 50% of the contract amount may be withheld until all Operating Instructions and Service Manuals are received as referenced in the

accompanying Operating Instructions and Service Manual Log at the end of this section (1.E.4).

e. The Contractor shall submit to the Owner's Representative all items referenced in the accompanying Closeout Log (1.E.5) within 30 days following substantial completion of the work. The Owner's Representative will maintain the closeout log and include as an agenda item at all coordination meetings.

7. NOTIFICATION

Before beginning Demolition Work or service outages, the Contractor shall provide, at minimum, seventy-two (72) hours advance notice to Owner's Representative for purpose of verifying utility locations including, but not limited to, gas, telecommunications, electric, water, steam, sewer, and nitrogen. Contractor shall minimize the number of outages, minimize the length of outages and related work shall be continuous until the utility is restored.

8. USE OF PREMISES

a. Access: Access to construction site shall be as indicated on Drawings and as directed by the Owner's Representative.

b. Parking:

- (1) The Owner will issue Contractor two (2) service vehicle parking permits for Tiger Ave. parking structure, level 4 and above. These spaces are not available to the Contractor during any days with home Football games. The permits will be issued at no cost to the contractor up to the contract completion date. After the contract completion date, the permits will be reissued on an as available basis at the contractors' expense. These permits are to be used for general contractor or subcontractor owned and labeled vehicles only. Personal vehicles are prohibited from use of these permits. Violation of this requirement may result in ticketing and/or towing at the vehicle owner's expense and suspension of progress payments.
- (2) Parking of personal vehicles within project access/lay down/staging areas is prohibited. Violation of this requirement may result in ticketing and/or towing at the vehicle owner's expense and suspension of progress payments.
- (3) Parking or driving on sidewalks, landscaped areas, within fire and service lanes or generally in areas not designated for vehicular traffic is prohibited except as allowed in the contract documents. Violation of this requirement may result in ticketing and/or towing at the vehicle owner's expense and suspension of progress payments.
- (4) Sidewalk(s) and Hardscape Parking/driving on hardscapes is strictly prohibited unless specifically directed by the Owner's Representative through the MU sidewalk permitting process. Restricted use permits will

be limited to activities that are constrained by an absolute need to access from a sidewalk. Such activities shall be considered the exception and not the norm. Adequate signage, fencing and alternate routes must be provided in the immediate and adjacent areas.

- (5) Free parking for contractor employees is available in the Ashland Road Contractor lot on an as available basis. This space is for use by contractor employees for parking their personal vehicles only and is not to be used for staging or storage.
- (6) Vendor Permits may be purchased by contractor management personnel on an as available basis by contacting the Parking and Transportation office in the General Services Building. These permits will allow contractor management personnel to park in various University lots while conducting business on University construction projects.
- (7) Temporary University parking permits may be purchased by contractor employees for use with their personal vehicles on an as available basis by contacting the Parking and Transportation office in the General Services Building.
- (8) Conley Avenue between Missouri Avenue and University Avenue and Hitt Street between University Avenue and the Memorial Union are designated for pedestrian use only during the work week between the hours of 8:15 AM and 3:45 PM. Unless otherwise indicated in the contract documents, this area is strictly off limits to vehicular traffic without authorization from the Owner's Representative.
- c. Storage of materials: The Contractor shall store all materials within project limits. The Contractor shall confine apparatus, materials, and operation of workers to location established by the Owner's Representative. The Contractor shall not unreasonably encumber premises with materials. In addition, storage trailer locations may be available within 1-1/2 miles of project site as directed by the Owner's Representative. Storage trailer locations shall be subject to approval by the Owner's Representative and are available to the Contractor without cost.
- d. Utilities: Drinking water, water required to carry on work, and 120 volt electrical power required for small tool operation may be obtained without cost to the Contractor from existing utilities at locations designated by the Owner's Representative. Provisions for obtaining power, including temporary extensions, shall be furnished and maintained by the Contractor. Upon completion of work such extensions shall be removed and any damage caused by use of such extensions shall be repaired to satisfaction of the Owner's Representative, at no cost to the Owner.
- e. Restroom: Existing toilet facilities within Project Limits or Restrooms designated by the Owner's Representative for use by the Contractor will be available. Failure of the Contractor to maintain restrooms in a clean condition will be cause for the Contractor's discontinued use of the restroom.

- f. Smoking is prohibited at the University of Missouri and all properties owned, operated, leased or controlled by the University of Missouri. Violation of the policy is defined as smoking any tobacco products, including e-cigarettes.
- g. Landfill: The Contractor shall not use the Owner's landfill. Dumping or disposal of excavated or demolition materials on Owner's property shall not be permitted. The Contractor shall remove and legally dispose of excavated or demolished materials off the Owner's property.
- h. Care of Project Work Site: The contractor shall be responsible for maintaining the construction site in a reasonably neat and orderly condition by regular cleaning and mowing of the premises as determined by the Owner's Representative.
- i. Discharge to Sewer Request: The University of Missouri's MS4 permit and NPDES Storm Water Discharge Permits along with the City of Columbia's POTW Operating Permit as well as local ordinances, and state and federal environmental regulations prohibit hazardous materials from being disposed into either the storm water or sanitary sewer systems. Unless specifically approved, all chemical products such as paints, dyes, lawn care products, maintenance products, and oil is are prohibited from drain disposal. Any product, including contaminated water, being discarded into the storm water or sanitary sewer systems requires written approval from the Owner through a formal "Discharge to Sewer Request" form obtained at Discharge to Sewer Request Form. The contractor should submit the form to the Owner's Representative, not to the Department of Environmental Health and Safety as the form indicates.
- j. All concrete waste material including washout water shall be totally contained and removed from the Owner's property.
- k. Artifacts Found During Construction: Contractor shall immediately notify the Owner's Representative when artifacts are uncovered or found during the demolition or construction process. Artifacts include, but are not limited to, tools, drawings (construction or other), photographs, books and other objects/devices which may hold historical importance/significance. Do not remove or disturb the object(s) in question. Artifacts are not considered part of demolished materials and shall remain the property of the University of Missouri.
- 1. <u>"Permit Required Confined Space" Entry Communication and Coordination</u>
 (See OSHA 1926 subpart aa Construction Confined Space for the definition of "permit required confined spaces" Note: OSHA does not apply to the University. However, the University will provide a list of all known "permit required confined spaces")

There are no known "permit required confined spaces" within the project limits. Each contractor shall conduct a survey to confirm whether or not any confined spaces exist within the project limits. It is incumbent upon each contractor to list all "permit required spaces".

The Contractor shall notify the Owner's Representative if 1) conditions change resulting in a non-permit required confined space being reclassified to a "permit required confined space" after evaluation of the space by a competent person; 2) a space previously thought to be non-permit required space is classified as a "permit required confined space"; or 3) during the course of construction a "permit required confined space" is created after evaluation by a competent person.

The Contractor shall submit to the Owner's Representative a copy of the cancelled confined space entry permit and a written report summarizing the permit space program followed and all hazards confronted or created during entry operations. This information shall be submitted within one week of cancelling the permit.

9. PROTECTION OF OWNER'S PROPERTY

- a. The Contractor shall be responsible for repair of damage to building exterior and interior, drives, curbs, streets, walks, grass, shrubbery and trees, which was caused by workmen or equipment employed during progress of work. All such repairs shall be made to satisfaction of the Owner's Representative, at no cost to the Owner, or reimburse the Owner if the Owner elects to make repairs. For landscape damage, the Owner shall make such repairs. Compensation for these repairs shall be determined by the Owner's Representative using the "Valuation of Landscape Trees, Shrubs, and other Plants" as published by the International Society of Arboriculture, as last revised.
 - (1) Fencing will not be required as a part of work.

10. SUBSTITUTIONS and EQUALS

- a. Substitutions are defined in General Conditions article 3.11.8 for and Equals are defined General Conditions Article 3.12.
- b. Use of materials, products or equipment other than those named and described in the Contract Documents are substitutions and/or equal. Substitutions and/or equals submitted during the bidding period shall be received by both the Architect and the Owner at least ten calendar days prior to the date for receipt of bids. To be considered, bidder's proposal shall include a complete description of the proposed substitution and/or equal and a comparison of significant qualities of the proposed substitution and/or equal with those specified including drawings, performance and test data, and other information necessary for an evaluation. The Architect's decision on the approval or disapproval of a proposed substitution and/or equal shall be final.
- c. If the Architect and Owner approve a proposed substitution prior to receipt of Bids, such approval will be set forth in an Addendum. Bidders shall not rely upon approval made in any other manner.
- d. No substitutions and/or equal will be allowed for the following items:

Item Specification Section

11. CODES AND STANDARDS

The Contractor shall comply with applicable codes and standards as listed in General Conditions.

- 12. PERMITS (NOT USED)
- 13. SPECIALTIES (NOT USED)
- 14. PRE-BID INSPECTION

All pre-bid inspections of work areas shall be scheduled with pre-bid inspection guide, telephone: (573) 882-2228.

- 15. ROOF WARRANTY REQUIREMENT (NOT USED)
- 16. MODIFICATIONS TO INFORMATION TO BIDDERS (NOT USED)
- 17. MODIFICATION TO INFORMATION FOR BIDDERS: BIDDERS STATEMENT OF QUALIFICATIONS (NOT USED)
- 18. MODIFICATIONS TO GENERAL CONDITIONS (NOT USED)

19. PROJECT SCHEDULING

The project scheduling specification for the project are included immediately after the Special Conditions. For this project the Contractor shall meet the following scheduling requirements.

Option 1: Contractor Schedule (Small Projects only) – Contractor is responsible for the schedule and must comply with the Owner's requirements. See Contractor Schedule Specification included in these documents.

20. PROJECT COORDINATION

Coordination between CP232661 MUTH Nitrogen Generator Replacement, CP241261 CCA Generator Exhaust Stack Replacement, CP245251 UMTH Bulk Oxygen Storage Facility Concrete Pad Replacement and MUHC daily operations. Dumpster location shall be coordinated with the Owner's Representative.

- 21. PROJECT PARTNERING (NOT USED)
- 22. VALUE ENGINEERING (NOT USED)
- 23. BUILDING SYSTEM COMMISSIONING

- a. Contractor shall provide all personnel and equipment required to complete the commissioning activities referenced in the Commissioning Plan. The requirements of the commissioning plan shall be completed in their entirety before substantial completion and submitted as referenced in the Closeout Log.
- b. The contractor shall designate a competent person, separate from the superintendent or Project Manager, to act as the contractor's commissioning coordinator. The commissioning coordinator is responsible for planning, scheduling, coordinating, conducting and verifying all commissioning activities required by the commissioning plan and ensuring all building systems are complete, operable and ready for use by the Owner. At a minimum, building ventilation systems, chilled/hot water generation systems, hydronic distribution systems, power distributions systems and fire detection and alarm systems, as applicable.

24. MECHANICAL, ELECTRICAL, PLUMBING (MEP) PRE-INSTALLATION MEETING(S)

- a. Before the start of MEP installation, the Owner's Representative will convene an MEP pre-installation meeting. Meeting participants to include contractor (including MEP subcontractors), Owner's Representative and additional contractor and University operational staff invited by the Owner's Representative. Topics will include sprinkler piping, hot water piping, electrical system, duct, telephone/data wiring, control wiring. Additional meetings will be conducted as required for the review of coordination drawings and scope specific installations. Cross section drawings of corridor ceilings and other congested areas will be of highest priority and will be reviewed prior to the start of installations in the affected areas. Meeting minutes and sign-up sheet will be transcribed by contractor and distributed to attendees.
- 25. COST BREAKOUT FOR OWNER'S ACCOUNTING PURPOSES (NOT USED)
- 26. PROJECT MANAGEMENT/COMMUNICATION REQUIREMENTS (NOT USED)
- 27. SAFETY PRECAUTIONS AND PROGRAMS (NOT USED)
- 28. HOT WORK PERMITTING AND GENERAL REQUIREMENTS

Hot work Requirements: The contractor shall comply with the following hot work requirements and the requirements of the International Fire Code and 2014 NFPA 51B.

- a. Hot work shall be defined as any work involving burning, welding, grinding, cutting, or similar operations that are capable of initiating fires or explosions.
- b. The Contractor shall utilize the hot work permit decision tree and permit provided in the 2014 NFPA 51B for all Hot Work operations.
- c. A hot work permit shall be used on all hot work performed outside a designated hot work area. The hot work permit shall be posted and clearly visible within proximity

of the hot work area. The hot work permit authorizing individual (PAI) shall be as designated by the Contractor.

- d. Notify the Owner's Representative 24 hours prior to starting hot work in buildings with operational fire alarm or fire suppression systems. The Owner's Representative will coordinate the appropriate system outage with Campus Maintenance personnel.
- e. Unless otherwise instructed by the Owner's Representative, the Contractor shall post a copy of each completed hot work permit to the Owner's project management file system the following business day.

29. GENERAL REQUIREMENTS FOR CRANE AND HOISTING OPERATIONS

All crane and hoisting operations shall be performed in compliance with OSHA 29 CFR 1926. All Operators, riggers, and signal persons must have the proper qualifications and training necessary to perform the intended hoisting activities for this project.

- a. Only fully certified and evaluated Operators shall perform equipment operations. Operators in an "Operator in Training" status shall not be used.
- b. Submittal requirements:
 - 1. Submit copies of Operator certifications, licenses, and evaluations to the Owners Representative.
 - 2. Submit Rigger and Signal Person qualifications to the Owners Representative.
 - 3. Unless otherwise directed by the Owners Representative, submit a lift plan and conduct a lift coordination meeting for hoisting or crane operations for any lift greater than 2,000 pounds, or for any multi pick lift. Include protective measures for existing underground utilities, occupied buildings, pedestrian and vehicle pathways, adjacent buildings and overhead power lines. If the lift is to occur over an occupied building, provide a registered structural engineer's review and verification that the building can resist the impact of a dropped load for the intended lift. If evacuation of an occupied building is necessary to conduct the lift, the decision for building evacuation or scheduling the lift for off-hours will be determined by the Owner.

30. CONSTRUCTION WASTE MANAGEMENT (NOT USED)

31. WARRANTY WALKTHROUGH

Contractor shall attend a walk-thru with the Owner at 11 months after acceptance to review and document any warranty items to be addressed as part of the 12 month warranty stated in article 3.1 of the General Conditions.

END OF SECTION

Option #1 – Contractor Schedule

1. GENERAL

a) Time is of the essence for this contract.

The time frames spelled out in this contract are essential to the success of this project. The University understands that effective schedule management, in accordance with the General Conditions and these Special Conditions is necessary to insure to that the critical milestone and end dates spelled out in the contract are achieved.

b) Related Documents

Drawings and general provisions of the Contract, including General Conditions' Article 3.17 shall apply to this Section.

c) Stakeholders

A Stakeholder is anyone with a stake in the outcome of the Project, including the University, the University Department utilizing the facility, the Design Professionals, the Contractor and subcontractors.

- d) Weather
 - (1) Contractor acknowledges that there will be days in which work cannot be completed due to the weather, and that a certain number of these lost days are to be expected under normal weather conditions in Missouri.
 - (2) Rather than speculate as to what comprises "normal" weather at the location of the project, Contractor agrees that it will assume a total of 44 lost days due to weather over the course of a calendar year, and include same in its as planned schedule. For projects of less than a calendar year, lost weather days should be prorated for the months of construction in accordance with the following schedule.
 - (3) Anticipated weather days for allocation/proration only. For projects lasting 12 months or longer, the 44 days per year plus whatever additional months are included will constitute normal weather.

Jan – 5 days	Feb – 5 days	Mar – 4 days	Apr – 4 days
May – 3 days	Jun – 3 days	Jul – 2 days	Aug – 2 days
Sep – 3 days	Oct – 4 days	Nov – 4 days	Dec – 5 days

2. SCHEDULING PROCESS

a) The intent of this section is to insure that a well-conceived plan, that addresses the milestone and completion dates spelled out in these documents, is developed with input from all stakeholders in the project. Input is limited to all reasonable requests that are consistent with the requirements of the contract documents, and do not prejudice the Contractor's ability to perform its work consistent with the contract documents.

Further, the plan must be documented in an understandable format that allows for each stakeholder in the project to understand the plan for the construction and/or renovation contained in the Project.

b) Contractor Requirements

(1) Schedule Development

Contractor shall prepare the Project Schedule using Primavera SureTrack or P3, Microsoft Project, Oracle P6, or other standard industry scheduling software, approved by the Owner's Representative.

(2) Schedule Development

Within 2 weeks of the NTP, contractor shall prepare a schedule, preferably in CPM format, but in detailed bar chart format at a minimum, that reflects the contractor's and each subcontractors plan for performing the contract work.

SS-1

Contractor shall review each major subcontractor's schedule with the sub and obtain the subcontractor's concurrence with the schedule, prior to submitting to the University.

(3) Schedule Updates.

- (a) Schedule Updates will be conducted once a month, at a minimum.

 Actual Start and Finish dates should be recorded regularly during the month. Percent Complete, or Remaining Duration shall be updated as of the data date, just prior to Contractor's submittal of the update data.
- (b) Contractor will copy the previous months schedule and will input update information into the new monthly update version.
- (c) Contractor will meet with the Owner's Representative to review the draft of the updated schedule. At this meeting, Owner's Representative and Contractor will:
 - (i) Review out of sequence progress, making adjustments as necessary,
 - (ii) Add any fragnets necessary to describe changes or other impacts to the project schedule and
 - (iii) Review the resultant critical and near critical paths to determine any impact of the occurrences encountered over the last month.

(4) Schedule Narrative

After finalization of the update, the Contractor will prepare a Narrative that describes progress for the month, impacts to the schedule and an assessment as to the Contractor's entitlement to a time extension for occurrences beyond its control during the month and submit in accordance with this Section.

(5) Progress Meetings

- (a) Review the updated schedule at each monthly progress meeting. Payments to the Contractor may be suspended if the progress schedule is not adequately updated to reflect actual conditions.
- (b) Submit progress schedules to subcontractors to permit coordinating their progress schedules to the general construction work. Include 4 week look ahead schedules to allow subs to focus on critical upcoming work.

3. CRITICAL PATH METHOD (CPM)

- a) This Section includes administrative and procedural requirements for the critical path method (CPM) of scheduling and reporting progress of the Work.
- b) Refer to the General and Special Conditions and the Agreement for definitions and specific dates of Contract Time.
- c) Critical Path Method (CPM): A method of planning and scheduling a construction project where activities are arranged based on activity relationships and network calculations determine when activities can be performed and the critical path of the Project.
- d) Critical Path: The longest continuous chain of activities through the network schedule that establishes the minimum overall project duration.
- e) Network Diagram: A graphic diagram of a network schedule, showing the activities and activity relationships.
- f) Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling, the construction project. Activities included in a construction schedule consume time and resources.
- g) Critical activities are activities on the critical path.
- h) Predecessor activity is an activity that must be completed before a given activity can be started.
- i) Milestone: A key or critical point in time for reference or measurement.

Option 1 SS-2

- j) Float or Slack Time: The measure of leeway in activity performance. Accumulative float time is not for the exclusive use or benefit of the Owner or Contractor, but is a project resource available to both parties as needed to meet contract milestones and the completion date.
- k) Total float is herein defined as the measure of leeway in starting or completing an activity without adversely affecting the planned project completion date.
- 1) Weather: Adverse weather that is normal for the area must be taken into account in the Contractor's Project Schedule. See 1.d.3, above.
- m) Force Majeure Event: Any event that delays the project but is beyond the control and/or contractual responsibility of either party.
- n) Schedule shall including the following, in addition to Contractor's work.
 - (1) Phasing: Provide notations on the schedule to show how the sequence of the Work is affected by the following:
 - (a) Requirements for phased completion and milestone dates.
 - (b) Work by separate contractors.
 - (c) Work by the Owner.
 - (d) Coordination with existing construction.
 - (e) Limitations of continued occupancies.
 - (f) Uninterruptible services.
 - (g) Partial occupancy prior to Substantial Completion.
- o) Area Separations: Use Activity Codes to identify each major area of construction for each major portion of the Work. For the purposes of this Article, a "major area" is a story of construction, a separate building, or a similar significant construction element.

4. TIME EXTENSION REQUEST

- a) Refer to General Conditions of the Contract for Construction, Article 4.7 Claims for Additional Time.
- b) Changes or Other Impacts to the Contractor's Work Plan
 - The Owner will consider and evaluate requests for time extensions due to changes or other events beyond the control of the Contractor on a monthly basis only, with the submission of the Contractor's updated schedule, in conjunction with the monthly application for payment. The Update must include:
 - (1) An activity depicting the event(s) impacting the Contractors work plan shall be added to the CPM schedule, using the actual start date of the impact, along with actually required predecessors and successors.
 - (2) After the addition of the impact activity(ies), the Contractor will identify subsequent activities on the critical path, with finish to start relationships that can be realistically adjusted to overlap using good, standard construction practice.
 - (a) If the adjustments above result in the completion date being brought back within the contract time period, no adjustment will be made in the contract time.
 - (b) If the adjustments above still result in a completion date beyond the contract completion date, the delay shall be deemed excusable and the contract completion date shall be extended by the number of days indicated by the analysis.
 - (c) Contractor agrees to continue to utilize its best efforts to make up the time caused by the delays. However the Contractor is not expected to expend costs not contemplated in its contract, in making those efforts.
- c) Questions of compensability of any delays shall be held until the actual completion of the project. If the actual substantial completion date of the project based on excusable delays, excluding weather delays, exceeds the original contract completion date, AND there are no delays that are the responsibility of the contractor to consider, the delays days shall be considered compensable. The actual costs, if any, of the Contractor's time sensitive jobsite supervision and general conditions costs, shall be quantified and a change order issued for these costs.

Option 1 SS-3

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
024119	SELECTIVE DEMOLITION										
	Proposed Protection Measures										
	Predemolition Photos										
061000	ROUGH CARPENTRY										
	Product Data										
064023	INTERIOR ARCHITECTURAL WOODWORK										
	Product Data										
	Shop Drawings										
	Samples										
079200	JOINT SEALANTS										
	Product Data										
081213	HOLLOW METAL FRAMES										
	Product Data										
	Shop Drawings										
	Product Schedule										
081416	FLUSH WOOD DOORS										
	Product Data										
	Shop Drawings										
	Samples										

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
087100	DOOR HARDWARE										
	Product Data										
	Hardware Schedule										
088000	GLAZING										
	Product Data										
092216	NON-STRUCTURAL METAL FRAMING										
	Product Data										
	Evaluation Reports										
092900	GYPSUM BOARD										
	Product Data										
095113	ACOUSTICAL PANEL CEILINGS										
	Product Data										
	Samples										
	Evaluation Reports										
096513	RESILIENT BASE AND ACCESSORIES										
	Product Data										
	Samples										

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
096516	RESILIENT SHEET FLOORING										
	Product Data										
	Shop Drawings										
	Samples										
	Qualification Data										
096813	TILE CARPETING										
	Product Data										
	Samples										
	Qualification Data										
	Product Test Reports										
099123	INTERIOR PAINTING										
	Product Data										
	Samples										
102600	WALL AND DOOR PROTECTION										
	Product Data										
_	Samples										_
	Material Certificates										

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
122413	ROLLER WINDOW SHADES										
	Product Data										
	Shop Drawings										
	Samples										
	Product Certificates										
210500	COMMON WORK RESULTS FOR FIRE SUPPRESSION										
	Product Data										
	Welding Certificates										
211313	WET-PIPE SPRINKLER SYSTEMS										
	Product Data										
	Shop Drawings										
	Delegated-Design Submittal										
	Coordination Drawings										
	Qualification Data										
	Approved Sprinkler Piping Drawings										
	Welding Certificates										
_	Fire-Hydrant Flow Test Report									_	

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
	Field Test Reports and Certificates										
	Field Quality-Control Reports										
220500	COMMON WORK RESULTS FOR PLUMBING										
	Product Data										
220523	GENERAL-DUTY VALVES FOR PLUMBING PIPING										
	Product Data										
220529	HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT										
	Product Data										
	Welding Certificates										
220553	IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT										
	Product Data										
	Equipment Label Schedule										
	Valve Numbering Scheme										
	Valve Schedules										
220700	PLUMBING INSULATION										
	Product Data										
	Shop Drawings										

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
221116	DOMESTIC WATER PIPING										
	Product Data										
	Field Quality-Control Reports										
221316	SANITARY WASTE AND VENT PIPING										
	Product Data										
	Field Quality-Control Inspection and Test Reports										
226113	COMPRESSED-AIR PIPING FOR LABORATORY AND HEALTHCARE FACILITIES										
	Product Data										
	Shop Drawings										
	Piping Material Certification										
	Qualification Data										
	Brazing Certificates										
	Field Quality-Control Test Reports										
226213	VACUUM PIPING FOR LABORATORY AND HEALTHCARE FACILITIES										
	Product Data										
	Shop Drawings										
	Piping Material Certification										

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
	Qualification Data										
	Brazing Certificates										
	Field Quality-Control Test Reports										
226313	GAS PIPING FOR LABORATORY AND HEALTHCARE FACILITIES										
	Product Data										
	Shop Drawings										
	Piping Material Certification										
	Qualification Data										
	Brazing Certificates										
	Manufacturer Seismic Qualification Certification										
	Certificates of Shop Inspection and Data Report for Bulk Gas Storage Tanks										
	Field Quality-Control Test Reports										
230500	COMMON WORK RESULTS FOR HVAC										
_	Product Data										
	Welding Certificates										
230523	GENERAL-DUTY VALVES FOR HVAC PIPING										
	General										

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
	Product Data										
230529	HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT										
	Product Data										
	Welding Certificates with Picture ID										
230553	IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT										
	Product Data										
	Equipment Label Schedule										
	Valve Numbering Scheme										
	Valve Schedules										
230700	HVAC INSULATION										
	Product Data										
230900	CONTROL SYSTEMS										
	Shop Drawings										
	Product Data										
	Schematic Flow Diagrams										
	Label Each Control Device										
	Indicate All Required Electrical Wiring										

			D.		D. C.	D.		D /		Copies	
Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	To Owner	File
	Provide Details of Faces on Control Panels										
	Written Description of Sequence of Operation										
	Wiring Diagrams of Contractor Provided Interface and I/O Panels										
	Field Routing of Proposed Network Bus Diagram										
232113	HYDRONIC PIPING										
	General										
	Product Data										
	Shop Drawings										
	Field Test Reports										
233113	METAL DUCTS										
	Product Data										
	Shop Drawings										
	Coordination Drawings										
	Field Quality-Control Reports										
233300	AIR DUCT ACCESSORIES										
	Product Data										
	Shop Drawings					_					

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
	Coordination Drawings										
	Source Quality-Control Reports										
233600	AIR TERMINAL UNITS										
	Product Data										
	Shop Drawings										
	Coordination Drawings										
	Field Quality-Control Reports										
233713	DIFFUSERS, REGISTERS, AND GRILLES										
	Product Data										
	Coordination Drawings										
260519	LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES										
	Product Data										
	Field Quality-Control Test Reports										
260526	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS										
	Product Data										
	Field Quality-Control Test Reports										

			Date		Date Sent	Date		Date		Copies To	
Section	Description	Contractor	Rec'd	#	to Cons.	Ret'd	Remarks	ret'd	Cont'r	Owner	File
260529	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS										
	Product Data										
	Shop Drawings										
	Welding Certificates										
260533	RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS										
	Product Data										
	Shop Drawings										
	Coordination Drawings										
260553	IDENTIFICATION FOR ELECTRICAL SYSTEMS										
	Product Data										
	Identification Schedule										
260573	OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY AND ARC FLASH HAZARD ANALYSIS										
	Product Data										
	Product Certificates										
	Qualification Data										
	Studies Submitted										
	Preliminary Arc Flash Hazard Analysis										

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
	Final Short-Circuit, Protective Device Coordination and Arc Flash Hazard Analysis Studies										
	Other Action Submittals										
260923	LIGHTING CONTROL DEVICES										
	Product Data										
	Shop Drawings										
	Field Quality-Control Test Reports										
262726	WIRING DEVICES										
	Product Data										
	Shop Drawings										
	Field Quality-Control Test Reports										
265100	INTERIOR LIGHTING										
	Product Data										
	Coordination Drawings										
	Field Quality-Control Test Reports										
270500	COMMON WORK RESULTS FOR COMMUNICATIONS										
	Product Data										

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
271500	COMMUNICATIONS HORIZONTAL CABLING										
	Product Data										
	Qualification Data										
280500	COMMON WORK RESULTS FOR ELECTRONIC SAFETY AND SECURITY										
	Product Data										
280513	CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY										
	Product Data										
	Shop Drawings										
	Qualification Data										
	Field Quality-Control Test Reports										
283111	DIGITAL, ADDRESSABLE FIRE- ALARM SYTEM										
	General Submittal Requirements										
	Product Data										
	Shop Drawings										
	Qualification Data										
	Proposed Vendors Ability to Respond										
	Seismic Qualification Certificates										

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Contractor	Date Rec'd	#	Date Sent to Cons.	Date Ret'd	Remarks	Date ret'd	Cont'r	Copies To Owner	File
	Field Quality-Control Reports										

OPERATING INSTRUCTIONS AND SERVICE MANUAL LOG

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Catalog Data	Wiring Diagrams	Installation Instructions	Service & Maintenance Instructions	Parts List & Availability	PerformanceC urves	Startup & Operating Instructions
064023	INTERIOR ARCHITECTURAL WOODWORK							
	Maintenance Data							
095113	ACOUSTICAL PANEL CEILINGS							
	Maintenance Data							
096516	RESILIENT SHEET FLOORING							
	Maintenance Data							
096813	TILE CARPETING							
	Maintenance Data							
102600	WALL AND DOOR PROTECTION							
	Maintenance Data							
122413	ROLLER WINDOW SHADES							
	Maintenance Data							
211313	WET-PIPE SPRINKLER SYSTEMS							
	Operation and Maintenance Data							
226113	COMPRESSED-AIR PIPING FOR LABORATORY AND HEALTHCARE FACILITIES							
	Operation and Maintenance Data							

OPERATING INSTRUCTIONS AND SERVICE MANUAL LOG

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Catalog Data	Wiring Diagrams	Installation Instructions	Service & Maintenance Instructions	Parts List & Availability	PerformanceC urves	Startup & Operating Instructions
226213	VACUUM PIPING FOR LABORATORY AND HEALTHCARE FACILITIES							
	Operation and Maintenance Data							
226313	GAS PIPING FOR LABORATORY AND HEALTHCARE FACILITIES							
	Operation and Maintenance Data							
230523	GENERAL-DUTY VALVES FOR HVAC PIPING							
	Maintenance Data for Valves							
232113	HYDRONIC PIPING							
	Maintenance Data for Hydronic Specialties							
233300	AIR DUCT ACCESSORIES							
	Operation and Maintenance Data							
233600	AIR TERMINAL UNITS							
	Operation and Maintenance Data							
260526	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS							
	Operation and Maintenance Data							
260923	LIGHTING CONTROL DEVICES							
	Operation and Maintenance Data							

OPERATING INSTRUCTIONS AND SERVICE MANUAL LOG

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Catalog Data	Wiring Diagrams	Installation Instructions	Service & Maintenance Instructions	Parts List & Availability	PerformanceC urves	Startup & Operating Instructions
262726	WIRING DEVICES							
	Operation and Maintenance Data							
265100	INTERIOR LIGHTING							
	Operation and Maintenance Data							
280513	CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY							
	Maintenance Data							
283111	DIGITAL, ADDRESSABLE FIRE-ALARM SYTEM							
	Operation and Maintenance Data							
	Software and Firmware Operational Documentation							

CLOSEOUT LOG

Project: Clinical Support and Education Building - SIM Center Renovation Project Number: CP242241

Section	Description	Contractor/Subcontractor	Date Rec'd	# of Copies	CPM Initials	Remarks
GC /3.11	As-built drawings					
GC /13.5.6	Final Affidavit of Supplier Diversity Participation for each Diverse firm					
SC/20	Executed commissioning plan w/ required documentation					
091416	FLUSH WOOD DOORS					
	Warranty					
088000	GLAZING					
	Warranty					
095113	ACOUSTICAL PANEL CEILINGS					
	Extra Materials					
096513	RESILIENT BASE AND ACCESSORIES					
	Extra Materials					
096516	RESILIENT SHEET FLOORING					
	Extra Materials					
096813	TILE CARPETING					
	Extra Materials					

CLOSEOUT LOG

Section	Description	Contractor/Subcontractor	Date Rec'd	# of Copies	CPM Initials	Remarks
099123	INTERIOR PAINTING					
	Extra Materials					
102600	WALL AND DOOR PROTECTION					
	Warranty					
265100	INTERIOR LIGHTING					
	Warranties					

CP242241 CSE 6th Floor Sim Center Rnvation Commissioning Checklist

					8	
Vo Commissioning Items by CSI Division	erified by: Name	Firm	Date compl	Coord Initial	Documentation Required	Owner Witness Required
1						
Building System Commissioning						
Commissioning Agent - Conduct pre-installation meetings per specifications.					Meeting Minutes	✓
24119					- I	
Selective Demolition						
Do not start demolition until utility disconnect and sealing has been verified in writing						✓
79200			<u> </u>			
Joint Sealants						
Clean out joints immediately before installing joint sealant						✓
81213			<u> </u>			
Hollow Metal Frames						
Inspect label for fire rated doors and frames					itemized list of doors	✓
81416				ı		
Flush Wood Doors						
Inspect label for fire rated doors and frames					Door List	✓
87100				1	1	
Door Hardware						
Perform Demonstration and Training section of specifications					Sign-in Sheet	✓
Perform Field Quality Control section of specifications					Test Report	✓

2/20/2024

V	erified by:		Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
Verify that all fire doors close and latch positively					test report	
88000				<u> </u>		
Glazing						
Wash clear glass on both faces not more than 4 days prior to punch list inspection						
92900			<u> </u>	•	•	
Gypsum Board						
Verify fire rating compliance is maintained, including all wall penetrations. Ensure walls stenciled as specified					inspection report	✓
95113					-	
Acoustical Panel Ceilings						
Complete all above ceiling inspections prior to installation of tiles						✓
Provide Extra Material as specified					Transmittal	✓
96513						
Resilient Base and Accessories						
Provide Extra Material as specified					Transmittal	✓
96516				1		
Resilient Sheet Flooring						
Perform pH, Chloride (moisture) and bond tests per manufacturer. Do not proceed until all manufacturing requirements are met.					test reports	V
Provide Extra Material as specified					Transmittal	✓

2/20/2024 COM 2 of 12

Ve	erified by:		Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
96813						
Tile Carpeting						
Provide Extra Material as specified					Transmittal	✓
99123						
Interior Painting						
Periodically Check Wet Film Thickness To Assure Conformance With Manufacturer's Requirements To Achieve Dry Film Thickness					field report	✓
Provide Extra Material as specified					Transmittal	✓
122413			<u> </u>			
Roller Window Shades						
Provide factory training per demonstration section of specificaitons					Sign-in Sheet	✓
211313				•		
Wet-Pipe Sprinkler Systems						
Perform Field Quality Control section of specifications					NFPA 13 Certification	✓
Provide Extra Material as specified					Transmittal	✓
Provide system operation & maintenance training Per specifications					Sign In Sheet	✓
220500				1		
Common Work Results For Plumbing						
Hold MEP pre-installation meeting(s).					Meeting Minutes and Sign- Sheet	up 🗸

2/20/2024 COM 3 of 12

Ve	erified by:		Date	Coord	Documentation	Owner Witnes
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
220523						
General Duty Valves for Plumbing Piping						
Check valves for leaks and replace in necessary						
220553						
Identification for Plumbing Piping and Equipment						
Install valve tags on valves and control devices per specifications					Valve Schedule framed/poste	d
220700				<u> </u>	1	
Plumbing Insulation						
Perform Field Quality Control section of specifications					Test Report	✓
Verify all valve stems are extended and accessible						
		<u> </u>	I		<u> </u>	
Domestic Water Piping						
Perform Disinfection of Domestic Water Piping System section of specifications					Bacteria test results	✓
Perform Field Quality Control section of specifications					Test Report	V
Provide pressure testing per Field Quality Control section of specifications					test report	✓
221316			I	•	1	
Sanitary Waste and Vent and Storm Piping						
Verify rough-in complete prior to slab pour or wall installation						✓

2/20/2024 COM 4 of 12

Verified by:			Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl		Required	Required
Sanitary Waste and Vent Piping						
Perform leak test per Field Quality Control section of specifications					test report	✓
226113				1		
Compressed-Air Piping for Laboratory and Healthcare Facilities						
Perform Field Quality Control section of specifications					Test Report	✓
Provide Extra Materials as specified					Transmittal	✓
Provide factory training per Demonstration section of spec					Sign In Sheet	✓
226213				1		
Vacuum Piping for Laboratory and Healthcare Facilities						
Perform Field Quality Control section of specifications					Test Report	✓
Provide Extra Materials as specified					Transmittal	✓
226313		<u>I</u>		1	1	
Gas Piping for Laboratory and Healthcare Facilities						
Perform Field Quality Control for Healthcare Facility Medical Gas section of specifications					Test Report	✓
Provide factory training per Demonstration section of specifications					Sign In Sheet	✓

2/20/2024 COM 5 of 12

Verified by:			Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
230500						
Common Work Results for HVAC						
Hold MEP pre-installation meeting(s).					Meeting Minutes	✓
Install equipment to provide maximum possible headroom if mounting heights are not indicated.						
Train all End Users on the equipment they will use on a periodic basis.					Sign-in Sheet	✓
230523			•	•		
General Duty Valves for HVAC Piping						
Test and adjust valves per specifications						
230553				•		
Identification for HVAC Piping and Equipment						
Install pipe markers per specifications						
230593						
Testing, Adjusting and Balancing for HVAC Piping						
Hold Prebalancing conference as specified					Meeting Minutes	✓
Perform Section 1.2 C 4 of spec before TAB commences						
Place outlet dampers in full open position						
Provide a complete set of as-builts prior to testing						

2/20/2024 COM 6 of 12

Verified by:			Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
Supply control diagram					control diagram	
Verify TAB Engineer notified of differences between design and installed equipment						
230700				·		
HVAC Insulation						
Perform Field Quality Control section of specifications					Test Report	✓
Verify all piping unions are accessible for maintenance						
Verify proper insulation used for piping and duct work						
230900		•	I		•	
Control Systems						
Check and record amp draw on supply transformers of I/O panels					Test Report	✓
Ensure shipping material has been removed from thermostats and other control devices						
Post laminated control diagram in mechanical room						
Provide factory authorized training for maintenance personnel					training report summary	V
232113						
Hydronic Piping						
Furnish Extra Material as specified					Transmittal	✓

2/20/2024 COM 7 of 12

Verified by:			Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
Pressure test piping per Field Quality Control section of specifications					test report	✓
233113			L	1	L	
Metal Ducts						
test for duct leakage per "Field Quality Control" section of spec. Ducts shall meet leakage requirement prior to testing and balancing. Leakage Class of 4					test report	✓
233300						
Air Duct Accessories						
Demonstrate Proper Operation of All Fire Dampers per NFPA-90A.					Inspection report	~
Perform Field Quality Control section of specifications					Test Report	V
Provide Extra Materials as specified					Transmittal	✓
233600						
Air Terminal Units						
Notify owner's rep after fully installing a representative unit (in-place mockup) for approval. Coordinate and cooperate with owner's commissioning of the boxes.						
Perform Commissioning section of specifications					Commissionig Report	✓
Perform Field Quality Control section of specifications					Test Report	✓
260500				•		
Common Work Results for Electrical						
Train all End Users on the equipment they will use on a periodic basis per Demonstration section of specifications					Sign-in Sheet	V

2/20/2024 COM 8 of 12

	Verified by:		Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
Verify that every penetration through fire walls (re: life safety plans) has been properly firestopped					certification	
260505				•	•	
Electrical Testing						
Perform General Testing Section of specifications					Test Report	✓
Perform Lighting Test Section of specifications					Test Report	✓
Perform Motor Test Section of specifications					Test Report	✓
Perform Wiring Test Section of specifications			†		Commissioning Report	V
260519						
Low-Voltage Electrical Power Conductors and Cables						
Ensure wires are color coded per specifications						
Perform independent tests per "Field Quality Control" section of spec, including megohm/high pot tests					test report	
260526			•	•	•	
Grounding and Bonding for Electrical Systems						
Perform resistance test as described in "Field Quality Control" section of spec					test report	✓
260553			•		•	
Identification for Electrical Systems						
Ensure identification devices are applied per specifications						

2/20/2024 COM 9 of 12

Verified by:			Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
Verify all equipment, panels, conduits and conductors are correctly labeled.						
260573			<u> </u>	•	L	
Overcurrent Protective Device Coordination Study and Arc Flash Hazard Analysis						
Factory certified technician to set electronic overcurrent devices to approved coordination study setpoints					Inspection Report	✓
Perform 'Testing' section of specifications					Test Report	V
Place arcflash labels on equipment as specified						V
SKM data to be e-mailed to MU Commissioning Engineer					SKM Data	V
Train owners representatives in setting of overcurrent devices					Sign-up Sheet	✓
260923			!	<u> </u>		
Lighting Control Devices						
Perform tests as noted in "Field Quality Control" section of spec					field report	✓
Provide factory training per Demonstration section of spec.					Sign in sheet	V
262726				•		
Wiring Devices						
Furnish Extra Materials as specified					Transmittal	✓


2/20/2024 COM 10 of 12

	Verified by:		Date	Coord	Documentation	Owner Witness
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required
Perform checks per "Field Quality Control" section of spec					Test Report	✓
265100			·	1		
Interior Lighting						
Illuminate emergency lights for 90 minutes on battery power.					Test Report	✓
Illuminate exit lights for 90 minutes on battery power.					Test Report	✓
Perform checks per "Field Quality Control" section of spec					Test Report	✓
280513			l .	1	· ·	
Conductors and Cables for Electronic Safety and Security						
Perform checks per "Field Quality Control" section of spec					Test Report	✓
283111			•	•	•	
Digital, Addressable Fire-Alarm System						
Perform checks per "Field Quality Control" section of spec					NFPA 72 Certification	✓
Precheck all fire alarm devices					Precheck Checklist	
Provide Extra Material as specified					Transmittal	V
Provide factory training per Demonstration section of spec.					Sign in sheet	✓
Fest each system for continuity					†	

2/20/2024 COM 11 of 12

Verified by:			Date	Coord	Documentation	Owner Witness	
Commissioning Items by CSI Division	Name	Firm	compl	Initial	Required	Required	
Test system operation of pull stations horns/strobes by factory trained representative					Written certification of fire alarm system per NFP	V	
Verify battery power available							
Verify door hardware interlock						V	

2/20/2024 COM 12 of 12



SECTION 1.F

INDEX OF DRAWINGS

Drawings referred to in and accompanying Project Manual consist of following sheets **February 27, 2024.**

G000	COVER SHEET
G001	GENERAL INFORMATION
G002	LIFE SAFETY PLAN / CODE ANALYSIS
D100	DEMOLITION ELOOP DI ANI AND CEILING DI ANG
D100	DEMOLITION FLOOR PLAN AND CEILING PLANS
D800	DEMOLITION PHOTOGRAPHS
D801	DEMOLITION PHOTOGRAPHS
A100	FLOOR PLAN
A400	CEILING PLAN
A520	SECTION DETAILS
A600	INTERIOR ELEVATIONS
A700	DOOR SCHEDULE & FINISH SCHEDULE
11/00	DOOK SCHEDOLL & THUSH SCHEDOLL
M000	MECHANICAL COVER SHEET
F206	6TH FLOOR FIRE PROTECTION PLAN
P106	6TH FLOOR DEMO PLAN – PLUMBING & MED GAS
P206	6TH FLOOR PLAN – PLUMBING & MED GAS
M106	6TH FLOOR DEMOLITION PLAN – PIPING
M116	6TH FLOOR DEMOLITION PLAN – VENTILATION
M206	6TH FLOOR PLAN – PIPING
M216	6TH FLOOR PLAN – VENTILATION
M400	MECHANICAL DETAILS
M600	MECHANICAL SCHEDULES & TEMP CONTROLS
Food	ELECTRICAL COVER GUEET
E000	ELECTRICAL COVER SHEET
E106	6TH FLOOR DEMOLITION PLAN – LIGHTING
E116	6TH FLOOR DEMOLITION PLAN – POWER
E126	6TH FLOOR DEMOLITION PLAN – SYSTEMS
E206	6TH FLOOR PLAN – LIGHTING
E216	6TH FLOOR PLAN – POWER
E226	6TH FLOOR PLAN – SYSTEMS
E400	ELECTRICAL DETAILS
E600	ELECTRICAL SCHEDULES

END OF SECTION

SECTION 1.G


PREVAILING WAGE RATES

[The rates will be supplied to the Consultant in packet immediately before project is advertised.]

END OF SECTION

Missouri Division of Labor Standards

WAGE AND HOUR SECTION



MICHAEL L. PARSON, Governor

Annual Wage Order No. 30

Section 010 **BOONE COUNTY**

In accordance with Section 290.262 RSMo 2000, within thirty (30) days after a certified copy of this Annual Wage Order has been filed with the Secretary of State as indicated below, any person who may be affected by this Annual Wage Order may object by filing an objection in triplicate with the Labor and Industrial Relations Commission, P.O. Box 599, Jefferson City, MO 65102-0599. Such objections must set forth in writing the specific grounds of objection. Each objection shall certify that a copy has been furnished to the Division of Labor Standards, P.O. Box 449, Jefferson City, MO 65102-0449 pursuant to 8 CSR 20-5.010(1). A certified copy of the Annual Wage Order has been filed with the Secretary of State of Missouri.

Original Signed by

Todd Smith, Director Division of Labor Standards

Filed With Secretary of State: March 10, 2023

Last Date Objections May Be Filed: April 10, 2023

Prepared by Missouri Department of Labor and Industrial Relations

	**D:::
OCCUPATIONAL TITLE	**Prevailing
OCCUPATIONAL TITLE	Hourly
	Rate
Asbestos Worker	\$58.05
Boilermaker	\$73.87
Bricklayer	\$53.18
Carpenter	\$49.00
Lather	
Linoleum Layer	
Millwright	
Pile Driver	
Cement Mason	\$47.52
Plasterer	
Communications Technician	\$57.48
Electrician (Inside Wireman)	\$58.51
Electrician Outside Lineman	\$76.79
Lineman Operator	
Lineman - Tree Trimmer	
Groundman	
Groundman - Tree Trimmer	
Elevator Constructor	\$31.16*
Glazier	\$65.21
Ironworker	\$65.92
Laborer	\$42.86
General Laborer	ψ 12.00
First Semi-Skilled	
Second Semi-Skilled	
Mason	\$31.16*
Marble Mason	ΨΟΙ.ΤΟ
Marble Finisher	
Terrazzo Worker	
Terrazzo Finisher	
Tile Setter	+
Tile Finisher	+
Operating Engineer	\$64.73
Group I	ψ04.73
Group II	
Group III	
	+
Group III-A	-
Group IV	
Group V	#40.00
Painter	\$40.26
Plumber	\$69.73
Pipe Fitter	050.44
Roofer	\$53.14
Sheet Metal Worker	\$56.02
Sprinkler Fitter	\$61.21
Truck Driver	\$31.16*
Truck Control Service Driver	
Group I	
Group II	
Group III	
Group IV	

^{*}The Division of Labor Standards received fewer than 1,000 reportable hours for this occupational title. The public works contracting minimum wage is established for this occupational title using data provided by Missouri Economic Research and Information Center.

^{**}The Prevailing Hourly Rate includes any applicable fringe benefit amounts for each occupational title as defined in RSMO Section 290.210.

BOONE County	
OCCUPATIONAL TITLE	**Prevailing Hourly
	Rate
Carpenter	\$53.37
Millwright	
Pile Driver	
Electrician (Outside Lineman)	\$76.79
Lineman Operator	
Lineman - Tree Trimmer	
Groundman	
Groundman - Tree Trimmer	
Laborer	\$46.32
General Laborer	
Skilled Laborer	
Operating Engineer	\$65.15
Group I	
Group II	
Group III	
Group IV	
Truck Driver	\$31.16*
Truck Control Service Driver	
Group I	
Group II	
Group III	
Group IV	

Use Heavy Construction Rates on Highway and Heavy construction in accordance with the classifications of construction work established in 8 CSR 30-3.040(3).

Use Building Construction Rates on Building construction in accordance with the classifications of construction work established in 8 CSR 30-3.040(2).

If a worker is performing work on a heavy construction project within an occupational title that is not listed on the Heavy Construction Rate Sheet, use the rate for that occupational title as shown on the Building Construction Rate Sheet.

*The Division of Labor Standards received fewer than 1,000 reportable hours for this occupational title. Public works contracting minimum wage is established for this occupational title using data provided by Missouri Economic Research and Information Center.

^{**}The Prevailing Hourly Rate includes any applicable fringe benefit amounts for each occupational title.

OVERTIME and HOLIDAYS

OVERTIME

For all work performed on a Sunday or a holiday, not less than twice (2x) the prevailing hourly rate of wages for work of a similar character in the locality in which the work is performed or the public works contracting minimum wage, whichever is applicable, shall be paid to all workers employed by or on behalf of any public body engaged in the construction of public works, exclusive of maintenance work.

For all overtime work performed, not less than one and one-half (1½) the prevailing hourly rate of wages for work of a similar character in the locality in which the work is performed or the public works contracting minimum wage, whichever is applicable, shall be paid to all workers employed by or on behalf of any public body engaged in the construction of public works, exclusive of maintenance work or contractual obligation. For purposes of this subdivision, "overtime work" shall include work that exceeds ten hours in one day and work in excess of forty hours in one calendar week; and

A thirty-minute lunch period on each calendar day shall be allowed for each worker on a public works project, provided that such time shall not be considered as time worked.

HOLIDAYS

January first;
The last Monday in May;
July fourth;
The first Monday in September;
November eleventh;
The fourth Thursday in November; and December twenty-fifth;

If any holiday falls on a Sunday, the following Monday shall be considered a holiday.

SECTION 024119 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Demolition and removal of selected portions of building or structure.

1.3 DEFINITIONS

- A. Remove: Detach items from existing construction and dispose of them off-site unless indicated to be salvaged or reinstalled.
- B. Existing to Remain: Leave existing items that are not to be removed and that are not otherwise indicated to be salvaged or reinstalled.

1.4 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.
- B. Historic items, relics, antiques, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, and other items of interest or value to Owner that may be uncovered during demolition remain the property of Owner.
 - 1. Carefully salvage in a manner to prevent damage and promptly return to Owner.

1.5 INFORMATIONAL SUBMITTALS

- A. Proposed Protection Measures: Submit report, including Drawings, that indicates the measures proposed for protecting individuals and property, for dust control and, for noise control. Indicate proposed locations and construction of barriers.
- B. Predemolition Photographs or Video: Show existing conditions of adjoining construction, including finish surfaces that might be misconstrued as damage caused by demolition operations.

1.6 FIELD CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.

024119 - 1 Project No.: CP242241 February 27, 2024

SELECTIVE DEMOLITION

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
 - 1. If suspected hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.

1.7 COORDINATION

A. Arrange selective demolition schedule so as not to interfere with Owner's operations.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ASSE A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs or video.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off utility services and mechanical/electrical systems serving areas to be selectively demolished.
 - 1. Owner will arrange to shut off indicated services/systems when requested by Contractor.

Project No.: CP242241 February 27, 2024

- 2. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
- 3. Disconnect, demolish, and remove fire-suppression systems, plumbing, and HVAC systems, equipment, and components indicated on Drawings to be removed.
 - a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
 - b. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material and leave in place.
 - c. Equipment to Be Removed: Disconnect and cap services and remove equipment.
 - d. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.

3.3 PROTECTION

- A. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
 - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
 - 2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
- B. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
 - 1. Strengthen or add new supports when required during progress of selective demolition.
- C. Remove temporary barricades and protections where hazards no longer exist.

3.4 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - 1. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
 - 3. Maintain fire watch during and for at least six hours after flame-cutting operations.
 - 4. Maintain adequate ventilation when using cutting torches.
 - 5. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
 - 6. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
 - 7. Dispose of demolished items and materials promptly.

Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

3.5 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

A. Masonry: Demolish in small sections. Cut masonry at junctures with construction to remain, using power-driven saw, and then remove masonry between saw cuts.

3.6 DISPOSAL OF DEMOLISHED MATERIALS

- A. Remove demolition waste materials from Project site and dispose of them in an EPA-approved construction and demolition waste landfill acceptable to authorities having jurisdiction.
 - 1. Do not allow demolished materials to accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
 - 3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
- B. Burning: Do not burn demolished materials.

3.7 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

024119 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 061000 - ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Wood blocking.
 - 2. Plywood backing panels.

1.2 DEFINITIONS

- A. Boards or Strips: Lumber of less than 2 inches nominal (38 mm actual) size in least dimension.
- B. Dimension Lumber: Lumber of 2 inches nominal (38 mm actual) size or greater but less than 5 inches nominal (114 mm actual) size in least dimension.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Stack wood products flat with spacers beneath and between each bundle to provide air circulation. Protect wood products from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

- A. Lumber: Comply with DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, comply with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Grade lumber by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.
 - 1. Factory mark each piece of lumber with grade stamp of grading agency.

B. Maximum Moisture Content of Lumber:

1. Boards: **19** percent unless otherwise noted.

ROUGH CARPENTRY **061000 - 1** Project No.: CP242241 February 27, 2024

2.2 MISCELLANEOUS LUMBER

- A. Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:
 - 1. Blocking.
 - Nailers.
- B. Concealed Boards: **19** percent maximum moisture content and **any of** the following species and grades:
 - 1. Mixed southern pine or southern pine; No. 2 grade; SPIB.
 - Hem-fir or hem-fir (north); Construction or No. 2 Common grade; NLGA, WCLIB, or WWPA.
 - 3. Spruce-pine-fir (south) or spruce-pine-fir; Construction or No. 2 Common grade;
- C. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.
- D. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.
- E. For furring strips for installing plywood or hardboard paneling, select boards with no knots capable of producing bent-over nails and damage to paneling.

2.3 PLYWOOD BACKING PANELS

A. Equipment Backing Panels: Plywood, DOC PS 1, **Exterior**, **A-C**, in thickness indicated or, if not indicated, not less than **3/4-inch** nominal thickness.

2.4 FASTENERS

- A. General: Fasteners shall be of size and type indicated and shall comply with requirements specified in this article for material and manufacture.
- B. Nails, Brads, and Staples: ASTM F1667.
- C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.
- D. Wood Screws: ASME B18.6.1.
- E. Lag Bolts: ASME B18.2.1.
- F. Bolts: Steel bolts complying with ASTM A 307, Grade A; with ASTM A 563 hex nuts and, where indicated, flat washers.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Set rough carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry accurately to other construction. Locate nailers, blocking, and similar supports to comply with requirements for attaching other construction.
- B. Install plywood backing panels by fastening to studs; coordinate locations with utilities requiring backing panels.
- C. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.
- D. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.
- E. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
 - 1. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code (IBC).
 - 2. ICC-ES evaluation report for fastener.
- F. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 INSTALLATION OF WOOD BLOCKING AND NAILERS

- A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work.
- B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.

END OF SECTION 061000

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 064023 - INTERIOR ARCHITECTURAL WOODWORK

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - Solid-surface-material window sills.
- B. Related Requirements:
 - Section 061000 "Rough Carpentry" for wood furring, blocking, shims, and hanging strips required for installing interior architectural woodwork that are concealed within other construction before interior architectural woodwork installation.

1.3 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to ensure that interior architectural woodwork can be supported and installed as indicated.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For interior architectural woodwork.
 - 1. Include plans, elevations, sections, and attachment details.
 - 2. Show large-scale details.
 - 3. Show locations and sizes of furring, blocking, and hanging strips, including blocking and reinforcement concealed by construction and specified in other Sections.
- A. Samples for Verification:
 - 1. Solid surface material, 6 inches square

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For solid surface to include in maintenance manuals. Include Product Data for care products used or recommended by Installer and names, addresses, and telephone numbers of local sources for products.

INTERIOR ARCHITECTURAL WOODWORK 064023 - 1 Project No.: CP242241 February 27, 2024

1.6 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful inservice performance.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver interior architectural woodwork until painting and similar finish operations that might damage woodwork have been completed in installation areas. Store woodwork in installation areas or in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.8 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install interior architectural woodwork until building is enclosed, wet-work is complete, and HVAC system is operating and maintaining temperature and relative humidity at levels planned for building occupants during the remainder of the construction period.
- B. Field Measurements: Where interior architectural woodwork is indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
 - 1. Locate concealed framing, blocking, and reinforcements that support woodwork by field measurements before being concealed by construction, and indicate measurements on Shop Drawings.

PART 2 - PRODUCTS

2.1 INTERIOR ARCHITECTURAL WOODWORK, GENERAL

A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of interior architectural woodwork indicated for construction, finishes, installation, and other requirements.

2.2 SOLID-SURFACE-MATERIAL WINDOW SILLS

- A. Configuration: Provide window sills with the following front style:
 - Front: Straight, slightly eased at top.
- B. Window Sills: 1/2-inch- thick, solid surface material.
- C. Solid Surface Material: Homogeneous solid sheets of filled plastic resin complying with ANSI SS1.

INTERIOR ARCHITECTURAL WOODWORK 064023 - 2 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Corian, an E. I. du Pont de Nemours and Company.
 - b. Samsung Chemical USA, Inc.
 - c. Wilsonart International Holdings, Inc.
 - d. Avonite Surfaces.
- 2. Type: Provide Standard Type unless Special Purpose Type is indicated.
- 3. Colors and Patterns: As indicated by manufacturer's designations.
 - a. SS-1: Corian; As selected by Architect from manufacturer's full range of standard colors.
- D. Fabrication: Fabricate sills in one piece unless otherwise indicated. Comply with solid-surface-material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

2.3 MISCELLANEOUS MATERIALS

- A. Furring, Blocking, Shims, and Nailers: Softwood or hardwood lumber, kiln-dried to less than 15 percent moisture content.
- B. Installation Adhesive: Product recommended by fabricator for each substrate for secure anchorage.

2.4 FABRICATION

- A. Fabricate architectural cabinets to dimensions, profiles, and details indicated.
- B. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.
 - Trial fit assemblies at fabrication shop that cannot be shipped completely assembled. Install dowels, screws, bolted connectors, and other fastening devices that can be removed after trial fitting. Verify that various parts fit as intended and check measurements of assemblies against field measurements before disassembling for shipment.
- C. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition woodwork to average prevailing humidity conditions in installation areas.

INTERIOR ARCHITECTURAL WOODWORK 064023 - 3 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Before installing woodwork, examine shop-fabricated work for completion and complete work as required.

3.2 INSTALLATION

- A. Grade: Install woodwork to comply with same grade as item to be installed.
- B. Assemble woodwork and complete fabrication at Project site to the extent that it was not completed in the shop.
- C. Install woodwork level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches.
- D. Scribe and cut woodwork to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.

3.3 ADJUSTING AND CLEANING

- A. Repair damaged and defective woodwork, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.
- B. Clean woodwork on exposed and semiexposed surfaces.

END OF SECTION 064023

INTERIOR ARCHITECTURAL WOODWORK 064023 - 4 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 079200 - JOINT SEALANTS

PART 1 - GENERAL

1.1 **SUMMARY**

- Α. Section Includes:
 - 1. Latex joint sealants.

ACTION SUBMITTALS 1.2

- Α. Product Data:
 - 1. Joint-sealants.
 - 2. Joint sealant backing materials.

1.3 FIELD CONDITIONS

- Α. Do not proceed with installation of joint sealants under the following conditions:
 - When ambient and substrate temperature conditions are outside limits permitted by joint-1. sealant manufacturer.
 - 2. When joint substrates are wet.
 - Where joint widths are less than those allowed by joint-sealant manufacturer for 3. applications indicated.
 - 4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

PART 2 - PRODUCTS

2.1 JOINT SEALANTS, GENERAL

- Compatibility: Provide joint sealants, backings, and other related materials that are compatible Α. with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.
- B. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.2 LATEX JOINT SEALANTS

Acrylic Latex: Acrylic latex or siliconized acrylic latex, ASTM C834, Type OP, Grade NF. Α.

JOINT SEALANTS 079200 - 1 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the
 - Pecora Corporation.
 - b. Sherwin-Williams Company (The).
 - Tremco Incorporated. C.

JOINT-SEALANT BACKING 2.3

- Sealant Backing Material. General: Nonstaining: compatible with joint substrates, sealants. Α. primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Cylindrical Sealant Backings: ASTM C1330, Type C (closed-cell material with a surface skin), and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

2.4 MISCELLANEOUS MATERIALS

- Α. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 **EXAMINATION**

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 **PREPARATION**

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:
 - 1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
 - 2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning

JOINT SEALANTS 079200 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

- Concrete.
- Masonry.
- Remove laitance and form-release agents from concrete. 3.
- Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:
 - Metal.
 - b. Glass.
 - Porcelain enamel. C.
- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of jointsealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

- General: Comply with joint-sealant manufacturer's written installation instructions for products Α. and applications indicated, unless more stringent requirements apply.
- Sealant Installation Standard: Comply with recommendations in ASTM C1193 for use of joint B. sealants as applicable to materials, applications, and conditions indicated.
- C. Install sealant backings of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 - 1. Do not leave gaps between ends of sealant backings.
 - 2. Do not stretch, twist, puncture, or tear sealant backings.
 - 3. Remove absorbent sealant backings that have become wet before sealant application. and replace them with dry materials.
- D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.
- Install sealants using proven techniques that comply with the following and at the same time E. backings are installed:
 - 1. Place sealants so they directly contact and fully wet joint substrates.
 - Completely fill recesses in each joint configuration. 2.
 - Produce uniform, cross-sectional shapes and depths relative to joint widths that allow 3. optimum sealant movement capability.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
 - 1. Remove excess sealant from surfaces adjacent to joints.
 - 2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
 - 3. Provide concave joint profile in accordance with Figure 8A in ASTM C1193 unless otherwise indicated.

3.4 **CLEANING**

Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by Α. methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.5 **PROTECTION**

Protect joint sealants during and after curing period from contact with contaminating substances A. and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.6 JOINT-SEALANT SCHEDULE

- A. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces not subject to significant movement.
 - 1. Joint Locations:
 - Perimeter joints between interior wall surfaces and frames of interior doors and
 - b. Other interior joints as indicated on Drawings.
 - 2. Joint Sealant: Acrylic latex.
 - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

END OF SECTION 079200

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Interior standard steel frames.
- B. Related Requirements:
 - 1. Section 087100 "Door Hardware" for door hardware for hollow-metal doors.

1.3 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

1.4 COORDINATION

- A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.
- B. Coordinate requirements for installation of door hardware, electrified door hardware, and access control and security systems.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, and finishes.
- B. Shop Drawings: Include the following:
 - 1. Elevations of each frame type.
 - 2. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
 - 3. Locations of reinforcement and preparations for hardware.
 - 4. Details of each different wall opening condition.
 - 5. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
 - 6. Details of anchorages, joints, field splices, and connections.

C. Product Schedule: For hollow-metal frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hardware schedule.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver hollow-metal frames palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.
- B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.
- C. Store hollow-metal frames vertically under cover at Project site with head up. Place on minimum 4-inch- high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Ceco Door; ASSA ABLOY.
 - 2. Curries Company; ASSA ABLOY.
 - 3. Steelcraft; an Ingersoll-Rand brand.
 - 4. Stiles Custom Metal, Inc.
 - 5. Republic Doors & Frames.

2.2 STANDARD STEEL FRAMES

- A. Construct hollow-metal frames to comply with standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
- B. Interior Frames: SDI A250.8. At locations indicated in the Door and Frame Schedule.
 - 1. Materials: Uncoated steel sheet, minimum thickness of 0.053 inch.
 - 2. Construction: Face welded.
 - 3. Exposed Finish: Prime.

2.3 FRAME ANCHORS

A. Jamb Anchors:

1. Type: Anchors of minimum size and type required by applicable door and frame standard, and suitable for performance level indicated.

HOLLOW METAL FRAMES 081213 - 2 Project No.: CP242241 February 27, 2024

- 2. Quantity: Minimum of three anchors per jamb, with one additional anchor for frames with no floor anchor. Provide one additional anchor for each 24 inches of frame height above 7 feet.
- 3. Postinstalled Expansion Anchor: Minimum 3/8-inch- diameter bolts with expansion shields or inserts, with manufacturer's standard pipe spacer.
- B. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor.
- C. Material: ASTM A879/A879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.

2.4 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A1008/A1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- B. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.

2.5 FABRICATION

- A. Hollow-Metal Frames: Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as frames.
 - Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
 - 2. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.
 - a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
 - b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.
- B. Hardware Preparation: Factory prepare hollow-metal frames to receive templated mortised hardware, and electrical wiring; include cutouts, reinforcement, mortising, drilling, and tapping according to SDI A250.6, the Door Hardware Schedule, and templates.
 - 1. Reinforce frames to receive nontemplated, mortised, and surface-mounted door hardware.
 - 2. Comply with BHMA A156.115 for preparing hollow-metal frames for hardware.

2.6 STEEL FINISHES

- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.
 - 1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

HOLLOW METAL FRAMES 081213 - 3 Project No.: CP242241 February 27, 2024

PART 3 - EXECUTION

3.1 PREPARATION

- A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces. Touch up factory-applied finishes where spreaders are removed.
- B. Drill and tap frames to receive nontemplated, mortised, and surface-mounted door hardware.

3.2 INSTALLATION

- A. General: Install hollow-metal frames plumb, rigid, properly aligned, and securely fastened in place. Comply with approved Shop Drawings and with manufacturer's written instructions. Comply with SDI A250.11.
- B. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces without damage to completed Work.
 - 1. Where frames are fabricated in sections, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces. Touch-up finishes.
- C. Floor Anchors: Secure with postinstalled expansion anchors.
 - 1. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
- D. Solidly pack mineral-fiber insulation inside frames.
- E. Installation Tolerances: Adjust hollow-metal frames to the following tolerances:
 - 1. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
 - Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
 - 3. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
 - 4. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.

3.3 CLEANING AND TOUCHUP

A. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

END OF SECTION 081213

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 081416 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Five-ply flush wood veneer-faced doors for transparent finish.
- B. Related Requirements:
 - 1. Section 088000 "Glazing" for glass view panels in flush wood doors.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of door. Include details of core and edge construction and trim for openings. Include factory-finishing specifications.
- B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each type of door; construction details not covered in Product Data; and the following:
 - 1. Dimensions and locations of blocking.
 - 2. Dimensions and locations of mortises and holes for hardware.
 - 3. Undercuts.

C. Samples for Verification:

1. Factory finishes applied to actual door face materials, approximately 8 by 10 inches, for each material and finish. For each wood species and transparent finish, provide set of three Samples showing typical range of color and grain to be expected in finished Work.

1.4 INFORMATIONAL SUBMITTALS

A. Sample Warranty: For special warranty.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Comply with requirements of referenced standard and manufacturer's written instructions.
- B. Package doors individually in plastic bags or cardboard cartons.
- C. Mark each door on bottom rail with opening number used on Shop Drawings.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install doors until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during remainder of construction period.

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Warping (bow, cup, or twist) more than 1/4 inch in a 42-by-84-inch section.
 - b. Telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch span.
 - 2. Warranty Period for Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Eggers Industries
 - 2. Graham Wood Doors; ASSA-ABLOY Group company.
 - 3. Mohawk Flush Doors, Inc.
 - 4. VT Industries Inc.
 - 5. Marshfield Door Systems
 - 6. Oshkosh Door Company
- B. Source Limitations: Obtain wood doors from single manufacturer.

2.2 FLUSH WOOD DOORS, GENERAL

- A. Quality Standard: In addition to requirements specified, comply with WDMA I.S.1-A, "Architectural Wood Flush Doors."
- B. Low-Emitting Materials: Fabricate doors with adhesives and composite wood products that do not contain urea formaldehyde.
- C. WDMA I.S.1-A Performance Grade: Extra Heavy Duty.
 - 1. Construction: Five plies. Stiles and rails are bonded to core, then entire unit is abrasive planed before veneering.
- D. Fire-Rated Wood Doors: Doors complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 1. Cores: Provide core specified or mineral core as needed to provide fire-protection rating
- Edge Construction: Provide edge construction with intumescent seals concealed by outer 2. stile. Comply with specified requirements for exposed edges.
- Smoke- and Draft-Control Door Assemblies: Listed and labeled for smoke and draft control, based E. on testing according to UL 1784.
- F. Particleboard-Core Doors:
 - Particleboard: ANSI A208.1, Grade LD-2, made with binder containing ureaformaldehyde.
 - 2. Blocking: Provide wood blocking in particleboard-core doors as needed to eliminate through bolting hardware.
 - Provide doors with glued-wood-stave or structural-composite-lumber cores instead of 3. particleboard cores for doors indicated to receive exit devices.
- Structural-Composite-Lumber-Core Doors: G.
 - Structural Composite Lumber: WDMA I.S.10.
 - Screw Withdrawal Face: 700 lbf. a.
 - b. Screw Withdrawal Edge: 400 lbf.

2.3 SOLID-CORE FIVE-PLY FLUSH WOOD VENEER-FACED DOORS FOR TRANSPARENT **FINISH**

Interior Doors: Α.

- 1. Performance Grade: ANSI/WDMA I.S 1A Extra Heavy Duty.
- 2. Faces: Single-ply wood veneer not less than 1/50 inch thick.
 - Species: Red oak. a.
 - b. Cut: Plain sliced (flat sliced).
 - Match between Veneer Leaves: Book match. C.
 - Assembly of Veneer Leaves on Door Faces: Balance match.
- Exposed Vertical Edges: Same species as faces Architectural Woodwork Standards edge 3. Type A.

2.4 LIGHT FRAMES AND LOUVERS

- A. Wood Beads for Light Openings in Wood Doors: Provide manufacturer's standard wood beads unless otherwise indicated.
 - Wood Species: Same species as door faces. 1.
 - Profile: Manufacturer's standard shape. 2.

2.5 FLUSH WOOD DOOR FABRICATION

- Factory fit doors to suit frame-opening sizes indicated. Α.
 - Comply with clearance requirements of referenced quality standard for fitting unless 1. otherwise indicated.

FLUSH WOOD DOORS Project No.: CP242241 081416 - 3

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Factory machine doors for hardware that is not surface applied.
 - 1. Locate hardware to comply with DHI-WDHS-3.
 - 2. Comply with final hardware schedules, door frame Shop Drawings, ANSI/BHMA-156.115-W, and hardware templates.
 - 3. Coordinate with hardware mortises in metal frames, to verify dimensions and alignment before factory machining.
- C. Openings: Factory cut and trim openings through doors.
 - 1. Light Openings: Trim openings with moldings of material and profile indicated.
 - 2. Glazing: Factory install glazing in doors indicated to be factory finished. Comply with applicable requirements in Section 088000 "Glazing."

2.6 FACTORY FINISHING

- A. Comply with referenced quality standard for factory finishing.
 - 1. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
 - 2. Finish faces, all four edges, edges of cutouts, and mortises.
 - 3. Stains and fillers may be omitted on top and bottom edges, edges of cutouts, and mortises.
- B. Factory finish doors.
- C. Transparent Finish:
 - 1. ANSI/WDMA I.S. 1A Grade: Custom.
 - 2. Finish: ANSI/WDMA I.S. 1A TR-8 UV Cured Acrylated Polyester/Urethane
 - 3. Stain: To match existing door stain color.
 - 4. Effect: Open-grain finish.
 - 5. Sheen: Satin.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine doors and installed door frames, with Installer present, before hanging doors.
 - 1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
 - 2. Reject doors with defects.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF SOLID-COOR DOORS

A. Hardware: For installation, see Section 087100 "Door Hardware."

FLUSH WOOD DOORS **081416 - 4** Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.
- C. Factory-Fitted Doors: Align in frames for uniform clearance at each edge.
- D. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

3.3 ADJUSTING

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION 081416

FLUSH WOOD DOORS **081416 - 5** Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 087100 - DOOR HARDWARE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes finish hardware for the proper operation and control of all doors in the Project. Prior to bidding, notify Architect of any doors that do not have hardware meeting this intention.
- B. Hardware supplier will be responsible to furnish and install hardware on labeled doors to satisfy State and Local Building Codes.
- C. Related Sections include the following:
 - 1. Division 8 Section "Hollow Metal Doors and Frames."
 - Division 8 Section "Flush Wood Doors."
 - 3. Division 26 Sections for electrical connections provided separately including conduit and wiring for power to, and control of, automatic door operators.

1.3 SUBMITTALS

- A. Product Data: For each product and material indicated, submit manufacturer's technical product data. Include information necessary to show compliance with requirements, installation instructions and maintenance instructions.
- B. Hardware Schedule: Submit a hardware schedule organized into sets, including the information below. Designations for door numbers and hardware sets shall match those used in the construction documents.
 - 1. Opening Number
 - 2. Door Type and Size
 - 3. Frame Type and Size
 - 4. Frame Anchoring Method
 - 5. Hardware Set
 - 6. Assembly Rating
- C. Hardware Schedule shall be coordinated with the doors, frames and related work to ensure proper size, thickness, hand function and finish of door hardware

1.4 QUALITY ASSURANCE

A. Supplier Qualifications: A recognized Architectural Finish Hardware Supplier, with warehousing facilities, who has been furnishing hardware in the Project's vicinity for a period of not less than two (2) years. Supplier shall be or employ an experienced Architectural Hardware Consultant (AHC) who is certified by and member of the Door and Hardware Institute. The Architectural hardware Consultant shall be available, at reasonable times during the course of the work, for

DOOR HARDWARE 087100 - 1 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- consultation about Project's hardware requirements, to Owner, Architect and Contractor.
- B. Fire-Rated Openings: Provide hardware for fire-rated openings in compliance with NFPA Standard No. 80, No. 101 and local building code requirements. Provide only hardware, which has been tested and listed, by UL, FM or Warnock Hersey for types and sizes of doors required and complies with requirements of door and door frame labels.
- C. Standards: Comply with the requirements of the latest edition of the following standards unless indicated otherwise:
 - 1. American National Standards Institute Publications:
 - a. A115 Series Door and Frame Preparation
 - b. A156 Series Hardware
 - c. ANSI/BHMA A156.10: Standard for Power Operated Pedestrian Doors.
 - d. ANSI/BHMA A156.19: Standard for Power Assist and Low Energy Power Operated Doors.
 - 2. Builders Hardware Manufacturer's Association Publications:
 - a. 1201 Auxiliary Hardware
 - b. 1301 Materials and Finishes
 - 3. Door and Hardware Institute Publications:
 - a. Keying Procedures, Systems and Nomenclature
 - b. Abbreviations and Symbols
 - c. Hardware for Labeled Fire Doors
 - d. Recommended Locations for Builder's Hardware for Standard and Custom Steel Doors and Frames
 - e. Wood Door Standards W1, W2, WDHS-2, WDHS-3
 - 4. National Fire Protection Association Publications
 - a. NFPA 80 Standards for Fire Doors and Windows
 - o. NFPA 101 Life Safety Code
 - 5. International Building Code 2021 Edition
 - 6. American with Disabilities Act.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Package each hardware item in separate containers with all screws, wrenches, installation instructions and installation templates. Mark each box with hardware heading and door number according to approved hardware schedule.
- B. Deliver individually packaged hardware items at the proper times to the proper locations (shop or project site) for installation: Provide a complete packing list showing items, door numbers and hardware headings with each shipment.
- C. Store hardware in shipping cartons above ground and under cover to prevent damage. Provide secure lockup for door hardware delivered to the Project, but not yet installed. Control handling and installation of hardware items that are not immediately replaceable -so that completion of the Work will not be delayed by hardware losses both before and after installation.

1.6 DEFINITIONS

- A. Activation Device: Device that, when actuated, sends an electrical signal to the door operator to open the door.
- B. Knowing act: Consciously initiating the opening of a power operated door using acceptable methods including wall mounted switches such as push plates and controlled access devices

DOOR HARDWARE 087100 - 2 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

such as keypads, card readers and key switches.

1.7 PERFORMANCE REQUIREMENTS

- A. General: Provide automatic door operators capable of withstanding loads and thermal movements based on testing manufacturer's standard units in assemblies similar to those indicated for this Project.
- B. Operating Range: Minus 30 deg F to 130 deg F.
- C. Opening-Force Requirements for Egress Doors: In the event power failure to the operator, swinging automatic entrance doors shall open with a manual force, not to exceed 30 lbf to set door in motion, and not more than 15 lbf to fully open the door. Forces shall be applied at 1" from the latch edge of the door.

1.8 COORDINATION

- A. Templates: Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing automatic door operators to comply with indicated requirements.
- B. Electrical System Roughing-in: Coordinate layout and installation of automatic door operators with connections to, power supplies and remote activation devices.

1.9 **PROJECT CONDITIONS**

A. Environmental Limitations: Do not proceed with delivery and/or installation when ambient and substrate temperature conditions are outside limits permitted by material manufacturers.

PART 2 - PRODUCTS

2.1 HARDWARE GENERAL

- A. Provide the materials of products indicated by trade names, manufacturer's name, or catalog number. Substitutions will not be permitted except as described in Division 1.
- Provide manufacturer's standard products meeting the design intent of this Specification, free of B. imperfections affecting appearance or serviceability.
 - Provide hardware complete with all fasteners, anchors, instructions, layout templates, and 1. any specialized tools as required for satisfactory installation and adjustment.
 - Hand of Door: Drawings show direction of slide, swing or hand of each door leaf. Furnish 2. each item of hardware for proper installation and operation of door movement as shown.
 - Furnish screws for installation with each hardware item. Provide Phillips flat head screws 3. except as otherwise indicated or approved. Finish screws exposed under any condition to match hardware finish, or, if exposed in surface of other work, to match finish of such other work as closely as possible. Use machine screws for metal connections and wood screws for connections to wood. Use manufacturer's screws to secure hardware.
 - Provide concealed fasteners for hardware unit with care exposed when door is closed, 4. except to extent no standard units of type specified are available with concealed fasteners. Do not use thru-bolts for installation where bolt, head or nut on opposite face is exposed in other work, except where indicated otherwise or where it is not feasible to adequately reinforce the work. In such cases, provide sleeves for each thru-bolt or use sex screw fasteners.

DOOR HARDWARE 087100 - 3 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Special Tools: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance and removal and replacement of finish hardware.
- C. Hardware is specified in the hardware schedule by set, type and functions, which have been selected as best meeting the application requirements. Acceptable products for each category are specified in Paragraph 2.5 "Hardware Products".

2.2 SPECIAL REQUIREMENTS

A. General:

Where new doors and hardware are scheduled to be installed in existing frames, contractor to coordinate hinge sizes and locations, lockset backsets, strikes, hardware mounting heights, etc with existing frames to ensure new door and hardware fits and functions properly in existing frame.

B. Hinges:

1. Use heavy weight hinges for all doors.

C. Locksets:

1. All locksets to be grade 1 heavy duty cylindrical or as specified.

D. Closers:

- Comply with manufacturer's recommendations for unit size based on door size and usage.
- 2. Provide parallel arms for all overhead closers, except as otherwise indicated.
- 3. All closers UL Listed Certified to be in compliance with UBC 7.2 and UL 10C.
- Closers with Pressure Relief Valves will not be acceptable.
- 5. Supplier to provide any brackets or plates required for proper installation of door closers.

E. Automatic Door Operators:

- 1. Header Case: Header case shall not exceed 6" square in section and shall be fabricated from extruded aluminum with structurally integrated end caps, designed to conceal door operators and controls. The operator shall be sealed against dust, dirt, and corrosion within the header case. Access to the operator and electronic control box shall be provided by a full-length removable cover, edge rabbeted to the header to ensure a flush fit. Removable cover shall be secured to prevent unauthorized access.
- 2. Door Arms: A combination of door arms and linkage shall provide positive control of door through entire swing; units shall permit use of butt hung, center pivot, and offset pivothung doors.
- 3. Signage: Provide signage in accordance with ANSI/BHMA A156.19.

F. Push Plates:

- 1. Interior push plates shall be wall mounted in single or double gang electrical boxes and hardwired to door operator controls.
- 2. Exterior push plates shall be post mounted and hardwired to door operator controls.

G. Exit Devices:

- 1. All latchbolts to be deadlatching type.
- 2. All touchbars to be stainless steel.

2.3 KEYING DOOR HARDWARE

087100 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

A. Contractor to turn all cylinders over to MU key shop for keying.

2.4 **FINISHES**

- A. Standard: Comply with BHMA A156.18
 - All door hardware to be US26D throughout project.
- B. Provide quality of finish, including thickness of plating or coating (if any), composition, hardness and other qualities complying with manufacturer's standards, but in no case less than specified by referenced standards for the application units of hardware.
- C. Protect finishes on exposed surfaces from any damage by applying a strippable temporary protective covering before shipping.
- D. BHMA Designations: Comply with base material and finish requirements indicated by BHMA standards.

2.5 HARDARE PRODUCTS

ITEM **SPECIFIED** APPROVED EQUAL Hinges Ives Stanley Best, Corbin Russwin Locksets Schlage **Best** No Substitutions Cylinders

Closers LCN Norton, Rixson, Stanley

QDC100 Series

Auto Door Operators Stanley M-Force No Substitutions

Panic Devices Von Duprin Sargent, Yale, Precision

Apex 2000 Series (MLR

only)

Burns, Rockwood, Trimco Flatgoods Ives

Stops Burns, Rockwood Ives

Overhead Stops Glynn Johnson Rixson, Dorma 900 Series

NGP, Reese Gasket Zero **Electric Strikes** Von Duprin Adams Rite

DOOR HARDWARE 087100 - 5 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine doors and frames with installer present for compliance with the requirements, for installation tolerances, labeled fire door assembly construction, wall and floor construction, and other conditions affecting performance.
- B. Examine rough-in for electrical source power to verify actual locations of wiring connections before electrified door hardware installation.
- C. Notify Architect of any discrepancies or conflicts between the door schedule, door types, frame types, drawings, scheduled hardware and built condition.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Steel Frames: Comply with ANSI/DHI A115 Series
- B. Wood Doors: Comply with ANSI/DHI A115-W Series.

3.3 INSTALLATION

- A. Mounting Heights: Mount door hardware units at heights indicated in the following applicable publications, or as required to comply with governing regulations:
 - Standard Steel Doors and Frames: DHI's "Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames."
 - Custom Steel Doors and Frames: DHI's "Recommended Locations for Builder's Hardware for Custom Steel Doors and Frames."
 - 3. Wood Doors: DHI WDHS.2 "Recommended Locations for Architectural Hardware for Wood Flush Doors."
- B. Install each door hardware item to complete with manufacturer's written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage and reinstallation of surface protective trim units to with finishing work. Do not install surface mounted items until finishes have been completed on substrates involved.
- C. Door Operators: Connect door operators to electrical power distribution system as specified in Division 26 Sections.

3.4 FIELD QUALITY CONTROL

A. Field Inspection: Supplier will perform a final inspection of installed door hardware and state in written report whether work complies with or deviates from requirements, including whether door hardware is properly installed, operating and adjusted.

3.5 ADJUSTING

A. Initial Adjustment: Adjust and check each operating items of door hardware and each door to ensure proper operation of function of every unit. Replace units that cannot be adjusted to operate as intended and/or required. Adjust door control devices to compensation for final operation of

UNIVERSITY OF MISSOURI

ISSUED FOR BID

heating and ventilating equipment and to comply with referenced accessibility requirements.

B. Adjust door operators, controls, and hardware for smooth and safe operation, for tight closure, and complying with requirements in specified ANSI/BHMA operating standard by AAADM Certified Technician.

3.6 CLEANING AND PROTECTION

- A. Clean adjacent surfaces soiled by door hardware installation.
- B. Clean operating items as necessary to restore proper finish, and provide final protection and maintain condition that ensure door hardware is without damage or deterioration at time of owner occupancy.

3.7 DEMOSTRATION AND TRAINING

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate and maintain door hardware and door hardware finishes.

3.8 DOOR HARDWARE SETS

Hardware Group No. 1

For use on Door #(s): 631 632

631 632 Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER		FINISH	MFR
3	EA	HINGE	5BB1HW 4.5 X 4.5		652	IVE
1	EA	SFIC	OWNER PROVIDED		626	BES
1	EA	STOREROOM LOCK	ND80BD SPA		626	SCH
1	EA	ELECTRIC STRIKE	6211 FSE 12/16/24/28 VAC/VDC	N	630	VON
1	EA	SURFACE CLOSER	4040XP REG OR PA AS REQ		689	LCN
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS		630	IVE
1	EA	WALL STOP	WS406/407CCV		656	IVE
1	EA	DOOR CONTACT	679-05	N	BLK	SCE
1	EA	HIDR CARD READER	BY OWNER			
1	EA	POWER SUPPLY	PS902 900-2RS 120/240 VAC	×	LGR	SCE

OPERATION: DOOR UNLOCKED DURING PROGRAMMED HOURS. ENTRY BY VALID CARD READ WHEN LOCKED. FREE EGRESS AT ALL TIMES BY INSIDE LEVER.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Hardware Group No. 2

For use on Door #(s):

631A 631B 631C Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1HW 4.5 X 4.5	652	IVE
1	EA	SFIC	OWNER PROVIDED	626	BES
1	EA	ENTRANCE LOCK	ND53BD SPA	626	SCH
1	EA	WALL STOP	WS406/407CCV	656	IVE

END OF SECTION 087100

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 088000 - GLAZING

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 **SUMMARY**

- Section includes: A.
 - Glass products. 1.
 - 2. One-way glass.
 - Glazing sealants and accessories. 3.

1.3 **DEFINITIONS**

- Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in A. referenced glazing publications.
- Glass Thicknesses: Indicated by thickness designations in millimeters according to B. ASTM C 1036.
- C. IBC: International Building Code.
- D. Interspace: Space between lites of an insulating-glass unit.

COORDINATION 1.4

A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

1.5 **ACTION SUBMITTALS**

Product Data: For each type of product. Α.

1.6 INFORMATIONAL SUBMITTALS

A. Warranties.

GLAZING 088000 - 1 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.7 QUALITY ASSURANCE

- Fabricated-Glass Manufacturer Qualifications: A qualified manufacturer of fabricated glass units A. who is approved and certified by primary glass manufacturer.
- B. Installer Qualifications: A qualified installer who employs glass installers for this Project who are certified under the National Glass Association's Certified Glass Installer Program.
- C. Sealant Testing Agency Qualifications: An independent testing agency qualified according to ASTM C 1021 to conduct the testing indicated.
- D. Safety Glass: Category II materials complying with testing requirements in 16 CFR 1201 and ANSI Z97.1.
 - Subject to compliance with requirements, permanently mark safety glass with certification label of Safety Glazing Certification Council or another certification agency acceptable to authorities having jurisdiction.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Protect glazing materials according to manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

1.9 FIELD CONDITIONS

- Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature Α. conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.
 - Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or are below 40 deg F.

1.10 **WARRANTY**

- Manufacturer's Special Warranty for Insulating Glass: Manufacturer agrees to replace insulating-Α. glass units that deteriorate within specified warranty period. Deterioration of insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is obstruction of vision by dust, moisture, or film on interior surfaces of glass.
 - Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 **MANUFACTURERS**

Source Limitations for Glass: Obtain from single source from single manufacturer for each glass A. type.

GLAZING 088000 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Source Limitations for Glazing Accessories: Obtain from single source from single manufacturer for each product and installation method.

2.2 PERFORMANCE REQUIREMENTS

- Α. General: Installed glazing systems shall withstand normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.
- Structural Performance: Glazing shall withstand the following design loads within limits and under В. conditions indicated determined in accordance with the IBC and ASTM E1300:
 - Design Wind Pressures: Determine design wind pressures applicable to Project in 1. accordance with ASCE/SEI 7, based on heights above grade indicated on Drawings.
 - Basic Wind Speed: 90 mph.
 - b. Exposure Category: C.
 - 2. Maximum Lateral Deflection: For glass supported on all four edges, limit center-of-glass deflection at design wind pressure to not more than 1/50 times the short-side length or 1 inch, whichever is less.
- C. Thermal Loads: Design glazing to resist thermal stress breakage induced by differential temperature conditions and limited air circulation within individual glass lites and insulated glazing units.
- Safety Glazing: Where safety glazing is indicated, provide glazing that complies with D. 16 CFR 1201, Category II.
- E. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:
 - For monolithic-glass lites, properties are based on units with lites 6 mm thick. 1.
 - 2. For insulating-glass units, properties are based on units of thickness indicated for overall unit and for each lite.
 - 3. U-Factors: Center-of-glazing values, in accordance with NFRC 100 and based on most current non-beta version of LBL's WINDOW computer program, expressed as Btu/sq. ft. x h x deg F.
 - 4. SHGC and Visible Transmittance: Center-of-glazing values, in accordance with NFRC 200 and based on most current non-beta version of LBL's WINDOW computer program.

2.3 GLASS PRODUCTS, GENERAL

- Glazing Publications: Comply with published recommendations of glass product manufacturers A. and organizations below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.
 - GANA Publications: "Laminated Glazing Reference Manual" and "Glazing Manual." 1.
 - 2. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."

GLAZING 088000 - 3 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or manufacturer. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.
- C. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass that complies with performance requirements and is not less than the thickness indicated.
 - Minimum Glass Thickness for Exterior Lites: 6 mm.
- D. Strength: Where annealed float glass is indicated, provide annealed float glass, heatstrengthened float glass, or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened float glass is indicated, provide heatstrengthened float glass or fully tempered float glass as needed to comply with "Performance Requirements" Article. Where fully tempered float glass is indicated, provide fully tempered float glass.

2.4 **GLASS PRODUCTS**

- Clear Annealed Float Glass: ASTM C1036, Type I, Class 1 (clear), Quality-Q3. Α.
- Fully Tempered Float Glass: ASTM C1048, Kind FT (fully tempered), Condition A (uncoated) В. unless otherwise indicated. Type I. Class 1 (clear) or Class 2 (tinted) as indicated. Quality-Q3.
- C. Heat-Strengthened Float Glass: ASTM C1048, Kind HS (heat strengthened), Type I, Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.
- D. Reflective- and Low-E-Coated Vision Glass: ASTM C1376.
- E. Silicone-Coated Spandrel Glass: ASTM C1048, Type I, Condition C, Quality-Q3.

2.5 **INSULATING GLASS**

- Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by Α. a dehydrated interspace, qualified in accordance with ASTM E2190.
 - 1. Sealing System: Dual seal, with manufacturer's standard primary and secondary sealants.
 - 2. Perimeter Spacer: Manufacturer's standard spacer material and construction.
 - 3. Desiccant: Molecular sieve or silica gel, or a blend of both.

2.6 MISCELLANEOUS GLAZING MATERIALS

- General: Provide products of material, size, and shape complying with referenced glazing Α. standard, with requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.
- B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

GLAZING 088000 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Setting Blocks: Elastomeric material with a Shore, Type A durometer hardness of 85, plus or minus 5.
- D. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).
- Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and E. density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.
- F. Glazing Tape: Butyl or silicone preshimmed tape similar to Tremco 440 Tape.

2.7 **FABRICATION OF GLAZING UNITS**

- A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.
 - 1. Allow for thermal movements from ambient and surface temperature changes acting on glass framing members and glazing components.
 - a. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

PART 3 - EXECUTION

3.1 **EXAMINATION**

- A. Examine framing, glazing channels, and stops, with Installer present, for compliance with the following:
 - 1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
 - 2. Minimum required face and edge clearances.
 - Effective sealing between joints of glass-framing members. 3.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 **PREPARATION**

- Clean glazing channels and other framing members receiving glass immediately before glazing. Α. Remove coatings not firmly bonded to substrates.
- B. Examine glazing units to locate exterior and interior surfaces. Label or mark units as needed so that exterior and interior surfaces are readily identifiable. Do not use materials that leave visible marks in the completed Work.

GLAZING 088000 - 5 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.3 GLAZING, GENERAL

- Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other Α. glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.
- B. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass includes glass with edge damage or other imperfections that, when installed, could weaken glass, impair performance, or impair appearance.
- C. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.
- D. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.
- E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- F. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.
- G. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.
- H. Set glass lites with proper orientation so that coatings face exterior or interior as specified.
- Ι. Where wedge-shaped gaskets are driven into one side of channel to pressurize sealant or gasket on opposite side, provide adequate anchorage so gasket cannot walk out when installation is subjected to movement.
- J. Square cut wedge-shaped gaskets at corners and install gaskets in a manner recommended by gasket manufacturer to prevent corners from pulling away; seal corner joints and butt joints with sealant recommended in writing by gasket manufacturer.

3.4 **GASKET GLAZING (DRY)**

- Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings Α. exactly, with allowance for stretch during installation.
- Insert soft compression gasket between glass and frame or fixed stop so it is securely in place B. with joints miter cut and bonded together at corners.
- C. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressureglazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.

GLAZING 088000 - 6 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressureglazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended in writing by gasket manufacturer.
- E. Install gaskets so they protrude past face of glazing stops.

3.5 **CLEANING AND PROTECTION**

- A. Immediately after installation remove nonpermanent labels and clean surfaces.
- В. Remove and replace glass that is damaged during construction period.
- C. Wash glass on both exposed surfaces not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended in writing by glass manufacturer.

MONOLITHIC GLASS SCHEDULE 3.6

- Α. Clear Glass Type <GLZ-1>: Fully tempered float glass.
 - Minimum Thickness: 6 mm.

3.7 **INSULATING GLASS SCHEDULE**

- Low-E-Coated, Clear Insulating Glass Type <GLZ-3>: A.
 - Basis-of-Design Product: Match existing adjacent glazing in building.
 - Overall Unit Thickness: 1 inch. 2.
 - 3. Minimum Thickness of Each Glass Lite: 6 mm.
 - 4. Outdoor Lite: Fully tempered float glass.
 - Interspace Content: Air. 5.
 - Indoor Lite: Fully tempered float glass. 6.
 - 7. Low-E Coating: Pyrolytic on second surface.
 - 8. Safety glazing required.
- Silicone-Coated, Insulating Spandrel Glass Type <CLZ-4>: B.
 - Basis-of-Design Product: Match existing adjacent glazing in building.
 - Coating Color: Match existing adjacent glazing in building. 2.
 - Overall Unit Thickness: 1 inch. 3.
 - Minimum Thickness of Each Glass Lite: 6 mm.
 - Outdoor Lite: Clear heat-strengthened float glass.
 - Interspace Content: Air. 6.
 - 7. Indoor Lite: Clear heat-strengthened float glass.
 - 8. Coating Location: Fourth surface.

END OF SECTION 088000

GLAZING 088000 - 7 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 092216 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Non-load-bearing steel framing systems for interior partitions.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.3 INFORMATIONAL SUBMITTALS

A. Evaluation Reports: For embossed, high-strength steel studs and tracks, and firestop tracks, from ICC-ES or other qualified testing agency acceptable to authorities having jurisdiction.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Notify manufacturer of damaged materials received prior to installation.
- B. Deliver materials in manufacturer's original, unopened, undamaged containers with identification labels intact.
- C. Protect cold-formed metal framing from corrosion, deformation, and other damage during delivery, storage, and handling as required by AISI S202, "Code of Standard Practice for Cold-Formed Steel Structural Framing."

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For fire-resistance-rated assemblies that incorporate non-load-bearing steel framing, provide materials and construction identical to those tested in assembly indicated, according to ASTM E119 by an independent testing agency.
- B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings, according to ASTM E90 and classified according to ASTM E413 by an independent testing agency.
- C. Design framing systems in accordance with AISI S220, "North American Specification for the Design of Cold-Formed Steel Framing Nonstructural Members," unless otherwise indicated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

D. Design Loads: As indicated on architectural Drawings or 5 lbf/sq. ft. minimum as required by the IBC.

2.2 FRAMING SYSTEMS

- A. Embossed, High Strength Steel Studs and Tracks: Roll-formed and embossed with surface deformations to stiffen the framing members so that they are structurally comparable to conventional ASTM C645 steel studs and tracks.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. ClarkDietrich.
 - b. MarinoWARE.
 - c. SCAFCO Steel Stud Company.
 - d. Minimum Base-Steel Thickness: 0.0190 inch.
 - e. Depth: As indicated on Drawings.
- B. Slip-Type Head Joints: Where indicated, provide the following:
 - 1. Deflection Track: Steel sheet top track manufactured to prevent cracking of finishes applied to interior partition framing resulting from deflection of structure above; in thickness not less than indicated for studs and in width to accommodate depth of studs.
 - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) ClarkDietrich.
 - 2) MarinoWARE.
 - 3) SCAFCO Steel Stud Company.

2.3 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards.
 - Fasteners for Steel Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Installation Standard: ASTM C754.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 1. Gypsum Board Assemblies: Also comply with requirements in ASTM C840 that apply to framing installation.
- B. Install framing and accessories plumb, square, and true to line, with connections securely fastened.
- C. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
- D. Install bracing at terminations in assemblies.
- E. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

3.3 INSTALLING FRAMED ASSEMBLIES

- A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
 - 1. Single-Layer Application: 16 inches o.c. unless otherwise indicated.
- B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.
- C. Install studs so flanges within framing system point in same direction.
- D. Install tracks at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.
 - Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
 - 2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install track section (for cripple studs) at head and secure to jamb studs.
 - a. Install two studs at each jamb unless otherwise indicated.
 - b. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.
 - 3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
 - 4. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.
- E. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch from the plane formed by faces of adjacent framing.

END OF SECTION 092216

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 092900 - GYPSUM BOARD

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

Drawings and general provisions of the Contract, including General and Supplementary A. Conditions and Division 01 Specification Sections, apply to this Section.

1.2 **SUMMARY**

- Section Includes: A.
 - Interior gypsum board. 1.
 - Sound-attenuation blankets. 2.
 - Partition gap closure. 3.
- Related Requirements: B.
 - Section 092216 "Non-Structural Metal Framing" for steel framing and suspension systems that support gypsum board panels.

1.3 **ACTION SUBMITTALS**

A. Product Data: For each type of product.

1.4 DELIVERY, STORAGE AND HANDLING

Store materials inside under cover and keep them dry and protected against weather, Α. condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

1.5 FIELD CONDITIONS

- Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board Α. manufacturer's written instructions, whichever are more stringent.
- B. Do not install panels that are wet, moisture damaged, and mold damaged.
 - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
 - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 2 - PRODUCTS

2.1 GYPSUM BOARD, GENERAL

A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

2.2 INTERIOR GYPSUM BOARD

- A. Gypsum Board, Type X: ASTM C 1396/C 1396M.
 - Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - Georgia-Pacific Building Products.
 - b. National Gypsum Company.
 - C. USG Corporation.
 - 2. Thickness: 5/8 inch.
 - 3. Long Edges: Tapered.

2.3 TRIM ACCESSORIES

- A. Interior Trim: ASTM C 1047.
 - Material: Paper-faced galvanized-steel sheet.
 - 2. Shapes:
 - a. Cornerbead.
 - b. LC-Bead: J-shaped; exposed long flange receives joint compound.
 - Expansion (control) joint. C.

2.4 JOINT TREATMENT MATERIALS

- General: Comply with ASTM C 475/C 475M. A.
- Joint Tape: В.
 - Interior Gypsum Board: Paper.
- C. Joint Compound for Interior Gypsum Board: For each coat, use formulation that is compatible with other compounds applied on previous or for successive coats.
 - 1. Prefilling: At open joints, rounded or beveled panel edges, and damaged surface areas, use setting-type taping compound.
 - 2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use drying-type, all-purpose compound.
 - Use setting-type compound for installing paper-faced metal trim accessories.
 - 3. Fill Coat: For second coat, use drying-type, all-purpose compound.
 - Finish Coat: For third coat, use drying-type, all-purpose compound.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.5 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written instructions.
- B. Steel Drill Screws: ASTM C 1002 unless otherwise indicated.
 - Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch thick.
- C. Sound-Attenuation Blankets: ASTM C665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.
- D. Acoustical Joint Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834. Product effectively reduces airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.
 - Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Grabber Construction Products.
 - b. Pecora Corporation.
 - c. USG Corporation.

2.6 PARTITION GAP CLOSURE

- A. Partition-To-Curtain Wall Joint Closure Assemblies: Provide joint closures at conditions where partitions abut curtain wall vertical mullions or glazing, as shown on Drawings. Provide closure capable of accommodating variations in adjacent surfaces, and allowing for thermal movements from ambient and surface temperature changes.
 - Adjustable Closure Assembly: Provide complete STC-rated, compressed closure with extruded aluminum partition end cap.
 - Basis of Design: Emseal: QuietJoint.
 - b. Sound Transmission: STC 52
 - c. Color: As selected by Architect from manufacturer's full range.
 - Extruded aluminum end cap shall have mud-in flanges and be paintable to match the wall color.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and substrates including welded hollow-metal frames and support framing, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLYING AND FINISHING PANELS, GENERAL

- Α. Comply with ASTM C 840.
- B. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch of open space between panels. Do not force into place.
- C. Form control and expansion joints with space between edges of adjoining gypsum panels.
- D. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments. Provide 1/4- to 1/2-inch-wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- E. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.
- F. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical sealant. Install acoustical sealant at both faces of partitions at perimeters and through penetrations. Comply with ASTM C919 and with manufacturer's written instructions for locating edge trim and closing off sound-flanking paths around or through assemblies, including sealing partitions above acoustical ceilings.
- G. Install sound attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

3.3 APPLYING INTERIOR GYPSUM BOARD

- A. Install interior gypsum board in the following locations:
 - Type X: Vertical and ceiling surfaces unless otherwise indicated.
- Single-Layer Application: B.
 - On partitions/walls, apply gypsum panels horizontally (perpendicular to framing) unless otherwise indicated or required by fire-resistance-rated assembly, and minimize end joints.
 - 2. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

3.4 **INSTALLING TRIM ACCESSORIES**

- General: For trim with back flanges intended for fasteners, attach to framing with same fasteners Α. used for panels. Otherwise, attach trim according to manufacturer's written instructions.
- Control Joints: Install control joints according to ASTM C 840 and in specific locations approved B. by Architect for visual effect.
- C. Interior Trim: Install in the following locations:
 - Cornerbead: Use at outside corners. 1.
 - 2. LC-Bead: Use at exposed panel edges.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.5 FINISHING GYPSUM BOARD

- General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, Α. fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.
- B. Prefill open joints and damaged surface areas.
- C. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.
- Gypsum Board Finish Levels: Finish panels to levels indicated below and according to D. ASTM C 840:
 - Level 4: At panel surfaces that will be exposed to view unless otherwise indicated
 - Primer and its application to surfaces are specified in Section 099123 "Interior Painting."

3.6 **PROTECTION**

- Protect adjacent surfaces from drywall compound and promptly remove from floors and other A. non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.
- Protect installed products from damage from weather, condensation, direct sunlight, construction, B. and other causes during remainder of the construction period.
- C. Remove and replace panels that are wet, moisture damaged, and mold damaged.
 - Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
 - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 092900

GYPSUM BOARD 092900 - 5 Project No.: CP242241

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes acoustical panels and exposed suspension systems for interior ceilings.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified, 6 inches in size.

1.4 INFORMATIONAL SUBMITTALS

A. Evaluation Reports: For each acoustical panel ceiling suspension system and anchor and fastener type, from ICC-ES.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For finishes to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Acoustical Ceiling Units: Full-size panels equal to 2 percent of quantity installed.
 - 2. Suspension-System Components: Quantity of each exposed component equal to 2 percent of quantity installed.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver acoustical panels, suspension-system components, and accessories to Project site and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.

1.8 FIELD CONDITIONS

- A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.
 - 1. Pressurized Plenums: Operate ventilation system for not less than 48 hours before beginning acoustical panel ceiling installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain each type of acoustical ceiling panel and its supporting suspension system from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Suspended ceilings shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- B. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: Class A according to ASTM E 1264.
 - 2. Smoke-Developed Index: 50 or less.

2.3 ACOUSTICAL PANELS <ACT-1>

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Armstrong World Industries, Inc; Ultima or a comparable product by one of the following:
 - 1. CertainTeed Corporation.
 - 2. Chicago Metallic Corporation.
 - 3. USG Corporation.
- B. Acoustical Panel Standard: Provide manufacturer's standard panels according to ASTM E 1264 and designated by type, form, pattern, acoustical rating, and light reflectance unless otherwise indicated.
- C. Classification: Provide panels as follows:
 - 1. Type and Form: Type IV, mineral-fiber base with membrane-faced overlay; Form 2, cloth. Binder shall not contain urea formaldehyde.
 - 2. Pattern: E (lightly textured).
- D. Color: White.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- E. Light Reflectance (LR): Not less than 0.87.
- F. Noise Reduction Coefficient (NRC): Not less than 0.80.
- G. Edge/Joint Detail: Reveal sized to fit flange of exposed suspension-system members.
- H. Thickness: 3/4 inch.
- I. Modular Size: 24 by 24 inches.
- J. Antimicrobial Treatment: Manufacturer's standard broad spectrum, antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273, ASTM D 3274, or ASTM G 21 and evaluated according to ASTM D 3274 or ASTM G 21.

2.4 METAL SUSPENSION SYSTEM <ACT-1>

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Armstrong World Industries, Inc.
 - 2. CertainTeed Corporation.
 - 3. Chicago Metallic Corporation.
 - 4. USG Corporation.
- B. Metal Suspension-System Standard: Provide manufacturer's standard, direct-hung, metal suspension system and accessories according to ASTM C 635/C 635M and designated by type, structural classification, and finish indicated.
- C. Narrow-Face, Uncapped, Double-Web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized, G30 coating designation; to produce structural members with 9/16-inch-wide faces.
 - 1. Structural Classification: Heavy-duty system.
 - 2. Face Design: 15/16 inch.
 - 3. Face Finish: Painted white.

2.5 ACCESSORIES

- A. Attachment Devices: Size for five times the design load indicated in ASTM C 635/C 635M, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.
 - 1. Anchors in Concrete: Anchors of type and material indicated below, with holes or loops for attaching hangers of type indicated and with capability to sustain, without failure, a load equal to five times that imposed by ceiling construction, as determined by testing according to ASTM E 488/E 488M or ASTM E 1512 as applicable, conducted by a qualified testing and inspecting agency.
 - a. Type: Postinstalled expansion anchors.
 - b. Corrosion Protection: Carbon-steel components zinc plated according to ASTM B 633, Class SC 1 (mild) service condition.
 - 2. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hangers of type indicated and with capability to sustain, without

UNIVERSITY OF MISSOURI

ISSUED FOR BID

failure, a load equal to 10 times that imposed by ceiling construction, as determined by testing according to ASTM E 1190, conducted by a qualified testing and inspecting agency.

- B. Wire Hangers, Braces, and Ties: Provide wires as follows:
 - 1. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
 - 2. Size: Wire diameter sufficient for its stress at three times hanger design load (ASTM C 635/C 635M, Table 1, "Direct Hung") will be less than yield stress of wire, but not less than 0.135-inch- diameter wire.

2.6 METAL EDGE MOLDINGS AND TRIM

- A. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that comply with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension-system runners.
 - 1. Edge moldings shall fit acoustical panel edge details and suspension systems indicated and match width and configuration of exposed runners unless otherwise indicated.
 - 2. For lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.
 - 3. For circular penetrations of ceiling, provide edge moldings fabricated to diameter required to fit penetration exactly.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.
- B. Examine acoustical panels before installation. Reject acoustical panels that are wet, moisture damaged, or mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders unless otherwise indicated, and comply with layout shown on reflected ceiling plans.
- B. Layout openings for penetrations centered on the penetrating items.

3.3 INSTALLATION

- A. Install acoustical panel ceilings according to ASTM C 636/C 636M, seismic design requirements, and manufacturer's written instructions.
- B. Suspend ceiling hangers from building's structural members and as follows:
 - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
 - 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 - 3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
 - 4. Secure wire hangers to ceiling-suspension members and to supports above with a minimum of three tight turns. Connect hangers directly to structure or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
 - 5. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
 - 6. Space hangers not more than 48 inches o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than 8 inches from ends of each member.
 - 7. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards.
- C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.
- D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
 - 1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
 - 2. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends. Miter corners accurately and connect securely.
 - 3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- E. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- F. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide precise fit.
 - 1. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension-system runners and moldings.
 - 2. For reveal-edged panels on suspension-system members with box-shaped flanges, install panels with reveal surfaces in firm contact with suspension-system surfaces and panel faces flush with bottom face of runners.
 - 3. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.4 ERECTION TOLERANCES

- A. Suspended Ceilings: Install main and cross runners level to a tolerance of 1/8 inch in 12 feet, non-cumulative.
- B. Moldings and Trim: Install moldings and trim to substrate and level with ceiling suspension system to a tolerance of 1/8 inch in 12 feet, non-cumulative.

3.5 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage.
- B. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 095113

095113 - 6 Project No.: CP242241 February 27, 2024

ACOUSTICAL PANEL CEILINGS

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 096513 - RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Thermoset-rubber base.
 - 2. Rubber molding accessories.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples for Verification: For each type of product indicated and for each color, texture, and pattern required in manufacturer's standard-size Samples, but not less than 12 inches long.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Furnish not less than 10 linear feet for every 500 linear feet or fraction thereof, of each type, color, pattern, and size of resilient product installed.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F.

1.6 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following periods:
 - 1. 48 hours before installation.

096513 - 1 Project No.: CP242241 February 27, 2024

RESILIENT BASE AND ACCESSORIES

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. During installation.
- 3. 48 hours after installation.
- B. Install resilient products after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 THERMOSET-RUBBER BASE [RB-1]

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Tarkett; Baseworks Rubber Wall Base or comparable product by one of the following:
 - 1. Flexco: Roppe Holding Company.
 - 2. Roppe Corporation; Roppe Holding Company.
- B. Product Standard: ASTM F 1861, Type TS (rubber, vulcanized thermoset), Group I (solid, homogeneous).
 - 1. Style and Location:
 - a. Style B, Cove.
- C. Thickness: 0.125 inch.
- D. Height: 4 inches.
- E. Lengths: Coils in manufacturer's standard length.
- F. Outside Corners: Job formed.
- G. Inside Corners: Job formed.
- H. Colors: Charcoal 20.

2.2 RUBBER MOLDING ACCESSORY

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. Johnsonite; A Tarkett Company
 - 2. Flexco.
 - 3. Roppe Corporation, USA.
- B. Description: Rubber flooring transition for carpet to resilient floor finishes.
- C. Profile and Dimensions: Johnsonite Slim Line Transitions
- D. Locations: Provide flooring transitions at all transitions between different flooring types.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

E. Colors: Charcoal - 20.

2.3 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
 - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
 - 1. Installation of resilient products indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- C. Do not install resilient products until materials are the same temperature as space where they are to be installed.
 - 1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.
- D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.3 RESILIENT BASE INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient base.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.

G. Job-Formed Corners:

- 1. Outside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches in length.
 - a. Form without producing discoloration (whitening) at bends.
- 2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches in length.
 - Cope corners to minimize open joints.

3.4 RESILIENT ACCESSORY INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient accessories.
- B. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

3.5 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Perform the following operations immediately after completing resilient-product installation:
 - 1. Remove adhesive and other blemishes from surfaces.
- C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 096513

SECTION 096516 - RESILIENT SHEET FLOORING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Vinyl sheet floor covering, with backing.
- B. Related Sections:
 - 1. Division 09 Section "Resilient Base and Accessories" for resilient base, reducer strips, and other accessories installed with resilient floor coverings.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: For each type of floor covering. Include floor covering layouts, locations of seams, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.
 - 1. Show details of special patterns.
 - 2. Show locations of all seams.
- C. Samples for Verification: In manufacturer's standard size, but not less than 6-by-9-inch sections of each different color and pattern of floor covering required.
 - 1. For heat-welding bead, manufacturer's standard-size Samples, but not less than 9 inches long, of each color required.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified Installer.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of floor covering to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Floor Covering: Furnish quantity of 2 full rolls, in roll form and in full roll width for each color, pattern, and type of floor covering installed.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for floor covering installation and seaming method indicated.
 - 1. Engage an installer who employs workers for this Project who are trained or certified by floor covering manufacturer for installation techniques required.
- B. Fire-Test-Response Characteristics: As determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
 - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Store floor coverings and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F. Store rolls upright.

1.9 PROJECT CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 85 deg F, in spaces to receive floor coverings during the following time periods:
 - 1. 7 days before installation.
 - 2. During installation.
 - 3. 7 days after installation.
- B. Until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 85 deg F.
- C. Close spaces to traffic during floor covering installation.
- D. Close spaces to traffic for 48 hours after floor covering installation.
- E. Install floor coverings after other finishing operations, including painting, have been completed.

1.10 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace flooring that fails in materials or workmanship within specified warranty period.
 - 1. Warranty Period: Ten years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 VINYL SHEET FLOOR COVERING [VSF]:

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Mannington; Paradigm II or comparable product by one of the following:
 - 1. Armstrong World Industries, Inc.
 - 2. Forbo Flooring, Inc.
 - 3. Mannington Mills, Inc.
 - 4. Tarkett, Inc.
- B. Vinyl Sheet Floor Covering with Backing: ASTM F 1303.
 - 1. Wear-Layer Thickness: Grade 1.
 - 2. Overall Thickness: 0.080 inches.
 - 3. Interlayer Material: Polyurethane reinforced.
 - 4. Product must be a no-wax type flooring material.
- C. Wearing Surface: Non-embossed.
- D. Sheet Width: 6 feet.
- E. Seaming Method: Heat welded.
- F. Colors and Patterns: Intersect; Basis PD112.

2.2 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by manufacturer to suit floor covering and substrate conditions indicated.
- C. Seamless-Installation Accessories:
 - 1. Heat-Welding Bead: Manufacturer's solid-strand product for heat welding seams.
 - a. Color: Match floor covering.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of floor coverings.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of floor coverings.
- B. Concrete Substrates: Prepare according to ASTM F 710.
 - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
 - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
 - 3. Alkalinity and Adhesion Testing: Perform tests recommended by manufacturer. Proceed with installation only after substrates pass testing.
 - 4. Moisture Testing: Perform tests recommended by manufacturer and as follows. Proceed with installation only after substrates pass testing.
 - a. Perform anhydrous calcium chloride test, ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound and remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install floor coverings until they are same temperature as space where they are to be installed.
 - 1. Move floor coverings and installation materials into spaces where they will be installed at least 48 hours in advance of installation.
- E. Sweep and vacuum clean substrates to be covered by floor coverings immediately before installation.

3.3 FLOOR COVERING INSTALLATION

- A. Comply with manufacturer's written instructions for installing floor coverings.
- B. Unroll floor coverings and allow them to stabilize before cutting and fitting.

- C. Lay out floor coverings as follows:
 - 1. Maintain uniformity of floor covering direction.
 - 2. Minimize number of seams; place seams in inconspicuous and low-traffic areas, at least 6 inches away from parallel joints in floor covering substrates.
 - 3. Match edges of floor coverings for color shading at seams.
 - 4. Avoid cross seams.
 - 5. Seams are not allowed to intersect doorways.
- D. Scribe and cut floor coverings to butt neatly and tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, and door frames.
- E. Extend floor coverings into toe spaces, door reveals, closets, and similar openings.
- F. Maintain reference markers, holes, or openings that are in place or marked for future cutting by repeating on floor coverings as marked on substrates. Use chalk or other nonpermanent marking device.
- G. Install floor coverings on covers for telephone and electrical ducts and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of floor coverings installed on covers and adjoining floor covering. Tightly adhere floor covering edges to substrates that abut covers and to cover perimeters.
- H. Adhere floor coverings to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- I. Seamless Installation:
 - Heat-Welded Seams: Comply with ASTM F 1516. Rout joints and use welding bead to permanently fuse sections into a seamless floor covering. Prepare, weld, and finish seams to produce surfaces flush with adjoining floor covering surfaces.

3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protection of floor coverings.
- B. Perform the following operations immediately after completing floor covering installation:
 - 1. Remove adhesive and other blemishes from floor covering surfaces.
 - 2. Sweep and vacuum floor coverings thoroughly.
 - 3. Damp-mop floor coverings to remove marks and soil.
- C. Protect floor coverings from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Cover floor coverings until Substantial Completion.

END OF SECTION 096516

096516 - 5 Project No.: CP242241

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 096813 - TILE CARPETING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes modular carpet tile.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - Include manufacturer's written data on physical characteristics, durability, and fade resistance.
 - 2. Include manufacturer's written installation recommendations for each type of substrate.
- B. Samples: For each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.
 - 1. Carpet Tile: Full-size Sample.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For carpet tile, for tests performed by a qualified testing agency.
- C. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For carpet tiles to include in maintenance manuals. Include the following:
 - 1. Methods for maintaining carpet tile, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
 - 2. Precautions for cleaning materials and methods that could be detrimental to carpet tile.

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Carpet Tile: Full-size units equal to 5 percent of amount installed for each type indicated, but not less than 10 sq. yd.

1.7 QUALITY ASSURANCE

A. Installer Qualifications: An experienced installer who is certified by the International Certified Floorcovering Installers Association at the Commercial II certification level.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Comply with CRI's "CRI Carpet Installation Standard."

1.9 FIELD CONDITIONS

- A. Comply with CRI's "CRI Carpet Installation Standard" for temperature, humidity, and ventilation limitations.
- B. Environmental Limitations: Do not deliver or install carpet tiles until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at levels planned for building occupants during the remainder of the construction period.
- C. Do not install carpet tiles over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended by carpet tile manufacturer.
- D. Where demountable partitions or other items are indicated for installation on top of carpet tiles, install carpet tiles before installing these items.

1.10 WARRANTY

- A. Special Warranty for Carpet Tiles: Manufacturer agrees to repair or replace components of carpet tile installation that fail in materials or workmanship within specified warranty period.
 - 1. Warranty does not include deterioration or failure of carpet tile due to unusual traffic, failure of substrate, vandalism, or abuse.
 - 2. Failures include, but are not limited to, the following:
 - a. More than 10 percent edge raveling, snags, and runs.
 - b. Dimensional instability.
 - c. Excess static discharge.
 - d. Loss of tuft-bind strength.
 - e. Loss of face fiber.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- f. Delamination.
- 3. Warranty Period: Lifetime.

PART 2 - PRODUCTS

2.1 CARPET TILE < CPT-1>

- A. Basis-of-Design Product: Subject to compliance with requirements, provide Bentley Mills; High Score II tile or a comparable product as approved by the Architect.
- B. Color: Cooldown 400057.
- C. Installation Method: Brick.
- D. Pile Characteristic: Tufted texture loop.
- E. Dye Method: 100% solution dyed.
- F. Pile Thickness: 0.215 inches for finished carpet tile.
- G. Backing System: Affixx Hardback.
- H. Size: 18 inches by 36 inches.
- I. Applied Treatments:
 - 1. Soil-Resistance Treatment: Manufacturer's standard treatment.
 - 2. Antimicrobial Treatment: Manufacturer's standard treatment that protects carpet tiles as follows:
 - a. Antimicrobial Activity: Not less than 2-mm halo of inhibition for gram-positive bacteria, not less than 1-mm halo of inhibition for gram-negative bacteria, and no fungal growth, according to AATCC 174.

2.2 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended by carpet tile manufacturer.
- B. Adhesives: Water-resistant, mildew-resistant, nonstaining, pressure-sensitive type to suit products and subfloor conditions indicated, that comply with flammability requirements for installed carpet tile, and are recommended by carpet tile manufacturer for releasable installation.
 - 1. Adhesives shall have a VOC content of 50 g/L or less.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet tile performance.
- B. Examine carpet tile for type, color, pattern, and potential defects.
- C. Concrete Slabs: Verify that surfaces are free of cracks, ridges, depressions, scale, and foreign deposits.
 - 1. Moisture Testing: Perform tests so that each test area does not exceed 200 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.
 - a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. (1.36 kg of water/92.9 sq. m) in 24 hours.
 - b. Relative Humidity Test: Using in situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.
- D. Perform additional moisture tests recommended in writing by adhesive and carpet tile manufacturers. Proceed with installation only after substrates pass testing. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Comply with CRI's "Carpet Installation Standards" and with carpet tile manufacturer's written installation instructions for preparing substrates indicated to receive carpet tile.
- B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, depressions, and protrusions in substrates. Fill or level cracks, holes and depressions 1/8 inch wide or wider, and protrusions more than 1/32 inch unless more stringent requirements are required by manufacturer's written instructions.
- C. Broom and vacuum clean substrates to be covered immediately before installing carpet tile.

3.3 INSTALLATION

A. General: Comply with CRI's "CRI Carpet Installation Standard," Section 18, "Modular Carpet" and with carpet tile manufacturer's written installation instructions.

TILE CARPETING 096813 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Installation Method: Glue down; install every tile with full-spread, releasable, pressure-sensitive adhesive.
- C. Maintain dye-lot integrity. Do not mix dye lots in same area.
- D. Maintain pile-direction patterns recommended in writing by carpet tile manufacturer.
- E. Cut and fit carpet tile to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet tile manufacturer.
- F. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- G. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on carpet tile as marked on subfloor. Use nonpermanent, nonstaining marking device.
- H. Install pattern parallel to walls and borders.

3.4 CLEANING AND PROTECTION

- A. Perform the following operations immediately after installing carpet tile:
 - 1. Remove excess adhesive and other surface blemishes using cleaner recommended by carpet tile manufacturer.
 - 2. Remove yarns that protrude from carpet tile surface.
 - 3. Vacuum carpet tile using commercial machine with face-beater element.
- B. Protect installed carpet tile to comply with CRI's "Carpet Installation Standard," Section 20, "Protecting Indoor Installations."
- C. Protect carpet tile against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet tile manufacturer.

END OF SECTION 096813

TILE CARPETING **096813 - 5** Project No.: CP242241

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 099123 - INTERIOR PAINTING

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- Α. Section Includes:
 - 1. Primers.
 - Water-based finish coatings. 2.

1.3 **ACTION SUBMITTALS**

- Product Data: For each type of product. Include preparation requirements and application Α. instructions.
 - 1. Include preparation requirements and application instructions.
 - Indicate VOC content. 2.
- Samples for Verification: For each type of paint system and each color and gloss of topcoat. B.
 - 1. Submit Samples on rigid backing, 8 inches square.
 - 2. Apply coats on Samples in steps to show each coat required for system.
 - Label each coat of each Sample. 3.
 - Label each Sample for location and application area.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- Α. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - Paint Products: 5 percent, but not less than 1 gal. of each material and color applied. 1.

1.5 DELIVERY, STORAGE, AND HANDLING

- Α. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.
 - 1. Maintain containers in clean condition, free of foreign materials and residue.
 - 2. Remove rags and waste from storage areas daily.

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.6 FIELD CONDITIONS

- A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.
- B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures of less than 5 deg F above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, undefined:
 - 1. Benjamin Moore & Co.
 - 2. PPG Paints.
 - 3. Sherwin-Williams Company (The).
- B. Source Limitations: Obtain each paint product from single source from single manufacturer.

2.2 PAINT PRODUCTS, GENERAL

- A. Material Compatibility:
 - 1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
 - 2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.
- B. Colors: As indicated in a color schedule.

2.3 PRIMERS

- A. Interior Latex Primer Sealer: Water-based latex sealer used on gypsum wallboard surfaces.
 - 1. PPG: Speedhide Int. Latex Primer Sealer.
 - 2. Akzo Nobel Paints: Glidden Pro. Hi-Hide Wall Interior Water-Based Primer Sealer.
 - 3. Benjamin Moore: Super Spec Latex Enamel Undercoater & Primer Sealer.
 - 4. Sherwin-Williams: ProMar 200 Int. Latex Primer Primer.

B. METAL PRIMERS

- 1. Primer, Rust-Inhibitive, Water Based: MPI #107.
 - a. PPG: Pitt-Tech Int/Ext DTM Industrial Primer Gray.
 - b. Akzo Nobel Paints: Devoe DEVFLEX 4020 Direct to Metal Primer & Flat Finish.
 - c. Benjamin Moore: IRONCLAD Latex Low Lustre Metal & Wood Enamel.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

d. Sherwin-Williams: Pro -Cryl Universal Primer.

2.4 WATER-BASED FINISH COATS

- A. Latex, Interior, Flat, (Gloss Level 1): MPI #53.
 - 1. PPG: Speedhide Interior Flat Latex.
 - 2. Akzo Nobel Paints: Glidden Pro. Diamond 450 Interior Premium Acrylic Eggshell.
 - 3. Benjamin Moore: Super Spec Premium Latex Interior Flat Finish.
 - 4. Sherwin-Williams: ProMar 200 Interior Latex Flat.
- B. Latex, Interior, Eggshell, (Gloss Level 2): MPI #44.
 - PPG: Speedhide Interior Eggshell Latex.
 - 2. Akzo Nobel Paints: Glidden Pro. Diamond 450 Interior Premium Acrylic Flat.
 - 3. Benjamin Moore: Super Spec Premium Latex Interior Eggshell Enamel.
 - 4. Sherwin-Williams: ProMar 200 Interior Latex Eg-Shel.
- C. Light Industrial Coating, Interior, Water Based, Semi-Gloss (Gloss Level 5): MPI #153.
 - 1. PPG: Pitt-Tech Int/Ext High Semi-Gloss DTM Industrial Enamels.
 - 2. Akzo Nobel Paints: Devoe DEVFLEX 4216 High Performance WB Acrylic SG Enamel.
 - 3. Benjamin Moore: Super Spec D.T.M. Acrylic Semi-Gloss Enamel.
 - 4. Sherwin-Williams: Sher-Cryl HPA Semi-Gloss.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
 - 1. Wood: 15 percent.
 - 2. Gypsum Board: 12 percent.
- C. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.
- D. Verify suitability of substrates, including surface conditions and compatibility, with existing finishes and primers.
- E. Proceed with coating application only after unsatisfactory conditions have been corrected.
 - 1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations applicable to substrates and paint systems indicated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
 - 1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
 - 1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.
- D. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and areas where shop paint is abraded. Paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

3.3 INSTALLATION

- A. Apply paints according to manufacturer's written instructions.
 - 1. Use applicators and techniques suited for paint and substrate indicated.
 - 2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
 - 3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
 - 4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
 - 5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
- B. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
- C. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

3.4 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
 - 1. Do not clean equipment with free-draining water and prevent solvents, thinners, cleaners, and other contaminants from entering into waterways, sanitary and storm drain systems, and ground.
 - 2. Dispose of contaminants in accordance with requirements of authorities having jurisdiction.
 - 3. Allow empty paint cans to dry before disposal.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- After completing paint application, clean spattered surfaces. Remove spattered paints by B. washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- At completion of construction activities of other trades, touch up and restore damaged or D. defaced painted surfaces.

3.5 INTERIOR PAINTING SCHEDULE

Steel Substrates: A.

- Water-Based Light Industrial Coating System:
 - Prime Coat: Primer, rust-inhibitive, water based MPI #107 or factory primed.
 - Intermediate Coat: Light industrial coating, interior, water based, matching topcoat. b.
 - Topcoat: Light industrial coating, interior, water based, semi-gloss (Gloss C. Level 2), MPI #153.

Gypsum Board Substrates: B.

- Latex System:
 - Prime Coat: Primer sealer, latex, interior, MPI #50.
 - b. Intermediate Coat: Latex, interior, matching topcoat.
 - Topcoat at Ceilings: Latex, interior, flat, (Gloss Level 1), MPI #53. C.
 - Topcoat at all Walls: Latex, interior, eggshell, (Gloss Level 2), MPI #44. d.

END OF SECTION 099123

INTERIOR PAINTING 099123 - 5 Project No.: CP242241

February 27, 2024

SECTION 102600 - WALL AND DOOR PROTECTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Corner guards.
 - 2. Wall guards.
 - 3. Door-frame protection.
- B. Related Requirements:
 - 1. Section 087100 "Door Hardware" for metal protective trim units, according to BHMA A156.6, used for armor, kick, mop, and push plates.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, impact strength, dimensions of individual components and profiles, and finishes.
- B. Samples for Initial Selection: For each type of impact-resistant wall-protection unit indicated, in each color and texture specified.

1.4 INFORMATIONAL SUBMITTALS

- A. Material Certificates: For each type of exposed plastic material.
- B. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of wall protection product to include in maintenance manuals.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Store wall and door protection in original undamaged packages and containers inside well-ventilated area protected from weather, moisture, soiling, extreme temperatures, and humidity.

- 1. Maintain room temperature within storage area at not less than 70 deg F during the period plastic materials are stored.
- 2. Keep plastic materials out of direct sunlight.
- 3. Store plastic wall- and door-protection components for a minimum of 72 hours, or until plastic material attains a minimum room temperature of 70 deg F.
 - a. Store corner-guard covers in a vertical position.

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of wall-protection units that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Structural failures including detachment of components from each other or from the substrates, delamination, and permanent deformation beyond normal use.
 - b. Deterioration of metals, metal finishes, plastics, and other materials beyond normal use.
 - 2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain wall- and door-protection products of each type from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

- A. Surface Burning Characteristics: Comply with ASTM E 84 or UL 723; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 25 or less.
 - 2. Smoke-Developed Index: 450 or less.
- B. Regulatory Requirements: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines for Buildings and Facilities.

2.3 CORNER GUARDS

- A. Surface-Mounted, Resilient, Plastic Corner Guards: Assembly consisting of snap-on plastic cover, installed over continuous retainer; including mounting hardware; fabricated with 90- or 135-degree turn to match wall condition; full wall height.
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Construction Specialties, Inc.; SSM-20AN or comparable product by one of the following:

- a. Arden Architectural Specialties, Inc.
- b. IPC Door and Wall Protection Systems; Division of InPro Corporation.
- 2. Cover: Extruded rigid plastic, minimum 0.078-inch wall thickness; as follows:
 - a. Profile: Nominal 2-inch- long leg and 1/4-inch corner radius.
 - b. Height: 48 inches.
 - c. Color and Texture: As selected by Architect from manufacturer's full range.
- 3. Retainer: Minimum 0.060-inch- thick, one-piece, extruded aluminum.

2.4 IMPACT-RESISTANT WALL COVERINGS

- A. Impact-Resistant Sheet Wall Covering: Fabricated from plastic sheet wall-covering material.
 - Basis-of-Design Product: Subject to compliance with requirements, provide Construction Specialties, Inc.; Acrovyn 4000 or comparable product by one of the following:
 - a. Arden Architectural Specialties, Inc.
 - b. IPC Door and Wall Protection Systems; Division of InPro Corporation.
 - 2. Size: 48 by 96 inches for sheet.
 - 3. Sheet Thickness: 0.060 inch.
 - 4. Color and Texture: Match existing wall protection.
 - 5. Height: Wainscot height matching existing.
 - 6. Trim and Joint Moldings: Extruded rigid plastic that matches sheet wall covering color.
 - 7. Mounting: Adhesive.

2.5 DOOR-FRAME PROTECTION

- A. Door-Frame Protector: One piece fabricated from extruded rigid plastic, minimum 0.040-inch wall thickness; formed to fit entire door-frame profile.
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Construction Specialties, Inc.; Acrovyn B1-DFP or comparable product by one of the following:
 - a. Arden Architectural Specialties, Inc.
 - b. IPC Door and Wall Protection Systems; Division of InPro Corporation.
 - 2. Height: 36 inches.
 - 3. Color and Texture: As selected by Architect from manufacturer's full range.
 - 4. Mounting: Adhesive.

2.6 MATERIALS

A. Adhesive: As recommended by protection product manufacturer.

2.7 FABRICATION

- A. Fabricate wall and door protection according to requirements indicated for design, performance, dimensions, and member sizes, including thicknesses of components.
- B. Quality: Fabricate components with uniformly tight seams and joints and with exposed edges rolled. Provide surfaces free of wrinkles, chips, dents, uneven coloration, and other imperfections. Fabricate members and fittings to produce flush, smooth, and rigid hairline joints.

2.8 FINISHES

- A. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and wall areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine walls to which wall and door protection will be attached for blocking, grounds, and other solid backing that have been installed in the locations required for secure attachment of support fasteners.
 - 1. For wall and door protection attached with adhesive, verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Complete finishing operations, including painting, before installing wall and door protection.
- B. Before installation, clean substrate to remove dust, debris, and loose particles.

3.3 INSTALLATION

- A. Installation Quality: Install wall and door protection according to manufacturer's written instructions, level, plumb, and true to line without distortions. Do not use materials with chips, cracks, voids, stains, or other defects that might be visible in the finished Work.
- B. Abuse-Resistant Wall Covering: Install top and edge moldings, corners, and divider bars as required for a complete installation.
- C. Door-Frame Protectors: Install on both door jams.

3.4 CLEANING

A. Remove excess adhesive using methods and materials recommended in writing by manufacturer.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

END OF SECTION 102600

WALL AND DOOR PROTECTION

102600 - 5

SECTION 122413 - ROLLER WINDOW SHADES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - Manually-operated roller shades.
- B. Related Requirements:
 - 1. Section 061000 "Rough Carpentry" for wood blocking and grounds for mounting roller shades and accessories.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include styles, material descriptions, construction details, dimensions of individual components and profiles, features, finishes, and operating instructions for roller shades.
- B. Shop Drawings: Show fabrication and installation details for roller shades, including shadeband materials, their orientation to rollers, and their seam and batten locations.
- C. Samples: For each exposed product and for each color and texture specified, 10 inches long.

1.4 INFORMATIONAL SUBMITTALS

A. Product Certificates: For each type of shadeband material, signed by product manufacturer.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For roller shades to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: Fabricator of products or manufacturer approved and trained installer.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver roller shades in factory packages, marked with manufacturer, product name, and location of installation using same designations indicated on Drawings.

1.8 FIELD CONDITIONS

- A. Environmental Limitations: Do not install roller shades until construction and finish work in spaces, including painting, is complete and dry and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.
- B. Field Measurements: Where roller shades are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operating hardware of operable glazed units through entire operating range. Notify Architect of installation conditions that vary from Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Basis-of-Design Product: Subject to compliance with requirements, provide products by MechoShade Systems, Inc or a comparable product by one of the following:
 - 1. Draper Inc.
 - 2. Hunter Douglas Contract.
- B. Source Limitations: Obtain roller shades from single source from single manufacturer.

2.2 MANUALLY-OPERATED SHADES WITH SINGLE ROLLERS

- A. Basis-of-Design Product: MechoShade Systems; Mecho /5 with fascia and related heavy duty mounting system and accessories.
- B. Chain-and-Clutch Operating Mechanisms: With continuous-loop bead chain and clutch that stops shade movement when bead chain is released; permanently adjusted and lubricated.
 - Bead Chains: Manufacturer's standard.
 - a. Loop Length: Full length of roller shade.
 - b. Limit Stops: Provide upper and lower ball stops.
 - c. Chain-Retainer Type: Clip, jamb mount.
- C. Rollers: Corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shadebands indicated without deflection. Provide with permanently lubricated drive-end assemblies and idle-end assemblies designed to facilitate removal of shadebands for service.
 - 1. Roller Drive-End Location: Right side of interior face of shade.
 - 2. Direction of Shadeband Roll: Regular, from back (exterior face) of roller.
 - 3. Shadeband-to-Roller Attachment: Removable spline fitting into integral channel in tube.

- D. Mounting Hardware: Brackets or endcaps, corrosion resistant and compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated.
- E. Installation Accessories:
 - 1. Fascia Enclosure for Ceiling Mount: Rectangular, extruded-aluminum enclosure designed for surface mounted ceiling installation; with front, top, and back formed as one piece, end plates, and removable bottom closure panel.
 - Height: Manufacturer's standard height required to enclose roller and shadeband when shade is fully open.
 - 2. Installation Accessories Color and Finish: As selected by architect from manufacturer's full range.

2.3 SHADEBAND MATERIALS

- A. Shadeband Material Flame-Resistance Rating: Comply with NFPA 701. Testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
- B. Light-Filtering Fabric: Woven fabric, stain and fade resistant.
 - 1. Basis-of-Design: Mechoshade; EcoVeil 1350 Series.
 - 2. Type: 1005 TPO
 - 3. Weave: Mesh.
 - 4. Weight: 12.68 oz./sq. yd.
 - 5. Openness Factor: 5 percent.
 - 6. Color: As selected by Architect from manufacturer's full range.

2.4 ROLLER-SHADE FABRICATION

- A. Product Safety Standard: Fabricate roller shades to comply with WCMA A 100.1, including requirements for flexible, chain-loop devices; lead content of components; and warning labels.
- B. Unit Sizes: Fabricate units in sizes to fill window and other openings as follows, measured at 74 deg F:
 - 1. Between (Inside) Jamb Installation: Width equal to jamb-to-jamb dimension of opening in which shade is installed less 1/4 inch per side or 1/2-inch total, plus or minus 1/8 inch. Length equal to head-to-sill or -floor dimension of opening in which shade is installed less 1/4 inch, plus or minus 1/8 inch.
- C. Shadeband Fabrication: Fabricate shadebands without battens or seams to extent possible except as follows:
 - 1. Vertical Shades: Where width-to-length ratio of shadeband is equal to or greater than 1:4, provide battens and seams at uniform spacings along shadeband length to ensure shadeband tracking and alignment through its full range of movement without distortion of the material.
 - 2. Railroaded Materials: Railroad material where material roll width is less than the required width of shadeband and where indicated. Provide battens and seams as required by railroaded material to produce shadebands with full roll-width panel(s) plus, if required, one partial roll-width panel located at top of shadeband.

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, accurate locations of connections to building electrical system, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 ROLLER-SHADE INSTALLATION

A. Install roller shades level, plumb, and aligned with adjacent units according to manufacturer's written instructions.

3.3 ADJUSTING

A. Adjust and balance roller shades to operate smoothly, easily, safely, and free from binding or malfunction throughout entire operational range.

3.4 CLEANING AND PROTECTION

- A. Clean roller-shade surfaces after installation, according to manufacturer's written instructions.
- B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that roller shades are without damage or deterioration at time of Substantial Completion.
- C. Replace damaged roller shades that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain motor-operated roller shades.

END OF SECTION 122413

SECTION 210500 - COMMON WORK RESULTS FOR FIRE SUPPRESSION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Piping materials and installation instructions common to most piping systems.
 - Mechanical sleeve seals.
 - Sleeves.
 - 4. Escutcheons.
 - Coordination drawings.
 - 6. Project record drawings.
 - 7. Fire-suppression equipment and piping demolition.
 - 8. Equipment installation requirements common to equipment sections.
 - 9. Painting and finishing.
 - 10. Supports and anchorages.

1.3 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe chases, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspaces, and tunnels.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in chases.
- D. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.
- E. The following are industry abbreviations for rubber materials:
 - 1. EPDM: Ethylene-propylene-diene terpolymer rubber.
 - 2. NBR: Acrylonitrile-butadiene rubber.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.4 SUBMITTALS

- A. Product Data: For the following:
 - Mechanical sleeve seals.
 - Escutcheons.
- B. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Steel Support Welding: Qualify processes and operators according to AWS D1.1, "Structural Welding Code--Steel."
- B. Electrical Characteristics for Fire-Suppression Equipment: Equipment of higher electrical characteristics may be furnished provided such proposed equipment is approved in writing and connecting electrical services, circuit breakers, and conduit sizes are appropriately modified. Any additional costs as a result of these modifications shall be borne by the contractor. If minimum energy ratings or efficiencies are specified, equipment shall comply with requirements.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- B. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, if stored inside.
- C. Protect flanges, fittings, and piping specialties from moisture and dirt.

1.7 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for fire-suppression installations.
- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Coordinate requirements for access panels and doors for fire-suppression items requiring access that are concealed behind finished surfaces. Access panels and doors are specified in Division 08 Section "Access Doors and Frames."
- D. Sequence, coordinate, and integrate installations of fire suppression materials and equipment for efficient flow of the Work. Coordinate installation of large equipment requiring positioning before closing in building.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- E. Coordinate installation of identifying devices after completing covering and painting, if devices are applied to surfaces. Install identifying devices before installing acoustical ceilings and similar concealment.
- F. Sequence, coordinate, and integrate removal of existing equipment and material as required to maintain services for existing building and for portions of remodeled areas at all times.

1.8 SCHEDULING AND PHASING

A. All fire suppression work shall be scheduled to meet project completion data. Fire suppression work shall be phased for projects requiring phasing of work. Install additional fittings, valves, caps as required to support phasing. Refer to phasing schedule on drawings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where subparagraph titles below introduce lists, the following requirements apply for product selection:
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the manufacturers specified.
 - 2. Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified.

2.2 PIPE, TUBE, AND FITTINGS

- A. Refer to individual Division 21 piping Sections for pipe, tube, and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

2.3 JOINING MATERIALS

- A. Refer to individual Division 21 piping Sections for special joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.

- 2. AWWA C110, rubber, flat face, 1/8 inch thick, unless otherwise indicated; and full-face or ring type, unless otherwise indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.

2.4 MECHANICAL SLEEVE SEALS

- A. Description: Modular sealing element unit, designed for field assembly, to fill annular space between pipe and sleeve.
 - 1. Acceptable Manufacturers:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Metraflex Co.
 - d. Pipeline Seal and Insulator, Inc. (LINK SEAL)
 - 2. Sealing Elements: EPDM or NBR interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Carbon steel. Include two for each sealing element.
 - Connecting Bolts and Nuts: Carbon steel with corrosion-resistant coating of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.5 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Steel Pipe: ASTM A 53, Type E, Grade B, Schedule 40, galvanized, plain ends.
- C. Cast Iron: Cast or fabricated "wall pipe" equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- D. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.

2.6 ESCUTCHEONS

- A. Description: Manufactured wall and ceiling escutcheons and floor plates, with an ID to closely fit around pipe, tube, and insulation of insulated piping and an OD that completely covers opening.
- B. One-Piece, Cast-Brass Type: With set screw.
 - 1. Finish: Polished chrome-plated or Rough brass.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Split-Casting, Cast-Brass Type: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated.
- D. One-Piece, Stamped-Steel Type: With set screw or spring clips and chrome-plated finish.
- E. Split-Plate, Stamped-Steel Type: With concealed hinge, set screw or spring clips, and chrome-plated finish.
- F. One-Piece, Floor-Plate Type: Cast-iron floor plate.
- G. Split-Casting, Floor-Plate Type: Cast brass with concealed hinge and set screw.

2.7 COORDINATION DRAWINGS

- A. The Contractor shall prepare CAD generated drawings (min. 1/4" scale) showing following systems/items as a minimum:
 - Fire suppression piping routing including locations of valves, drops to sprinkler heads, risers, etc.
 - 2. Fire suppression equipment locations and clearances required.
- B. The Contractor shall submit the CAD generated drawings to HVAC contractor for coordination with other trades. The drawings shall be submitted either in electronic format or printed copies as requested by HVAC Contractor.
- C. The Contractor shall participate in coordination meetings when requested by HVAC Contractor.

2.8 PROJECT RECORD DRAWINGS

- A. Drawings shall be furnished in electronic-media (CD-Rewritable type) and at least one hard copy prints.
 - 1. Format: Same CAD program, version and operating system as the original Contract Drawings.
 - 2. Incorporate changes and additional information previously marked on Record prints. Delete, re-draw and add details and notations where applicable.
- B. Identify and date each drawing and include the designation "PROJECT RECORD DRAWINGS" or "AS-BUILT DRAWING" in a prominent location.

PART 3 - EXECUTION

3.1 FIRE-SUPPRESSION DEMOLITION

A. Refer to Division 01 Section "Cutting and Patching" and Division 02 Section "Selective Structure Demolition" for general demolition requirements and procedures.

3.2 PIPING SYSTEMS - COMMON REQUIREMENTS

- A. Install piping according to the following requirements and Division 21 Sections specifying piping systems.
- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- C. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping minimum 8 inches above accessible ceilings to allow sufficient space for ceiling panel removal and service access.
- F. Install piping to permit valve servicing.
- G. Install piping at indicated slopes.
- H. Install piping free of sags and bends.
- I. Install fittings for changes in direction and branch connections.
- J. Install piping to allow application of insulation.
- K. Select system components with pressure rating equal to or greater than system operating pressure.
- L. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. New Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type.
 - b. Chrome-Plated Piping: One-piece, cast-brass type with polished chrome-plated finish
 - c. Insulated Piping: One-piece, stamped-steel type with spring clips.
 - d. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece, castbrass type with polished chrome-plated finish.
 - e. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece or split-casting, cast-brass type with polished chrome-plated finish.
 - f. Bare Piping in Unfinished Service Spaces: One-piece, cast-brass type with roughbrass finish.
 - g. Bare Piping in Equipment Rooms: One-piece, cast-brass type.
 - h. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece, floor-plate type.
- M. Sleeves are not required for core-drilled holes.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- N. Permanent sleeves are not required for holes formed by removable PE sleeves.
- O. Install sleeves for pipes passing through concrete and masonry walls and concrete floor and roof slabs.
- P. Install sleeves for pipes passing through concrete and masonry walls, gypsum-board partitions, and concrete floor and roof slabs.
 - 1. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
 - 2. Install sleeves in new walls and slabs as new walls and slabs are constructed.
 - 3. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Use the following sleeve materials:
 - a. Steel Pipe Sleeves: For pipes smaller than NPS 6.
 - b. Steel Sheet Sleeves: For pipes NPS 6 and larger, penetrating gypsum-board partitions.
 - c. Stack Sleeve Fittings: For pipes penetrating floors with membrane waterproofing. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level. Refer to Division 07 Section "Sheet Metal Flashing and Trim" for flashing.
 - 1) Seal space outside of sleeve fittings with grout.
- Q. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Refer to Division 07 Section "Penetration Firestopping" for materials.
- R. Verify final equipment locations for roughing-in.
- S. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.

3.3 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 21 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

COMMON WORK RESULTS FOR FIRE SUPPRESSION

210500 - 7

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- E. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.

3.4 PAINTING

- A. Painting of fire-suppression systems, equipment, and components is specified in Division 09 Sections "Interior Painting."
- B. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.5 ERECTION OF METAL SUPPORTS AND ANCHORAGES

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor fire-suppression materials and equipment.
- B. Field Welding: Comply with AWS D1.1.

END OF SECTION 210500

COMMON WORK RESULTS FOR FIRE SUPPRESSION

210500 - 8

SECTION 211313 - WET-PIPE SPRINKLER SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Pipes, fittings, and specialties.
- 2. Fire-protection valves.
- 3. Sprinklers.
- 4. Pressure gages.

1.3 DEFINITIONS

A. Standard-Pressure Sprinkler Piping: Wet-pipe sprinkler system piping designed to operate at working pressure of 175 psig maximum.

1.4 SYSTEM DESCRIPTIONS

A. Wet-Pipe Sprinkler System: Automatic sprinklers are attached to piping containing water and that is connected to water supply through alarm valve. Water discharges immediately from sprinklers when they are opened. Sprinklers open when heat melts fusible link or destroys frangible device. Hose connections are included if indicated.

1.5 PERFORMANCE REQUIREMENTS

- A. Standard-Pressure Piping System Component: Listed for 175-psig minimum working pressure.
- B. Delegated Design: Design sprinkler system(s), including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
 - 1. Contractor shall obtain fire-hydrant flow test records from authorities having jurisdiction.
- C. Sprinkler system design shall be approved by Engineer and authorities having jurisdiction.
 - 1. Margin of Safety for Available Water Flow and Pressure: 10 percent, including losses through water-service piping, valves, and backflow preventers.

- Sprinkler Occupancy Hazard Classifications According to NFPA 13 Unless Otherwise Noted:
 - a. Building Service Areas: Ordinary Hazard, Group 1.
 - b. Electrical Equipment Rooms: Ordinary Hazard, Group 1.
 - c. General Business Occupancy: Light Hazard
 - d. General Storage Areas: Ordinary Hazard, Group 2.
 - e. Mechanical Equipment Rooms: Ordinary Hazard, Group 1.
 - f. Office and Public Areas: Light Hazard.
 - g. Restaurant Service Areas: Ordinary Hazard, Group 1.
- 3. Minimum Density for Automatic-Sprinkler Piping Design According to NFPA 13 Unless Noted Otherwise:
 - a. Light-Hazard Occupancy: 0.10 gpm over 1500-sq. ft. area.
 - b. Ordinary-Hazard, Group 1 Occupancy: 0.15 gpm over 1500-sq. ft. area.
 - c. Ordinary-Hazard, Group 2 Occupancy: 0.20 gpm over 1500-sq. ft. area.
 - d. Extra-Hazard, Group 1 Occupancy: 0.30 gpm over 2500-sq. ft. area.
 - e. Extra-Hazard, Group 2 Occupancy: 0.40 gpm over 2500-sq. ft. area.
 - f. Special Occupancy Hazard: As determined by authorities having jurisdiction.
- 4. Maximum Protection Area per Sprinkler According to NFPA 13 Unless Noted Otherwise:
 - a. Office Spaces and Classrooms: 225 sq. ft.
 - b. Storage Areas: 130 sq. ft.
 - c. Mechanical Equipment Rooms: 130 sq. ft.
 - d. Electrical Equipment Rooms: 130 sq. ft.
 - e. Other Areas: According to NFPA 13 recommendations unless otherwise indicated.
- 5. Total Combined Hose-Stream Demand Requirement: According to NFPA 13 unless otherwise indicated:
 - a. Light-Hazard Occupancies: 100 gpm for 30 minutes.
 - b. Ordinary-Hazard Occupancies: 250 gpm for 60 to 90 minutes.
 - c. Extra-Hazard Occupancies: 500 gpm for 90 to 120 minutes.
- D. Seismic Performance: Sprinkler piping shall withstand the effects of earthquake motions determined according to NFPA 13 and ASCE/SEI 7.

1.6 SUBMITTALS

- A. Product Data: For each type of product indicated. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Shop Drawings: For wet-pipe sprinkler systems. Include plans, elevations, sections, details, and attachments to other work.
 - 1. Wiring Diagrams: For power, signal, and control wiring.
- C. Delegated-Design Submittal: For sprinkler systems indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Coordination Drawings: Sprinkler systems, drawn to minimum ¼" scale, on CAD generated drawings. Refer to Section "Common Work Results for Fire Suppression".
- E. Qualification Data: For qualified Installer.
- F. Approved Sprinkler Piping Drawings: Working plans, prepared according to NFPA 13, that have been approved by the Engineer, including hydraulic calculations.
- G. Welding certificates.
- H. Fire-hydrant flow test report.
- Field Test Reports and Certificates: Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13. Include "Contractor's Material and Test Certificate for Aboveground Piping."
- J. Field quality-control reports.
- K. Operation and Maintenance Data: For sprinkler specialties to include in emergency, operation, and maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications:
 - 1. Installer's responsibilities include designing, fabricating, and installing sprinkler systems and providing professional engineering services needed to assume engineering responsibility. Base calculations on results of fire-hydrant flow test.
 - a. Engineering Responsibility: Preparation of working plans, calculations, and field test reports by a qualified professional engineer.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. NFPA Standards: Sprinkler system equipment, specialties, accessories, installation, and testing shall comply with the following:
 - 1. NFPA 13, "Installation of Sprinkler Systems."
 - 2. NFPA 24, "Installation of Private Fire Service Mains and Their Appurtenances."

1.8 COORDINATION

A. Coordinate layout and installation of sprinklers with other construction that penetrates ceilings, including light fixtures, HVAC equipment, and partition assemblies. Refer to Section "Common Work Results for Fire Suppression" for details.

1.9 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Sprinkler Cabinets: Finished, wall-mounted, steel cabinet with hinged cover, and with space for minimum of six spare sprinklers plus sprinkler wrench. Include number of sprinklers required by NFPA 13 and sprinkler wrench. Include separate cabinet with sprinklers and wrench for each type of sprinkler used on Project.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, and fitting materials, and for joining methods for specific services, service locations, and pipe sizes.

2.2 STEEL PIPE AND FITTINGS

- A. Standard Weight, Black-Steel Pipe: ASTM A 53, Type E, Grade B. Pipe ends may be factory or field formed to match joining method.
- B. Schedule 40, Black-Steel Pipe: ASTM A 135 or ASTM A 795, Schedule 40 in NPS 6 and smaller.
- C. Standard-Weight, Black-Steel Pipe Nipples: ASTM A 733, made of ASTM A 53, seamless steel pipe with threaded ends.
- D. Malleable- or Ductile-Iron Unions: UL 860.
- E. Cast-Iron Flanges: ASME B16.1, Class 125.
- F. Steel Flanges and Flanged Fittings: ASME B16.5, Class 150.
- G. Steel Welding Fittings: ASTM A 234 and ASME B16.9.
- H. Grooved-Joint, Steel-Pipe Appurtenances:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Victaulic Company.
 - 2. Pressure Rating: 175 psig minimum.
 - 3. Uncoated, Grooved-End Fittings for Steel Piping: ASTM A 47, malleable-iron casting or ASTM A 536, ductile-iron casting; with dimensions matching steel pipe.
 - 4. Grooved-End-Pipe Couplings for Steel Piping: AWWA C606 and UL 213, rigid pattern, unless otherwise indicated, for steel-pipe dimensions. Include ferrous housing sections, EPDM-rubber gasket, and bolts and nuts.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

I. Steel Pressure-Seal Fittings: UL 213, FM-approved, 175-psig pressure rating with steel housing, rubber O-rings, and pipe stop; for use with fitting manufacturers' pressure-seal tools.

2.3 PIPING JOINING MATERIALS

- A. Pipe-Flange Gasket Materials: AWWA C110, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free.
 - 1. Class 125, Cast-Iron Flanges and Class 150, Bronze Flat-Face Flanges: Full-face gaskets.
 - 2. Class 250, Cast-Iron Flanges and Class 300, Steel Raised-Face Flanges: Ring-type gaskets.
- B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.

2.4 LISTED FIRE-PROTECTION VALVES

- A. General Requirements:
 - 1. Valves shall be UL listed or FM approved.
 - 2. Minimum Pressure Rating for Standard-Pressure Piping: 175 psig.
- B. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Anvil International, Inc.
 - 2. Crane Co.
 - 3. Globe Fire Sprinkler Corporation.
 - Metraflex. Inc.
 - 5. Milwaukee Valve Company.
 - 6. Mueller Co.; Water Products Division.
 - 7. NIBCO INC.
 - 8. Potter Roemer.
 - 9. Reliable Automatic Sprinkler Co., Inc.
 - 10. Tyco Fire & Building Products LP.
 - 11. Victaulic Company.
 - 12. Viking Corporation.
 - 13. Watts Water Technologies, Inc.

C. Ball Valves:

- 1. Standard: UL 1091 except with ball instead of disc.
- 2. Valves NPS 1-1/2 and Smaller: Bronze body with threaded ends.
- 3. Valves NPS 2 and NPS 2-1/2: Bronze body with threaded ends or ductile-iron body with grooved ends.
- 4. Valves NPS 3: Ductile-iron body with grooved ends.
- D. Bronze Butterfly Valves:
 - Standard: UL 1091.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Pressure Rating: 175 psig.
- 3. Body Material: Bronze.
- Disc Material: Aluminum bronze. 4.
- End Connections: Threaded. 5.

E. Iron Butterfly Valves:

- 1. Standard: UL 1091.
- 2. Pressure Rating: 175 psig.
- 3. Body Material: Cast or ductile iron.
- 4. Disc Material: Aluminum Bronze.
- 5. Style: Lug or wafer.
- End Connections: Grooved. 6.

Check Valves: F.

- 1. Standard: UL 312.
- 2. Pressure Rating: 250 psig minimum.
- Type: Swing check. 3.
- Body Material: Cast iron. 4.
- 5. End Connections: Flanged or grooved.

Bronze OS&Y Gate Valves: G.

- Standard: UL 262. 1.
- Pressure Rating: 175 psig. 2.
- Body Material: Bronze. 3.
- 4. End Connections: Threaded.

Η. Iron OS&Y Gate Valves:

- Standard: UL 262. 1.
- 2. Pressure Rating: 250 psig minimum.
- Body Material: Cast or ductile iron. 3.
- End Connections: Flanged or grooved.

Indicating-Type Butterfly Valves: I.

- 1. Standard: UL 1091.
- 2. Pressure Rating: 175 psig minimum.
- 3. Valves NPS 2 and Smaller:
 - Valve Type: Ball or butterfly. a.
 - Body Material: Bronze. b.
 - End Connections: Threaded.

4. Valves NPS 2-1/2 and Larger:

- Valve Type: Butterfly.
- Body Material: Cast or ductile iron. b.
- Disc Material: Aluminum bronze. C.
- End Connections: Flanged, grooved, or wafer. d.

WET-PIPE SPRINKLER SYSTEMS 211313 - 6

UNIVERSITY OF MISSOURI

ISSUED FOR BID

5. Valve Operation: Integral electrical, 115-V ac, prewired, two-circuit, supervisory switch visual indicating device.

J. NRS Gate Valves:

- 1. Standard: UL 262.
- 2. Pressure Rating: 250 psig minimum.
- 3. Body Material: Cast iron with indicator post flange.
- 4. Stem: Nonrising.
- 5. End Connections: Flanged or grooved.

2.5 SPECIALTY VALVES

A. General Requirements:

- 1. Standard: UL's "Fire Protection Equipment Directory" listing or "Approval Guide," published by FM Global, listing.
- 2. Pressure Rating:
 - a. Standard-Pressure Piping Specialty Valves: 175 psig minimum.
- 3. Body Material: Cast or ductile iron.
- 4. Size: Same as connected piping.
- 5. End Connections: Flanged or grooved.
- B. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Globe Fire Sprinkler Corporation.
 - 2. Reliable Automatic Sprinkler Co., Inc.
 - 3. Tyco Fire & Building Products LP.
 - 4. Victaulic Company.
 - 5. Viking Corporation.

C. Automatic (Ball Drip) Drain Valves:

- 1. Standard: UL 1726.
- 2. Pressure Rating: 175 psig minimum.
- 3. Type: Automatic draining, ball check.
- 4. Size: NPS 3/4.
- 5. End Connections: Threaded.

2.6 SPRINKLER SPECIALTY PIPE FITTINGS

A. Branch Outlet Fittings:

- 1. Standard: UL 213.
- 2. Pressure Rating: 175 psig minimum.
- 3. Body Material: Ductile-iron housing with EPDM seals and bolts and nuts.
- 4. Type: Mechanical-T and -cross fittings.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 5. Configurations: Ductile-iron housing with branch outlets.
- 6. Size: Of dimension to fit onto sprinkler main and with outlet connections as required to match connected branch piping.
- 7. Branch Outlets: Grooved, plain-end pipe, or threaded.

B. Flow Detection and Test Assemblies:

- 1. Standard: UL's "Fire Protection Equipment Directory" listing or "Approval Guide," published by FM Global, listing.
- 2. Pressure Rating: 175 psig minimum.
- 3. Body Material: Cast- or ductile-iron housing with orifice, sight glass, and integral test valve.
- 4. Size: Same as connected piping.
- 5. Inlet and Outlet: Threaded.

C. Branch Line Testers:

- 1. Standard: UL 199.
- 2. Pressure Rating: 175 psig.
- 3. Body Material: Brass.
- 4. Size: Same as connected piping.
- 5. Inlet: Threaded.
- 6. Drain Outlet: Threaded and capped.
- 7. Branch Outlet: Threaded, for sprinkler.

D. Sprinkler Inspector's Test Fittings:

- Standard: UL's "Fire Protection Equipment Directory" listing or "Approval Guide," published by FM Global, listing.
- 2. Pressure Rating: 175 psig minimum.
- 3. Body Material: Cast- or ductile-iron housing with sight glass.
- 4. Size: Same as connected piping.
- Inlet and Outlet: Threaded.

E. Adjustable Drop Nipples:

- 1. Standard: UL 1474.
- 2. Pressure Rating: 250 psig minimum.
- 3. Body Material: Steel pipe with EPDM-rubber O-ring seals.
- 4. Size: Same as connected piping.
- 5. Length: Adjustable.
- 6. Inlet and Outlet: Threaded.

2.7 SPRINKLERS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Globe Fire Sprinkler Corporation.
 - 2. Reliable Automatic Sprinkler Co., Inc.
 - 3. Tyco Fire & Building Products LP.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 4. Victaulic Company.
- 5. Viking Corporation.
- B. General Requirements:
 - 1. Standard: UL's "Fire Protection Equipment Directory" listing or "Approval Guide," published by FM Global, listing.
 - 2. Type: All sprinklers shall be quick response type.
 - 3. Pressure Rating for Automatic Sprinklers: 175 psig minimum.
- C. Sprinkler Finishes:
 - 1. Chrome plated.
 - 2. Bronze.
 - 3. Painted.
- D. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.
 - 1. Ceiling Mounting: Chrome-plated steel, one piece, flat.
 - 2. Sidewall Mounting: Chrome-plated steel, one piece, flat.
- E. Sprinkler Guards:
 - 1. Standard: UL 199.
 - 2. Type: Wire cage with fastening device for attaching to sprinkler.

2.8 PRESSURE GAGES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. AMETEK; U.S. Gauge Division.
 - 2. Ashcroft, Inc.
 - 3. Brecco Corporation.
 - 4. WIKA Instrument Corporation.
- B. Standard: UL 393.
- C. Dial Size: 3-1/2- to 4-1/2-inch diameter.
- D. Pressure Gage Range: 0 to 250 psig.
- E. Water System Piping Gage: Include "WATER" or "AIR/WATER" label on dial face.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Perform fire-hydrant flow test according to NFPA 13 and NFPA 291. Use results for system design calculations required in "Quality Assurance" Article.
- B. Report test results promptly and in writing.

3.2 WATER-SUPPLY CONNECTIONS

A. Connect sprinkler piping to building's interior water-distribution piping. Comply with requirements for interior piping in Division 22 Section "Domestic Water Piping."

3.3 PIPING INSTALLATION

- A. Piping Standard: Comply with requirements for installation of sprinkler piping in NFPA 13.
- B. Install seismic restraints on piping. Comply with requirements for seismic-restraint device materials and installation in NFPA 13.
- C. Use listed fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.
- D. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- E. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- F. Install "Inspector's Test Connections" in sprinkler system piping, complete with shutoff valve, and sized and located according to NFPA 13.
- G. Install sprinkler piping with drains for complete system drainage.
- H. Install sprinkler control valves, test assemblies, and drain risers adjacent to standpipes when sprinkler piping is connected to standpipes.
- I. Install hangers and supports for sprinkler system piping independent of all other systems according to NFPA 13. Comply with requirements for hanger materials in NFPA 13.
- J. Fill sprinkler system piping with water.

3.4 JOINT CONSTRUCTION

A. Install couplings, flanges, flanged fittings, unions, nipples, and transition and special fittings that have finish and pressure ratings same as or higher than system's pressure rating for aboveground applications unless otherwise indicated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Install unions adjacent to each valve in pipes NPS 2 and smaller.
- C. Install flanges, flange adapters, or couplings for grooved-end piping on valves, apparatus, and equipment having NPS 2-1/2 and larger end connections.
- D. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- E. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- F. Flanged Joints: Select appropriate gasket material in size, type, and thickness suitable for water service. Join flanges with gasket and bolts according to ASME B31.9.
- G. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- H. Steel-Piping, Roll-Grooved Joints: Roll rounded-edge groove in end of pipe according to AWWA C606. Assemble coupling with housing, gasket, lubricant, and bolts. Join steel pipe and grooved-end fittings according to AWWA C606 for steel-pipe grooved joints.

3.5 VALVE AND SPECIALTIES INSTALLATION

- A. Install listed fire-protection valves, trim and drain valves, specialty valves and trim, controls, and specialties according to NFPA 13 and authorities having jurisdiction.
- B. Install listed fire-protection shutoff valves supervised open, located to control sources of water supply except from fire-department connections. Install permanent identification signs indicating portion of system controlled by each valve.
- C. Install check valve in each water-supply connection. Install backflow preventers instead of check valves in potable-water-supply sources.
- D. Specialty Valves:
 - 1. General Requirements: Install in vertical position for proper direction of flow, in main supply to system.

3.6 SPRINKLER INSTALLATION

A. Install sprinklers in suspended ceilings in center of narrow dimension of acoustical ceiling panels.

3.7 ESCUTCHEON INSTALLATION

- A. Install escutcheons for penetrations of walls, ceilings, and floors.
- B. Escutcheons for New Piping:
 - 1. Piping with Fitting or Sleeve Protruding from Wall: One piece, deep pattern.
 - 2. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
 - 3. Bare Piping at Ceiling Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
 - 4. Bare Piping in Unfinished Service Spaces: One piece, cast brass with rough-brass finish or stamped steel with set-screw or spring clips.
 - 5. Bare Piping in Equipment Rooms: One piece, cast brass stamped steel with set-screw or spring clips.
 - 6. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece floor plate.

3.8 SLEEVE INSTALLATION

- A. General Requirements: Install sleeves for pipes and tubes passing through penetrations in floors, partitions, roofs, and walls.
- B. Sleeves are not required for core-drilled holes.
- C. Permanent sleeves are not required for holes formed by removable PE sleeves.
- D. Cut sleeves to length for mounting flush with both surfaces unless otherwise indicated.
- E. Install sleeves in new partitions, slabs, and walls as they are built.
- F. For interior wall penetrations, seal annular space between sleeve and pipe or pipe insulation using joint sealants appropriate for size, depth, and location of joint. Comply with requirements for joint sealants in Division 07 Section "Joint Sealants."
- G. For exterior wall penetrations above grade, seal annular space between sleeve and pipe using joint sealants appropriate for size, depth, and location of joint. Comply with requirements for joint sealants in Division 07 Section "Joint Sealants."
- H. Seal space outside of sleeves in concrete slabs and walls with grout.
- I. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation unless otherwise indicated.
- J. Install sleeve materials according to the following applications:
 - 1. Sleeves for Piping Passing through Concrete Floor Slabs: Galvanized-steel pipe.
 - 2. Sleeves for Piping Passing through Concrete Floor Slabs of Mechanical Equipment Areas or Other Wet Areas: Galvanized-steel pipe.
 - a. Extend sleeves 2 inches above finished floor level.

- b. For pipes penetrating floors with membrane waterproofing, extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level. Comply with requirements for flashing in Division 07 Section "Sheet Metal Flashing and Trim."
- 3. Sleeves for Piping Passing through Gypsum-Board Partitions:
 - a. Galvanized-steel-pipe sleeves for pipes smaller than NPS 6.
 - b. Galvanized-steel-sheet sleeves for pipes NPS 6 and larger.
 - c. Exception: Sleeves are not required for water-supply tubes and waste pipes for individual plumbing fixtures if escutcheons will cover openings.
- 4. Sleeves for Piping Passing through Concrete Roof Slabs: Molded PE or Galvanized-steel pipe.
- 5. Sleeves for Piping Passing through Exterior Concrete Walls:
 - a. Galvanized-steel-pipe sleeves for pipes smaller than NPS 6.
 - b. Cast-iron wall-pipe sleeves for pipes NPS 6 and larger.
 - c. Install sleeves that are large enough to provide 1-inch annular clear space between sleeve and pipe or pipe insulation when sleeve seals are used.
- 6. Sleeves for Piping Passing through Interior Concrete Walls:
 - a. Galvanized-steel-pipe sleeves for pipes smaller than NPS 6.
 - b. Galvanized-steel-sheet sleeves for pipes NPS 6 and larger.
- K. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements for firestop materials and installations in Division 07 Section "Penetration Firestopping."

3.9 SLEEVE SEAL INSTALLATION

- A. Install sleeve seals in sleeves in exterior concrete walls at water-service piping entries into building.
- B. Select type and number of sealing elements, minimum two rows required for pipe material and size. Position pipe in center of sleeve. Assemble sleeve seal components and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal. All bolts shall be accessible from inside of building.

3.10 IDENTIFICATION

- A. Install labeling and pipe markers on equipment and piping according to requirements in NFPA 13.
- B. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."

3.11 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
 - 1. Leak Test: After installation, charge systems and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 3. Flush, test, and inspect sprinkler systems according to NFPA 13, "Systems Acceptance" Chapter.
 - 4. Sprinkler systems shall be hydrostatically tested at 200 psi for 2 hours in accordance with NFPA 13.
 - 5. Energize circuits to electrical equipment and devices.
 - 6. Coordinate with fire-alarm tests. Operate as required.
 - 7. Verify that equipment hose threads are same as local fire-department equipment.
- C. Sprinkler piping system will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

3.12 CLEANING

- A. Clean dirt and debris from sprinklers.
- B. Remove and replace sprinklers with paint other than factory finish.

3.13 PIPING SCHEDULE

- A. Piping between Fire-Department Connections and Check Valves: Galvanized, standard-weight steel pipe with threaded ends; cast-iron threaded fittings; and threaded or grooved ends; grooved-end fittings; grooved-end-pipe couplings; and grooved joints.
- B. Sprinkler specialty fittings may be used, downstream of control vales, instead of specified fittings.
- C. Standard-pressure, wet-pipe sprinkler system, NPS 2 and smaller, shall be one of the following:
 - 1. Standard-weight, black-steel pipe with threaded ends; uncoated, gray-iron threaded fittings; and threaded joints.
- D. Standard-pressure, wet-pipe sprinkler system, NPS 2-1/2 and larger, shall be one of the following:
 - 1. Standard-weight, black-steel pipe with roll-grooved ends; uncoated, grooved-end fittings for steel piping; grooved-end-pipe couplings for steel piping; and grooved joints.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.14 SPRINKLER SCHEDULE

- A. Use sprinkler types in subparagraphs below for the following applications:
 - 1. Rooms without Ceilings: Upright sprinklers.
 - 2. Rooms with Suspended Ceilings: Concealed sprinklers.
 - 3. Wall Mounting: Concealed sidewall sprinklers.
 - 4. Spaces Subject to Freezing: Upright, pendent, dry sprinklers; and sidewall, dry sprinklers as indicated.
 - 5. Special Applications: Extended-coverage, flow-control, sprinklers where indicated.
- B. Provide sprinkler types in subparagraphs below with finishes indicated.
 - 1. Concealed Sprinklers: Rough brass, with factory-painted cover plate color as directed by Architect.
 - 2. Upright and Pendent Sprinklers: Chrome plated in finished spaces exposed to view; rough bronze in unfinished spaces not exposed to view; wax coated where exposed to acids, chemicals, or other corrosive fumes.

END OF SECTION 211313



SECTION 220500 - COMMON WORK RESULTS FOR PLUMBING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Piping materials and installation instructions common to most piping systems.
 - 2. Transition fittings.
 - 3. Dielectric fittings.
 - Mechanical sleeve seals.
 - 5. Sleeves.
 - 6. Escutcheons.
 - 7. Grout.
 - 8. Trenching, excavation and backfill
 - 9. Project record drawings.
 - 10. Plumbing demolition.
 - 11. Equipment installation requirements common to equipment sections.
 - 12. Painting and finishing.
 - 13. Supports and anchorages.

1.3 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe chases, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspaces, and tunnels.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in chases.
- E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Transition fittings.
 - 2. Dielectric fittings.
 - 3. Mechanical sleeve seals.
 - 4. Escutcheons.

1.5 QUALITY ASSURANCE

- A. Electrical Characteristics for Plumbing Equipment: Equipment of higher electrical characteristics may be furnished provided such proposed equipment is approved in writing and connecting electrical services, circuit breakers, and conduit sizes are appropriately modified. Any additional costs as a result of these modifications shall be borne by the Contractor. If minimum energy ratings or efficiencies are specified, equipment shall comply with requirements.
- B. Plumbing work to comply with International Plumbing Code (IPC) as listed on Drawings and General Conditions.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- B. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, if stored inside.
- C. Protect flanges, fittings, and piping specialties from moisture and dirt.

1.7 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for plumbing installations.
- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Sequence, coordinate, and integrate installations of plumbing materials and equipment for efficient flow of the Work. Coordinate installation of large equipment requiring positioning before closing in building.
- D. Coordinate connection of plumbing systems with exterior underground utilities and services. Comply with requirements of governing regulations, franchised service companies, and controlling agencies.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- E. Coordinate installation of identifying devices after completing covering and painting, if devices are applied to surfaces. Install identifying devices before installing acoustical ceilings and similar concealment.
- F. Sequence, coordinate, and integrate removal of existing equipment and material as required to maintain services for existing building and for portions of remodeled areas at all times.

1.8 SCHEDULING AND PHASING

A. All plumbing work shall be scheduled to meet project completion date. Plumbing work shall be phased for projects requiring phasing of work. Install additional fittings, valves, caps as required to support phasing. Refer to phasing schedule on drawings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where subparagraph titles below introduce lists, the following requirements apply for product selection:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified.

2.2 PIPE, TUBE, AND FITTINGS

- A. Refer to individual Division 22 piping Sections for pipe, tube, and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

2.3 JOINING MATERIALS

- A. Refer to individual Division 22 piping Sections for special joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
 - 2. AWWA C110, rubber, flat face, 1/8 inch thick, unless otherwise indicated; and full-face or ring type, unless otherwise indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.

- D. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- E. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing, unless otherwise indicated; and AWS A5.8, BAg1, silver alloy for refrigerant piping, unless otherwise indicated.

2.4 TRANSITION FITTINGS

- A. Acceptable Manufacturers:
 - 1. Cascade Waterworks Mfg. Co.
 - 2. Dresser Industries, Inc.; DMD Div.
 - 3. Ford Meter Box Company, Incorporated (The); Pipe Products Div.
 - 4. JCM Industries.
 - 5. Smith-Blair, Inc.
 - 6. Viking Johnson.
- B. Flexible Transition Couplings for Underground Nonpressure Drainage Piping: ASTM C 1173 with elastomeric sleeve, ends same size as piping to be joined, and corrosion-resistant metal band on each end.

2.5 DIELECTRIC FITTINGS

- A. Description: Combination fitting of copper alloy and ferrous materials with threaded, solder-joint, plain, or weld-neck end connections that match piping system materials.
- B. Insulating Material: Suitable for system fluid, pressure, and temperature.
- C. Acceptable Manufacturers:
 - 1. Capitol Manufacturing Co.
 - 2. Victaulic Company
 - 3. Calpico, Inc.
 - 4. Epco Sales, Inc.
 - 5. Hart Industries, International, Inc.
 - 6. Lochinvar Corp.
 - 7. Watts Industries, Inc.; Water Products Div.
 - 8. Zurn Industries, Inc.; Wilkins Div.
- D. Dielectric Flanges: Factory-fabricated, companion-flange assembly, for 150- or 300-psig minimum working pressure as required to suit system pressures.
- E. Dielectric-Flange Kits: Companion-flange assembly for field assembly. Include flanges, full-faceor ring-type neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
 - 1. Separate companion flanges and steel bolts and nuts shall have 150- or 300-psig minimum working pressure where required to suit system pressures.

- F. Dielectric Couplings: Galvanized-steel coupling with inert and noncorrosive, thermoplastic lining; threaded ends; and 300-psig minimum working pressure at 225 deg F.
- G. Dielectric Nipples: Electroplated steel nipple with inert and noncorrosive, thermoplastic lining; plain, threaded, or grooved ends; and 300-psig minimum working pressure at 225 deg F. Victaulic Style 47.

2.6 MECHANICAL SLEEVE SEALS

- A. Description: Modular sealing element unit, designed for field assembly, to fill annular space between pipe and sleeve.
 - 1. Acceptable Manufacturers:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Link Seal
 - d. Metraflex Co.
 - e. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: EPDM or NBR interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Carbon steel. Include two for each sealing element.
 - 4. Connecting Bolts and Nuts: Carbon steel with corrosion-resistant coating of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.7 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Steel Pipe: ASTM A 53, Type E, Grade B, Schedule 40, galvanized, plain ends.
- C. Cast Iron: Cast or fabricated "wall pipe" equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- D. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.

2.8 ESCUTCHEONS

- A. Description: Manufactured wall and ceiling escutcheons and floor plates, with an ID to closely fit around pipe, tube, and insulation of insulated piping and an OD that completely covers opening.
- B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with polished chrome-plated finish.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. One-Piece, Cast-Brass Type: With set screw.
 - 1. Finish: Polished chrome-plated or rough brass.
- D. Split-Casting, Cast-Brass Type: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated.
- E. One-Piece, Floor-Plate Type: Cast-iron floor plate.
- F. Split-Casting, Floor-Plate Type: Cast brass with concealed hinge and set screw.

2.9 GROUT

- A. Description: ASTM C 1107, Grade B, nonshrink and nonmetallic, dry hydraulic-cement grout.
 - 1. Characteristics: Post-hardening, volume-adjusting, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.
 - 3. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 TRENCHING, EXCAVATING AND BACKFILLING

- A. Excavate to required dimensions and depth. The trench excavation shall be in open cut from surface and shall be minimum width necessary to permit the placing of the pipe as required. Excess excavation shall be backfilled with crusher run rock. Such rocks shall be placed at the Contractor's expense. Lines shall be used to lay out trenches.
- B. All excavations shall be properly protected by the necessary bracing and timbers, to prevent any cave-ins or injury to adjacent improvements. The sides of the excavations shall be securely held by bracing or sheathing, which bracing or sheathing shall not be removed until the level of the backfill has reached the point where such removal can be safely carried out. Where adjacent improvements might be injured by the removal of such bracing, the braces shall be left in place to prevent such injury. The thickness of the sheathing and dimensions of the brass braces, shoes and miscellaneous supports to be used by the Contractor shall be of the type required to properly protect the sides of the trench and to prevent injurious cave-ins or erosions.
- C. The Contractor shall do all pumping and bailing necessary to keep all excavations free of water and shall provide for the uninterrupted flow of the surface water adjacent to the line of the work during the progress of the work. The Contractor shall inspect the ground where excavation is required to ascertain the structure of the soil. Additional consideration will not be allowed for encountering rock, stone, old foundations or other unfavorable excavating conditions.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. The Contractor shall replace all existing walks, roads, street pavements, curbs, retaining walls, steps and miscellaneous work removed or damaged in connection with the utility service installation, whether or not the improvement is shown on the drawings. Such repairs shall be done to the satisfaction of the Architect. All street cuts shall be repaired in a manner meeting the approval of the Owner.
- E. In cases where existing water, sewer, electric, steam or other pipes are encountered, they shall not be displaced or disturbed unless necessary, in which case they shall promptly be replaced in good condition. All water, sewer, steam or electric lines damaged or disturbed in the construction shall be replaced or repaired at the Contractor's expense, unless, in the opinion of the Architect, such damage was caused through no fault of the Contractor.
- F. Contractor shall provide all temporary bridges, steel plates, barricades, lanterns, and such other signs and signals by day as shall be necessary to warn the public of and protect the public from the dangers caused by excavations and other obstructions, day and night.
- G. The backfilling of trenches shall be carried out as rapidly as the testing and acceptance of the finished sections of the installation will permit. The trench shall be backfilled in layers of not to exceed eight inches (8") with good selected clean earth, thoroughly tamped with mechanical tamper to a 95% optimum compaction. Density shall be tested by an approved laboratory, using a standard method. Tests shall be made for each 2 ft. depth on the basis of one test per 1000 sq. ft. of fill area. Last 12" of backfill (except under streets, drives, and walks) shall be made with good clean top soil. Contractor shall obtain and pay for tests. Submit five (5) copies of tests for approval. Note: Broken stones, cinders, wood and rubbish are not acceptable for backfilling. Backfill all street cuts in a manner meeting the approval of the Architect.
- H. In spaces between walls and line of excavation, fill with thin layers of selected <u>clean earth</u>; thoroughly tamp in eight inches (8") thick layers and bring up to a finished level of established grades. All wood and foreign materials shall be removed from excavation prior to backfilling.
- I. After backfilling, all surplus excavated materials shall be removed from the property.
- J. The work shall be executed so that existing culverts, walks, retaining walls, steps, fences or any permanent structure along and adjacent to the new work are properly protected. Any damage occurring to these structures shall be repaired by the Contractor at his own expense.
- K. The Contractor shall make a field inspection of the location along which the underground piping is to be constructed, and note all obstructions and improvements at the surface and overhead which may affect the method of operation in the construction of these lines. Such overhead wires and underground pipes or conduits which may exist, or which may be encountered, shall be protected by the Contractor during this construction. Any expense or inconvenience caused by their existence and the necessary protection for utilities adjacent thereto shall be considered as covered and included in the contract, without additional cost to the Owner.

3.2 PIPING SYSTEMS - COMMON REQUIREMENTS

A. Install piping according to the following requirements and Division 22 Sections specifying piping systems.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- C. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping minimum 8 inches above accessible ceilings to allow sufficient space for ceiling panel removal and service access. In general install piping tight to slab, beams, joists and structural members if possible.
- F. Install piping to permit valve servicing.
- G. Install piping at indicated slopes.
- H. Install piping free of sags and bends.
- I. Install fittings for changes in direction and branch connections.
- J. Install piping to allow application of insulation.
- K. Select system components with pressure rating equal to or greater than system operating pressure.
- L. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. New Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type.
 - b. Chrome-Plated Piping: One-piece, cast-brass type with polished chrome-plated finish.
 - c. Insulated Piping: One-piece, stamped-steel type with spring clips.
 - d. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece, cast-brass type with polished chrome-plated finish.
 - e. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece or split-casting, cast-brass type with polished chrome-plated finish.
 - f. Bare Piping in Unfinished Service Spaces: One-piece, cast-brass type with roughbrass finish.
 - g. Bare Piping in Equipment Rooms: One-piece, cast-brass type.
 - h. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece, floor-plate type.
- M. Sleeves are not required for core-drilled holes.
- N. Permanent sleeves are not required for holes formed by removable PE sleeves.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Install sleeves for pipes passing through concrete and masonry walls and concrete floor and roof slabs.
- P. Install sleeves for pipes passing through concrete and masonry walls, gypsum-board partitions, and concrete floor and roof slabs.
 - 1. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
 - 2. Install sleeves in new walls and slabs as new walls and slabs are constructed.
 - 3. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Use the following sleeve materials:
 - a. Steel Pipe Sleeves: For pipes smaller than NPS 6.
 - b. Steel Sheet Sleeves: For pipes NPS 6 and larger, penetrating gypsum-board partitions.
 - c. Stack Sleeve Fittings: For pipes penetrating floors with membrane waterproofing. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level. Refer to Division 07 Section "Sheet Metal Flashing and Trim" for flashing.
 - 1) Seal space outside of sleeve fittings with grout.
 - 4. Except for underground wall penetrations, seal annular space between sleeve and pipe or pipe insulation, using joint sealants appropriate for size, depth, and location of joint. Refer to Division 07 Section "Joint Sealants" for materials and installation.
- Q. Aboveground, Exterior-Wall Pipe Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
 - 1. Install steel pipe for sleeves smaller than 6 inches in diameter.
 - 2. Install cast-iron "wall pipes" for sleeves 6 inches and larger in diameter.
 - 3. Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- R. Underground, Exterior-Wall Pipe Penetrations: Install cast-iron "wall pipes" for sleeves. Seal pipe penetrations using mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
 - Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- S. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Refer to Division 07 Section "Penetration Firestopping" for materials.
- T. Verify final equipment locations for roughing-in.
- U. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.
- V. Draining and Refilling of Systems: Provide all shutoff valves, drain valves, pipe, fittings, and miscellaneous material required to drain each existing system as required for new work. After new work is completed, tested, and found tight, refill each system as required. Time for shutting down existing system for draining shall be coordinated with all other work and with Owner's representative. Cost for all chemicals and additives for refill shall be borne by the Contractor.

3.3 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 22 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8.
- F. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- G. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.4 PIPING CONNECTIONS

- A. Make connections according to the following, unless otherwise indicated:
 - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
 - 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.
 - 3. Dry Piping Systems: Install dielectric unions and flanges to connect piping materials of dissimilar metals.
 - 4. Wet Piping Systems: Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

3.5 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to allow maximum possible headroom unless specific mounting heights are not indicated.
- B. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- C. Install plumbing equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- D. Install equipment to allow right of way for piping installed at required slope.

3.6 PAINTING

- A. Painting of plumbing systems, equipment, and components is specified in Division 09 Sections "Interior Painting."
- B. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.7 ERECTION OF METAL SUPPORTS AND ANCHORAGES

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor plumbing materials and equipment.
- B. Field Welding: Comply with AWS D1.1.

3.8 GROUTING

- A. Mix and install grout for plumbing equipment base bearing surfaces, pump and other equipment base plates, and anchors.
- B. Clean surfaces that will come into contact with grout.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Provide forms as required for placement of grout.
- D. Avoid air entrapment during placement of grout.
- E. Place grout, completely filling equipment bases.
- F. Place grout around anchors.
- G. Cure placed grout.

END OF SECTION 220500

COMMON WORK RESULTS FOR PLUMBING

220500 - 12

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 220523 - GENERAL-DUTY VALVES FOR PLUMBING PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Bronze angle valves.
- 2. Bronze ball valves.
- 3. Bronze swing check valves.
- 4. Bronze globe valves.

B. Related Sections:

- 1. Division 22 plumbing piping Sections for specialty valves applicable to those Sections only.
- Division 22 Section "Identification for Plumbing Piping and Equipment" for valve tags and schedules.

1.3 DEFINITIONS

- A. CWP: Cold working pressure.
- B. EPDM: Ethylene propylene copolymer rubber.
- C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.
- D. NRS: Nonrising stem.
- E. OS&Y: Outside screw and yoke.
- F. RS: Rising stem.
- G. SWP: Steam working pressure.

1.4 SUBMITTALS

A. Product Data: For each type of valve indicated.

220523 - 1

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.5 QUALITY ASSURANCE

- A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.
- B. ASME Compliance:
 - 1. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
 - 2. ASME B31.9 for building services piping valves.
- C. NSF Compliance: NSF 61 and NSF-372 (lead free) for valve materials for potable water service.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Protect internal parts against rust and corrosion.
 - 2. Protect threads, flange faces, grooves, and weld ends.
 - 3. Set angle, gate, and globe valves closed to prevent rattling.
 - 4. Set ball and plug valves open to minimize exposure of functional surfaces.
 - 5. Set butterfly valves closed or slightly open.
 - 6. Block check valves in either closed or open position.
- B. Use the following precautions during storage:
 - 1. Maintain valve end protection.
 - 2. Store valves indoors and maintain at higher than ambient dew point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Refer to valve schedule articles for applications of valves.
- B. Valve Pressure and Temperature Ratings: Not less than as required for system pressures and temperatures.
- C. Valve Sizes: Same as upstream piping unless otherwise indicated.
- D. Valve Actuator Types:
 - 1. Gear Actuator: For quarter-turn valves NPS 8 and larger.
 - 2. Handwheel: For valves other than guarter-turn types.
 - 3. Handlever: For quarter-turn valves NPS 6 and smaller except plug valves.

GENERAL-DUTY VALVES FOR PLUMBING PIPING

220523 - 2

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 4. Wrench: For plug valves with square heads. Furnish Owner with 1 wrench for every ten (10) plug valves, for each size square plug-valve head.
- 5. Chainwheel: Device for attachment to valve handwheel, stem, or other actuator; of size and with chain for mounting height, as indicated in the "Valve Installation" Article.
- E. Valves in Insulated Piping: With 2-inch stem extensions and the following features:
 - 1. Gate Valves: With rising stem.
 - 2. Ball Valves: With extended operating handle of non-thermal-conductive material, and protective sleeve that allows operation of valve without breaking the vapor seal or disturbing insulation.
 - 3. Butterfly Valves: With extended neck.
- F. Valve-End Connections:
 - 1. Flanged: With flanges according to ASME B16.1 for iron valves.
 - 2. Grooved: With grooves according to AWWA C606.
 - 3. Solder Joint: With sockets according to ASME B16.18.
 - 4. Threaded: With threads according to ASME B1.20.1.
- G. Valve Bypass and Drain Connections: MSS SP-45.

2.2 BRONZE ANGLE VALVES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Crane Co., Crane Valve Group
 - 2. Hammond Valve.
 - 3. Milwaukee Valve Company.
 - 4. NIBCO Inc.
- B. Class 125, Bronze Angle Valves with Bronze Disc:
 - 1. Description:
 - a. Standard: MSS SP-80, Type 1.
 - b. CWP Rating: 200 psig.
 - c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
 - d. Ends: Threaded.
 - e. Stem and Disc: Bronze.
 - f. Packing: Asbestos free.
 - g. Handwheel: Malleable iron.
- C. Class 150, Bronze Angle Valves with Bronze Disc:
 - 1. Description:
 - a. Standard: MSS SP-80, Type 1.
 - b. CWP Rating: 300 psig.
 - c. Body Material: ASTM B 62, bronze with integral seat and union-ring bonnet.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- d. Ends: Threaded.
- e. Stem and Disc: Bronze.
- f. Packing: Asbestos free.
- g. Handwheel: Malleable iron.

2.3 BRONZE BALL VALVES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. American Valve, Inc.
 - 2. Conbraco Industries, Inc.; Apollo Valves.
 - 3. Crane Co.; Crane Valve Group; Crane Valves.
 - 4. Hammond Valve.
 - 5. Milwaukee Valve Company.
 - 6. NIBCO INC.
 - 7. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- B. Two-Piece, Full-Port, Bronze Ball Valves with Stainless-Steel Trim:
 - 1. Description:
 - a. Standard: MSS SP-110.
 - b. SWP Rating: 150 psig.
 - c. CWP Rating: 600 psig.
 - d. Body Design: Two piece.
 - e. Body Material: Lead Free Bronze.
 - f. Ends: Threaded.
 - g. Seats: PTFE or TFE.
 - h. Stem: Stainless steel.
 - i. Ball: Stainless steel, vented.
 - j. Port: Full.

2.4 IRON, SINGLE-FLANGE BUTTERFLY VALVES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Conbraco Industries, Inc.; Apollo Valves.
 - 2. Crane Co.; Crane Valve Group; Jenkins Valves.
 - 3. Crane Co.; Crane Valve Group; Stockham Division.
 - 4. DeZurik Water Controls.
 - 5. Hammond Valve.
 - 6. Milwaukee Valve Company.
 - 7. NIBCO INC.
 - 8. Spence Strainers International; a division of CIRCOR International, Inc.
 - 9. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Aluminum bronze Disc:
 - 1. Description:
 - a. Standard: MSS SP-67, Type I.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
 - d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
 - e. Seat: EPDM.
 - f. Stem: One- or two-piece stainless steel.
 - g. Disc: Aluminum bronze disc.

2.5 BRONZE SWING CHECK VALVES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. American Valve, Inc.
 - 2. Crane Co.; Crane Valve Group; Crane Valves.
 - 3. Crane Co.; Crane Valve Group; Jenkins Valves.
 - 4. Crane Co.; Crane Valve Group; Stockham Division.
 - 5. Hammond Valve.
 - 6. Milwaukee Valve Company.
 - 7. NIBCO Inc.
 - 8. Powell Valves.
 - 9. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- B. Class 125, Bronze Swing Check Valves with Bronze Disc:
 - 1. Description:
 - a. Standard: MSS SP-80, Type 3.
 - b. CWP Rating: 200 psig.
 - c. Body Design: Horizontal flow.
 - d. Body Material: ASTM B 62, bronze.
 - e. Ends: Threaded.
 - f. Disc: Bronze.
- C. Class 150, Bronze Swing Check Valves with Bronze Disc:
 - 1. Description:
 - a. Standard: MSS SP-80, Type 3.
 - b. CWP Rating: 300 psig.
 - c. Body Design: Horizontal flow.
 - d. Body Material: ASTM B 62, bronze.
 - e. Ends: Threaded.
 - f. Disc: Bronze.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.6 BRONZE GLOBE VALVES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Crane Co.; Crane Valve Group; Crane Valves.
 - 2. Crane Co.; Crane Valve Group; Stockham Division.
 - 3. Hammond Valve.
 - 4. Milwaukee Valve Company.
 - 5. NIBCO Inc.
 - 6. Powell Valves.
 - 7. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- B. Class 125, Bronze Globe Valves with Bronze Disc:
 - 1. Description:
 - a. Standard: MSS SP-80, Type 1.
 - b. CWP Rating: 200 psig.
 - c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
 - d. Ends: Threaded or solder joint.
 - e. Stem and Disc: Bronze.
 - f. Packing: Asbestos free.
 - g. Handwheel: Malleable iron.
- C. Class 125, Bronze Globe Valves with Nonmetallic Disc:
 - 1. Description:
 - a. Standard: MSS SP-80, Type 2.
 - b. CWP Rating: 200 psig.
 - c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
 - d. Ends: Threaded or solder joint.
 - e. Stem: Bronze.
 - f. Disc: PTFE or TFE.
 - g. Packing: Asbestos free.
 - h. Handwheel: Malleable iron.
- D. Class 150, Bronze Globe Valves with Nonmetallic Disc:
 - 1. Description:
 - a. Standard: MSS SP-80, Type 2.
 - b. CWP Rating: 300 psig.
 - c. Body Material: ASTM B 62, bronze with integral seat and union-ring bonnet.
 - d. Ends: Threaded.
 - e. Stem: Bronze.
 - f. Disc: PTFE or TFE.
 - g. Packing: Asbestos free.
 - h. Handwheel: Malleable iron.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- E. Do not attempt to repair defective valves; replace with new valves.

3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.
- D. Install valves in position to allow full stem movement.
- E. Install chainwheels on operators for valves 6 inches and larger and more than 96 inches above floor. Extend chains to 60 inches above finished floor.
- F. Install check valves for proper direction of flow and as follows:
 - 1. Swing Check Valves: In horizontal position with hinge pin level.
 - 2. Center-Guided Check Valves: In horizontal or vertical position, between flanges.
 - 3. Lift Check Valves: With stem upright and plumb.

3.3 ADJUSTING

A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

GENERAL-DUTY VALVES FOR PLUMBING PIPING

220523 - 7

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valve applications are not indicated, use the following:
 - 1. Shutoff Service: Ball, butterfly, gate, or plug valves.
 - 2. Butterfly Valve Dead-End Service: Single-flange (lug) type.
 - 3. Throttling Service: Globe or angle, ball, or butterfly valves.
- B. Pressure ratings for valves shall not be less than as required by system pressures.
- C. If valves with specified SWP classes or CWP ratings are not available, the same types of valves with higher SWP classes or CWP ratings may be substituted.
- D. Select valves, except wafer types, with the following end connections:
 - 1. For Copper Tubing, NPS 2 and Smaller: Threaded ends except where solder-joint valveend option is indicated in valve schedules below.

3.5 DOMESTIC, HOT- AND COLD-WATER VALVE SCHEDULE

- A. Pipe NPS 2 and Smaller:
 - 1. Bronze Valves: May be provided with solder-joint ends instead of threaded ends.
 - 2. Bronze Angle Valves: Class 125 or Class 150, bronze or nonmetallic disc.
 - 3. Ball Valves: Two piece, full port, bronze with brass, bronze, stainless-steel trim.
 - 4. Bronze Swing Check Valves: Class 125 or Class 150, bronze or nonmetallic disc.
 - 5. Bronze Globe Valves: Class 125 or Class 150, bronze or nonmetallic disc.

END OF SECTION 220523

GENERAL-DUTY VALVES FOR PLUMBING PIPING

220523 - 8

SECTION 220529 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following hangers and supports for plumbing system piping and equipment:
 - 1. Steel pipe hangers and supports.
 - 2. Trapeze pipe hangers.
 - 3. Metal framing systems.
 - 4. Thermal-hanger shield inserts.
 - 5. Fastener systems.
 - 6. Pipe stands.
 - 7. Pipe positioning systems.
 - 8. Equipment supports.

1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society for The Valve and Fittings Industry Inc.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.4 PERFORMANCE REQUIREMENTS

- A. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
- B. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

1.5 SUBMITTALS

- A. Product Data: For the following:
 - 1. Steel pipe hangers and supports.
 - 2. Thermal-hanger shield inserts.
 - 3. Powder-actuated fastener systems.
 - 4. Pipe positioning systems.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Welding certificates.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 STEEL PIPE HANGERS AND SUPPORTS

- A. Description: MSS SP-58, Types 1 through 58, factory-fabricated components. Refer to Part 3 "Hanger and Support Applications" Article for where to use specific hanger and support types.
- B. Acceptable Manufacturers:
 - 1. B-Line Systems, Inc.; a division of Cooper Industries.
 - 2. Carpenter & Paterson, Inc.
 - 3. Empire Industries, Inc.
 - 4. Globe Pipe Hanger Products, Inc.
 - 5. Grinnell Corp.
 - 6. GS Metals Corp.
 - 7. National Pipe Hanger Corporation.
 - 8. Piping Technology & Products, Inc.
- C. Galvanized, Metallic Coatings: Pregalvanized or hot dipped.
- D. Nonmetallic Coatings: Plastic coating, jacket, or liner.
- E. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion for support of bearing surface of piping.

2.3 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural-steel shapes with MSS SP-58 hanger rods, nuts, saddles, and U-bolts.

2.4 METAL FRAMING SYSTEMS

A. Description: MFMA-3, shop- or field-fabricated pipe-support assembly made of steel channels and other components.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Acceptable Manufacturers:

- 1. B-Line Systems, Inc.; a division of Cooper Industries.
- 2. GS Metals Corp.
- 3. Power-Strut Div.; Tyco International, Ltd.
- 4. Thomas & Betts Corporation.
- 5. Unistrut Corp.; Tyco International, Ltd.
- C. Coatings: Manufacturer's standard finish unless bare metal surfaces are indicated.
- D. Nonmetallic Coatings: Plastic coating, jacket, or liner.

2.5 THERMAL-HANGER SHIELD INSERTS

- A. Description: 100-psig minimum, compressive-strength insulation insert encased in sheet metal shield.
- B. Acceptable Manufacturers:
 - 1. Carpenter & Paterson, Inc.
 - 2. PHS Industries, Inc.
 - 3. Pipe Shields, Inc.
 - 4. Rilco Manufacturing Company, Inc.
 - 5. Value Engineered Products, Inc.
 - 6. Armacell, LLC.
- C. Insulation-Insert Material for Cold Piping: Single piece closed cell insulation with 30 mil thick painted aluminum outer shell and self-adhesive closure (Armafix IPH).
- D. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate.
- E. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- F. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- G. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.6 FASTENER SYSTEMS

- A. Mechanical-Expansion Anchors: Insert-wedge-type zinc-coated steel, for use in hardened Portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 - 1. Acceptable Manufacturers:
 - a. B-Line Systems, Inc.; a division of Cooper Industries.
 - b. Empire Industries, Inc.
 - c. Hilti, Inc.

- d. ITW Ramset/Red Head.
- e. MKT Fastening, LLC.
- f. Powers Fasteners.

2.7 PIPE STAND FABRICATION

- A. Pipe Stands, General: Shop or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
- B. Compact Pipe Stand: One-piece plastic unit with integral-rod-roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
- C. Low-Type, Single-Pipe Stand: One-piece plastic or stainless-steel base unit with plastic roller, for roof installation without membrane penetration.

2.8 MISCELLANEOUS MATERIALS

- A. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT APPLICATIONS

- A. Specific hanger and support requirements are specified in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized, metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use padded hangers for piping that is subject to scratching.
- F. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 30.

- 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of 120 to 450 deg F pipes, NPS 4 to NPS 16, requiring up to 4 inches of insulation.
- 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes, NPS 3/4 to NPS 24, requiring clamp flexibility and up to 4 inches of insulation.
- 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes, NPS 1/2 to NPS 24, if little or no insulation is required.
- 5. Pipe Hangers (MSS Type 5): For suspension of pipes, NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
- 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated stationary pipes, NPS 3/4 to NPS 8.
- 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 8.
- 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 8.
- 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 2.
- 10. Split Pipe-Ring with or without Turnbuckle-Adjustment Hangers (MSS Type 11): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 8.
- 11. Extension Hinged or 2-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 3.
- 12. U-Bolts (MSS Type 24): For support of heavy pipes, NPS 1/2 to NPS 30.
- 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
- 14. Pipe Saddle Supports (MSS Type 36): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange.
- 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange and with U-bolt to retain pipe.
- 16. Adjustable, Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes, NPS 2-1/2 to NPS 36, if vertical adjustment is required, with steel pipe base stanchion support and cast-iron floor flange.
- 17. Single Pipe Rolls (MSS Type 41): For suspension of pipes, NPS 1 to NPS 30, from 2 rods if longitudinal movement caused by expansion and contraction might occur.
- 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes, NPS 2-1/2 to NPS 20), from single rod if horizontal movement caused by expansion and contraction might occur.
- 19. Complete Pipe Rolls (MSS Type 44): For support of pipes, NPS 2 to NPS 42, if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
- 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes, NPS 2 to NPS 24, if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
- 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes, NPS 2 to NPS 30, if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- G. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers, NPS 3/4 to NPS 20.
 - 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers, NPS 3/4 to NPS 20, if longer ends are required for riser clamps.

- H. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 - 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 - 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 - 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 - 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- I. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 - 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction to attach to top flange of structural shape.
 - 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 - 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 - 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 - 6. C-Clamps (MSS Type 23): For structural shapes.
 - 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 - 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 - 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 - 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 - 11. Malleable Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 - 12. Welded-Steel Brackets: For support of pipes from below, or for suspending from above by using clip and rod. Use one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 - 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 - 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 - 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- J. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Steel Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 - 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 - 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.

- K. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 - 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 - 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.
 - 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 - 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from hanger.
 - 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from base support.
 - 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from trapeze support.
 - 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- L. Comply with MSS SP-69 for trapeze pipe hanger selections and applications that are not specified in piping system Sections.
- M. Comply with MFMA-102 for metal framing system selections and applications that are not specified in piping system Sections.
- N. Use mechanical-expansion anchors instead of building attachments where required in concrete construction.
- O. Use pipe positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

3.2 HANGER AND SUPPORT INSTALLATION

A. Steel Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.

- B. Trapeze Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping and support together on field-fabricated trapeze pipe hangers.
 - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified above for individual pipe hangers.
 - 2. Field fabricate from ASTM A 36/A 36M, steel shapes selected for loads being supported. Weld steel according to AWS D1.1.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled metal framing systems.
- D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- E. Fastener System Installation:
 - 1. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- F. Pipe Stand Installation:
 - 1. Pipe Stand Types except Curb-Mounting Type: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.
- G. Install hangers and supports complete with necessary inserts, bolts, rods, nuts, washers, and other accessories.
- H. Install hangers and supports to allow controlled thermal movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- I. Install lateral bracing with pipe hangers and supports to prevent swaying.
- J. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- K. Load Distribution: Install hangers and supports so piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- L. Pipe Joint Stress: Install hangers and supports to provide indicated pipe slopes so maximum pipe deflections and joint stresses allowed by ASME B31.9 (for building services piping) are not exceeded.
- M. Insulated Piping: Comply with the following:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.

- b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
- Do not exceed pipe stress limits according to ASME B31.9 for building services piping.
- 2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - Option: Thermal-hanger shield inserts may be used. Include steel weightdistribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
- 3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
- 4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
- 5. Insert Material: Length at least as long as protective shield.
- 6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make smooth bearing surface.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.4 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.

3.5 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.6 PAINTING

- A. Touch Up: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 220529

HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

220529 - 10

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 220553 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Equipment labels.
 - 2. Pipe labels.
 - 3. Stencils.
 - Valve tags.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- C. Valve numbering scheme.
- D. Valve Schedules: For each piping system to include in maintenance manuals.

1.4 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

A. Plastic Labels for Equipment:

- 1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
- 2. Letter Color: White.
- 3. Background Color: Black.
- 4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- 5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 6. Minimum Letter Size: 1/2 inch and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- 7. Fasteners: Stainless-steel self-tapping screws.
- 8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- B. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified.
- C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number and identify Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 PIPE LABELS

- A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.
- B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to partially cover circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings, pipe size, and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions, or as separate unit on each pipe label to indicate flow direction.
 - 2. Lettering Size: At least 1-1/2 inches high.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.3 STENCILS

- A. Stencils: Prepared with letter sizes according to ASME A13.1 for piping; and minimum letter height of 3/4 inch for access panel and door labels, equipment labels, and similar operational instructions.
 - 1. Stencil Material: Fiberboard or metal.
 - 2. Stencil Paint: Exterior, gloss, alkyd enamel black unless otherwise indicated. Paint may be in pressurized spray-can form.
 - 3. Identification Paint: Exterior, alkyd enamel in colors according to ASME A13.1 unless otherwise indicated.

2.4 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
 - Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 - 2. Fasteners: Brass wire-link or beaded chain; or S-hook.
- B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
 - 1. Valve-tag schedule shall be included in operation and maintenance data.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

3.3 PIPE LABEL INSTALLATION

A. Piping Color-Coding: Painting of piping is specified in Division 09 Section "Interior Painting".

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Stenciled Pipe Label Option: Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option. Install stenciled pipe labels complying with ASME A13.1, on each piping system.
 - 1. Identification Paint: Use for contrasting background.
 - 2. Stencil Paint: Use for pipe marking.
- C. Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
 - 1. Near each valve and control device.
 - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 - 3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
 - 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 - 5. Near major equipment items and other points of origination and termination.
 - 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment and within mechanical rooms, boiler rooms, chiller rooms, etc.
 - 7. On piping above removable acoustical ceilings.
- D. Pipe Label Color Schedule:
 - 1. Domestic Water Piping:
 - a. Background Color: Blue.
 - b. Letter Color: White.
 - 2. Sanitary Waste and Storm Drainage Piping:
 - a. Background Color: Black.
 - b. Letter Color: White.

3.4 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves; valves within factory-fabricated equipment units; shutoff valves; faucets; convenience and lawn-watering hose connections; and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:
 - 1. Valve-Tag Size and Shape:
 - a. Cold Water: 1-1/2 inches, round.
 - b. Hot Water: 1-1/2 inches.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Valve-Tag Color:
 - a. Cold Water: Natural.b. Hot Water: Natural.
- 3. Letter Color:

a. Cold Water: Black.b. Hot Water: Black.

END OF SECTION 220553

220553 - 5



SECTION 220700 - PLUMBING INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Insulation Materials:
 - a. Flexible elastomeric.
 - b. Mineral fiber.
 - c. Molded Close Cell.
 - 2. Fire-rated insulation systems
 - 3. Insulating cements.
 - 4. Adhesives.
 - 5. Mastics.
 - 6. Lagging adhesives.
 - 7. Sealants.
 - 8. Factory-applied jackets.
 - 9. Field-applied jackets.
 - 10. Tapes.
 - 11. Securements.
 - 12. Corner angles.
- B. Related Sections include the following:
 - 1. Division 23 Section "HVAC Insulation."

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated. Include thermal conductivity, thickness, and jackets (both factory and field applied, if any).
- B. Shop Drawings:
 - 1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
 - 2. Detail insulation application at elbows, fittings, flanges, valves, and specialties for each type of insulation.

PLUMBING INSULATION 220700 - 1 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3. Detail removable insulation at piping specialties, equipment connections, and access panels.
- 4. Detail application of field-applied jackets.
- 5. Detail field application for each equipment type.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Fire-Test-Response Characteristics: Insulation and related materials shall have fire-test-response characteristics indicated, as determined by testing identical products per ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing and inspecting agency.
 - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.6 COORDINATION

- A. Coordinate size and location of supports, hangers, and insulation shields specified in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation application and equipment Installer for equipment insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- C. Coordinate installation and testing of heat tracing.

1.7 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PLUMBING INSULATION 220700 - 2 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 2 - PRODUCTS

2.1 INSULATION MATERIALS

- A. Comply with requirements in Part 3 schedule articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- F. Flexible Elastomeric: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials and Type II for sheet materials.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products of one of the following:
 - a. Aeroflex USA Inc.; Aerocel.
 - b. Armacell LLC; AP Armaflex.
 - c. NOMACO Insulation.
 - 2. Thermal Conductivity: Not exceeding 0.25 BTU-in/hour sq. ft. °F at 75°F mean temperature.
- G. Mineral-Fiber, Preformed Pipe Insulation:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Johns Manville.
 - b. Knauf Insulation.
 - c. Manson Insulation Inc.
 - d. Owens Corning Fiberglas Corp.
 - 2. Type I, 850 deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ-SSL. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 3. Thermal Conductivity: Not exceeding 0.23 BTU-in/hour sq. ft. °F at 75°F mean temperature.

PLUMBING INSULATION 220700 - 3 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- H. Mineral-Fiber, Pipe and Tank Insulation: Mineral or glass fibers bonded with a thermosetting resin. Semirigid board material with factory-applied ASJ complying with ASTM C 1393, Type II or Type IIIA Category 2, or with properties similar to ASTM C 612, Type IB. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - CertainTeed Corp.
 - b. Johns Manville.
 - c. Knauf Insulation.
 - d. Manson Insulation Inc.
 - e. Owens Corning Fiberglas Corp.
 - 2. Density: 2.5 lbs/cu. ft.
 - 3. Thermal Conductivity: Not exceeding 0.27 BTU-in/hour °F at 75°F mean temperature.

2.2 INSULATING CEMENTS

- A. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.
- B. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449/C 449M.

2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated, unless otherwise indicated.
- B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Aeroflex USA Inc.
 - b. Armacell LCC.
 - c. Foster Products Corporation, H. B. Fuller Company.
 - d. RBX Corporation.
 - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Products, Division of ITW.
 - b. Foster Products Corporation, H. B. Fuller Company.
 - c. ITW TACC, Division of Illinois Tool Works.

- d. Marathon Industries, Inc.
- e. Mon-Eco Industries, Inc.
- 2. For indoor applications, use adhesive that has a VOC content of 80 g/L or less when calculated according to 40 FR 59, Subpart D (EPA Method 24).
- D. ASJ Adhesive, and FSK Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - Childers Products, Division of ITW.
 - b. Foster Products Corporation, H. B. Fuller Company.
 - c. ITW TACC, Division of Illinois Tool Works.
 - d. Marathon Industries, Inc.
 - e. Mon-Eco Industries, Inc.
 - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- E. PVC Jacket Adhesive: Compatible with PVC jacket.
 - Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Dow Chemical Company (The).
 - b. Johns-Manville; Zeston Perma-Weld.
 - c. P.I.C. Plastics, Inc.
 - d. Speedline Corporation.
 - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.4 MASTICS

- A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-C-19565C, Type II.
 - 1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Childers Products, Division of ITW.
 - 2. Foster Products Corporation, H. B. Fuller Company.
 - 3. ITW TACC, Division of Illinois Tool Works.
 - 4. Marathon Industries, Inc.
 - 5. Mon-Eco Industries, Inc.

PLUMBING INSULATION 220700 - 5 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Vapor-Barrier Mastic: Water or solvent based; suitable for indoor and outdoor use on below ambient services.
 - 1. Water-Vapor Permeance: ASTM E 96, Procedure B, 0.05 perm at 43-mi dry film thickness.
 - 2. Service Temperature Range: Minus 20 to plus 180 deg F.
 - 3. Solids Content: ASTM D 1644, 59 percent by volume and 71 percent by weight.
 - 4. Color: White.
- D. Breather Mastic: Water based; suitable for indoor and outdoor use on above ambient services.
 - 1. Water-Vapor Permeance: ASTM F 1249, 3 perms at 0.0625-inch dry film thickness.
 - 2. Service Temperature Range: Minus 20 to plus 200 deg F.
 - 3. Solids Content: 63 percent by volume and 73 percent by weight.
 - 4. Color: White.

2.5 LAGGING ADHESIVES

- A. Description: Comply with MIL-A-3316C, Class I, Grade A, and shall be compatible with insulation materials, jackets, and substrates.
 - 1. For indoor applications, use lagging adhesives that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 2. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Products, Division of ITW.
 - b. Foster Products Corporation, H. B. Fuller Company.
 - c. Marathon Industries, Inc.
 - d. Mon-Eco Industries. Inc.
 - 3. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over equipment and pipe insulation.
 - 4. Service Temperature Range: Minus 50 to plus 180 deg F.
 - Color: White.

2.6 SEALANTS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Childers Products, Division of ITW.
 - 2. Foster Products Corporation, H. B. Fuller Company.
 - 3. Marathon Industries, Inc.
 - 4. Mon-Eco Industries, Inc.
 - Pittsburgh Corning Corporation.
- B. Joint Sealants for Cellular-Glass:
 - 1. Materials shall be compatible with insulation materials, jackets, and substrates.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Permanently flexible, elastomeric sealant.
- 3. Service Temperature Range: Minus 100 to plus 300 deg F.
- 4. Color: White or gray.
- 5. For indoor applications, use sealants that have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

C. FSK and Metal Jacket Flashing Sealants:

- 1. Materials shall be compatible with insulation materials, jackets, and substrates.
- 2. Fire- and water-resistant, flexible, elastomeric sealant.
- 3. Service Temperature Range: Minus 40 to plus 250 deg F.
- 4. Color: Aluminum.
- 5. For indoor applications, use sealants that have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

D. ASJ Flashing Sealants and PVC Jacket Flashing Sealants:

- 1. Materials shall be compatible with insulation materials, jackets, and substrates.
- 2. Fire- and water-resistant, flexible, elastomeric sealant.
- 3. Service Temperature Range: Minus 40 to plus 250 deg F.
- 4. Color: White.
- 5. For indoor applications, use sealants that have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.7 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
 - 1. ASJ: White, Kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.
 - ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.
 - 3. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with Kraft-paper backing; complying with ASTM C 1136, Type II.

2.8 FIELD-APPLIED JACKETS

A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

B. Metal Jacket:

- Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Products, Division of ITW.
 - b. PABCO Metals Corporation.
 - c. RPR Products, Inc.

PLUMBING INSULATION 220700 - 7 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Aluminum Jacket: Comply with ASTM B 209, Alloy 3003, 3005, 3105 or 5005, Temper H-14.
 - a. Factory cut and rolled to size.
 - b. Finish and thickness are indicated in field-applied jacket schedules.
 - c. Moisture Barrier for Indoor Applications: 1-mil-thick, heat-bonded polyethylene and kraft paper.
 - d. Moisture Barrier for Outdoor Applications: 3-mil-thick, heat-bonded polyethylene and kraft paper.
 - e. Factory-Fabricated Fitting Covers:
 - 1) Same material, finish, and thickness as jacket.
 - Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius elbows.
 - 3) Tee covers.
 - 4) Flange and union covers.
 - 5) End caps.
 - 6) Beveled collars.
 - 7) Valve covers.
 - 8) Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

2.9 TAPES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Avery Dennison Corporation, Specialty Tapes Division.
 - 2. Compac Corp.
 - 3. Ideal Tape Co., Inc., an American Biltrite Company.
 - 4. Venture Tape.
- B. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.
 - 1. Width: 3 inches.
 - 2. Thickness: 11.5 mils.
 - 3. Adhesion: 90 ounces force/inch in width.
 - 4. Elongation: 2 percent.
 - 5. Tensile Strength: 40 lbf/inch in width.
 - 6. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.
- C. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.
 - 1. Width: 3 inches.
 - 2. Thickness: 6.5 mils.
 - 3. Adhesion: 90 ounces force/inch in width.
 - 4. Elongation: 2 percent.
 - 5. Tensile Strength: 40 lbf/inch in width.
 - 6. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.10 SECUREMENTS

A. Bands:

- 1. Stainless Steel: ASTM A 167 or ASTM A 240, Type 304; 0.015 inch thick, 1/2 inch wide with wing or closed seal.
- 2. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 1/2 inch wide with wing or closed seal.
- 3. Springs: Twin spring set constructed of stainless steel with ends flat and slotted to accept metal bands. Spring size determined by manufacturer for application.

B. Insulation Pins and Hangers:

- Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
- 2. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
- 3. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick, galvanized-steel or aluminum sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
 - Protect ends with capped self-locking washers incorporating a spring steel insert to ensure permanent retention of cap in exposed locations.
- C. Staples: Outward-clinching insulation staples, nominal 3/4-inch-wide, stainless steel or Monel.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation and other conditions affecting performance of insulation application.
 - 1. Verify that systems and equipment to be insulated have been tested and are free of defects.
 - 2. Verify that surfaces to be insulated are clean and dry.
 - 3. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

PLUMBING INSULATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Surface Preparation: Clean and prepare surfaces to be insulated.

220700 - 9 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of equipment and piping including fittings, valves, and specialties.
- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of equipment and pipe system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- G. Keep insulation materials dry during application and finishing.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
 - 1. Install insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
 - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
 - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- L. Install insulation with factory-applied jackets as follows:
 - 1. Draw jacket tight and smooth.
 - 2. Cover circumferential joints with 3-inch-wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.

PLUMBING INSULATION 220700 - 10 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.
 - a. For below ambient services, apply vapor-barrier mastic over staples.
- 4. Cover joints and seams with tape as recommended by insulation material manufacturer to maintain vapor seal.
- Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and 5. at ends adjacent to pipe flanges and fittings.
- Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal M. thickness.
- N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- Repair damaged insulation facings by applying same facing material over damaged areas. Ο. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- Ρ. For above ambient services, do not install insulation to the following:
 - 1. Vibration-control devices.
 - 2. Testing agency labels and stamps.
 - 3. Nameplates and data plates.
 - 4. Manholes.
 - Handholes. 5.
 - Cleanouts.

3.4 **PENETRATIONS**

- A. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- В. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
 - 1. Comply with requirements in Division 07 Section "Penetration Firestopping" and fireresistive joint sealers.
- C. Insulation Installation at Floor Penetrations:
 - 1. Pipe: Install insulation continuously through floor penetrations.
 - Seal penetrations through fire-rated assemblies. Comply with requirements in Division 07 2. Section "Penetration Firestopping."

PLUMBING INSULATION 220700 - 11 Project No.: CP242241

3.5 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:
 - 1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity, unless otherwise indicated.
 - 2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
 - Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
 - 4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
 - 5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below ambient services, provide a design that maintains vapor barrier.
 - 6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
 - 7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below ambient services and a breather mastic for above ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
 - 8. For services not specified to receive a field-applied jacket except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
 - 9. Stencil or label the outside insulation jacket of each union with the word "UNION." Match size and color of pipe labels.
- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes, vessels, and equipment. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.

PLUMBING INSULATION 220700 - 12 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Install removable insulation covers at locations indicated. Installation shall conform to the following:
 - Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
 - When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
 - 3. Construct removable valve insulation covers in same manner as for flanges except divide the two-part section on the vertical center line of valve body.
 - 4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
 - 5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

3.6 FLEXIBLE ELASTOMERIC INSULATION INSTALLATION

- A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- B. Insulation Installation on Pipe Flanges:
 - 1. Install pipe insulation to outer diameter of pipe flange.
 - 2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
 - 3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
 - 4. Secure insulation to flanges and seal seams with manufacturers' recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- C. Insulation Installation on Pipe Fittings and Elbows:
 - 1. Install mitered sections of pipe insulation.
 - 2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- D. Insulation Installation on Valves and Pipe Specialties:
 - 1. Install preformed valve covers manufactured of same material as pipe insulation when available.
 - 2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
 - 3. Install insulation to flanges as specified for flange insulation application.

PLUMBING INSULATION 220700 - 13 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.7 MINERAL-FIBER INSULATION INSTALLATION

A. Insulation Installation on Straight Pipes and Tubes:

- 1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
- 2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
- 3. For insulation with factory-applied jackets on above ambient surfaces, secure laps with outward clinched staples at 6 inches o.c.
- 4. For insulation with factory-applied jackets on below ambient surfaces, do not staple longitudinal tabs but secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:

- 1. Install preformed pipe insulation to outer diameter of pipe flange.
- 2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
- 3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
- 4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

- 1. Install preformed sections of same material as straight segments of pipe insulation when available.
- 2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

- Install preformed sections of same material as straight segments of pipe insulation when available.
- 2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
- 3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
- 4. Install insulation to flanges as specified for flange insulation application.

PLUMBING INSULATION 220700 - 14 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.8 FIELD-APPLIED JACKET INSTALLATION

- A. Where glass-cloth jackets are indicated, install directly over bare insulation or insulation with factory-applied jackets.
 - 1. Draw jacket smooth and tight to surface with 2-inch overlap at seams and joints.
 - 2. Embed glass cloth between two 0.062-inch-thick coats of lagging adhesive.
 - 3. Completely encapsulate insulation with coating, leaving no exposed insulation.
- B. Where FSK jackets are indicated, install as follows:
 - 1. Draw jacket material smooth and tight.
 - 2. Install lap or joint strips with same material as jacket.
 - 3. Secure jacket to insulation with manufacturer's recommended adhesive.
 - 4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch-wide joint strips at end joints.
 - 5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.
- C. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints; for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturer's recommended adhesive.
 - 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.
- D. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

3.9 FIRE-RATED INSULATION SYSTEM INSTALLATION

- A. Where fire-rated insulation system is indicated, secure system to piping and pipe hangers and supports to maintain a continuous fire rating.
- B. Install firestopping at penetrations through fire-rated assemblies. Fire-stop systems are specified in Division 07 Section "Penetration Firestopping".

3.10 FINISHES

- A. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.
- B. Do not field paint aluminum or stainless-steel jackets.

3.11 FIELD QUALITY CONTROL

A. Perform tests and inspections.

PLUMBING INSULATION 220700 - 15 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Tests and Inspections:

- Inspect field-insulated equipment, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one (1) location(s) for each type of equipment defined in the "Equipment Insulation Schedule" Article. For large equipment, remove only a portion adequate to determine compliance.
- 2. Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three (3) locations of straight pipe, locations of threaded valves, and three locations of flanged valves for each pipe service defined in the "Piping Insulation Schedule, General" Article.
- C. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.12 PIPING INSULATION SCHEDULE, GENERAL

- A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.
- B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
 - 1. Drainage piping located in crawl spaces.
 - 2. Underground piping.
 - 3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

3.13 INDOOR PIPING INSULATION SCHEDULE

- A. Domestic Cold Water:
 - 1. NPS 1/2" through 3/4": Insulation shall be the following:
 - a. Flexible elastomeric: 3/4 inch thick.
 - 2. NPS 1" and larger": Insulation shall be the following:
 - a. Flexible elastomeric: 1 inch thick.
- B. Domestic Hot and Recirculated Hot Water:
 - 1. NPS 1-1/4" and smaller: Insulation shall be the following:
 - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
 - b. Flexible elastomeric: 1 inch thick

PLUMBING INSULATION 220700 - 16 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. NPS 1-1/2" and larger:
 - Mineral-Fiber, Preformed Pipe Insulation, Type I: 1-1/2 inch thick.
 - Flexible elastomeric: 1-1/2 inch thick
- C. Waste, Vent, Storm Water and Overflow Location in Return Air Plenums:
 - Unifrax Fire Wrap 0.5 Plenum Insulation or Equal: 1/2 inch thick. 1.

3.14 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the fieldapplied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Equipment, Concealed:
 - 1. None.
- D. Equipment, Exposed:
 - None.
- E. Piping, Concealed:
 - 1. None.
- Piping, exposed in mechanical room piping that is within 6 ft. of the floor. F.
 - 1. Aluminum, Smooth: 0.016 inch thick.

END OF SECTION 220700

PLUMBING INSULATION

220700 - 17 Project No.: CP242241



SECTION 221116 - DOMESTIC WATER PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Aboveground domestic water pipes, tubes, fittings, and specialties inside the building.
- 2. Specialty valves.
- 3. Flexible connectors.
- 4. Escutcheons.
- 5. Sleeves.
- 6. Wall penetration systems.

1.3 SUBMITTALS

- A. Product Data: For the following products:
 - 1. Specialty valves.
 - 2. Transition fittings.
 - 3. Dielectric fittings.
 - 4. Flexible connectors.
 - 5. Escutcheons.
 - 6. Sleeves and sleeve seals.
 - 7. Wall penetration systems.
- B. Field quality-control reports.

1.4 QUALITY ASSURANCE

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 61 for potable domestic water piping and components.

1.5 PROJECT CONDITIONS

- A. Interruption of Existing Water Service: Do not interrupt water service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary water service according to requirements indicated:
 - 1. Notify Architect no fewer than seven (7) days in advance of proposed interruption of water service.
 - 2. Do not proceed with interruption of water service without Architect's written permission.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.2 COPPER TUBE AND FITTINGS

- A. Hard Copper Tube: ASTM B 88, Type L water tube, drawn temper.
 - 1. Cast-Copper Solder-Joint Fittings: ASME B16.18, pressure fittings.
 - 2. Wrought-Copper Solder-Joint Fittings: ASME B16.22, wrought-copper pressure fittings.
 - 3. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.
 - 4. Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body, with ball-and-socket, metal-to-metal seating surfaces, and solder-joint or threaded ends.

B. Copper Pressure-Seal-Joint Fittings:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Elkhart Products Corporation.
 - b. NIBCO Inc.
 - c. Viega.
- 2. Fittings for NPS 2 and Smaller: Wrought-copper fitting with EPDM-rubber, O- ring seal in each end.
- 3. Fittings for NPS 2-1/2 to NPS 4: Cast-bronze or wrought-copper fitting with EPDM-rubber, O-ring seal in each end.

2.3 PIPING JOINING MATERIALS

- A. Pipe-Flange Gasket Materials: AWWA C110, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free, unless otherwise indicated; full-face or ring type unless otherwise indicated.
- B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.

- C. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- D. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for generalduty brazing unless otherwise indicated.

2.4 DIELECTRIC FITTINGS

- A. General Requirements: Assembly of copper alloy and ferrous materials or ferrous material body with separating nonconductive insulating material suitable for system fluid, pressure, and temperature.
- B. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Calpico, Inc.
 - 2. Capitol Manufacturing Company.
 - 3. Central Plastics Company.
 - 4. EPCO Sales, Inc.
 - 5. Hart Industries International, Inc.
 - 6. Lochinvar Corp.
 - 7. Victaulic
 - 8. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
 - 9. Zurn Plumbing Products Group; Wilkins Water Control Products.

C. Dielectric Couplings:

- 1. Description:
 - a. Galvanized-steel coupling.
 - b. Pressure Rating: 300 psig at 225 deg F.
 - c. End Connections: Female threaded.
 - d. Lining: Inert and noncorrosive, thermoplastic.

D. Dielectric Nipples:

- 1. Description:
 - a. Electroplated steel nipple complying with ASTM F 1545 (Victaulic Style 47).
 - b. Pressure Rating: 300 psig at 225 deg F.
 - c. End Connections: Male threaded or grooved.
 - d. Lining: Inert and noncorrosive, propylene.

2.5 ESCUTCHEONS

- A. General: Manufactured ceiling, floor, and wall escutcheons and floor plates.
- B. One Piece, Cast Brass: Polished, chrome-plated finish with setscrews.
- C. One Piece, Deep Pattern: Deep-drawn, box-shaped brass with chrome-plated finish.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. One Piece, Stamped Steel: Chrome-plated finish with setscrew.
- E. Split Casting, Cast Brass: Polished, chrome-plated finish with concealed hinge and setscrew.
- F. Split Plate, Stamped Steel: Chrome-plated finish with concealed hinge, setscrew.
- G. One-Piece Floor Plates: Cast-iron flange with holes for fasteners.
- H. Split-Casting Floor Plates: Cast brass with concealed hinge.

2.6 SLEEVES

- A. Cast-Iron Wall Pipes: Fabricated of cast iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Galvanized-Steel-Sheet Sleeves: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint or ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc-coated, with plain ends.
- C. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with setscrews.

2.7 SLEEVE SEALS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Advance Products & Systems, Inc.
 - 2. Calpico, Inc.
 - 3. Metraflex, Inc.
 - 4. Pipeline Seal and Insulator, Inc.
- B. Description: Modular sealing element unit, designed for field assembly, used to fill annular space between pipe and sleeve.
 - 1. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 2. Pressure Plates: Carbon steel.
 - 3. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating of length required to secure pressure plates to sealing elements.

2.8 WALL PENETRATION SYSTEMS

- A. Description: Wall-sleeve assembly, consisting of housing and gland, gaskets, and pipe sleeve.
 - 1. Carrier-Pipe Deflection: Up to 5 percent without leakage.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Housing: Ductile-iron casting with hub, waterstop, anchor ring, and locking devices. Include gland, bolts, and nuts.
- 3. Housing-to-Sleeve Gasket: EPDM rubber.
- 4. Housing-to-Carrier-Pipe Gasket: AWWA C111, EPDM rubber.
- 5. Pipe Sleeve: AWWA C151, ductile-iron pipe or ASTM A 53/A 53M, Schedule 40, zinc-coated steel pipe.

2.9 GROUT

- A. Standard: ASTM C 1107, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- B. Characteristics: Nonshrink; recommended for interior and exterior applications.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 EARTHWORK

A. Comply with requirements in Section "Common Work Results for Plumbing" for excavating, trenching, and backfilling.

3.2 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve, inside the building at each domestic water service entrance. Comply with requirements in Division 22 Section "Meters and Gages for Plumbing Piping" for pressure gages and Division 22 Section "Domestic Water Piping Specialties" for drain valves and strainers.
- C. Install shutoff valve immediately upstream of each dielectric fitting.
- D. Install domestic water piping level with 0.25 percent slope downward toward drain and plumb.
- E. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- F. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- G. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.
- H. Install piping adjacent to equipment and specialties to allow service and maintenance.
- I. Install piping to permit valve servicing.
- J. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than system pressure rating used in applications below unless otherwise indicated.
- K. Install piping free of sags and bends.
- L. Install fittings for changes in direction and branch connections.
- M. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.
- N. Install thermometers on inlet and outlet piping from each water heater. Comply with requirements in Division 22 Section "Meters and Gages for Plumbing Piping" for thermometers.

3.3 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- C. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- D. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook," "Brazed Joints" Chapter.
- E. Soldered Joints: Apply ASTM B 813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B 828 or CDA's "Copper Tube Handbook."
- F. Pressure-Sealed Joints for Copper Tubing: Join copper tube and pressure-seal fittings with tools recommended by fitting manufacturer.
- G. Flanged Joints: Select appropriate asbestos-free, nonmetallic gasket material in size, type, and thickness suitable for domestic water service. Join flanges with gasket and bolts according to ASME B31.9.
- H. Dissimilar-Material Piping Joints: Make joints using adapters compatible with materials of both piping systems.

3.4 VALVE INSTALLATION

- A. General-Duty Valves: Comply with requirements in Division 22 Section "General-Duty Valves for Plumbing Piping" for valve installations.
- B. Install shutoff valve close to water main on each branch and riser serving plumbing fixtures or equipment, on each water supply to equipment, and on each water supply to plumbing fixtures that do not have supply stops. Use ball or gate valves for piping NPS 2 and smaller. Use butterfly or gate valves for piping NPS 2-1/2 and larger.
- C. Install drain valves for equipment at base of each water riser, at low points in horizontal piping, and where required to drain water piping. Drain valves are specified in Division 22 Section "Domestic Water Piping Specialties."
 - 1. Hose-End Drain Valves: At low points in water mains, risers, and branches.
 - 2. Stop-and-Waste Drain Valves: Instead of hose-end drain valves where indicated.

3.5 TRANSITION FITTING INSTALLATION

- A. Install transition couplings at joints of dissimilar piping.
- B. Transition Fittings in Underground Domestic Water Piping:
 - 1. NPS 1-1/2 and Smaller: Fitting-type waterways.
 - 2. NPS 2 and Larger: Sleeve-type coupling.
- C. Transition Fittings in Aboveground Domestic Water Piping NPS 2 and Smaller: Plastic-to-metal transition fittings or unions.

3.6 DIELECTRIC FITTING INSTALLATION

- A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
- B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric couplings.
- C. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric flanges.

3.7 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support products and installation.
 - 1. Vertical Piping: MSS Type 8 or 42, clamps.
 - 2. Individual, Straight, Horizontal Piping Runs:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - 3. Base of Vertical Piping: MSS Type 52, spring hangers.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Support vertical piping and tubing at base and at each floor.
- C. Rod diameter may be reduced one size for double-rod hangers, to a minimum of 3/8 inch.
- D. Install hangers for copper piping with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 3/4 and Smaller: 60 inches with 3/8-inch rod.
 - 2. NPS 1 and NPS 1-1/4: 72 inches with 3/8-inch rod.
 - 3. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
 - 4. NPS 2-1/2: 108 inches with 1/2-inch rod.
 - 5. NPS 3 to NPS 5: 10 feet with 1/2-inch rod.
- E. Install supports for vertical copper piping every 10 feet. For piping 2" and smaller install guide at midpoint between supports.
- F. Install supports for vertical steel piping every 15 feet.
- G. Support piping and tubing not listed in this article according to MSS SP-69 and manufacturer's written instructions.

3.8 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment and machines to allow service and maintenance.
- C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.
- D. Connect domestic water piping to water-service piping with shutoff valve; extend and connect to the following:
 - 1. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
 - 2. Plumbing Fixtures: Cold- and hot-water supply piping in sizes indicated, but not smaller than required by plumbing code. Comply with requirements in Division 22 plumbing fixture Sections for connection sizes.
 - 3. Equipment: Cold- and hot-water supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

3.9 ESCUTCHEON INSTALLATION

- A. Install escutcheons for penetrations of walls, ceilings, and floors.
- B. Escutcheons for New Piping:
 - 1. Piping with Fitting or Sleeve Protruding from Wall: One piece, deep pattern.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
- 3. Bare Piping at Ceiling Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
- 4. Bare Piping in Unfinished Service Spaces: One piece, stamped steel with set screw.
- 5. Bare Piping in Equipment Rooms: One piece, stamped steel with set screw.
- 6. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece floor plate.

3.10 SLEEVE INSTALLATION

- A. General Requirements: Install sleeves for pipes and tubes passing through penetrations in floors, partitions, roofs, and walls.
- B. Sleeves are not required for core-drilled holes.
- C. Permanent sleeves are not required for holes formed by removable PE sleeves.
- D. Cut sleeves to length for mounting flush with both surfaces unless otherwise indicated.
- E. Install sleeves in new partitions, slabs, and walls as they are built.
- F. For interior wall penetrations, seal annular space between sleeve and pipe or pipe insulation using joint sealants appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants" for joint sealants.
- G. For exterior wall penetrations above grade, seal annular space between sleeve and pipe using joint sealants appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants" for joint sealants.
- H. For exterior wall penetrations below grade, seal annular space between sleeve and pipe using sleeve seals specified in this Section.
- I. Seal space outside of sleeves in concrete slabs and walls with grout.
- J. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation unless otherwise indicated.
- K. Install sleeve materials according to the following applications:
 - 1. Sleeves for Piping Passing through Concrete Floor Slabs: Steel pipe.
 - 2. Sleeves for Piping Passing through Concrete Floor Slabs of Mechanical Equipment Areas or Other Wet Areas: Steel pipe.
 - a. Extend sleeves 2 inches above finished floor level.
 - b. For pipes penetrating floors with membrane waterproofing, extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3. Sleeves for Piping Passing through Gypsum-Board Partitions:
 - a. Galvanized-steel sheet sleeves for pipes smaller than NPS 6.
 - b. Galvanized-steel sheet sleeves for pipes NPS 6 and larger.
 - c. Exception: Sleeves are not required for water supply tubes and waste pipes for individual plumbing fixtures if escutcheons will cover openings.
- 4. Sleeves for Piping Passing through Interior Concrete Walls:
 - a. Steel pipe sleeves for pipes smaller than NPS 6.
 - b. Galvanized-steel sheet sleeves for pipes NPS 6 and larger.
- L. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping" for firestop materials and installations.

3.11 WALL PENETRATION SYSTEM INSTALLATION

- A. Install wall penetration systems in new, exterior concrete walls.
- B. Assemble wall penetration system components with sleeve pipe. Install so that end of sleeve pipe and face of housing are flush with wall. Adjust locking devices to secure sleeve pipe in housing.

3.12 IDENTIFICATION

- A. Identify system components. Comply with requirements in Division 22 Section "Identification for Plumbing Piping and Equipment" for identification materials and installation.
- B. Label pressure piping with system operating pressure.

3.13 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Piping Inspections:
 - 1. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.
 - 2. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
 - a. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 - b. Final Inspection: Arrange final inspection for authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.

221116 - 10 Project No.: CP242241 February 27, 2024

- 3. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
- 4. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

C. Piping Tests:

- 1. Fill domestic water piping. Check components to determine that they are not air bound and that piping is full of water.
- 2. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.
- 3. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.
- 4. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.
- 5. Repair leaks and defects with new materials and retest piping or portion thereof until satisfactory results are obtained.
- 6. Prepare reports for tests and for corrective action required.
- D. Domestic water piping will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

3.14 ADJUSTING

- A. Perform the following adjustments before operation:
 - 1. Close drain valves, hydrants, and hose bibbs.
 - 2. Open shutoff valves to fully open position.
 - 3. Open throttling valves to proper setting.
 - 4. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
 - a. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide flow of hot water in each branch.
 - b. Adjust calibrated balancing valves to flows indicated.
 - 5. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
 - 6. Remove and clean strainer screens. Close drain valves and replace drain plugs.
 - 7. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and are clean and ready for use.
 - 8. Check plumbing specialties and verify proper settings, adjustments, and operation.

Project No.: CP242241 February 27, 2024

3.15 CLEANING

- A. Clean and disinfect potable and non-potable domestic water piping as follows:
 - 1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
 - 2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:
 - a. Flush piping system with clean, potable water until dirty water does not appear at outlets. Flush at 10 ft/sec to comply with NFPA standards.
 - b. Fill and isolate system according to either of the following:
 - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
 - 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.
 - c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
 - d. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.
- B. Prepare and submit reports of purging and disinfecting activities.
- C. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

3.16 PIPING SCHEDULE

- A. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.
- B. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.
- C. Aboveground domestic water piping, NPS 2 and smaller, shall be one of the following:
 - 1. Hard copper tube, ASTM B 88, Type L; cast- or wrought- copper solder-joint fittings; and brazed or soldered joints.
- D. Aboveground domestic water piping, NPS 2-1/2 and larger, shall be one of the following:
 - 1. Hard copper tube, ASTM B 88, Type L; cast- or wrought-copper solder-joint fittings; and brazed or soldered joints.
 - 2. Hard copper tube, ASTM B 88, Type L; grooved-joint copper-tube appurtenances; and grooved joints.
 - 3. Hard copper tube, ASTM B 88, Type L; copper pressure-seal-joint fittings; and pressure-sealed joints.

221116 - 12

Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.17 VALVE SCHEDULE

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
 - 1. Shutoff Duty: Use ball or gate valves for piping NPS 2 and smaller. Use butterfly, ball, or gate valves with flanged ends for piping NPS 2-1/2 and larger.
 - 2. Throttling Duty: Use ball or globe valves for piping NPS 2 and smaller. Use butterfly or ball valves with flanged ends for piping NPS 2-1/2 and larger.
 - 3. Drain Duty: Hose-end drain valves.
- B. Use check valves to maintain correct direction of domestic water flow to and from equipment.
- C. Iron grooved-end valves may be used with grooved-end piping.

END OF SECTION 221116

221116 - 13 Project No.: CP242241 February 27, 2024



SECTION 221316 - SANITARY WASTE AND VENT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following for soil, waste, and vent piping inside the building:
 - 1. Pipe, tube, and fittings.

1.3 PERFORMANCE REQUIREMENTS

- A. Components and installation shall be capable of withstanding the following minimum working pressure, unless otherwise indicated:
 - 1. Soil, Waste, and Vent Piping: 10-foot head of water.
 - 2. Sanitary Sewer, Force-Main Piping: 50 psig.

1.4 SUBMITTALS

- A. Product Data: For pipe, tube, fittings, and couplings.
- B. Field quality-control inspection and test reports.

1.5 QUALITY ASSURANCE

A. Piping materials shall bear label, stamp, or other markings of specified testing agency.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.2 PIPING MATERIALS

A. Refer to Part 3 "Piping Applications" Article for applications of pipe, tube, fitting, and joining materials.

2.3 PVC PIPE AND FITTINGS

- A. Solid-Wall PVC Pipe: ASTM D 1785, drain, waste, and vent.
- B. PVC Socket Fittings: ASTM D 1785, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.
- C. Adhesive Primer: ASTM F 656.
 - 1. Adhesive primer shall have a VOC content of 550 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 2. Adhesive primer shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- D. Solvent Cement: ASTM D 2564.
 - 1. PVC solvent cement shall have a VOC content of 510 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 2. Solvent cement shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

2.4 SPECIALTY PIPE FITTINGS

A. Transition Couplings:

- General Requirements: Fitting or device for joining piping with small differences in OD's or of different materials. Include end connections same size as and compatible with pipes to be joined.
- 2. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
- 3. Unshielded, Nonpressure Transition Couplings:
 - a. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1) Dallas Specialty & Mfg. Co.
 - 2) Fernco Inc.
 - 3) Mission Rubber Company; a division of MCP Industries, Inc.
 - 4) Plastic Oddities; a division of Diverse Corporate Technologies, Inc.

- b. Standard: ASTM C 1173.
- Description: Elastomeric, sleeve-type, reducing or transition pattern. Include shear ring and corrosion-resistant-metal tension band and tightening mechanism on each end.
- d. Sleeve Materials:
 - 1) For Cast-Iron Soil Pipes: ASTM C 564, rubber.
 - 2) For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
 - 3) For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.
- 4. Shielded, Nonpressure Transition Couplings:
 - a. Manufacturers: Subject to compliance with requirements available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1) Cascade Waterworks Mfg. Co.
 - 2) Mission Rubber Company; a division of MCP Industries, Inc.
 - b. Standard: ASTM C 1460.
 - Description: Elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.

PART 3 - EXECUTION

3.1 EXCAVATION

A. Refer to Section "Common Work Results for Plumbing" for excavating, trenching, and backfilling.

3.2 PIPING APPLICATIONS

- A. Flanges and unions may be used on aboveground pressure piping, unless otherwise indicated.
- B. Aboveground, soil and waste piping NPS 4 and smaller shall be any of the following:
 - 1. Solid wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
- C. Aboveground, vent piping NPS 4 and smaller shall be any of the following:
 - 1. Solid wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
- D. Underground, soil, waste, and vent piping shall be any of the following:
 - 1. Solid wall PVC pipe, PVC socket fittings, and solvent-cemented joints.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.3 PIPING INSTALLATION

- A. Basic piping installation requirements are specified in Division 22 Section "Common Work Results for Plumbing."
- B. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers.
- C. Install cleanout fitting with closure plug inside the building in sanitary force-main piping.
- D. Install underground, steel, force-main piping.
- E. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
 - 1. Install encasement on underground piping according to ASTM A 674 or AWWA C105.
- F. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical. Use long-turn, double Y-branch and 1/8-bend fittings if 2 fixtures are installed back to back or side by side with common drain pipe. Straight tees, elbows, and crosses may be used on vent lines. Do not change direction of flow more than 90 degrees. Use proper size of standard increasers and reducers if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.
- G. Lay buried building drainage piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements. Maintain swab in piping and pull past each joint as completed.
- H. Install soil and waste drainage and vent piping at the following minimum slopes, unless otherwise indicated:
 - 1. Building Sanitary Drain: 2 percent (1/4" slope) downward in direction of flow for piping NPS 3 and smaller; 1 percent (1/8" slope) downward in direction of flow for piping NPS 4 and larger.
 - 2. Horizontal Sanitary Drainage Piping: 2 percent (1/4" slope) downward in direction of flow.
 - 3. Vent Piping: 1 percent (1/8" slope) down toward vertical fixture vent or toward vent stack.
- I. Install engineered soil and waste drainage and vent piping systems as follows:
 - 1. Combination Waste and Vent: Comply with standards of authorities having jurisdiction.
- J. Sleeves are not required for cast-iron soil piping passing through concrete slabs-on-grade if slab is without membrane waterproofing.
- K. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.4 JOINT CONSTRUCTION

- A. Basic piping joint construction requirements are specified in Division 22 Section "Common Work Results for Plumbing."
- B. PVC Nonpressure Piping Joints: Join piping according to ASTM D 2665.
- C. Soldered Joints: Use ASTM B 813, water-flushable, lead-free flux; ASTM B 32, lead-free-alloy solder; and ASTM B 828 procedure, unless otherwise indicated.
- D. Grooved Joints: Assemble joint with keyed coupling, gasket, lubricant, and bolts according to coupling and fitting manufacturer's written instructions.

3.5 SPECIALTY PIPE FITTING INSTALLATION

- A. Transition Couplings:
 - 1. Install transition couplings at joints of piping with small differences in OD's.
 - 2. In Drainage Piping: Shielded, nonpressure transition couplings.

3.6 VALVE INSTALLATION

- A. General valve installation requirements are specified in Division 22 Section "General-Duty Valves for Plumbing Piping."
- B. Shutoff Valves: Install shutoff valve on each sewage pump discharge.
 - 1. Install gate or full-port ball valve for piping NPS 2 and smaller.
- C. Check Valves: Install swing check valve, between pump and shutoff valve, on each sewage pump discharge.
- D. Backwater Valves: Install backwater valves in piping subject to sewage backflow.
 - 1. Horizontal Piping: Horizontal backwater valves.
 - 2. Floor Drains: Drain outlet backwater valves, unless drain has integral backwater valve.
 - 3. Install backwater valves in accessible locations.
 - 4. Backwater valves are specified in Division 22 Section "Sanitary Waste Piping Specialties."

3.7 HANGER AND SUPPORT INSTALLATION

- A. Pipe hangers and supports are specified in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment." Install the following:
 - 1. Vertical Piping: MSS Type 8 or Type 42, clamps.
 - 2. Install individual, straight, horizontal piping runs according to the following:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3. Base of Vertical Piping: MSS Type 52, spring hangers.
- B. Install supports according to Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment."
- C. Support vertical piping and tubing at base and at each floor.
- D. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- E. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
 - 2. NPS 3: 60 inches with 1/2-inch rod.
 - 3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
- F. Install supports for vertical cast-iron soil piping every 15 feet.
- G. Install hangers for steel piping with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 1-1/4: 84 inches with 3/8-inch rod.
 - 2. NPS 1-1/2: 108 inches with 3/8-inch rod.
 - 3. NPS 2: 10 feet with 3/8-inch rod.
 - 4. NPS 2-1/2: 11 feet with 1/2-inch rod.
 - 5. NPS 3: 12 feet with 1/2-inch rod.
 - 6. NPS 4 and NPS 5: 12 feet with 5/8-inch rod.
- H. Install supports for vertical steel piping every 15 feet.

3.8 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.
- C. Connect drainage and vent piping to the following:
 - 1. Plumbing Fixtures: Connect drainage piping in sizes indicated, but not smaller than required by plumbing code.
 - 2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
 - 3. Plumbing Specialties: Connect drainage and vent piping in sizes indicated, but not smaller than required by plumbing code.
 - 4. Equipment: Connect drainage piping as indicated. Provide shutoff valve, if indicated, and union for each connection. Use flanges instead of unions for connections NPS 2-1/2 and larger.

3.9 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
 - 1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 - 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary drainage and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
 - 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
 - 2. Leave uncovered and unconcealed new, altered, extended, or replaced drainage and vent piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
 - Roughing-in Plumbing Test Procedure: Test drainage and vent piping, except outside leaders, on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water. From 60 minutes before inspection starts to completion of inspection, water level must not drop. Inspect joints for leaks.
 - 4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg. Use U-tube or manometer inserted in trap of water closet to measure this pressure. Air pressure must remain constant without introducing additional air throughout period of inspection. Inspect plumbing fixture connections for gas and water leaks.
 - 5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
 - 6. Prepare reports for tests and required corrective action.

3.10 CLEANING

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.

END OF SECTION 221316



SECTION 226113 - COMPRESSED-AIR PIPING FOR LABORATORY AND HEALTHCARE FACILITIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Medical air piping and specialties, designated "medical air," operating at 50 to 55 psig.
 - 2. Healthcare laboratory air piping and specialties, designated "medical laboratory air," operating at 100 psig.
- B. Related Sections include the following:
 - 1. Division 12 Section "Healthcare Casework" for compressed-air outlets in medical casework.

1.3 DEFINITIONS

- A. D.I.S.S.: Diameter-index safety system.
- B. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control, signaling power-limited circuits.
- C. Medical Compressed-Air Piping Systems: Include medical air, dental air and medical laboratory air piping systems.

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Compressed-air tubes and fittings.
 - 2. Compressed-air valves and valve boxes.
 - 3. Medical compressed-air service connections.
 - 4. Medical compressed-air pressure control panels.
 - 5. Medical compressed-air manifolds.
 - 6. Medical compressed-air alarm system components.
- B. Shop Drawings: Diagram power, signal, and control wiring.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Piping Material Certification: Signed by Installer certifying that medical compressed-air piping materials comply with NFPA 99 requirements.
- D. Qualification Data: For testing agency.
- E. Brazing certificates.
- F. Field quality-control test reports.
- G. Operation and Maintenance Data: For compressed-air piping specialties to include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications:
 - 1. Medical Compressed-Air Piping Systems for Healthcare Facilities: Qualify installers according to ASSE Standard #6010.
 - 2. Pressure-Seal Joining Procedure for Copper Tubing: Qualify operators according to training provided by Viega; Plumbing and Heating Systems.
- B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the vacuum piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.
 - 1. Qualify testing personnel according to ASSE Standard #6020 for inspectors and ASSE Standard #6030 for verifiers.
- C. Source Limitations: Obtain compressed-air service connections of same type and from same manufacturer as service connections provided for in Division 22 Section "Gas Piping for Laboratory and Healthcare Facilities."
- D. Brazing: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications," or AWS B2.2, "Standard for Brazing Procedure and Performance Qualification."
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- F. ASME Compliance:
 - 1. Comply with ASME B31.9, "Building Services Piping," for laboratory compressed-air piping operating at 150 psig or less.
- G. Comply with NFPA 99, "Health Care Facilities," for medical compressed-air system materials and installation in healthcare facilities.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.6 PROJECT CONDITIONS

- A. Interruption of Existing Laboratory and Medical Compressed-Air Service(s): Do not interrupt laboratory or medical compressed-air service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
 - 1. Notify Architect no fewer than seven days in advance of proposed interruption of laboratory and medical compressed-air service(s).
 - 2. Do not proceed with interruption of laboratory and medical compressed-air service(s) without Architect's written permission.

1.7 COORDINATION

- A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.
- B. Coordinate medical compressed-air service connections with other service connections. Medical vacuum service connections are specified in Division 22 Section "Vacuum Piping for Laboratory and Healthcare Facilities," and medical gas service connections are specified in Division 22 Section "Gas Piping for Laboratory and Healthcare Facilities."

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Quick-Coupler Service Connections: Furnish complete noninterchangeable medical compressed-air pressure outlets.
 - a. Medical Compressed-Air Service Connections: Equal to ten percent of amount installed, but no fewer than two units.
 - 2. D.I.S.S. Connections: Furnish complete noninterchangeable medical compressed-air pressure outlets complying with CGA V-5.
 - a. Compressed-Air D.I.S.S. No. 1160: Equal to ten percent of amount installed, but no fewer than two units.

PART 2 - PRODUCTS

2.1 PIPES, TUBES, AND FITTINGS

- A. Copper Medical Gas Tube: ASTM B 819, Type L, seamless, drawn temper, that has been manufacturer cleaned, purged, and sealed for medical gas service or according to CGA G-4.1 for oxygen service. Include standard color marking "OXY," "MED," "OXY/MED," "OXY/ACR," or "ACR/MED" in blue for Type L tube.
 - 1. General Requirements for Copper Fittings: Manufacturer cleaned, purged, and bagged for oxygen service according to CGA G-4.1.
 - 2. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type or MSS SP-73, with dimensions for brazed joints.
 - 3. Copper Unions: ASME B16.22 or MSS SP-123, wrought copper or cast-copper alloy.
 - 4. Press-Type Fittings:
 - a. NPS 2 and Smaller: Wrought-copper fitting with EPDM O-ring seal in each end.
 - b. NPS 2-1/2 to NPS 4: Bronze fitting with stainless-steel grip ring and EPDM O-ring seal in each end.
- B. Memory-Metal Couplings: Cryogenic compression fitting made of ASTM F 2063, nickel-titanium, shape-memory alloy, and that has been manufacturer cleaned, purged, and sealed for oxygen service according to CGA G-4.1.
- C. Copper Water Tube: ASTM B 88, Type M, seamless, drawn temper.
 - 1. Copper Fittings: ASME B16.18, cast-copper or ASME B16.22, wrought-copper, solder-joint pressure type.
 - 2. Press-Type Fittings:
 - a. NPS 2 and Smaller: Wrought-copper fitting with EPDM O-ring seal in each end.
 - b. NPS 2-1/2 to NPS 4: Bronze fitting with stainless-steel grip ring and EPDM O-ring seal in each end.

2.2 JOINING MATERIALS

- A. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- B. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for general-duty brazing unless otherwise indicated.
- C. Threaded-Joint Tape: PTFE.
- D. Solvent Cement for Joining PVC Piping: ASTM D 2564. Include primer complying with ASTM F 656.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.3 VALVES

- A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged according to CGA G-4.1 for oxygen service.
- B. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. BeaconMedaes.
- C. Ball Valves: MSS SP-110, 3-piece body, brass or bronze.
 - 1. Pressure Rating: 300 psig minimum.
 - 2. Ball: Full-port, chrome-plated brass.
 - 3. Seats: PTFE or TFE.
 - 4. Handle: Lever type with locking device.
 - 5. Stem: Blowout proof with PTFE or TFE seal.
 - 6. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
- D. Check Valves: In-line pattern, bronze.
 - 1. Pressure Rating: 300 psig minimum.
 - 2. Operation: Spring loaded.
 - 3. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
- E. Zone Valves: MSS SP-110, 3-piece-body, brass or bronze ball valve with gage.
 - 1. Pressure Rating: 300 psig minimum.
 - 2. Ball: Full-port, chrome-plated brass.
 - Seats: PTFE or TFE.
 - 4. Handle: Lever type with locking device.
 - 5. Stem: Blowout proof with PTFE or TFE seal.
 - 6. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
 - 7. Pressure Gage: Manufacturer installed on one copper-tube extension.
- F. Zone Valve Boxes: Formed steel with anchors for recessed mounting, holes with grommets in box sides for tubing extension protection, and of size for single or multiple valves with pressure gages and in sizes required to permit manual operation of valves.
 - 1. Interior Finish: Factory-applied white enamel.
 - 2. Cover Plate: Aluminum or extruded-anodized aluminum with frangible or removable windows
 - 3. Valve-Box Windows: Clear or tinted transparent plastic with labeling that includes rooms served, according to NFPA 99.
- G. Safety Valves: Bronze-body, ASME-construction, poppet, pressure-relief type with settings to match system requirements.
- H. Pressure Regulators: Bronze body and trim; spring-loaded, diaphragm-operated relieving type; manual pressure-setting adjustment; rated for 250-psig minimum inlet pressure; and capable of controlling delivered air pressure within 0.5 psig for each 10-psig inlet pressure.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

I. Automatic Drain Valves: Stainless-steel body and internal parts, rated for 200-psig minimum working pressure, capable of automatic discharge of collected condensate. Include mounting bracket where wall mounting is indicated.

2.4 MEDICAL COMPRESSED-AIR SERVICE CONNECTIONS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - BeaconMedaes.
- B. Connection Devices: For specific medical compressed-air pressure and service listed. Include roughing-in assemblies, finishing assemblies, and cover plates. Individual cover plates are not required if service connection is in multiple unit or assembly with cover plate. Furnish recessed-type units made for concealed piping unless otherwise indicated.
 - 1. Roughing-in Assembly:
 - a. Steel outlet box for recessed mounting and concealed piping.
 - b. Brass-body outlet block with secondary check valve that will prevent gas flow when primary valve is removed.
 - c. Double seals that will prevent air leakage.
 - d. ASTM B 819, NPS 3/8 copper outlet tube brazed to valve with service marking and tube-end dust cap.
 - 2. Finishing Assembly:
 - a. Brass housing with primary check valve.
 - b. Double seals that will prevent air leakage.
 - c. Cover plate with gas-service label.
 - 3. Quick-Coupler Service Connections: Pressure outlet with noninterchangeable keyed indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment, and with positive-locking ring that retains equipment stem in valve during use.
 - 4. D.I.S.S. Service Connections: Pressure outlets, complying with CGA V-5, with threaded indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment.
 - a. Medical Air Service Connections: CGA V-5, D.I.S.S. No. 1160.
 - b. Instrument Air Service Connections: CGA V-5, D.I.S.S. No. 1160.
 - 5. Cover Plates: One piece, stainless steel, with NAAMM AMP 503, No. 4 finish or anodized aluminum and permanent, color-coded, identifying label matching corresponding service.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.5 MEDICAL COMPRESSED-AIR MANIFOLDS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - BeaconMedaes.
- B. General Requirements for Medical Compressed-Air Manifolds: Comply with NFPA 99, Ch. 5, "Manifolds for Gas Cylinders without Reserve Supply."
- C. Central Control Panel Unit: Weatherproof cabinet, supply and delivery pressure gages, electrical alarm system connections and transformer, indicator lights or devices, manifold connection, pressure changeover switch, line-pressure regulator, shutoff valves, and safety valve.
- D. Manifold and Headers: Duplex, nonferrous-metal header for number of cylinders indicated, divided into two equal banks. Units include design for 2000-psig minimum inlet pressure. Include cylinder bank headers with inlet (pigtail) connections complying with CGA V-1, individual inlet check valves, shutoff valve, pressure regulator, check valve, and pressure gage.
- E. Compressed-Air Cylinders: Will be furnished by Owner.
- F. Operation: Automatic, pressure-switch-activated changeover from one cylinder bank to the other when first bank becomes exhausted, without line-pressure fluctuation or resetting of regulators and without supply interruption by shutoff of either cylinder bank header.
- G. Mounting: Wall with mounting brackets for manifold control cabinet and headers/Floor with support legs for manifold control cabinet.
- H. Label manifold control unit with permanent label identifying compressed air and system operating pressure.
- I. Medical Air Manifolds: For number of cylinders and capacity at 55-psig line pressure.

2.6 MEDICAL COMPRESSED-AIR-PIPING ALARM SYSTEMS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. BeaconMedaes.
- B. Components: Designed for continuous service and to operate on power supplied from 120-V ac power source to alarm panels and with connections for low-voltage wiring to remote sensing devices. Include step-down transformers if required.
- C. Dew Point Monitors: Continuous line monitoring, having panel with gage or digital display, pipeline sensing element, electrical connections for alarm system, factory- or field-installed valved bypass, and visual and cancelable audio signal for dryer site and master alarm panels. Alarm signals when pressure dew point rises above 39 deg F at 55 psig.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

- D. Pressure Switches or Transducer Sensors: Continuous line monitoring with electrical connections for alarm system.
 - 1. Low-Pressure Operating Range: 0- to 100-psig.
 - 2. High-Pressure Operating Range: Up to 250-psig.
- E. Carbon Monoxide Monitors: Panel with gage or digital display, pipeline sensing element, electrical connections for alarm system, and factory- or field-installed valved bypass. Alarm signals when carbon monoxide level rises above 10 ppm.

2.7 FLEXIBLE PIPE CONNECTORS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Flex-Hose Co., Inc.
 - 2. Flexicraft Industries.
 - 3. Hyspan Precision Products, Inc.
 - 4. Metraflex, Inc.
 - 5. Unaflex.
 - Universal Metal Hose; a Hyspan Co.
- B. Description: Corrugated-bronze tubing with bronze wire-braid covering and ends brazed to inner tubing.
 - 1. Working-Pressure Rating: 200 psig minimum.
 - 2. End Connections: Threaded copper pipe or plain-end copper tube.

2.8 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.

2.9 ESCUTCHEONS

- A. General Requirements for Escutcheons: Manufactured wall and ceiling escutcheons and floor plates, with ID to closely fit around pipe and tube and OD that completely covers opening.
- B. One-Piece, Deep-Pattern Escutcheons: Deep-drawn, box-shaped brass with polished chrome-plated finish.
- C. One-Piece, Cast-Brass Escutcheons: With set screw.
 - Finish: Polished chrome-plated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Split-Casting, Cast-Brass Escutcheons: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated.
- E. One-Piece, Stamped-Steel Escutcheons: With set screw or spring clips and chrome-plated finish.
- F. Split-Plate, Stamped-Steel Escutcheons: With concealed hinge, set screw or spring clips, and chrome-plated finish.
- G. One-Piece, Floor-Plate Escutcheons: Cast iron.
- H. Split-Casting, Floor-Plate Escutcheons: Cast brass with concealed hinge and set screw.

2.10 GROUT

- A. Description: ASTM C 1107, Grade B, nonshrink and nonmetallic, dry hydraulic-cement grout.
 - 1. Characteristics: Post-hardening, volume adjusting, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.
 - 3. Packaging: Premixed and factory packaged.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Cleaning of Medical Gas Tubing: If manufacturer-cleaned and -capped fittings or tubing are not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction perform the following procedures:
 - Clean medical gas tube and fittings, valves, gages, and other components of oil, grease, and other readily oxidizable materials as required for oxygen service according to CGA G-4.1, "Cleaning Equipment for Oxygen Service."
 - 2. Wash medical gas tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb of chemical to 3 gal. of water.
 - a. Scrub to ensure complete cleaning.
 - b. Rinse with clean, hot water to remove cleaning solution.

3.2 PIPING APPLICATIONS

- A. Connect new tubing to existing tubing with memory-metal couplings.
- B. Medical Air Piping: Use Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Dental Air Piping: Use Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.
- D. Medical Laboratory Air Piping: Use Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.
- E. Drain Piping: Use one of the following piping materials:
 - 1. Copper water tube, cast- or wrought-copper fittings, and soldered joints.

3.3 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of compressed-air piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, air-compressor sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Comply with ASSE Standard #6010 for installation of compressed-air piping.
- C. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal and coordinate with other services occupying that space.
- F. Install piping adjacent to equipment and specialties to allow service and maintenance.
- G. Install air and drain piping with 1 percent slope downward in direction of flow.
- H. Install nipples, unions, special fittings, and valves with pressure ratings same as or higher than system pressure rating used in applications below unless otherwise indicated.
- I. Install eccentric reducers, if available, where compressed-air piping is reduced in direction of flow, with bottoms of both pipes and reducer fitting flush.
- J. Install branch connections to compressed-air mains from top of main. Provide drain leg and drain trap at end of each main and branch and at low points.
- K. Install thermometer and pressure gage on discharge piping from each air compressor and on each receiver. Comply with requirements in Division 22 Section "Meters and Gages for Plumbing Piping."
- L. Install piping to permit valve servicing.
- M. Install piping free of sags and bends.
- N. Install fittings for changes in direction and branch connections.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- O. Install medical compressed-air piping to medical compressed-air service connections specified in this Section, to medical compressed-air service connections in equipment specified in Division 22 Section "Gas Piping for Laboratory and Healthcare Facilities," and to equipment specified in other Sections requiring medical compressed-air service.
- P. Install seismic restraints on compressed-air piping. Seismic-restraint devices are specified in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- Q. Install compressed-air service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.
- R. Connect compressed-air piping to air compressors and to compressed-air outlets and equipment requiring compressed-air service.
- S. Install unions in copper compressed-air tubing adjacent to each valve and at final connection to each piece of equipment, machine, and specialty.

3.4 VALVE INSTALLATION

- A. Install shutoff valve at each connection to and from compressed-air equipment and specialties.
- B. Install check valves to maintain correct direction of compressed-air flow from compressed-air equipment.
- C. Install valve boxes recessed in wall and anchored to substrate. Single boxes may be used for multiple valves that serve same area or function.
- D. Install zone valves and gages in valve boxes. Rotate valves to angle that prevents closure of cover when valve is in closed position.
- E. Install safety valves on compressed-air receivers where required by NFPA 99 and where recommended by specialty manufacturers.
- F. Install pressure regulators on compressed-air piping where reduced pressure is required.
- G. Install automatic drain valves on equipment, specialties, and piping with drain connection. Run drain piping to floor drain so contents spill over or into it.
- H. Install flexible pipe connectors in discharge piping of each air compressor.

3.5 JOINT CONSTRUCTION

- A. Ream ends of PVC pipes and remove burrs.
- B. Remove scale, slag, dirt, and debris from outside of cleaned tubing and fittings before assembly.
- C. Threaded Joints: Apply appropriate tape to external pipe threads.

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook," "Brazed Joints" Chapter. Continuously purge joint with oil-free dry nitrogen during brazing.
- E. Soldered Joints: Apply ASTM B 813, water-flushable flux to tube end. Join copper tube and fittings according to ASTM B 828.
- F. Pressure-Sealed Joints: Join copper tube and press-type fittings with tools recommended by fitting manufacturer.
- G. Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of memory-metal coupling joints.
- H. Solvent-Cemented Joints: Clean and dry joining surfaces. Join PVC pipe and fittings according to the following:
 - 1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
 - Apply primer and join according to ASME B31.9 for solvent-cemented joints, and ASTM D 2672.

3.6 SLEEVE INSTALLATION

- A. Sleeves are not required for core-drilled holes.
- B. Permanent sleeves are not required for holes formed by removable PE sleeves.
- C. Install sleeves for pipes passing through concrete and masonry walls and concrete floor and roof slabs using galvanized-steel pipe/stack sleeve fittings.
 - 1. Wall Penetrations: Cut sleeves to length for mounting flush with both surfaces.
 - 2. Floor Penetrations: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
- D. Install sleeves in new walls and slabs as new walls and slabs are constructed.
- E. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Use the following sleeve materials:
 - 1. Steel Pipe Sleeves: For pipes smaller than NPS 6.
 - 2. Steel Sheet Sleeves: For pipes NPS 6 and larger penetrating gypsum board partitions.
 - 3. Stack Sleeve Fittings: For pipes penetrating floors with membrane waterproofing. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level. Comply with requirements in Division 07 Section "Sheet Metal Flashing and Trim" for flashing.
 - a. Seal space outside of sleeve fittings with grout.
- F. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping."

3.7 ESCUTCHEON INSTALLATION

- A. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. New Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One piece, deep pattern.
 - b. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
 - c. Bare Piping at Ceiling Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
 - d. Bare Piping in Unfinished Service Spaces: One piece, cast brass with rough-brass finish, stamped steel with set screw or spring clips.
 - e. Bare Piping in Equipment Rooms: One piece, cast brass stamped steel with set screw or spring clips.
 - f. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece floor plate.

2. Existing Piping:

- a. Chrome-Plated Piping: Split casting, cast brass with chrome-plated finish.
- b. Insulated Piping: Split plate, stamped steel with concealed hinge and spring clips.
- c. Bare Piping at Wall and Floor Penetrations in Finished Spaces: Split casting, cast brass with chrome-plated finish.
- d. Bare Piping at Ceiling Penetrations in Finished Spaces: Split casting, cast brass with chrome-plated finish.
- e. Bare Piping in Unfinished Service Spaces: Split casting, cast brass with roughbrass finish/plate, stamped steel with concealed hinge and set screw or spring clips.
- f. Bare Piping in Equipment Rooms: Split casting, cast brass/plate, stamped steel with set screw or spring clips.
- g. Bare Piping at Floor Penetrations in Equipment Rooms: Split-casting floor plate.

3.8 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.
- B. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support devices.
- C. Vertical Piping: MSS Type 8 or 42, clamps.
- D. Individual, Straight, Horizontal Piping Runs:
 - 1. 100 Feet and Less: MSS Type 1, adjustable, steel, clevis hangers.
 - 2. Longer Than 100 Feet: MSS Type 43, adjustable, roller hangers.
- E. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- F. Base of Vertical Piping: MSS Type 52, spring hangers.
- G. Support horizontal piping within 12 inches of each fitting and coupling.
- H. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- I. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 1/4: 60 inches with 3/8-inch rod.
 - 2. NPS 3/8 and NPS 1/2: 72 inches with 3/8-inch rod.
 - 3. NPS 3/4: 84 inches with 3/8-inch rod.
 - 4. NPS 1: 96 inches with 3/8-inch rod.
 - 5. NPS 1-1/4: 108 inches with 3/8-inch rod.
 - 6. NPS 1-1/2: 10 feet with 3/8-inch rod.
 - 7. NPS 2: 11 feet with 3/8-inch rod.
 - 8. NPS 2-1/2: 13 feet with 1/2-inch rod.
 - NPS 3: 14 feet with 1/2-inch rod.
 - 10. NPS 3-1/2: 15 feet with 1/2-inch rod.
 - 11. NPS 4: 16 feet with 1/2-inch rod.
 - 12. NPS 5: 18 feet with 1/2-inch rod.
 - 13. NPS 6: 20 feet with 5/8-inch rod.
 - 14. NPS 8: 23 feet with 3/4-inch rod.
- J. Install supports for vertical copper tubing every 10 feet.

3.9 LABELING AND IDENTIFICATION

- A. Install identifying labels and devices for nonmedical laboratory compressed-air piping, valves, and specialties. Comply with requirements in Division 22 Section "Identification for Plumbing Piping and Equipment."
- B. Install identifying labels and devices for medical compressed-air piping systems according to NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:
 - 1. Medical Air: Black letters on yellow background.
 - 2. Dental Air: Black letters on yellow-and-white diagonal stripe background.
 - 3. Medical Laboratory Air: Black letters on yellow-and-white checkerboard background.

3.10 FIELD QUALITY CONTROL FOR MEDICAL COMPRESSED-AIR PIPING IN HEALTHCARE FACILITIES

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections of medical compressed-air piping in healthcare facilities and prepare test reports.
- B. Perform tests and inspections of medical compressed-air piping systems in healthcare facilities and prepare test reports.

C. Tests and Inspections:

- 1. Medical Compressed-Air Testing Coordination: Perform tests, inspections, verifications, and certification of medical compressed-air piping systems concurrently with tests, inspections, and certification of medical vacuum piping and medical gas piping systems.
- Preparation: Perform the following Installer tests according to requirements in NFPA 99 and ASSE Standard #6010:
 - a. Initial blowdown.
 - b. Initial pressure test.
 - c. Cross-connection test.
 - d. Piping purge test.
 - e. Standing pressure test for positive-pressure medical compressed-air piping.
 - f. Repair leaks and retest until no leaks exist.
- 3. System Verification: Comply with requirements in NFPA 99, ASSE Standard #6020, and ASSE Standard #6030 for verification of medical compressed-air piping systems and perform the following tests and inspections:
 - a. Standing pressure test.
 - b. Individual-pressurization or pressure-differential cross-connection test.
 - c. Valve test.
 - d. Master and area alarm tests.
 - e. Piping purge test.
 - f. Piping particulate test.
 - g. Piping purity test.
 - h. Final tie-in test.
 - i. Operational pressure test.
 - j. Medical air purity test.
 - k. Verify correct labeling of equipment and components.
- 4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed and certify report results. Include the following:
 - a. Inspections performed.
 - b. Procedures, materials, and gases used.
 - c. Test methods used.
 - d. Results of tests.
- D. Remove and replace components that do not pass tests and inspections and retest as specified above.

3.11 DEMONSTRATION

A. Engage factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain medical compressed-air alarm systems. Refer to Division 01 Section "Demonstration and Training."

END OF SECTION 226113



SECTION 226213 - VACUUM PIPING FOR LABORATORY AND HEALTHCARE FACILITIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Medical surgical vacuum piping and specialties, designated "medical vacuum" operating at 20 inches mercury.
 - 2. Waste anesthetic gas disposal piping and specialties, designated "WAGD evacuation" operating at 15 inches mercury.
- B. Related Sections include the following:

1.3 DEFINITIONS

- A. D.I.S.S.: Diameter-index safety system.
- B. HVE: High-volume (oral) evacuation.
- C. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control, signaling power-limited circuits.
- D. WAGD: Waste anesthetic gas disposal.
- E. Medical vacuum piping systems include medical vacuum, WAGD evacuation, dental vacuum and medical laboratory vacuum piping systems.

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Vacuum pipes, tubes and fittings.
 - 2. Vacuum valves and valve boxes.
 - 3. Medical vacuum service connections and vacuum-bottle brackets.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Piping Material Certification: Signed by Installer certifying that medical vacuum piping materials comply with NFPA 99 requirements.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Qualification Data: For Installer.
- E. Brazing certificates.
- F. Field quality-control test reports.
- G. Operation and Maintenance Data: For vacuum piping specialties to include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

A. Installer Qualifications:

- 1. Medical Vacuum Piping Systems for Healthcare Facilities: Qualify installers according to ASSE Standard #6010.
- 2. Pressure-Seal Joining Procedure for Copper Tubing: Qualify operators according to training provided by Viega; Plumbing and Heating Systems.
- B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the vacuum piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.
 - Qualify testing personnel according to ASSE Standard #6020 for inspectors and ASSE Standard #6030 for verifiers.
- C. Source Limitations: Obtain vacuum service connections of same type and from same manufacture as service connections provided for in Division 22 Section "Gas Piping for Laboratory and Healthcare Facilities".
- D. Brazing: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications," or AWS B2.2, "Standard for Brazing Procedure and Performance Qualification".
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- F. Comply with ASME B31.9, "Building Services Piping", for vacuum piping in laboratory facilities.
- G. NFPA Compliance: Comply with NFPA 99, "Health Care Facilities", for medical vacuum system materials and installation in healthcare facilities.

1.6 PROJECT CONDITIONS

- A. Interruption of Existing Laboratory and Medical Vacuum Service(s): Do not interrupt laboratory or medical vacuum service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
 - 1. Notify Architect no fewer than seven days in advance of proposed interruption of laboratory and medical vacuum service(s).
 - 2. Do not proceed with interruption of laboratory and medical vacuum service(s) without Architect's written permission.

1.7 COORDINATION

A. Coordinate medical vacuum service connections with other service connections.

PART 2 - PRODUCTS

2.1 PIPES, TUBES, AND FITTINGS

- A. Copper Medical Gas Tube: ASTM B 819, Type L, seamless, drawn temper that has been manufacturer cleaned, purged, and sealed for medical gas service or according to CGA G-4.1 for oxygen service. Include standard color marking "OXY", "MED", "OXY/MED", "OXY/ACR", or "ACR/MED" in blue.
 - 1. General Requirements for Copper Fittings: Manufacturer cleaned, purged, and bagged for oxygen service according to CGA G-4.1.
 - 2. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type or MSS SP-73, with dimensions for brazed joints.
 - 3. Copper Unions: ASME B16.22 or MSS SP-123, wrought copper or cast-copper alloy.
 - 4. Press-Type Fittings:
 - a. NPS 2 and Smaller: Wrought-copper fitting with EPDM O-ring seal in each end.
 - b. NPS 2-1/2 to NPS 4: Bronze fitting with stainless-steel grip ring and EPDM O-ring seal in each end.
- B. Memory-Metal Couplings: Cryogenic compression fitting made of ASTM F 2063, nickel-titanium, shape-memory alloy, and that has been manufacturer cleaned, purged, and sealed for oxygen service according to CGA G-4.1.

2.2 JOINING MATERIALS

- A. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- B. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for general-duty brazing unless otherwise indicated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Threaded-Joint Tape: PTFE.
- D. Pipe-Flange Gasket Materials: ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness, full-face type.
- E. Flange Bolts and Nuts: ASME B18.2.1, carbon steel.

2.3 VALVES

- A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged according to CGA G-4.1 for oxygen service.
 - 1. Exception: Factory cleaning and bagging are not required for valves for WAGD service.
- B. Copper-Alloy Ball Valves: MSS SP-110, 3-piece body, brass or bronze.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. BeaconMedaes.
 - 2. Pressure Rating: 300 psig minimum.
 - 3. Ball: Full-port, chrome-plated brass.
 - 4. Seats: PTFE or TFE.
 - 5. Handle: Lever type with locking device.
 - 6. Stem: Blowout proof with PTFE or TFE seal.
 - 7. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
- C. Bronze Check Valves: In-line pattern.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BeaconMedaes.
 - 2. Pressure Rating: 300 psig minimum.
 - 3. Operation: Spring loaded.
 - 4. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
- D. Zone Valves: MSS SP-110, 3-piece-body, brass or bronze ball valve with gage.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by the following:
 - BeaconMedaes.
 - 2. Pressure Rating: 300 psig minimum.
 - 3. Ball: Full-port, chrome-plated brass.
 - 4. Seats: PTFE or TFE.
 - 5. Handle: Lever type with locking device.
 - 6. Stem: Blowout proof with PTFE or TFE seal.

- 7. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
- 8. Vacuum Gage: Manufacturer installed on one copper-tube extension.
- E. Zone Valve Boxes: Formed steel with anchors for recessed mounting, holes with grommets in box sides for tubing extension protection, and of size for single or multiple valves with vacuum gages and in sizes required to permit manual operation of valves.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by the following:
 - BeaconMedaes.
 - 2. Interior Finish: Factory-applied white enamel.
 - Cover Plate: Aluminum or extruded-anodized aluminum with frangible or removable windows.
 - 4. Valve-Box Windows: Clear or tinted transparent plastic with labeling that includes rooms served, according to NFPA 99.
- F. Safety Valves: Bronze-body, ASME-construction, pressure-relief type with settings to match system requirements.
- G. Automatic Drain Valves: Stainless-steel body and internal parts, rated for 200-psig minimum working pressure, capable of automatic discharge of collected condensate. Include mounting bracket where wall mounting is indicated.

2.4 MEDICAL VACUUM SERVICE CONNECTIONS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by the following:
 - 1. BeaconMedaes Gemini III
- B. Connection Devices: For specific medical vacuum service listed. Include roughing-in assemblies, finishing assemblies, and cover plates. Individual cover plates are not required if service connection is in multiple unit or assembly with cover plate. Furnish recessed-type units made for concealed piping unless otherwise indicated.
 - 1. Roughing-in Assembly:
 - a. Steel outlet box for recessed mounting and concealed piping.
 - b. Brass-body inlet block.
 - c. Seals that will prevent vacuum leakage.
 - d. ASTM B 819, NPS 3/8 copper outlet tube brazed to valve with service marking and tube-end dust cap.
 - 2. Finishing Assembly:
 - a. Brass housing with primary check valve.
 - b. Seals that will prevent vacuum leakage.
 - c. Cover plate with gas-service label.

- Quick-Coupler Service Connections: Suction inlets for medical vacuum and WAGD
 evacuation service outlets with noninterchangeable keyed indexing to prevent
 interchange between services, constructed to permit one-handed connection and
 removal of equipment, and with positive-locking ring that retains equipment stem in valve
 during use.
- 4. D.I.S.S. Service Connections: Suction inlets, complying with CGA V-5, with threaded indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment.
 - a. Medical Vacuum Service Connections: CGA V-5, D.I.S.S. No. 1220.
 - b. WAGD Evacuation Service Connections: CGA V-5, D.I.S.S. No. 2220.
- 5. Vacuum Bottle Brackets: One piece, with pattern and finish matching corresponding service cover plate.
- 6. Cover Plates: One piece, anodized aluminum and permanent, color-coded, identifying label matching corresponding service.

2.5 MEDICAL VACUUM PIPING ALARM SYSTEMS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. BeaconMedaes.
- B. Components: Designed for continuous service and to operate on power supplied from 120-V ac power source to alarm panels and with connections for low-voltage wiring to remote sensing devices. Include step-down transformers if required.
- C. Vacuum Switches or Transducer Sensors: Continuous line monitoring with electrical connections for alarm system.
 - 1. Vacuum Operating Range: 0- to 30-in. Hg.

2.6 FLEXIBLE PIPE CONNECTORS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Flex-Hose Co., Inc.
 - 2. Flexicraft Industries.
 - 3. Hyspan Precision Products, Inc.
 - 4. Metraflex, Inc.
 - 5. Universal Metal Hose; a Hyspan Co.
- B. Description: Corrugated-bronze tubing with bronze wire-braid covering and ends brazed to inner tubing.
 - 1. Working-Pressure Rating: 200 psig minimum.
 - 2. End Connections: Threaded copper pipe or plain-end copper tube.

2.7 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.

2.8 ESCUTCHEONS

- A. General Requirements for Escutcheons: Manufactured wall and ceiling escutcheons and floor plates, with ID to closely fit around pipe and tube and OD that completely covers opening.
- B. One-Piece, Deep-Pattern Escutcheons: Deep-drawn, box-shaped brass with polished chrome-plated finish.
- C. One-Piece, Cast-Brass Escutcheons: With set screw.
 - 1. Finish: Polished chrome-plated and rough brass.
- D. Split-Casting, Cast-Brass Escutcheons: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated and rough brass.
- E. One-Piece, Stamped-Steel Escutcheons: With set screw or spring clips and chrome-plated finish.
- F. Split-Plate, Stamped-Steel Escutcheons: With concealed hinge, set screw or spring clips, and chrome-plated finish.
- G. One-Piece, Floor-Plate Escutcheons: Cast iron.
- H. Split-Casting, Floor-Plate Escutcheons: Cast brass with concealed hinge and set screw.

2.9 GROUT

- A. Description: ASTM C 1107, Grade B, nonshrink and nonmetallic, dry hydraulic-cement grout.
 - 1. Characteristics: Post-hardening, volume adjusting, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.
 - 3. Packaging: Premixed and factory packaged.

2.10 NITROGEN

A. Description: Comply with USP 28 - NF 23 for oil-free dry nitrogen.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Cleaning of Medical Gas Tubing: If manufacturer-cleaned and -capped fittings or tubing are not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction perform the following procedures:
 - 1. Clean medical gas tube and fittings, valves, gages, and other components of oil, grease, and other readily oxidizable materials as required for oxygen service according to CGA G-4.1, "Cleaning Equipment for Oxygen Service".
 - Wash medical gas tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb of chemical to 3 gal. of water.
 - a. Scrub to ensure complete cleaning.
 - b. Rinse with clean, hot water to remove cleaning solution.

3.2 PIPING APPLICATIONS

- A. Connect new copper tubing to existing tubing with memory-metal couplings.
- B. Medical Vacuum Piping: Use one of the following piping materials for each size range:
 - 1. NPS 4 and Smaller: Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.
 - NPS 4 and Smaller: Type L, copper medical gas tube; press-type fittings; and pressuresealed joints.
 - 3. NPS 5 to NPS 8: Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.
- C. WAGD Evacuation Piping: Use one of the following piping materials for each size range:
 - 1. NPS 4 and Smaller: Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.
 - 2. NPS 4 and Smaller: Type L, copper medical gas tube; press-type fittings; and pressure-sealed joints.
 - 3. NPS 5 to NPS 8: Type L, copper medical gas tube; wrought-copper fittings; and brazed ioints.
- D. Drain Piping: Use one of the following piping materials:
 - 1. Copper water tube, cast- or wrought-copper fittings, and soldered joints.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.3 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of vacuum piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, air-compressor sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Comply with ASSE Standard #6010 for installation of vacuum piping.
- C. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal and coordinate with other services occupying that space.
- F. Install piping adjacent to equipment and specialties to allow service and maintenance.
- G. Install vacuum and drain piping with 1 percent slope downward in direction of flow.
- H. Install nipples, unions, and special fittings, and valves with pressure ratings same as or higher than piping pressure rating used in applications below unless otherwise indicated.
- I. Install eccentric reducers, if available, where vacuum piping is reduced in direction of flow, with bottoms of both pipes and reducer fitting flush.
- J. Provide drain leg and drain trap at end of each main and branch and at low points.
- K. Install thermometer and vacuum gage on inlet piping to each vacuum producer and on each receiver and separator. Comply with requirements in Division 22 Section "Meters and Gages for Plumbing Piping".
- L. Install piping to permit valve servicing.
- M. Install piping free of sags and bends.
- N. Install fittings for changes in direction and for branch connections. Extruded-tee branch outlets in copper tubing may be made where specified.
- O. Install medical vacuum piping to medical vacuum service connections specified in this Section and to equipment specified in other Sections requiring medical vacuum service.
- P. Install medical vacuum service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.
- Q. Install medical vacuum bottle bracket adjacent to each wall-mounted medical vacuum service connection suction inlet.
- R. Connect vacuum piping to vacuum producers and to equipment requiring vacuum service.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

S. Install unions, in copper vacuum tubing adjacent to each valve and at final connection to each piece of equipment, machine, and specialty.

3.4 VALVE APPLICATIONS

A. Valves for Copper Vacuum Tubing: Use copper alloy ball and bronze check types.

3.5 VALVE INSTALLATION

- A. Install shutoff valve at each connection to and from vacuum equipment and specialties.
- B. Install check valves to maintain correct direction of vacuum flow to vacuum-producing equipment.
- C. Install valve boxes recessed in wall and anchored to substrate. Single boxes may be used for multiple valves that serve same area or function.
- D. Install zone valves and gages in valve boxes. Rotate valves to angle that prevents closure of cover when valve is in closed position.
- E. Install safety valves on vacuum receivers, where required by NFPA 99, and where recommended by specialty manufacturers.
- F. Install automatic drain valves on equipment, specialties, and piping with drain connection. Run drain piping to floor drain, so contents spill over or into it.
- G. Install flexible pipe connectors in suction inlet piping to each vacuum producer.

3.6 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs.
- B. Remove scale, slag, dirt, and debris from outside of cleaned tubing and fittings before assembly.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Threaded Joints: Apply appropriate tape to external pipe threads.
- E. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook", "Brazed Joints" Chapter. Continuously purge joint with oil-free dry nitrogen during brazing.
- F. Soldered Joints: Apply ASTM B 813, water-flushable flux to tube end. Join copper tube and fittings according to ASTM B 828.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

G. Flanged Joints:

- 1. Copper Tubing: Install flange on copper tubes. Use pipe-flange gasket between flanges. Join flanges with gasket and bolts according to ASME B31.9 for bolting procedure.
- 2. PVC Piping: Install PVC flange on PVC pipes. Use pipe-flange gasket between flanges. Join flanges with gasket and bolts according to ASME B31.9 for bolting procedure.
- H. Pressure-Sealed Joints: Join copper tube and copper and copper-alloy fittings with tools recommended by fitting manufacturer.
- I. Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of memory-metal coupling joints.

3.7 MEDICAL VACUUM PIPING ALARM SYSTEM INSTALLATION

A. Install medical vacuum piping system alarm system components in locations required by and according to NFPA 99.

3.8 SLEEVE INSTALLATION

- A. Sleeves are not required for core-drilled holes.
- B. Permanent sleeves are not required for holes formed by removable PE sleeves.
- C. Install sleeves for pipes passing through concrete and masonry walls and concrete floor and roof slabs using galvanized-steel pipe, stack sleeve fittings.
 - 1. Wall Penetrations: Cut sleeves to length for mounting flush with both surfaces.
 - 2. Floor Penetrations: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
- D. Install sleeves in new walls and slabs as new walls and slabs are constructed.
- E. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Use the following sleeve materials:
 - 1. Steel Pipe Sleeves: For pipes smaller than NPS 6.
 - 2. Steel Sheet Sleeves: For pipes NPS 6 and larger, penetrating gypsum board partitions.
 - 3. Stack Sleeve Fittings: For pipes penetrating floors with membrane waterproofing. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level. Comply with requirements in Division 07 Section "Sheet Metal Flashing and Trim" for flashing.
 - a. Seal space outside of sleeve fittings with grout.
- F. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping".

3.9 ESCUTCHEON INSTALLATION

- A. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. New Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One piece, deep pattern.
 - b. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
 - c. Bare Piping at Ceiling Penetrations in Finished Spaces: One piece or split casting, cast brass with polished chrome-plated finish.
 - d. Bare Piping in Unfinished Service Spaces: One piece, cast brass with rough-brass finish stamped steel with set screw or spring clips.
 - e. Bare Piping in Equipment Rooms: One piece, cast brass/stamped steel with set screw or spring clips.
 - f. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece floor plate.

2. Existing Piping:

- a. Chrome-Plated Piping: Split casting, cast brass with chrome-plated finish.
- b. Insulated Piping: Split plate, stamped steel with concealed hinge and spring clips.
- c. Bare Piping at Wall and Floor Penetrations in Finished Spaces: Split casting, cast brass with chrome-plated finish.
- d. Bare Piping at Ceiling Penetrations in Finished Spaces: Split casting, cast brass with chrome-plated finish.
- e. Bare Piping in Unfinished Service Spaces: Split casting, cast brass with roughbrass finish/plate, stamped steel with concealed hinge and set screw or spring clips.
- f. Bare Piping in Equipment Rooms: Split casting, cast brass/plate, stamped steel with set screw or spring clips.
- g. Bare Piping at Floor Penetrations in Equipment Rooms: Split-casting floor plate.

3.10 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support devices.
- B. Vertical Piping: MSS Type 8 or 42 clamps.
- C. Individual, Straight, Horizontal Piping Runs:
 - 1. 100 Feet and Less: MSS Type 1, adjustable, steel, clevis hangers.
 - 2. Longer Than 100 Feet: MSS Type 43, adjustable, roller hangers.
- D. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.
- E. Base of Vertical Piping: MSS Type 52, spring hangers.
- F. Support horizontal piping within 12 inches of each fitting and coupling.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- G. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- H. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 1/4: 60 inches with 3/8-inch rod.
 - 2. NPS 3/8 and NPS 1/2: 72 inches with 3/8-inch rod.
 - 3. NPS 3/4: 84 inches with 3/8-inch rod.
 - 4. NPS 1: 96 inches with 3/8-inch rod.
 - 5. NPS 1-1/4: 108 inches with 3/8-inch rod.
 - 6. NPS 1-1/2: 10 feet with 3/8-inch rod.
 - 7. NPS 2: 11 feet with 3/8-inch rod.
 - 8. NPS 2-1/2: 13 feet with 1/2-inch rod.
 - 9. NPS 3: 14 feet with 1/2-inch rod.
 - 10. NPS 4: 16 feet with 1/2-inch rod.
 - 11. NPS 5: 18 feet with 1/2-inch rod.
 - 12. NPS 6: 20 feet with 5/8-inch rod.
 - 13. NPS 8: 23 feet with 3/4-inch rod.
- I. Install supports for vertical copper tubing every 10 feet.

3.11 LABELING AND IDENTIFICATION

- A. Install identifying labels and devices for laboratory vacuum piping, valves, and specialties. Comply with requirements in Division 22 Section "Identification for Plumbing Piping and Equipment".
- B. Install identifying labels and devices for medical vacuum piping systems according to NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:
 - 1. Medical Vacuum: Black letters on yellow background.
 - 2. WAGD: White letters on violet background.
 - 3. Medical Laboratory Vacuum: Black boxed letters on white-and-black checkerboard background.

3.12 FIELD QUALITY CONTROL FOR LABORATORY FACILITY NONMEDICAL VACUUM PIPING

- A. Testing Agency: Engage qualified testing agency to perform field tests and inspections of vacuum piping in nonmedical laboratory facilities.
- B. Perform tests and inspections of vacuum piping in nonmedical laboratory facilities.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

C. Tests and Inspections:

- 1. Piping Leak Tests for Vacuum Piping: Test new and modified parts of existing piping. Cap and fill vacuum piping with oil-free, dry nitrogen. Isolate test source and let stand for four hours to equalize temperature. Refill system, if required, to test pressure; hold for two hours with no drop in pressure.
 - a. Test Pressure for Copper Tubing: 100 psig.
- 2. Repair leaks and retest until no leaks exist.
- 3. Inspect filters for proper operation.
- D. Prepare test reports.

3.13 FIELD QUALITY CONTROL FOR HEALTHCARE FACILITY MEDICAL VACUUM PIPING

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections of medical vacuum piping systems in healthcare facilities and prepare test reports.
- B. Perform tests and inspections of medical vacuum piping systems in healthcare facilities and prepare test reports.
- C. Tests and Inspections:
 - 1. Medical Vacuum Testing Coordination: Perform tests, inspections, verifications, and certification of medical vacuum piping systems concurrently with tests, inspections, and certification of medical compressed-air piping and medical gas piping systems.
 - Perform the following Installer tests according to requirements in NFPA 99 and ASSE Standard #6010:
 - a. Initial blow down.
 - b. Initial pressure test.
 - c. Cross-connection test.
 - d. Piping purge test.
 - e. Standing pressure test for vacuum systems.
 - f. Repair leaks and retest until no leaks exist.
 - 3. System Verification: Comply with requirements in NFPA 99, ASSE Standard #6020, and ASSE Standard #6030 for verification of medical vacuum piping systems and perform the following tests and inspections:
 - a. Standing pressure test.
 - b. Individual-pressurization or pressure-differential cross-connection test.
 - c. Valve test.
 - d. Master and area alarm tests.
 - e. Piping purge test.
 - f. Final tie-in test.
 - g. Operational vacuum test.
 - h. Verify correct labeling of equipment and components.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed and certify report results. Include the following:
 - a. Inspections performed.
 - b. Procedures, materials, and gases used.
 - c. Test methods used.
 - d. Results of tests.
- D. Remove and replace components that do not pass tests and inspections and retest as specified above.

END OF SECTION 226213

Project No.: CP242241 February 27, 2024



SECTION 226313 - GAS PIPING FOR LABORATORY AND HEALTHCARE FACILITIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Carbon dioxide piping and specialties designated "medical carbon dioxide" operating at 50 to 55 psig.
 - 2. Helium piping, designated "medical helium" operating at 50 to 55 psig.
 - 3. Nitrogen piping and specialties designated "medical nitrogen" operating at 160 to 185 psig.
 - 4. Nitrous oxide piping and specialties designated "medical nitrous oxide" operating at 50 to 55 psig.
 - 5. Oxygen piping and specialties designated "medical oxygen" operating at 50 to 55 psig.
 - 6. Other specialty gas piping and specialties as designated on drawings operating at 50 to 55 psig.

B. Owner-Furnished Material:

- 1. Medical gas manifolds.
- 2. Ceiling columns.
- 3. Bulk gas storage tanks.
- 4. Owner will furnish gases for medical gas concentration testing specified in this Section.
- C. Related Sections include the following:
 - 1. Division 22 Section "Compressed-Air Piping for Laboratory and Healthcare Facilities" for compressed-air piping systems for laboratory and healthcare facilities.
 - 2. Division 22 Section "Vacuum Piping for Laboratory and Healthcare Facilities" for vacuum piping systems for laboratory and healthcare facilities.

1.3 DEFINITIONS

- A. CR: Chlorosulfonated polyethylene synthetic rubber.
- B. D.I.S.S.: Diameter-index safety system.
- C. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control, signaling power-limited circuits.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Medical gas piping systems include nonflammable gas for healthcare facility patient care or for healthcare laboratory applications.
- E. Specialty Gas: Gas, other than medical gas, for nonmedical laboratory facility applications.

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Tubes and fittings.
 - 2. Valves and valve boxes.
 - 3. Medical gas service connections.
 - 4. Electrical service connections.
 - 5. Medical nitrogen pressure control panels.
 - 6. Gas manifolds.
 - 7. Medical gas alarm system components.
 - 8. Gas cylinder storage racks.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Piping Material Certification: Signed by Installer certifying that medical gas piping materials comply with NFPA 99 requirements.
- D. Qualification Data: For Installer.
- E. Brazing certificates.
- F. Certificates of Shop Inspection and Data Report for Bulk Gas Storage Tanks: As required by ASME Boiler and Pressure Vessel Code.
- G. Field quality-control test reports.
- H. Operation and Maintenance Data: For medical gas piping specialties to include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications:
 - 1. Medical Gas Piping Systems for Healthcare Facilities: Qualify installers according to ASSE Standard #6010 for installers.
- B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the medical gas piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
 - Qualify testing personnel according to ASSE Standard #6020 for inspectors and ASSE Standard #6030 for verifiers.

- C. Brazing: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications"; or AWS B2.2, "Standard for Brazing Procedure and Performance Qualification."
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- E. ASME Compliance: Fabricate and label bulk medical gas storage tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.

F. NFPA Compliance:

- 1. Comply with NFPA 50, "Bulk Oxygen Systems at Consumer Sites," for bulk oxygen storage tanks.
- 2. Comply with NFPA 99, "Health Care Facilities," for medical gas piping system materials and installation.
- G. CGA Compliance: Comply with CGA G-8.1, "Nitrous Oxide Systems at Consumer Sites," for bulk nitrous oxide storage tanks.

H. UL Compliance:

- 1. Comply with UL 498, "Attachment Plugs and Receptacles," for electrical service connections.
- 2. Comply with UL 544, "Medical and Dental Equipment," for medical gas specialties.

1.6 PROJECT CONDITIONS

- A. Interruption of Existing Medical Gas Service(s): Do not interrupt medical gas service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
 - 1. Notify Architect no fewer than seven days in advance of proposed interruption of medical gas service(s).
 - 2. Do not proceed with interruption of medical gas service(s) without Architect's written permission.

1.7 COORDINATION

- A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.
- B. Coordinate medical gas service connections with other service connections. Compressed-air service connections are specified in Division 22 Sections "Compressed-Air Piping for Laboratory and Healthcare Facilities" and "Vacuum Piping for Laboratory and Healthcare Facilities."

PART 2 - PRODUCTS

2.1 PIPES, TUBES, AND FITTINGS

- A. Copper Medical Gas Tube: ASTM B 819, Type L, seamless, drawn temper that has been manufacturer cleaned, purged, and sealed for medical gas service or according to CGA G-4.1 for oxygen service. Include standard color marking "OXY," "MED," "OXY/MED," "OXY/ACR," or "ACR/MED" in green for Type K tube and blue for Type L tube.
 - 1. General Requirements for Copper Fittings: Manufacturer cleaned, purged, and bagged for oxygen service according to CGA G-4.1.
 - 2. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type or MSS SP-73, with dimensions for brazed joints.
 - 3. Copper Unions: ASME B16.22 or MSS SP-123, wrought copper or cast-copper alloy.
 - 4. Press-Type Fittings:
 - a. NPS 2 and Smaller: Wrought-copper fitting with EPDM O-ring seal in each end.
 - b. NPS 2-1/2 to NPS 4: Bronze fitting with stainless-steel grip ring and EPDM O-ring seal in each end.
 - 5. Memory-Metal Couplings: Cryogenic compression fitting made of ASTM F 2063, nickel-titanium, shape-memory-alloy, and that has been manufacturer cleaned, purged, and sealed for oxygen service according to CGA G-4.1.

2.2 JOINING MATERIALS

- A. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys.
- B. Threaded-Joint Tape: PTFE.

2.3 VALVES

- A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged according to CGA G-4.1 for oxygen service.
- B. Ball Valves: MSS SP-110, 3-piece body, brass or bronze.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BeaconMedaes.
 - 2. Pressure Rating: 300 psig minimum.
 - 3. Ball: Full-port, chrome-plated brass.
 - 4. Seats: PTFE or TFE.
 - 5. Handle: Lever type with locking device.
 - 6. Stem: Blowout proof with PTFE or TFE seal.
 - 7. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Check Valves: In-line pattern, bronze.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - BeaconMedaes.
 - 2. Pressure Rating: 300 psig minimum.
 - 3. Operation: Spring loaded.
 - 4. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
- D. Zone Valves: MSS SP-110, 3-piece-body, brass or bronze ball valve with gage.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BeaconMedaes.
 - 2. Pressure Rating: 300 psig minimum.
 - 3. Ball: Full-port, chrome-plated brass.
 - 4. Seats: PTFE or TFE.
 - 5. Handle: Lever type with locking device.
 - 6. Stem: Blowout proof with PTFE or TFE seal.
 - 7. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.
 - 8. Pressure Gage: Manufacturer-installed on one copper-tube extension.
- E. Zone Valve Boxes: Formed steel with anchors for recessed mounting, holes with grommets in box sides for tubing extension protection, and of size for single or multiple valves with pressure gages and in sizes required to permit manual operation of valves.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Amico Corporation.
 - b. BeaconMedaes.
 - 2. Interior Finish: Factory-applied white enamel.
 - Cover Plate: Aluminum or extruded-anodized aluminum with frangible or removable windows.
 - 4. Valve-Box Windows: Clear or tinted transparent plastic with labeling that includes rooms served, according to NFPA 99.
- F. Safety Valves: Bronze-body, ASME-construction, poppet, pressure-relief type with settings to match system requirements.
- G. Pressure Regulators: Bronze body and trim; spring-loaded, diaphragm-operated, relieving type; manual pressure-setting adjustment; rated for 250-psig minimum inlet pressure; and capable of controlling delivered gas pressure within 0.5 psig for each 10-psig inlet pressure.

2.4 MEDICAL GAS PIPING ALARM SYSTEMS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - BeaconMedaes.
- B. Components: Designed for continuous service and to operate on power supplied from 120-V ac power source to alarm panels and with connections for low-voltage wiring to remote sensing devices. Include step-down transformers if required.
- C. Pressure Switches or Pressure Transducer Sensors: Continuous line monitoring with electrical connections for alarm system.
 - 1. Low-Pressure Operating Range: 0- to 100-psig.
 - 2. High-Pressure Operating Range: Up to 250-psig.

2.5 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.

2.6 ESCUTCHEONS

- A. General Requirements for Escutcheons: Manufactured wall and ceiling escutcheons and floor plates, with ID to closely fit around pipe and tube and OD that completely covers opening.
- B. One-Piece, Deep-Pattern Escutcheons: Deep-drawn, box-shaped brass with polished chrome-plated finish.
- C. One-Piece, Cast-Brass Escutcheons: With set screw.
 - 1. Finish: Polished chrome-plated and rough brass.
- D. Split-Casting, Cast-Brass Escutcheons: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated and rough brass.
- E. One-Piece, Stamped-Steel Escutcheons: With set screw or spring clips and chrome-plated finish.
- F. Split-Plate, Stamped-Steel Escutcheons: With concealed hinge, set screw or spring clips, and chrome-plated finish.
- G. One-Piece, Floor-Plate Escutcheons: Cast iron.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

H. Split-Casting, Floor-Plate Escutcheons: Cast brass with concealed hinge and set screw.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Cleaning of Medical Gas Tubing: If manufacturer-cleaned and -capped fittings or tubing are not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction, perform the following procedures:
 - 1. Clean medical gas tube and fittings, valves, gages, and other components of oil, grease, and other readily oxidizable materials as required for oxygen service according to CGA G-4.1, "Cleaning Equipment for Oxygen Service."
 - 2. Wash medical gas tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb of chemical to 3 gal. of water.
 - a. Scrub to ensure complete cleaning.
 - b. Rinse with clean, hot water to remove cleaning solution.

3.2 PIPING APPLICATIONS

A. Medical Gas Piping: Use Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.

3.3 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of gas piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, air-compressor sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- B. Comply with ASSE Standard #6010 for installation of medical gas piping.
- C. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal and coordinate with other services occupying that space.
- F. Install piping adjacent to equipment and specialties to allow service and maintenance.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- G. Install nipples, unions, and special fittings, and valves with pressure ratings same as or higher than system pressure rating used in applications below unless otherwise indicated.
- H. Install piping to permit valve servicing.
- I. Install piping free of sags and bends.
- J. Install fittings for changes in direction and branch connections.
- K. Install medical gas piping to medical gas service connections specified in this Section, to medical gas service connections in equipment specified in this Section, and to equipment specified in other Sections requiring medical gas service.
- L. Install medical gas service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.
- M. Connect gas piping to gas sources and to gas outlets and equipment requiring gas service.
- N. Install unions, in copper tubing adjacent to each valve and at final connection to each piece of equipment and specialty.

3.4 VALVE INSTALLATION

- A. Install shutoff valve at each connection to gas laboratory and healthcare equipment and specialties.
- B. Install check valves to maintain correct direction of gas flow from laboratory and healthcare gas supplies.
- C. Install valve boxes recessed in wall and anchored to substrate. Single boxes may be used for multiple valves that serve same area or function.
- D. Install zone valves and gages in valve boxes. Rotate valves to angle that prevents closure of cover when valve is in closed position.
- E. Install pressure regulators on gas piping where reduced pressure is required.
- F. Install emergency oxygen connection with pressure relief valve and full-size discharge piping to outside, with check valve downstream from pressure relief valve and with ball valve and check valve in supply main from bulk oxygen storage tank.

3.5 JOINT CONSTRUCTION

- A. Remove scale, slag, dirt, and debris from outside of cleaned tubing and fittings before assembly.
- B. Threaded Joints: Apply appropriate tape to external pipe threads.
- C. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook," "Brazed Joints" Chapter. Continuously purge joint with oil-free, dry nitrogen during brazing.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241 February 27, 2024

- D. Pressure-Sealed Joints: Join copper tube and press-type fittings with tools recommended by fitting manufacturer.
- E. Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of memory-metal coupling joints.

3.6 MEDICAL GAS PIPING ALARM SYSTEM INSTALLATION

A. Install medical gas alarm system components in locations required by and according to NFPA 99.

3.7 SLEEVE INSTALLATION

- A. Sleeves are not required for core-drilled holes.
- B. Permanent sleeves are not required for holes formed by removable PE sleeves.
- C. Install sleeves for pipes passing through concrete and masonry walls and concrete floor and roof slabs using galvanized-steel pipe, galvanized-steel sheet, stack sleeve fittings.
 - 1. Wall Penetrations: Cut sleeves to length for mounting flush with both surfaces.
 - 2. Floor Penetrations: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
- D. Install sleeves in new walls and slabs as new walls and slabs are constructed.
- E. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Use the following sleeve materials:
 - 1. Steel Pipe Sleeves: For pipes smaller than NPS 6.
 - 2. Steel Sheet Sleeves: For pipes NPS 6 and larger, penetrating gypsum board partitions.
 - 3. Stack Sleeve Fittings: For pipes penetrating floors with membrane waterproofing. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level. Comply with requirements in Division 07 Section "Sheet Metal Flashing and Trim" for flashing.
 - a. Seal space outside of sleeve fittings with grout.
- F. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping."

3.8 ESCUTCHEON INSTALLATION

- A. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. New Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One piece, deep pattern.
 - b. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One piece, cast brass with polished chrome-plated finish.
 - c. Bare Piping at Ceiling Penetrations in Finished Spaces: One piece or split casting, cast brass with polished chrome-plated finish.
 - d. Bare Piping in Unfinished Service Spaces: One piece, cast brass with rough-brass finish/stamped steel with set screw or spring clips.
 - e. Bare Piping in Equipment Rooms: One piece, cast brass/stamped steel with set screw or spring clips.
 - f. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece floor plate.

2. Existing Piping:

- a. Chrome-Plated Piping: Split casting, cast brass with chrome-plated finish.
- b. Insulated Piping: Split plate, stamped steel with concealed hinge and spring clips.
- c. Bare Piping at Wall and Floor Penetrations in Finished Spaces: Split casting, cast brass with chrome-plated finish.
- d. Bare Piping at Ceiling Penetrations in Finished Spaces: Split casting, cast brass with chrome-plated finish.
- e. Bare Piping in Unfinished Service Spaces: Split casting, cast brass with roughbrass finish/plate, stamped steel with concealed hinge and set screw or spring clips.
- f. Bare Piping in Equipment Rooms: Split casting, cast brass/plate, stamped steel with set screw or spring clips.
- g. Bare Piping at Floor Penetrations in Equipment Rooms: Split-casting floor plate.

3.9 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support devices.
- B. Vertical Piping: MSS Type 8 or 42, clamps.
- C. Individual, Straight, Horizontal Piping Runs:
 - 1. 100 Feet and Less: MSS Type 1, adjustable, steel, clevis hangers.
 - 2. Longer Than 100 Feet: MSS Type 43, adjustable, roller hangers.
- D. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.
- E. Base of Vertical Piping: MSS Type 52, spring hangers.
- F. Support horizontal piping within 12 inches of each fitting and coupling.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- G. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- H. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
 - 1. NPS 1/4: 60 inches with 3/8-inch rod.
 - 2. NPS 3/8 and NPS 1/2: 72 inches with 3/8-inch rod.
 - 3. NPS 3/4: 84 inches with 3/8-inch rod.
 - 4. NPS 1: 96 inches with 3/8-inch rod.
 - 5. NPS 1-1/4: 108 inches with 3/8-inch rod.
 - 6. NPS 1-1/2: 10 feet with 3/8-inch rod.
 - 7. NPS 2: 11 feet with 3/8-inch rod.
 - 8. NPS 2-1/2: 13 feet with 1/2-inch rod.
 - 9. NPS 3: 14 feet with 1/2-inch rod.
 - 10. NPS 4: 16 feet with 1/2-inch rod.
 - 11. NPS 5: 18 feet with 1/2-inch rod.
 - 12. NPS 6: 20 feet with 5/8-inch rod.
 - 13. NPS 8: 23 feet with 3/4-inch rod.
- I. Install supports for vertical copper tubing every 10 feet.

3.10 LABELING AND IDENTIFICATION

- A. Install identifying labels and devices for specialty gas piping, valves, and specialties. Comply with requirements in Division 22 Section "Identification for Plumbing Piping and Equipment."
- B. Install identifying labels and devices for healthcare medical gas piping systems according to NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:
 - 1. Oxygen: White letters on green background or green letters on white background.

3.11 FIELD QUALITY CONTROL FOR LABORATORY FACILITY SPECIALTY GAS

- A. Testing Agency: Engage qualified testing agency to perform field tests and inspections of specialty gas piping for nonhealthcare laboratory facilities and prepare test reports.
- B. Perform field tests and inspections of specialty gas piping for nonhealthcare laboratory facilities and prepare test reports.
- C. Tests and Inspections:
 - 1. Piping Leak Tests for Specialty Gas Piping: Test new and modified parts of existing piping. Cap and fill specialty gas piping with oil-free, dry nitrogen to pressure of 50 psig above system operating pressure, but not less than 150 psig. Isolate test source and let stand for four hours to equalize temperature. Refill system, if required, to test pressure; hold for two hours with no drop in pressure.
 - 2. Repair leaks and retest until no leaks exist.
 - 3. Inspect specialty gas regulators for proper operation.

3.12 FIELD QUALITY CONTROL FOR HEALTHCARE FACILITY MEDICAL GAS

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections of medical gas piping systems in healthcare facilities and prepare test reports.
- B. Perform tests and inspections of medical gas piping systems in healthcare facilities and prepare test reports.
- C. Tests and Inspections:
 - 1. Medical Gas Piping Testing Coordination: Perform tests, inspections, verifications, and certification of medical gas piping systems concurrently with tests, inspections, and certification of medical compressed-air piping and medical vacuum piping systems.
 - 2. Preparation: Perform the following Installer tests according to requirements in NFPA 99 and ASSE Standard #6010:
 - Initial blow down.
 - b. Initial pressure test.
 - c. Cross-connection test.
 - d. Piping purge test.
 - e. Standing pressure test for positive pressure medical gas piping.
 - f. Standing pressure test for vacuum systems.
 - g. Repair leaks and retest until no leaks exist.
 - 3. System Verification: Comply with requirements in NFPA 99, ASSE Standard #6020, and ASSE Standard #6030 for verification of medical gas piping systems and perform the following tests and inspections:
 - a. Standing pressure test.
 - b. Individual-pressurization or pressure-differential cross-connection test.
 - c. Valve test.
 - d. Master and area alarm tests.
 - e. Piping purge test.
 - f. Piping particulate test.
 - g. Piping purity test.
 - h. Final tie-in test.
 - i. Operational pressure test.
 - j. Medical gas concentration test.
 - k. Medical air purity test.
 - I. Verify correct labeling of equipment and components.
 - m. Verify the following source equipment:
 - 1) Medical gas supply sources.
 - 4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed and certify report results. Include the following:
 - a. Inspections performed.
 - b. Procedures, materials, and gases used.
 - c. Test methods used.
 - Results of tests.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

D. Remove and replace components that do not pass tests and inspections and retest as specified above.

3.13 DEMONSTRATION

A. Engage factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain medical gas alarm system. Refer to Division 01 Section "Demonstration and Training."

END OF SECTION 226313

Project No.: CP242241 February 27, 2024



SECTION 230500 - COMMON WORK RESULTS FOR HVAC

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Piping materials and installation instructions common to most piping systems.
 - 2. Transition fittings.
 - 3. Dielectric fittings.
 - 4. Mechanical sleeve seals.
 - 5. Sleeves.
 - 6. Escutcheons.
 - 7. Grout.
 - 8. Coordination drawings.
 - 9. Project Record Drawings.
 - 10. Equipment installation requirements common to equipment sections.
 - 11. Painting and finishing.
 - 12. Supports and anchorages.

1.3 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct chases, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspaces, and tunnels.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and chases.
- E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- F. The following are industry abbreviations for plastic materials:
 - 1. CPVC: Chlorinated polyvinyl chloride plastic.
 - 2. PE: Polyethylene plastic.
 - 3. PVC: Polyvinyl chloride plastic.
- G. The following are industry abbreviations for rubber materials:
 - 1. EPDM: Ethylene-propylene-diene terpolymer rubber.
 - 2. NBR: Acrylonitrile-butadiene rubber.

1.4 SUBMITTALS

- A. Product Data: For the following:
 - 1. Transition fittings.
 - 2. Dielectric fittings.
 - 3. Mechanical sleeve seals.
 - Escutcheons.
- B. Welding certificates.

1.5 QUALITY ASSURANCE

- A. Steel Support Welding: Qualify processes and operators according to AWS D1.1, "Structural Welding Code--Steel".
- B. Steel Pipe Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications".
 - 1. Comply with provisions in ASME B31 Series, "Code for Pressure Piping".
 - Certify that each welder has passed AWS qualification tests for welding processes involved and that certification is current.
- C. Electrical Characteristics for HVAC Equipment: Equipment of higher electrical characteristics may be furnished provided such proposed equipment is approved in writing and connecting electrical services, circuit breakers, and conduit sizes are appropriately modified. Any additional costs as a result of these modifications shall be borne by the contractor. If minimum energy ratings or efficiencies are specified, equipment shall comply with requirements.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- B. Store plastic pipes protected from direct sunlight. Support to prevent sagging and bending.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.7 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for HVAC installations.
- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Coordinate requirements for access panels and doors for HVAC items requiring access that are concealed behind finished surfaces. Mechanical contractor shall be responsible for furnishing and installing access doors required for their work.
- D. Sequence, coordinate, and integrate installations of HVAC materials and equipment for efficient flow of the Work. Coordinate installation of large equipment requiring positioning before closing in building.
- E. Coordinate connection of HVAC systems with exterior underground and overhead utilities and services. Comply with requirements of governing regulations, franchised service companies, and controlling agencies.
- F. Coordinate installation of identifying devices after completing covering and painting, if devices are applied to surfaces. Install identifying devices before installing acoustical ceilings and similar concealment.
- G. Sequence, coordinate, and integrate removal of existing equipment and material as required to maintain services for existing building and for portions of remodeled areas at all times.

1.8 SCHEDULING AND PHASING

A. All HVAC work shall be scheduled to meet project completion date. HVAC work shall be phased for projects requiring phasing of work. Install additional fittings, valves, caps, and dampers as required to support phasing. Refer to phasing schedule on drawings.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where subparagraph titles below introduce lists, the following requirements apply for product selection:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified.

2.2 PIPE, TUBE, AND FITTINGS

A. Refer to individual Division 23 piping Sections for pipe, tube, and fitting materials and joining methods.

B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

2.3 JOINING MATERIALS

- A. Refer to individual Division 23 piping Sections for special joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is indicated.
 - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
 - 2. AWWA C110, rubber, flat face, 1/8 inch thick, unless otherwise indicated; and full-face or ring type, unless otherwise indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.
- D. Plastic, Pipe-Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer, unless otherwise indicated.
- E. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- F. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing, unless otherwise indicated; and AWS A5.8, BAg1, silver alloy for refrigerant piping, unless otherwise indicated.
- G. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- H. Solvent Cements for Joining Plastic Piping:
 - 1. CPVC Piping: ASTM F 493.
 - 2. PVC Piping: ASTM D 2564. Include primer according to ASTM F 656.
- I. Fiberglass Pipe Adhesive: As furnished or recommended by pipe manufacturer.

2.4 TRANSITION FITTINGS

- A. Acceptable Manufacturers:
 - 1. Eslon Thermoplastics.
 - 2. NIBCO, Inc.
 - 3. Thompson Plastics, Inc.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Plastic-to-Metal Transition Fittings: CPVC and PVC one-piece fitting with manufacturer's Schedule 80 equivalent dimensions; one end with threaded brass insert, and one solvent-cement-joint end.
- C. Plastic-to-Metal Transition Adaptors: One-piece fitting with manufacturer's SDR 11 equivalent dimensions; one end with threaded brass insert, and one solvent-cement-joint end.
- D. Plastic-to-Metal Transition Unions: MSS SP-107, CPVC and PVC four-part union. Include brass end, solvent-cement-joint end, rubber O-ring, and union nut.

2.5 DIELECTRIC FITTINGS

- A. Description: Combination fitting of copper alloy and ferrous materials with threaded, solder-joint, plain, or weld-neck end connections that match piping system materials.
- B. Insulating Material: Suitable for system fluid, pressure, and temperature.
- C. Acceptable Manufacturers:
 - 1. Capitol Manufacturing Co.
 - 2. Capico Inc.
 - 3. Epco Sales, Inc.
 - 4. Hart Industries, International, Inc.
 - Victaulic
 - 6. Watts Industries, Inc.; Water Products Div.
 - 7. Zurn Industries, Inc.; Wilkins Div.
- D. Dielectric Flanges: Factory-fabricated, companion-flange assembly, for 150- or 300-psig minimum working pressure as required to suit system pressures.
- E. Dielectric-Flange Kits: Companion-flange assembly for field assembly. Include flanges, full-faceor ring-type neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
 - 1. Separate companion flanges and steel bolts and nuts shall have 150- or 300-psig minimum working pressure where required to suit system pressures.
- F. Dielectric Couplings: Galvanized-steel coupling with inert and noncorrosive, thermoplastic lining; threaded ends; and 300-psig minimum working pressure at 225 deg F.
- G. Dielectric Waterways: Victaulic Series 47 or equal electroplated steel nipple with inert and noncorrosive, thermoplastic lining; plain, threaded, or grooved ends; and 300-psig minimum working pressure at 225 deg F.

2.6 MECHANICAL SLEEVE SEALS

- A. Description: Modular sealing element unit, designed for field assembly, to fill annular space between pipe and sleeve.
 - 1. Acceptable Manufacturers:
 - Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Metraflex Co.
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: EPDM or NBR interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Carbon steel. Include two for each sealing element.
 - 4. Connecting Bolts and Nuts: Carbon steel with corrosion-resistant coating of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.7 SLEEVES

- A. Galvanized-Steel Sheet: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- B. Steel Pipe: ASTM A 53, Type E, Grade B, Schedule 40, galvanized, plain ends.
- C. Cast Iron: Cast or fabricated "wall pipe" equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- D. Stack Sleeve Fittings: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring and bolts and nuts for membrane flashing.
 - 1. Underdeck Clamp: Clamping ring with set screws.
- E. Molded PVC: Permanent, with nailing flange for attaching to wooden forms.
- F. PVC Pipe: ASTM D 1785, Schedule 40.
- G. Molded PE: Reusable, PE, tapered-cup shaped and smooth-outer surface with nailing flange for attaching to wooden forms.

2.8 ESCUTCHEONS

- A. Description: Manufactured wall and ceiling escutcheons and floor plates, with an ID to closely fit around pipe, tube, and insulation of insulated piping and an OD that completely covers opening.
- B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with polished chrome-plated finish.

- C. One-Piece, Cast-Brass Type: With set screw.
 - 1. Finish: Polished chrome-plated or rough brass.
- D. Split-Casting, Cast-Brass Type: With concealed hinge and set screw.
 - 1. Finish: Polished chrome-plated.
- E. One-Piece, Stamped-Steel Type: With set screw or spring clips and chrome-plated finish.
- F. Split-Plate, Stamped-Steel Type: With concealed hinge, set screw or spring clips, and chromeplated finish.
- G. One-Piece, Floor-Plate Type: Cast-iron floor plate.
- H. Split-Casting, Floor-Plate Type: Cast brass with concealed hinge and set screw.

2.9 GROUT

- A. Description: ASTM C 1107, Grade B, nonshrink and nonmetallic, dry hydraulic-cement grout.
 - 1. Characteristics: Post-hardening, volume-adjusting, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.
 - 3. Packaging: Premixed and factory packaged.

2.10 COORDINATION DRAWINGS

- A. The contractor shall prepare CAD generated overall coordination drawings (min ½" scale) to coordinate HVAC systems installation with other trades. Following systems/items shall be indicated and co-coordinated, but not limited to, with each other based on input from installers of these systems:
 - Ceiling lavout.
 - 2. Sheet metal ductwork including locations of boxes, diffusers, grilles/registers, duct risers, fire/smoke dampers, etc.
 - 3. HVAC piping routing including locations of valves, expansion loops, risers, etc.
 - 4. Fire suppression piping mains, sprinkler heads, flow switches, etc.
 - 5. Plumbing piping routing including locations of valves, drops to fixtures, risers, etc.
 - Medical gas piping routing including locations of zone valves, drops to outlets/headwalls, etc.
 - 7. Electrical systems including locations of light fixtures, routing of main feeders/conduits larger than 3" dia., routing of cable tray, etc.
- B. Contractor shall obtain information of other systems from General Contractor, Electrical Contractor, Fire Suppression Contractor, Plumbing Contractor and others as required for incorporation in the coordination drawings.
- C. Contractor shall arrange coordination meeting with other contractors, whose systems need coordination, to resolve conflicts.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 3 - EXECUTION

3.1 PIPING SYSTEMS - COMMON REQUIREMENTS

- A. Install piping according to the following requirements and Division 23 Sections specifying piping systems.
- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- C. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas. Mechanical contractor shall be responsible for furnishing and installing access doors required for their work.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping minimum 8 inches above accessible ceilings to allow sufficient space for ceiling panel removal and service access.
- F. Install piping to permit valve servicing.
- G. Install piping at indicated slopes.
- H. Install piping free of sags and bends.
- I. Install fittings for changes in direction and branch connections.
- J. Install piping to allow application of insulation.
- K. Select system components with pressure rating equal to or greater than system operating pressure.
- L. Install escutcheons for penetrations of walls, ceilings, and floors according to the following:
 - 1. New Piping:
 - a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type.
 - b. Chrome-Plated Piping: One-piece, cast-brass type with polished chrome-plated finish.
 - c. Insulated Piping: One-piece, stamped-steel type with spring clips.
 - d. Bare Piping at Wall and Floor Penetrations in Finished Spaces: One-piece, castbrass type with polished chrome-plated finish.
 - e. Bare Piping at Ceiling Penetrations in Finished Spaces: One-piece or split-casting, cast-brass type with polished chrome-plated finish.

- f. Bare Piping in Unfinished Service Spaces: One-piece, cast-brass type with roughbrass finish.
- g. Bare Piping in Equipment Rooms: One-piece, cast-brass type.
- h. Bare Piping at Floor Penetrations in Equipment Rooms: One-piece, floor-plate type.
- 2. Existing Piping: Use the following:
 - a. Chrome-Plated Piping: Split-casting, cast-brass type with chrome-plated finish.
 - b. Insulated Piping: Split-plate, stamped-steel type with concealed hinge and spring clips.
 - c. Bare Piping at Wall and Floor Penetrations in Finished Spaces: Split-casting, castbrass type with chrome-plated finish.
 - d. Bare Piping at Ceiling Penetrations in Finished Spaces: Split-casting, cast-brass type with chrome-plated finish.
 - e. Bare Piping in Unfinished Service Spaces: Split-casting, cast-brass type with rough-brass finish.
 - f. Bare Piping in Equipment Rooms: Split-casting, cast-brass type.
 - g. Bare Piping at Floor Penetrations in Equipment Rooms: Split-casting, floor-plate type.
- M. Sleeves are not required for core-drilled holes.
- N. Permanent sleeves are not required for holes formed by removable PE sleeves.
- Install sleeves for pipes passing through concrete and masonry walls and concrete floor and roof slabs.
- P. Install sleeves for pipes passing through concrete and masonry walls, gypsum-board partitions, and concrete floor and roof slabs.
 - 1. Cut sleeves to length for mounting flush with both surfaces.
 - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
 - 2. Install sleeves in new walls and slabs as new walls and slabs are constructed.
 - 3. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation. Use the following sleeve materials:
 - a. Steel Pipe Sleeves: For pipes smaller than NPS 6.
 - b. Steel Sheet Sleeves: For pipes NPS 6 and larger, penetrating gypsum-board partitions.
 - c. Stack Sleeve Fittings: For pipes penetrating floors with membrane waterproofing. Secure flashing between clamping flanges. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level.
 - 1) Seal space outside of sleeve fittings with grout.
 - 4. Except for underground wall penetrations, seal annular space between sleeve and pipe or pipe insulation, using joint sealants appropriate for size, depth, and location of joint. Refer to Section 079200 "Joint Sealants" for materials and installation.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Q. Aboveground, Exterior-Wall Pipe Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
 - 1. Install steel pipe for sleeves smaller than 6 inches in diameter.
 - 2. Install cast-iron "wall pipes" for sleeves 6 inches and larger in diameter.
 - 3. Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- R. Underground, Exterior-Wall Pipe Penetrations: Install cast-iron "wall pipes" for sleeves. Seal pipe penetrations using mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
 - Mechanical Sleeve Seal Installation: Select type and number of sealing elements required for pipe material and size. Position pipe in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pipe and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- S. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials.
- T. Verify final equipment locations for roughing-in.
- U. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.
- V. Draining and Refilling of Systems: Provide all shutoff valves, drain valves, pipe, fittings, and miscellaneous material required to drain each existing system as required for new work. After new work is completed, tested, and found tight, refill each system as required. Time for shutting down existing system for draining shall be coordinated with all other work and with Owner's representative. Fill glycol system with type and percentage solutions as directed by Owner.

3.2 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 23 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using leadfree solder alloy complying with ASTM B 32.

- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook", "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8.
- F. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
 - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
 - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- G. Welded Joints: Construct joints according to AWS D10.12, using qualified processes and welding operators according to Part 1 "Quality Assurance" Article.
- H. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.
 - 1. Chilled Water: red rubber.
 - 2. Heating Water and Steam: Flexitaulic Flexicarb Style GC or equal.
- I. Plastic Piping Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
 - Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
 - 2. CPVC Piping: Join according to ASTM D 2846/D 2846M Appendix.
 - 3. PVC Pressure Piping: Join schedule number ASTM D 1785, PVC pipe and PVC socket fittings according to ASTM D 2672. Join other-than-schedule-number PVC pipe and socket fittings according to ASTM D 2855.
 - 4. PVC Nonpressure Piping: Join according to ASTM D 2855.
- J. Plastic Pressure Piping Gasketed Joints: Join according to ASTM D 3139.
- K. Plastic Nonpressure Piping Gasketed Joints: Join according to ASTM D 3212.
- L. PE Piping Heat-Fusion Joints: Clean and dry joining surfaces by wiping with clean cloth or paper towels. Join according to ASTM D 2657.
 - 1. Plain-End Pipe and Fittings: Use butt fusion.
 - 2. Plain-End Pipe and Socket Fittings: Use socket fusion.
- M. Fiberglass Bonded Joints: Prepare pipe ends and fittings, apply adhesive, and join according to pipe manufacturer's written instructions.

3.3 PIPING CONNECTIONS

- A. Make connections according to the following, unless otherwise indicated:
 - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.
- 3. Dry Piping Systems: Install dielectric unions and flanges to connect piping materials of dissimilar metals.
- 4. Wet Piping Systems: Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

3.4 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- Install equipment to allow maximum possible headroom unless specific mounting heights are not indicated.
- B. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- C. Install HVAC equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- D. Install equipment to allow right of way for piping installed at required slope.

3.5 PAINTING

- A. Painting of HVAC systems, equipment, and components is specified in Section 099123 "Interior Painting".
- B. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.6 ERECTION OF METAL SUPPORTS AND ANCHORAGES

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor HVAC materials and equipment.
- B. Field Welding: Comply with AWS D1.1.

3.7 ERECTION OF WOOD SUPPORTS AND ANCHORAGES

- A. Cut, fit, and place wood grounds, nailers, blocking, and anchorages to support, and anchor HVAC materials and equipment.
- B. Select fastener sizes that will not penetrate members if opposite side will be exposed to view or will receive finish materials. Tighten connections between members. Install fasteners without splitting wood members.
- C. Attach to substrates as required to support applied loads.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.8 GROUTING

- A. Mix and install grout for HVAC equipment base bearing surfaces, pump and other equipment base plates, and anchors.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms as required for placement of grout.
- D. Avoid air entrapment during placement of grout.
- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases and provide smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout.

END OF SECTION 230500

COMMON WORK RESULTS FOR HVAC

230500 - 13

Project No.: CP242241 February 27, 2024



SECTION 230523 - GENERAL-DUTY VALVES FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes general duty valves common to several mechanical piping systems.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Special purpose valves are specified in Division 23 piping system Sections.
 - 2. Valve tags and charts are specified in Division 23 Section "Mechanical Identification."

1.3 SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product Data for each valve type. Include body material, valve design, pressure and temperature classification, end connection details, seating materials, trim material and arrangement, dimensions and required clearances, and installation instructions. Include list indicating valve and its application.
- C. Maintenance data for valves to include in the operation and maintenance manual specified in Division 1. Include detailed manufacturer's instructions on adjusting, servicing, disassembling, and repairing.

1.4 QUALITY ASSURANCE

- A. Single-Source Responsibility: Comply with the requirements specified in Division 1 Section "Materials and Equipment," under "Source Limitations" Paragraph.
- B. ASME Compliance: Comply with ASME B31.9 for building services piping and ASME B31.1 for power piping.
- C. MSS Compliance: Comply with the various MSS Standard Practice documents referenced.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Protect internal parts against rust and corrosion.
 - 2. Protect threads, flange faces, grooves, and weld ends.
 - 3. Set globe and gate valves closed to prevent rattling.
 - 4. Set ball and plug valves open to minimize exposure of functional surfaces.
 - Set butterfly valves closed or slightly open.
 - 6. Block check valves in either closed or open position.
- B. Use the following precautions during storage:
 - 1. Maintain valve end protection.
 - 2. Store indoors and maintain valve temperature higher than ambient dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use a sling to handle large valves. Rig to avoid damage to exposed parts. Do not use handwheels and stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Gate Valves:
 - a. Crane Company; Valves and Fitting Division.
 - b. Milwaukee Valve Company, Inc.
 - c. NIBCO Inc.
 - d. Stockham Valves & Fittings, Inc.
 - Ball Valves:
 - a. Conbraco Industries, Inc.; Apollo Division.
 - b. Milwaukee Valve Company, Inc.
 - c. NIBCO Inc.
 - d. Stockham Valves & Fittings, Inc.
 - e. Nexus Valve.
 - 3. Butterfly Valves:
 - a. Bray.
 - b. Crane Company; Valves and Fitting Division.
 - c. Grinnell Corp.
 - d. Milwaukee Valve Company, Inc.

- e. NIBCO Inc.
- f. Stockham Valves & Fittings, Inc.
- 4. Swing Check Valves:
 - a. Crane Company; Valves and Fitting Division.
 - b. Milwaukee Valve Company, Inc.
 - c. NIBCO Inc.
 - d. Stockham Valves & Fittings, Inc.
- 5. Lift Check Valves:
 - a. Crane Company; Valves and Fitting Division.
 - b. Milwaukee Valve Company, Inc.
 - c. NIBCO Inc.
 - d. Stockham Valves & Fittings, Inc.
- 6. Globe Valves:
 - a. Crane Company; Valves and Fitting Division.
 - b. Milwaukee Valve Company, Inc.
 - c. NIBCO Inc.
 - d. Stockham Valves & Fittings, Inc.

2.2 BASIC, COMMON FEATURES

- A. Pressure and Temperature Ratings: As indicated in the "Application Schedule" of Part 3 of this Section and as required to suit system pressures and temperatures.
- B. Sizes: Same size as upstream pipe, unless otherwise indicated.
- C. Operators: Use specified operators and handwheels, except provide the following special operator features:
 - 1. Handwheels: For valves other than quarter turn.
 - 2. Lever Handles: For quarter-turn valves 6 inches (DN150) and smaller, except for plug valves, which shall have square heads. Furnish Owner with 1 wrench for every 10 plug valves.
 - 3. Chain-Wheel Operators: For valves 4 inches (DN100) and larger, installed 96 inches (2400 mm) or higher above finished floor elevation.
 - 4. Gear-Drive Operators: For quarter-turn valves 8 inches (DN200) and larger.
- D. Extended Stems: Where insulation is indicated or specified, provide extended stems arranged to receive insulation.
- E. Bypass and Drain Connections: Comply with MSS SP-45 bypass and drain connections.
- F. Threads: ASME B1.20.1.
- G. Flanges: ASME B16.1 for cast iron, ASME B16.5 for steel, and ASME B16.24 for bronze valves.

H. Solder Joint: ASME B16.18.

1. Caution: Where soldered end connections are used, use solder having a melting point below 840 deg F (450 deg C) for gate, globe, and check valves; below 421 deg F (216 deg C) for ball valves.

2.3 GATE VALVES

- A. Steam Distribution (15 65 psig) Gate Valves, 2" and Smaller: Threaded outside screw and yoke, Class 800 ASTM A105 forged steel body and bonnet, stainless steel wedge disc and seat; and with cast iron handwheel. Valves 2½" and larger, flanged, forged steel, outside screw and yoke, 150 lb. class.
- B. Steam (below 15 psig in building) Gate Valves 2" and Smaller: 150 lb. rising stem gate valves. Union shall not be integral to the valve. Valves 2½" and larger shall be flanged ends, outside screw and yoke, Class150.

2.4 BALL VALVES

- A. Chilled Water and Hot Water Ball Valves: MSS SP-110, 150 lb., 2" and smaller, ASTM B 584 bronze body and bonnet, 2-piece construction; stainless steel ball, full port blowout proof; stainless steel stem; Teflon seats and seals; soldered end connections, NIBCO T-595-Y, NIBCO S-595-Y or equal:
 - 1. Operator: Vinyl-covered steel lever handle.
 - 2. Stem Extension: 1-1/4" long for valves installed in insulated piping.
 - 3. Memory Stop: For operator handles.

2.5 GLOBE VALVES

A. Chilled Water and Hot Water - Globe Valves, 3 Inches (DN65) and Smaller: MSS SP-80; Class 125, 200-psi (1380-kPa) CWP, or Class 150, 300-psi (2070-kPa) CWP; ASTM B 62 cast-bronze body and screwed bonnet, rubber, bronze, or Teflon disc, silicon bronze-alloy stem, Teflon-impregnated packing with bronze nut, threaded or soldered end connections; and with aluminum or malleable-iron handwheel.

2.6 BUTTERFLY VALVES

- A. Chilled Water and Hot Water Butterfly Valves: MSS SP-67, 200-psi (1380-kPa) CWP, 150 psi maximum pressure differential, ASTM A 126 cast-iron full lug body and bonnet, extended neck, 316 stainless-steel stem, field-replaceable EPDM sleeve and stem seals, Grinnell Series 8000 or equal:
 - 1. Disc Type: 316 stainless steel.
 - 2. Operator for Sizes 2 Inches (DN50) to 5 Inches (DN150): Lever handle with latch lock with memory.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3. Operator for Sizes 6 Inches (DN200) to 24 Inches (DN600): Gear operator with position indicator with chain 6'-0" A.F.F.
- 4. Operator for Sizes 6 Inches (DN200) and Larger, 96 Inches (2400 mm) or Higher above Floor: Chain-wheel operator with chain 6'-0" A.F.F.

2.7 CHECK VALVES

- A. Swing Check Valves, 2 Inches (DN65) and Smaller: 150 lb.; horizontal swing, Y-pattern, ASTM B 62 cast-bronze body and cap, soldered connections, NIBCO T-433 or equal:
- B. Swing Check Valves, 2-1/2 Inches (DN80) and Larger: MSS SP-71, Class 125, 200-psi (1380-kPa) CWP, ASTM A 126 cast-iron body and bolted cap, horizontal-swing bronze disc, flanged end connections, NIBCO F-918 or equal.
- C. Lift Check Valves (Pump Discharge): Class 150, compact wafer, spring loaded, center guided lift check valve with bronze seat. Valves shall conform to MS-SP-125.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.
- B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- C. Operate valves from fully open to fully closed positions. Examine guides and seats made accessible by such operation.
- D. Examine threads on valve and mating pipe for form and cleanliness.
- E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Check gasket material for proper size, material composition suitable for service, and freedom from defects and damage.
- F. Do not attempt to repair defective valves; replace with new valves.

3.2 INSTALLATION

- A. Install valves as indicated, according to manufacturer's written instructions.
- B. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.

Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Install valves with unions or flanges at each piece of equipment arranged to allow servicing, maintenance, and equipment removal without system shutdown.
- D. Locate valves for easy access and provide separate support where necessary.
- E. Install valves in horizontal piping with stem at or above the center of the pipe.
- F. Install valves in a position to allow full stem movement.
- G. For chain-wheel operators, extend chains to 60 inches (1500 mm) above finished floor elevation.
- H. Installation of Check Valves: Install for proper direction of flow as follows:
 - 1. Swing Check Valves: Horizontal position with hinge pin level.
 - 2. Lift Check Valve: With stem upright and plumb.

3.3 SOLDERED CONNECTIONS

- A. Cut tube square and to exact lengths.
- B. Clean end of tube to depth of valve socket with steel wool, sand cloth, or a steel wire brush to a bright finish. Clean valve socket.
- C. Apply proper soldering flux in an even coat to inside of valve socket and outside of tube.
- D. Open gate and globe valves to fully open position.
- E. Remove the cap and disc holder of swing check valves having composition discs.
- F. Insert tube into valve socket, making sure the end rests against the shoulder inside valve. Rotate tube or valve slightly to ensure even distribution of the flux.
- G. Apply heat evenly to outside of valve around joint until solder melts on contact. Feed solder until it completely fills the joint around tube. Avoid hot spots or overheating valve. Once the solder starts cooling, remove excess amounts around the joint with a cloth or brush.

3.4 THREADED CONNECTIONS

- A. Note the internal length of threads in valve ends and proximity of valve internal seat or wall to determine how far pipe should be threaded into valve.
- B. Align threads at point of assembly.
- C. Apply appropriate tape or thread compound to the external pipe threads, except where dry seal threading is specified.
- D. Assemble joint, wrench tight. Wrench on valve shall be on the valve end into which the pipe is being threaded.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.5 FLANGED CONNECTIONS

- A. Align flange surfaces parallel.
- B. Assemble joints by sequencing bolt tightening to make initial contact of flanges and gaskets as flat and parallel as possible. Use suitable lubricants on bolt threads. Tighten bolts gradually and uniformly with a torque wrench.
- C. For dead-end service, butterfly valves require flanges both upstream and downstream for proper shutoff and retention.

3.6 VALVE END SELECTION

- A. Select valves with the following ends or types of pipe/tube connections:
 - 1. Copper Tube Size, 2-1/2 Inches (DN65) and Smaller: Threaded ends.
 - 2. Steel Pipe Sizes, 2-1/2 Inches (DN65) and Smaller: Threaded.
 - 3. Steel Pipe Sizes, 3 Inches (DN80) and Larger: Flanged.

3.7 APPLICATION SCHEDULE

- A. General Application: Use gate, ball, and butterfly valves for shutoff duty; lubricated plug cocks, and balancing valves for throttling duty, and butterfly valves on pump discharge. Refer to piping system Specification Sections for specific valve applications and arrangements.
- B. Heating and Chilled Water Systems: Use the following valve types:
 - 1. Ball Valves (up to and including 2"): Two-piece, full port, bronze with stainless-steel trim.
 - 2. Butterfly Valves 3" and Larger: Iron, 200 CWP, EPDM seat, 316 stainless steel disc.
 - 3. Bronze Swing Check: Class 150, with composition seat.
 - 4. Globe Valves: Class 125, 200 psi, cast bronze (ahead of pressure gauges).
 - 5. Balancing Valves: Bell and Gossett CBV or Armstrong Flowsetter ΔP type

3.8 ADJUSTING

A. Adjust or replace packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves if leak persists.

END OF SECTION 230523

GENERAL-DUTY VALVES FOR HVAC PIPING

230523 - 7

Project No.: CP242241 February 27, 2024



SECTION 230529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following hangers and supports for HVAC system piping and equipment:
 - 1. Steel pipe hangers and supports.
 - 2. Trapeze pipe hangers.
 - 3. Metal framing systems.
 - Thermal-hanger shield inserts.
 - 5. Fastener systems.
 - 6. Pipe stands.
 - 7. Equipment supports.
- B. Related Sections include the following:
 - 1. Division 23 Section(s) "Metal Ducts" for duct hangers and supports.

1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society for The Valve and Fittings Industry Inc.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.4 PERFORMANCE REQUIREMENTS

- A. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
- B. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.5 SUBMITTALS

- A. Product Data: For the following:
 - 1. Steel pipe hangers and supports.
 - 2. Thermal-hanger shield inserts.
 - 3. Powder-actuated fastener systems.
- B. Welding certificates with picture ID.

1.6 QUALITY ASSURANCE

- A. Welding: Qualify procedures and personnel according to the following:
 - 1. AWS D1.1, "Structural Welding Code--Steel."
 - 2. AWS D1.2, "Structural Welding Code--Aluminum."
 - 3. AWS D1.3, "Structural Welding Code--Sheet Steel."
 - 4. AWS D1.4, "Structural Welding Code--Reinforcing Steel."
 - 5. ASME Boiler and Pressure Vessel Code: Section IX.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 STEEL PIPE HANGERS AND SUPPORTS

- A. Description: MSS SP-58, Types 1 through 58, factory-fabricated components. Refer to Part 3 "Hanger and Support Applications" Article for where to use specific hanger and support types.
- B. Acceptable Manufacturers:
 - 1. B-Line Systems, Inc.; a division of Cooper Industries.
 - 2. Carpenter & Paterson, Inc.
 - 3. Empire Industries, Inc.
 - 4. Globe Pipe Hanger Products, Inc.
 - 5. Grinnell Corp.
 - 6. GS Metals Corp.
 - 7. National Pipe Hanger Corporation.
 - 8. Piping Technology & Products, Inc.
- C. Galvanized, Metallic Coatings: Pregalvanized or hot dipped.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Nonmetallic Coatings: Plastic coating, jacket, or liner.
- E. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion for support of bearing surface of piping.

2.3 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural-steel shapes with MSS SP-58 hanger rods, nuts, saddles, and U-bolts.

2.4 METAL FRAMING SYSTEMS

- A. Description: MFMA-3, shop- or field-fabricated pipe-support assembly made of steel channels and other components.
- B. Acceptable Manufacturers:
 - 1. B-Line Systems, Inc.; a division of Cooper Industries.
 - 2. GS Metals Corp.
 - 3. Power-Strut Div.; Tyco International, Ltd.
 - 4. Thomas & Betts Corporation.
 - 5. Unistrut Corp.; Tyco International, Ltd.
- C. Coatings: Manufacturer's standard finish, unless bare metal surfaces are indicated.
- D. Nonmetallic Coatings: Plastic coating, jacket, or liner.

2.5 THERMAL-HANGER SHIELD INSERTS

- A. Description: 100-psig-minimum, compressive-strength insulation insert encased in sheet metal shield.
- B. Acceptable Manufacturers:
 - 1. Carpenter & Paterson, Inc.
 - 2. PHS Industries, Inc.
 - 3. Pipe Shields, Inc.
 - 4. Rilco Manufacturing Company, Inc.
 - 5. Value Engineered Products, Inc.
- C. Insulation-Insert Material for Cold Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate with vapor barrier.
- D. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate.
- E. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- F. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.

G. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.6 FASTENER SYSTEMS

- A. Mechanical-Expansion Anchors: Insert-wedge-type zinc-coated steel, for use in hardened Portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
 - 1. Acceptable Manufacturers:
 - a. B-Line Systems, Inc.; a division of Cooper Industries.
 - b. Empire Industries, Inc.
 - c. Hilti, Inc.
 - d. ITW Ramset/Red Head.
 - e. MKT Fastening, LLC.
 - f. Powers Fasteners.

2.7 PIPE STAND FABRICATION

- A. Pipe Stands, General: Shop or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
- B. Compact Pipe Stand: One-piece plastic unit with integral-rod-roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
 - 1. Acceptable Manufacturers:
 - a. ERICO/Michigan Hanger Co.
 - b. MIRO Industries.
- C. Low-Type, Single-Pipe Stand: One-piece plastic or stainless-steel base unit with plastic roller, for roof installation without membrane penetration.
- D. High-Type, Single-Pipe Stand: Assembly of base, vertical and horizontal members, and pipe support, for roof installation without membrane penetration.
 - 1. Base: Plastic or Stainless steel.
 - Vertical Members: Two or more cadmium-plated-steel or stainless-steel, continuousthread rods.
 - 3. Horizontal Member: Cadmium-plated-steel or stainless-steel rod with plastic or stainless-steel, roller-type pipe support.
- E. High-Type, Multiple-Pipe Stand: Assembly of bases, vertical and horizontal members, and pipe supports, for roof installation without membrane penetration.
 - 1. Bases: One or more plastic.
 - 2. Vertical Members: Two or more protective-coated-steel channels.
 - 3. Horizontal Member: Protective-coated-steel channel.
 - 4. Pipe Supports: Galvanized-steel, clevis-type pipe hangers.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.8 EQUIPMENT SUPPORTS

A. Description: Welded, shop- or field-fabricated equipment support made from structural-steel shapes and then hot dipped or cold galvanized.

2.9 MISCELLANEOUS MATERIALS

- A. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
 - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 2. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT APPLICATIONS

- A. Specific hanger and support requirements are specified in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized, metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use padded hangers for piping that is subject to scratching.
- F. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 30.
 - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of 120 to 450 deg F pipes, NPS 4 to NPS 16, requiring up to 4 inches of insulation.
 - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes, NPS 3/4 to NPS 24, requiring clamp flexibility and up to 4 inches of insulation.
 - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes, NPS 1/2 to NPS 24, if little or no insulation is required.
 - 5. Pipe Hangers (MSS Type 5): For suspension of pipes, NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
 - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated stationary pipes, NPS 3/4 to NPS 8.

- 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 8.
- 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 8.
- 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 2.
- 10. Split Pipe-Ring with or without Turnbuckle-Adjustment Hangers (MSS Type 11): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 8.
- 11. Extension Hinged or 2-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 3.
- 12. U-Bolts (MSS Type 24): For support of heavy pipes, NPS 1/2 to NPS 30.
- 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
- 14. Pipe Saddle Supports (MSS Type 36): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange.
- 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange and with U-bolt to retain pipe.
- 16. Adjustable, Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes, NPS 2-1/2 to NPS 36, if vertical adjustment is required, with steel pipe base stanchion support and cast-iron floor flange.
- 17. Single Pipe Rolls (MSS Type 41): For suspension of pipes, NPS 1 to NPS 30, from 2 rods if longitudinal movement caused by expansion and contraction might occur.
- 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes, NPS 2-1/2 to NPS 20, from single rod if horizontal movement caused by expansion and contraction might occur.
- 19. Complete Pipe Rolls (MSS Type 44): For support of pipes, NPS 2 to NPS 42, if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
- 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes, NPS 2 to NPS 24, if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
- 21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes, NPS 2 to NPS 30, if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- G. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers, NPS 3/4 to NPS 20.
 - Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers, NPS 3/4 to NPS 20, if longer ends are required for riser clamps.
- H. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 - 2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
 - 3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 - 4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
 - 5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.

- I. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 - 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction to attach to top flange of structural shape.
 - 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 - 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 - 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 - 6. C-Clamps (MSS Type 23): For structural shapes.
 - 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 - 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 - 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 - 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 - 11. Malleable Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 - 12. Welded-Steel Brackets: For support of pipes from below, or for suspending from above by using clip and rod. Use one of the following for indicated loads:
 - a. Light (MSS Type 31): 750 lb.
 - b. Medium (MSS Type 32): 1500 lb.
 - c. Heavy (MSS Type 33): 3000 lb.
 - 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 - 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 - 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- J. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Steel Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 - 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
 - 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- K. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
 - 1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 - Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 - 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.
 - 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.

- 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from hanger.
- 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from base support.
- 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from trapeze support.
- 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- L. Comply with MSS SP-69 for trapeze pipe hanger selections and applications that are not specified in piping system Sections.
- M. Comply with MFMA-102 for metal framing system selections and applications that are not specified in piping system Sections.
- N. Use mechanical-expansion anchors instead of building attachments where required in concrete construction.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Steel Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Trapeze Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping and support together on field-fabricated trapeze pipe hangers.
 - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified above for individual pipe hangers.
 - Field fabricate from ASTM A 36/A 36M, steel shapes selected for loads being supported. Weld steel according to AWS D1.1.
- C. Metal Framing System Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled metal framing systems.
- D. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- E. Fastener System Installation:
 - 1. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.

F. Pipe Stand Installation:

- 1. Pipe Stand Types except Curb-Mounting Type: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.
- G. Install hangers and supports complete with necessary inserts, bolts, rods, nuts, washers, and other accessories.
- H. Equipment Support Installation: Fabricate from welded-structural-steel shapes and then hot dipped or cold galvanize.
- I. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- J. Install lateral bracing with pipe hangers and supports to prevent swaying.
- K. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- L. Load Distribution: Install hangers and supports so piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- M. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and so maximum pipe deflections allowed by ASME B31.1 (for power piping) and ASME B31.9 (for building services piping) are not exceeded.
- N. Insulated Piping: Comply with the following:
 - 1. Attach clamps and spacers to piping.
 - a. Heating Water, Steam, Steam Condensate and Pumped Condensate Piping: Clamp may project through insulation.
 - b. Chilled Water and Condensate Drain Piping: Use thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits according to ASME B31.1 for power piping and ASME B31.9 for building services piping.
 - 2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
 - 3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
 - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
- 5. Pipes NPS 8 and Larger: Include wood inserts.
- 6. Insert Material: Length at least as long as protective shield.
- 7. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make smooth bearing surface.
- C. Provide lateral bracing, to prevent swaying, for equipment supports.

3.4 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1 procedures for shielded metal arc welding, appearance and quality of welds, and methods used in correcting welding work, and with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. Finish welds at exposed connections so no roughness shows after finishing and contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.6 PAINTING

- A. Touch Up: Clean field welds and abraded areas of shop paint. Cold galvanize exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.
- B. Touch Up: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Division 09 painting Sections.
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair stick to comply with ASTM A 780.

END OF SECTION 230529

HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT 230529 - 11

Project No.: CP242241 February 27, 2024



SECTION 230553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Equipment labels.
- 2. Warning signs and labels.
- 3. Pipe labels.
- 4. Duct labels.
- 5. Stencils.
- 6. Valve tags.
- 7. Warning tags.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- C. Valve numbering scheme.
- D. Valve Schedules: For each piping system to include in maintenance manuals.

1.4 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 EQUIPMENT LABELS

A. Metal Labels for Equipment:

- 1. Material and Thickness: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
- 2. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 3. Minimum Letter Size: 1/2 inch and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- 4. Fasteners: Stainless-steel self-tapping screws.
- 5. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

B. Plastic Labels for Equipment:

- 1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
- 2. Letter Color: White.
- 3. Background Color: Black.
- Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- 5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- 6. Minimum Letter Size: 1/2 inch and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- 7. Fasteners: Stainless-steel self-tapping screws.
- 8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- C. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified.
- D. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number and identify Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

2.2 WARNING SIGNS AND LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
- B. Letter Color: White.
- C. Background Color: Red.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/2 inch and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- G. Fasteners: Stainless-steel self-tapping screws.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Label Content: Include caution and warning information, plus emergency notification instructions.

2.3 PIPE LABELS

- A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.
- B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to partially cover circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings, pipe size, and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions, or as separate unit on each pipe label to indicate flow direction.
 - 2. Lettering Size: At least 1-1/2 inches high.

2.4 DUCT LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
- B. Letter Color: White.
- C. Background Color: Black.
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/2 inch and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- G. Fasteners: Stainless-steel self-tapping screws.

- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Duct Label Contents: Include identification of duct service using same designations or abbreviations as used on Drawings, duct size, and an arrow indicating flow direction.
 - 1. Flow-Direction Arrows: Integral with duct system service lettering to accommodate both directions, or as separate unit on each duct label to indicate flow direction.
 - 2. Lettering Size: At least 1-1/2 inches high.

2.5 STENCILS

- A. Stencils: Prepared with letter sizes according to ASME A13.1 for piping; minimum letter height of 1-1/4 inches for ducts; and minimum letter height of 3/4 inch for access panel and door labels, equipment labels, and similar operational instructions.
 - 1. Stencil Material: Fiberboard or metal.
 - 2. Stencil Paint: Exterior, gloss, alkyd enamel black unless otherwise indicated. Paint may be in pressurized spray-can form.
 - 3. Identification Paint: Exterior, alkyd enamel in colors according to ASME A13.1 unless otherwise indicated.

2.6 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
 - Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
 - 2. Fasteners: Brass wire-link or beaded chain; or S-hook.
- B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
 - 1. Valve-tag schedule shall be included in operation and maintenance data.

2.7 WARNING TAGS

- A. Warning Tags: Preprinted or partially preprinted, accident-prevention tags, of plasticized card stock with matte finish suitable for writing.
 - 1. Size: 3 by 5-1/4 inches.
 - 2. Fasteners: Reinforced grommet and wire or string.
 - 3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
 - 4. Color: Yellow background with black lettering.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

3.2 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

3.3 PIPE LABEL INSTALLATION

- A. Piping Color-Coding: Painting of piping is specified in Division 09 Section "Interior Painting."
- B. Stenciled Pipe Label Option: Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option. Install stenciled pipe labels, complying with ASME A13.1, on each piping system.
 - 1. Identification Paint: Use for contrasting background.
 - 2. Stencil Paint: Use for pipe marking.
- C. Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:
 - 1. Near each valve and control device.
 - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 - 3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
 - At access doors, manholes, and similar access points that permit view of concealed piping.
 - 5. Near major equipment items and other points of origination and termination.
 - Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment, within mechanical rooms, boiler rooms, chiller rooms, etc.
 - 7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
- D. In general follow Pipe Label Color Schedule as shown below, unless the Owner has different schedule standards in which case the Owner's schedule shall be followed:
 - 1. Heating Water Piping:
 - a. Background Color: Orange.
 - b. Letter Color: White.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.4 DUCT LABEL INSTALLATION

- A. Install plastic-laminated or self-adhesive duct labels with permanent adhesive on air ducts in the following color codes:
 - 1. Blue: For cold-air supply ducts.
 - 2. Yellow: For hot-air supply ducts.
 - 3. Green: For exhaust-, outside-, relief-, return-, and mixed-air ducts.
 - 4. ASME A13.1 Colors and Designs: For hazardous material exhaust.
- B. Stenciled Duct Label Option: Stenciled labels, showing service and flow direction, may be provided instead of plastic-laminated duct labels, at Installer's option, if lettering larger than 1 inch high is needed for proper identification because of distance from normal location of required identification.
- C. Locate labels near points where ducts enter into concealed spaces and at maximum intervals of 50 feet in each space where ducts are exposed or concealed by removable ceiling system. Reduce intervals to 25 feet in areas of congested piping and equipment, within mechanical rooms, etc.

3.5 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves; valves within factory-fabricated equipment units; shutoff valves; and HVAC terminal devices and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:
 - 1. Valve-Tag Size and Shape:
 - a. Hot Water: 1-1/2 inches, round.
 - 2. Valve-Tag Color:
 - a. Hot Water: Natural.
 - 3. Letter Color:
 - a. Hot Water: Black.

3.6 WARNING-TAG INSTALLATION

A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION 230553

SECTION 230593 - TESTING, ADJUSTING AND BALANCING FOR HVAC PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 DESCRIPTION OF WORK

- A. This scope of services specified the requirements and procedures for mechanical systems testing, adjusting, and balancing. Requirements include measurement and establishment of the fluid quantities of the mechanical systems as required to meet design specifications, and recording and reporting the results. The test and balance work will be performed by the Owner's personnel. It is the Contractor's responsibility to assist as outlined below.
- B. Test, adjust and balance the following mechanical systems which are shown in the construction documents.
 - 1. Supply air systems.
 - 2. Exhaust air systems.
 - 3. Verify temperature control system operation.
- C. The contractor's responsibilities are as follows:
 - 1. Notify the Owner's Representative fourteen (14) days prior to the schedule date for balancing the system.
 - 2. Schedule a two (2) week allowance for the testing and balancing firm to complete the testing and balancing work when scheduling completion of all work required of the Contractor by the contract documents.
 - 3. Cooperate with the testing and balancing firm and shall make all necessary preparations for the TAB efforts.
 - 4. Complete the following work prior to requesting the TAB effort.
 - a. Clean and flush all piping systems.
 - b. Leak test and make tight all piping systems.
 - c. Fill all piping systems with clean water.
 - d. Clean and seal all ductwork systems.
 - e. Service and tag all equipment.
 - f. Set and align all motors and drives.
 - g. Start up and prove all equipment and systems.
 - h. Make preliminary settings on all control devices and have all systems operational.
 - i. Operate all systems successfully for twenty-four (24) hours minimum.
 - 5. Lubricate all motors and bearings.
 - 6. Check fan belt tension.
 - 7. Check fan rotation.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 8. Patch insulation, ductwork and housing, using materials identical to those removed.
- 9. Seal ducts and piping, and test for and repair leaks.
- 10. Seal insulation to re-establish integrity of the vapor barrier.
- 11. Attend a coordination meeting prior to the balancing of the system and a coordination meeting following the balancing of the system.
- 12. Provide a complete set of as-built drawings prior to the TAB effort.
- 13. Provide craftsmen of the proper trade to work with the TAB firm to make adjustments and installation changes as required.
- 14. Change out fan sheaves when and if required by the TAB firm.
- 15. Dedicate the resources to accommodate all changes identified by the test and balance firm in a timely manner.
- 16. If a significant rebalance (Owner's determination) of the HVAC system is required due to the Contractor's failure to properly install and check out the HVAC system, the cost of rebalancing the system shall be borne by the Contractor.

1.3 PRE-BALANCING CONFERENCE

A. Prior to beginning of the testing, adjusting and balancing procedures, a conference with the Owner's Representative, Engineer and the Test and Balance Agency's representative will be held. The objective of the conference is final coordination and verification of system operation and readiness for testing, adjusting and balancing.

1.4 SEQUENCING AND SCHEDULING OF SERVICES

A. Test, adjust and balance the air conditioning systems during summer season and heating systems during winter season. This includes at least a period of operation at outside conditions within 5 deg. F wet bulb temperature of maximum summer design condition, and within 10 deg. F dry bulb temperature of minimum winter design conditions. Take final temperature readings during seasonal operation.

PART 2 - PRODUCTS (Not applicable)

PART 3 - EXECUTION (Not applicable)

END OF SECTION 230593

SECTION 230700 - HVAC INSULATION

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

Drawings and general provisions of the Contract, including General and Supplementary Α. Conditions and Division 01 Specification Sections, apply to this Section.

1.2 **SUMMARY**

- A. Section Includes:
 - 1. Insulation Materials:
 - Flexible elastomeric. a.
 - Mineral fiber. b.
 - 2. Insulating cements.
 - Adhesives.
 - 4. Mastics.
 - Lagging adhesives. 5.
 - Sealants. 6.
 - Factory-applied jackets. 7.
 - Field-applied fabric-reinforcing mesh. 8.
 - 9. Field-applied cloths.
 - Field-applied jackets. 10.
 - 11. Tapes.
 - 12. Securements.
 - Corner angles. 13.

В. **Related Sections:**

1. Division 22 Section "Plumbing Insulation."

1.3 **SUBMITTALS**

Product Data: For each type of product indicated. Include thermal conductivity, thickness, and Α. jackets (both factory and field applied, if any).

1.4 **QUALITY ASSURANCE**

Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship Α. program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Fire-Test-Response Characteristics: Insulation and related materials shall have fire-test-В. response characteristics indicated, as determined by testing identical products per ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing and inspecting agency.
 - 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.

1.5 DELIVERY, STORAGE, AND HANDLING

Α. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

COORDINATION 1.6

- Coordinate size and location of supports, hangers, and insulation shields specified in Division Α. 23 Section "Hangers and Supports for HVAC Piping and Equipment."
- В. Coordinate clearance requirements with piping Installer for piping insulation application, duct Installer for duct insulation application, and equipment Installer for equipment insulation application. Before preparing piping and ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

1.7 **SCHEDULING**

A. Schedule insulation application after pressure testing systems. Insulation application may begin on segments that have satisfactory test results.

PART 2 - PRODUCTS

2.1 **INSULATION MATERIALS**

- Comply with requirements in Part 3 schedule articles for where insulating materials shall be Α.
- Products shall not contain asbestos, lead, mercury, or mercury compounds. B.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing E. process.

HVAC INSULATION 230700 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- F. Flexible Elastomeric: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials and Type II for sheet materials.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products of one of the following:
 - Aeroflex USA Inc.; Aerocel. a.
 - Armacell LLC; AP Armaflex. b.
 - NOMACO Insulation. C.
 - 2. Thermal Conductivity: Not exceeding 0.25 BTU-in/hour °F at 75°F mean temperature.
- G. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - CertainTeed Corp. a.
 - Johns Manville. b.
 - Knauf Insulation. C.
 - d. Manson Insulation Inc.
 - Owens Corning Fiberglas Corp.
 - 2. Density: 1.9 lbs/cu. ft.
 - 3. Thermal Conductivity: Not exceeding 0.25 BTU-in/hour sq. ft. °F at 75°F mean temperature.
- High-Temperature, Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a H. thermosetting resin. Comply with ASTM C 553, Type V, without factory-applied jacket.
 - Acceptable Manufacturers: Subject to compliance with requirements, provide products by 1. one of the following:
 - CertainTeed Corp. a.
 - Johns Manville. b.
 - Knauf Insulation. C.
 - Owens Corning Fiberglas Corp.
 - 2. Density: 3.0 lbs/cu. ft.
 - Thermal Conductivity: Not exceeding 0.30 BTU-in/hour sq. ft. °F at 100°F mean 3. temperature.

HVAC INSULATION 230700 - 3 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- I. Mineral-Fiber Board Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 612, Type IA or Type IB. For duct and plenum applications, provide insulation with factory-applied ASJ. For equipment applications, provide insulation with factoryapplied ASJ. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - CertainTeed Corp. a.
 - Johns Manville. b.
 - Knauf Insulation. C.
 - d. Manson Insulation Inc.
 - Owens Corning Fiberglas Corp. e.
 - 2. Density: 3.0 lbs/cu. ft.
 - 3. Thermal Conductivity: Not exceeding 0.23 BTU-in/hour sq. ft. °F at 75°F mean temperature.
- High-Temperature, Mineral-Fiber Board Insulation: Mineral or glass fibers bonded with a J. thermosetting resin. Comply with ASTM C 612, Type III, without factory-applied jacket.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Johns Manville.
 - b. Owens Corning Fiberglas Corp.
 - Rock Wool Manufacturing Company. C.
 - 2. Density: 3.0 lbs/cu. ft.
 - Thermal Conductivity: Not exceeding 0.30 BTU-in/hour sq. ft. °F at 100°F mean 3. temperature.
- K. Mineral-Fiber, Preformed Pipe Insulation:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - Johns Manville. a.
 - Knauf Insulation. b.
 - C. Manson Insulation Inc.
 - Owens Corning Fiberglas Corp.
 - 2. Type I, 850 deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A, with factory-applied ASJ-SSL. Factoryapplied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 3. Thermal Conductivity: Not exceeding 0.23 BTU-in/hour sq. ft. °F at 75°F mean temperature.

HVAC INSULATION 230700 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Mineral-Fiber, Pipe and Tank Insulation: Mineral or glass fibers bonded with a thermosetting L. resin. Semirigid board material with factory-applied ASJ complying with ASTM C 1393, Type II or Type IIIA Category 2, or with properties similar to ASTM C 612, Type IB. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - CertainTeed Corp. a.
 - Johns Manville. b.
 - Knauf Insulation. C.
 - d. Manson Insulation Inc.
 - Owens Corning Fiberglas Corp.
 - 2. Density: 2.5 lbs/cu. ft.
 - Thermal Conductivity: Not exceeding 0.27 BTU-in/hour sq. ft. °F at 75°F mean 3. temperature.

2.2 **INSULATING CEMENTS**

- Α. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.
- В. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449.

2.3 **ADHESIVES**

- Materials shall be compatible with insulation materials, jackets, and substrates and for bonding Α. insulation to itself and to surfaces to be insulated, unless otherwise indicated.
- B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide one of the following:
 - Aeroflex USA Inc. a.
 - b. Armacell LCC.
 - Foster Products Corporation, H. B. Fuller Company. c.
 - RBX Corporation.
 - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A. C.
 - 1. For indoor applications, use adhesive that has a VOC content of 80 q/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

HVAC INSULATION 230700 - 5 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Childers Products, Division of ITW.
 - b. Foster Products Corporation, H. B. Fuller Company.
 - c. ITW TACC, Division of Illinois Tool Works.
 - d. Marathon Industries, Inc.
 - e. Mon-Eco Industries, Inc.
 - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- E. PVC Jacket Adhesive: Compatible with PVC jacket.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Dow Chemical Company (The).
 - b. Johns-Manville.
 - c. P.I.C. Plastics. Inc.
 - d. Speedline Corporation
 - 2. For indoor applications, use adhesive that has a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.4 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
 - 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C 1136, Type I.
 - 2. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.
 - 3. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.
 - 4. FSP Jacket: Aluminum-foil, fiberglass-reinforced scrim with polyethylene backing; complying with ASTM C 1136, Type II.
 - 5. Vinyl Jacket: White vinyl with a permeance of 1.3 perms when tested according to ASTM E 96, Procedure A, and complying with NFPA 90A and NFPA 90B.

2.5 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- B. FSK Jacket: Aluminum-foil-face, fiberglass-reinforced scrim with kraft-paper backing.

HVAC INSULATION 230700 - 6 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - Johns Manville. a.
 - P.I.C. Plastics, Inc. b.
 - Proto PVC Corporation. c.
 - Speedline Corporation. d.
 - 2. Adhesive: As recommended by jacket material manufacturer.
 - Color: White.
 - Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
 - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.
 - 5. Factory-fabricated tank heads and tank side panels.

D. Metal Jacket:

- 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - Childers Products, Division of ITW.
 - PABCO Metals Corporation. b.
 - RPR Products, Inc. C.
- 2. Aluminum Jacket: Comply with ASTM B 209, Alloy 3003, 3005, 3105 or 5005, Temper H-14.
 - a. Factory cut and rolled to size.
 - Finish and thickness are indicated in field-applied jacket schedules. b.
 - Moisture Barrier for Indoor Applications: 1-mil-thick, heat-bonded polyethylene and C.
 - d. Moisture Barrier for Outdoor Applications: 3-mil-thick, heat-bonded polyethylene and kraft paper.
 - Factory-Fabricated Fitting Covers: e.
 - 1) Same material, finish, and thickness as jacket.
 - Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius 2) elbows.
 - 3) Tee covers.
 - 4) Flange and union covers.
 - 5) End caps.
 - Beveled collars. 6)
 - 7) Valve covers
 - 8) Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

HVAC INSULATION 230700 - 7 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.6 **TAPES**

- Α. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Avery Dennison Corporation, Specialty Tapes Division.
 - 2. Compac Corp.
 - Ideal Tape Co., Inc., an American Biltrite Company. 3.
 - 4. Venture Tape.
- В. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive. complying with ASTM C 1136.
 - 1. Width: 3 inches.
 - 2. Thickness: 11.5 mils.
 - 3. Adhesion: 90 ounces force/inch in width.
 - 4. Elongation: 2 percent.
 - 5. Tensile Strength: 40 lbf/inch in width.
 - ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape. 6.
- C. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.
 - Width: 3 inches. 1.
 - 2. Thickness: 6.5 mils.
 - 3. Adhesion: 90 ounces force/inch in width.
 - 4. Elongation: 2 percent.
 - 5. Tensile Strength: 40 lbf/inch in width.
 - FSK Tape Disks and Squares: Precut disks or squares of FSK tape. 6.
- D. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.
 - 1. Width: 2 inches.
 - 2. Thickness: 3.7 mils.
 - 3. Adhesion: 100 ounces force/inch in width.
 - Elongation: 5 percent. 4.
 - 5. Tensile Strength: 34 lbf/inch in width.

2.7 **SECUREMENTS**

A. Bands:

- 1. Stainless Steel: ASTM A 167 or ASTM A 240, Type 304; 0.015 inch thick, ½ inch wide with wing or closed seal.
- 2. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, ½ inch wide with wing or closed seal.
- Springs: Twin spring set constructed of stainless steel with ends flat and slotted to accept 3. metal bands. Spring size determined by manufacturer for application.

HVAC INSULATION 230700 - 8 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Insulation Pins and Hangers:

- Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
- 2. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-½-inch galvanized carbon-steel washer.
- 3. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick, galvanized-steel or aluminum sheet, with beveled edge sized as required to hold insulation securely in place but not less than 1-½ inches in diameter.
 - a. Protect ends with capped self-locking washers incorporating a spring steel insert to ensure permanent retention of cap in exposed locations.
- C. Staples: Outward-clinching insulation staples, nominal 3/4-inch-wide, stainless steel or Monel.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation and other conditions affecting performance of insulation application.
 - 1. Verify that systems and equipment to be insulated have been tested and are free of defects.
 - 2. Verify that surfaces to be insulated are clean and dry.
 - 3. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Surface Preparation: Clean and prepare surfaces to be insulated.

3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of equipment, ducts and fittings, and piping including fittings, valves, and specialties.
- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of equipment, duct system, and pipe system as specified in insulation system schedules.

HVAC INSULATION 230700 - 9 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- G. Keep insulation materials dry during application and finishing.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
 - 1. Install insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
 - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
 - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- K. Install insulation with factory-applied jackets as follows:
 - 1. Draw jacket tight and smooth.
 - 2. Cover circumferential joints with 3-inch-wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
 - 3. Overlap jacket longitudinal seams at least 1-½ inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 2 inches o.c.
 - a. For below ambient services, apply vapor-barrier mastic over staples.
 - 4. Cover joints and seams with tape as recommended by insulation material manufacturer to maintain vapor seal.
 - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct and pipe flanges and fittings.
- L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

HVAC INSULATION 230700 - 10 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- O. For above ambient services, do not install insulation to the following:
 - 1. Vibration-control devices.
 - 2. Testing agency labels and stamps.
 - 3. Nameplates and data plates.
 - 4. Manholes.
 - 5. Handholes.
 - 6. Cleanouts.

3.4 PENETRATIONS

- A. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.
- B. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- C. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions. Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.
 - 1. Comply with requirements in Division 07 Section "Penetration Firestopping" and fire-resistive joint sealers.
- D. Insulation Installation at Floor Penetrations:
 - 1. Duct: Install insulation continuously through floor penetrations that are not fire rated. For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
 - 2. Pipe: Install insulation continuously through floor penetrations.
 - 3. Seal penetrations through fire-rated assemblies. Comply with requirements in Division 07 Section "Penetration Firestopping."

3.5 EQUIPMENT, TANK, AND VESSEL INSULATION INSTALLATION

- A. Mineral Fiber, Pipe and Tank Insulation Installation for Tanks and Vessels: Secure insulation with adhesive and anchor pins and speed washers.
 - 1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of tank and vessel surfaces.
 - Groove and score insulation materials to fit as closely as possible to equipment, including contours. Bevel insulation edges for cylindrical surfaces for tight joints. Stagger end joints.
 - 3. Protect exposed corners with secured corner angles.

HVAC INSULATION 230700 - 11 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Install adhesively attached or self-sticking insulation hangers and speed washers on 4. sides of tanks and vessels as follows:
 - Do not weld anchor pins to ASME-labeled pressure vessels.
 - Select insulation hangers and adhesive that are compatible with service b. temperature and with substrate.
 - C. On tanks and vessels, maximum anchor-pin spacing is 3 inches from insulation end joints, and 16 inches o.c. in both directions.
 - d. Do not overcompress insulation during installation.
 - Cut and miter insulation segments to fit curved sides and domed heads of tanks e. and vessels.
 - f. Impale insulation over anchor pins and attach speed washers.
 - Cut excess portion of pins extending beyond speed washers or bend parallel with g. insulation surface. Cover exposed pins and washers with tape matching insulation facing.
- 5. Secure each layer of insulation with stainless-steel or aluminum bands. Select band material compatible with insulation materials.
- 6. Where insulation hangers on equipment and vessels are not permitted or practical and where insulation support rings are not provided, install a girdle network for securing insulation. Stretch prestressed aircraft cable around the diameter of vessel and make taut with clamps, turnbuckles, or breather springs. Place one circumferential girdle around equipment approximately 6 inches from each end. Install wire or cable between two circumferential girdles 12 inches o.c. Install a wire ring around each end and around outer periphery of center openings, and stretch prestressed aircraft cable radially from the wire ring to nearest circumferential girdle. Install additional circumferential girdles along the body of equipment or tank at a minimum spacing of 48 inches o.c. Use this network for securing insulation with tie wire or bands.
- Stagger joints between insulation layers at least 3 inches. 7.
- 8 Install insulation in removable segments on equipment access doors, manholes, handholes, and other elements that require frequent removal for service and inspection.
- 9. Bevel and seal insulation ends around manholes, handholes, ASME stamps, and nameplates.
- 10. For equipment with surface temperatures below ambient, apply mastic to open ends. joints, seams, breaks, and punctures in insulation.
- B. Flexible Elastomeric Thermal Insulation Installation for Tanks and Vessels: Install insulation over entire surface of tanks and vessels.
 - 1. Apply 100 percent coverage of adhesive to surface with manufacturer's recommended adhesive.
 - 2. Seal longitudinal seams and end joints.
- C. Insulation Installation on Pumps:
 - Apply 100 percent coverage of adhesive to surface with manufacturer's recommended 1. adhesive.
 - 2. Seal longitudinal seams and end joints.
 - For below ambient services, install a vapor barrier at seams, joints, and penetrations. 3. Seal between flanges with replaceable gasket material to form a vapor barrier.

HVAC INSULATION 230700 - 12 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.6 GENERAL PIPE INSULATION INSTALLATION

- Α. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:
 - 1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity, unless otherwise indicated.
 - 2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
 - 3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
 - 4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts, Fill joints, seams, and irregular surfaces with insulating cement.
 - 5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below ambient services, provide a design that maintains vapor barrier.
 - 6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
 - Cover segmented insulated surfaces with a layer of finishing cement and coat with a 7. mastic. Install vapor-barrier mastic for below ambient services and a breather mastic for above ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
 - 8. For services not specified to receive a field-applied jacket except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
 - Stencil or label the outside insulation jacket of each union with the word "UNION." Match 9. size and color of pipe labels.
- Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, C. test connections, flow meters, sensors, switches, and transmitters on insulated pipes, vessels, and equipment. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.

HVAC INSULATION 230700 - 13 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Install removable insulation covers at locations indicated. Installation shall conform to the D. following:

3.7 FLEXIBLE ELASTOMERIC INSULATION INSTALLATION

- Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate A. openings in insulation that allow passage of air to surface being insulated.
- B. Insulation Installation on Pipe Flanges:
 - 1. Install pipe insulation to outer diameter of pipe flange.
 - 2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
 - 3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
 - 4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- C. Insulation Installation on Pipe Fittings and Elbows:
 - 1. Install mitered sections of pipe insulation.
 - 2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- D. Insulation Installation on Valves and Pipe Specialties:
 - 1. Install preformed valve covers manufactured of same material as pipe insulation when available.
 - 2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
 - 3. Install insulation to flanges as specified for flange insulation application.
 - Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.8 MINERAL-FIBER INSULATION INSTALLATION

- Α. Insulation Installation on Straight Pipes and Tubes:
 - 1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
 - 2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
 - For insulation with factory-applied jackets on above ambient surfaces, secure laps with 3. outward clinched staples at 6 inches o.c.
 - For insulation with factory-applied jackets on below ambient surfaces, do not staple 4. longitudinal tabs but secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

HVAC INSULATION 230700 - 14 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Insulation Installation on Pipe Flanges:

- 1. Install preformed pipe insulation to outer diameter of pipe flange.
- 2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
- 3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
- 4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

- 1. Install preformed sections of same material as straight segments of pipe insulation when available.
- 2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

- 1. Install preformed sections of same material as straight segments of pipe insulation when available.
- 2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
- Arrange insulation to permit access to packing and to allow valve operation without 3. disturbing insulation.
- 4. Install insulation to flanges as specified for flange insulation application.

E. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.

- Apply adhesives according to manufacturer's recommended coverage rates per unit 1. area, for 100 percent coverage of duct and plenum surfaces.
- 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
- 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. b. each way, and 3 inches maximum from insulation joints, Install additional pins to hold insulation tightly against surface at cross bracing.
 - Pins may be omitted from top surface of horizontal, rectangular ducts and C. plenums.
 - d. Do not overcompress insulation during installation.
 - Impale insulation over pins and attach speed washers. e.
 - f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.

HVAC INSULATION 230700 - 15 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- For ducts and plenums with surface temperatures below ambient, install a continuous 4. unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from 1 edge and 1 end of insulation segment. Secure laps to adjacent insulation section with ½-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
 - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vaporbarrier seal.
 - Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot b. intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to 2 times the insulation thickness but not less than 3 inches.
- 5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
- 6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
- 7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.
- F. Board Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
 - 1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 100 percent coverage of duct and plenum surfaces.
 - 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
 - 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - On duct sides with dimensions larger than 18 inches, space pins 16 inches o.c. b. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
 - Pins may be omitted from top surface of horizontal, rectangular ducts and C. plenums.
 - d. Do not overcompress insulation during installation.
 - Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.

HVAC INSULATION 230700 - 16 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- For ducts and plenums with surface temperatures below ambient, install a continuous 4. unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from 1 edge and 1 end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
 - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vaporbarrier seal.
 - Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot b. intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to 2 times the insulation thickness but not less than 3 inches.
- 5. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
- 6. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

3.9 FIELD-APPLIED JACKET INSTALLATION

- Where glass-cloth jackets are indicated, install directly over bare insulation or insulation with A. factory-applied jackets.
 - Draw jacket smooth and tight to surface with 2-inch overlap at seams and joints. 1.
 - 2. Embed glass cloth between two 0.062-inch-thick coats of lagging adhesive.
 - 3. Completely encapsulate insulation with coating, leaving no exposed insulation.
- B. Where FSK jackets are indicated, install as follows:
 - 1. Draw jacket material smooth and tight.
 - Install lap or joint strips with same material as jacket. 2.
 - 3. Secure jacket to insulation with manufacturer's recommended adhesive.
 - 4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch-wide joint strips at end
 - 5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.
- C. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints; for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturer's recommended adhesive.
 - 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

HVAC INSULATION 230700 - 17 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end D. joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

3.10 FIRE-RATED INSULATION SYSTEM INSTALLATION

- Where fire-rated insulation system is indicated, secure system to ducts and duct hangers and A. supports to maintain a continuous fire rating.
- B. Insulate duct access panels and doors to achieve same fire rating as duct.
- C. Install firestopping at penetrations through fire-rated assemblies. Fire-stop systems are specified in Division 07 Section "Penetration Firestopping."

3.11 **FINISHES**

Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of Α. insulation manufacturer's recommended protective coating.

3.12 FIELD QUALITY CONTROL

- Perform tests and inspections. Α.
- B. Tests and Inspections:
 - 1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each duct system defined in the "Duct Insulation Schedule, General" Article.
 - Inspect field-insulated equipment, randomly selected by Architect, by removing field-2. applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each type of equipment defined in the "Equipment Insulation Schedule" Article. For large equipment, remove only a portion adequate to determine compliance.
 - 3. Inspect pipe, fittings, strainers, and valves, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to three locations of straight pipe for each pipe service defined in the "Piping Insulation Schedule, General" Article.
- C. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

3.13 DUCT INSULATION SCHEDULE, GENERAL

- A. Plenums and Ducts Requiring Insulation:
 - 1. Indoor, concealed supply and outdoor air.

HVAC INSULATION 230700 - 18 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Indoor, exposed supply and outdoor air.
- Indoor, concealed return and relief air located in non-conditioned space. 3.
- Indoor, exposed return and relief air located in non-conditioned space, mechanical room. 4.

Items Not Insulated: B.

- 1. Metal ducts with duct liner of sufficient thickness to comply with energy code and ASHRAE/IESNA 90.1.
- 2. Factory-insulated flexible ducts.
- Factory-insulated plenums and casings. 3.
- Flexible connectors. 4.
- Vibration-control devices. 5.
- 6. Factory-insulated access panels and doors.

3.14 INDOOR DUCT AND PLENUM INSULATION SCHEDULE

- Concealed, rectangular, round and flat-oval, supply-air, outdoor-air, return air and relief-air duct Α. insulation shall be one of the following:
 - 1. Mineral-Fiber Blanket: 1-1/2 inches thick.
 - 2. Mineral-Fiber Board: 1-1/2 inches thick.
- B. Exposed rectangular, round and flat-oval, supply-air, outdoor-air, return-air and relief-air duct insulation shall be the following:
 - 1. Mineral-Fiber Board: 1-1/2 inches thick.
- Exposed in Mechanical Rooms, supply-air, return-air, outdoor-air and relief-air plenum C. insulation shall be the following:
 - 1. Mineral-Fiber Board: 2 inches thick.

3.15 PIPING INSULATION SCHEDULE, GENERAL

- Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for Α. each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.
- B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
 - 1. Drainage piping located in crawl spaces.
 - Underground piping. 2.
 - Chrome-plated pipes and fittings unless there is a potential for personnel injury. 3.
 - Flexible Connectors. 4.
 - Vibration Control Devices.

HVAC INSULATION 230700 - 19 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.16 INDOOR PIPING INSULATION SCHEDULE

- Service: Condensate drain piping. A.
 - 1. Operating Temperature: 35 to 75 deg C.
 - Insulation Material: Flexible elastomeric. 2.
 - 3. Insulation Thickness: 1 inch.
 - 4. Field-Applied Jacket: None.
 - Vapor Retarder Required: Yes. 5.
 - 6. Finish: None.
- B. Service: Heating hot-water supply and return.
 - Operating Temperature: 100 to 200 deg F. 1.
 - Insulation Material: Mineral fiber. 2.
 - 3. Insulation Thickness: Apply the following insulation thicknesses:
 - Pipe Sizes up to 1-1/2": 1 inch. a.
 - Pipe Sizes 2" and Larger: 2 inches. b.
 - 4. Field-Applied Jacket: None.
 - Vapor Retarder Required: No. 5.
 - Finish: None. 6.

END OF SECTION 230700

HVAC INSULATION 230700 - 20 Project No.: CP242241

SECTION 230900 - CONTROL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

- A. University of Missouri Controls Specification.
- B. This section contains requirements for pneumatic, electric and digital control systems as indicated on the contract drawings.
- C. Contractor is responsible for providing, installing and connecting all sensors, pneumatic actuators, control valves, control dampers, electrical components and all interconnecting pneumatic tubing and electrical wiring between these devices and up to the Direct Digital Controller (DDC).
- D. DDC systems consist of Johnson Controls METASYS controllers. Contractor shall install owner provided control enclosures. Owner will provide and install controllers. After all equipment has been installed, wired and piped, Owner will be responsible for all termination connections at the DDC controller's and for checking, testing, programming and start-up of the control system. Contractor must be on site at start-up to make any necessary hardware adjustments as required.
- E. Once each mechanical system is completely operational under the new control system, contractor shall make any final connections and adjustments. For controls renovation jobs, contractor shall remove all unused sensors, operators, panels, wiring, tubing, conduit, etc. Owner shall have the option of retaining any removed pneumatic controls.

1.2 RELATED SECTIONS

A. Drawings and general provisions of Contract, including General and Special Conditions apply to work of this section.

1.3 QUALITY ASSURANCE

A. Contractor's Qualifications:

1. Contractor shall be regularly engaged in the installation of digital control systems and equipment, of types and sizes required. Contractor shall have a minimum of five years' experience installing digital control systems. Contractor shall supply sufficient and competent supervision and personnel throughout the project in accordance with General Condition's section 3.4.1 and 3.4.4.

B. Codes and Standards:

1. Electrical Standards: Provide electrical components of control systems which have been UL-listed and labeled, and comply with NEMA standards.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. NEMA Compliance: Comply with NEMA standards pertaining to components and devices for control systems.
- 3. NFPA Compliance: Comply with NFPA 90A "Standard for the Installation of Air Conditioning and Ventilating Systems" where applicable to controls and control sequences.
- 4. NFPA Compliance: Comply with NFPA 70 "National Electric Code".

1.4 SUBMITTALS

- A. Shop Drawings: Submit shop drawings for each control system, containing the following information:
- B. Product data for each damper, valve, and control device.
- C. Schematic flow diagrams of system showing fans, pumps, coils, dampers, valves, and control devices.
- D. Label each control device with setting or adjustable range of control.
- E. Indicate all required electrical wiring. Clearly differentiate between portions of wiring that are factory-installed and portions to be field-installed.
- F. Provide details of faces on control panels, including controls, instruments, and labeling.
- G. Include written description of sequence of operation.
- H. Provide wiring diagrams of contractor provided interface and I/O panels.
- I. Provide field routing of proposed network bus diagram listing all devices on bus.

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT

A. Air Piping:

- 1. Copper Tubing: Seamless copper tubing, Type M or L, ASTM B 88; wrought-copper solder-joint fittings, ANSI B16.22; except brass compression-type fittings at connections to equipment.
- 2. Flex Tubing: Virgin Polyethylene non-metallic tubing, ASTM D 2737, with flame-retardant harness for multiple tubing. Use compression or push-on polyethylene fittings. Tubing used above suspended ceilings to be plenum rated per NFPA 90A. See section 3.1.b for locations where flex tubing can be used.
- 3. Copper to polyethylene connections shall be compression barbed fittings or solder barbed fittings.

B. Conduit and Raceway:

1. Electrical Metallic Tubing: EMT and fittings shall conform to ANSI C80.3.

CONTROL SYSTEMS 230900 - 2 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Surface Metal Raceway and Fittings: Wiremold 500, Ivory, or approved equal.
- 3. Flexible Metal Conduit: Indoors, per National Electric Code for connection to moving or vibrating equipment.
- 4. Liquidtight Flexible Conduit: Outdoors, per National Electric Code for connection to moving or vibrating equipment.
- C. Control Valves: Provide factory fabricated pneumatic or electric control valves of type, body material, and pressure class as indicated on the drawings. Butterfly style control valves are not acceptable except for two position applications. Equip control valves with heavy-duty actuators, with proper shutoff rating for each individual application.
 - 1. Steam and Hot Water:
 - a. Manufacturer: Do not allow KMC valves and actuators.
 - b. Water Service Valves: Equal percentage characteristics.
 - c. Steam Service Valves: Equal percentage characteristics.
 - d. Single Seated Valves: Cage type trim, providing seating and guiding surfaces for plug on "top and bottom" guided plugs.
 - e. Valve Trim and Stems: Polished stainless steel.
 - f. Packing: Spring-loaded Teflon, self-adjusting.
 - g. Control valves should have a minimum 100 psi close-off rating for chilled water applications.
 - 2. Hydronic Chilled Water and Heating Water:
 - a. At minimum, hydronic control valves shall be pressure independent. High performing energy monitoring control valves may be considered depending on the project. The flow through the valve shall not vary more than +/- 5% due to system pressure fluctuations across the valve in the selected operating range. The control valve shall accurately control the flow from 1 to 100% full rated flow.
 - b. The valve bodies shall be of cast iron, steel or bronze and rated for 150 PSI working pressure. All internal parts shall be stainless steel, steel, Teflon, brass, or bronze.
 - c. DeltaP Valves manufactured by Flow Control Industries, Belimo, Danfoss Series, or approved equal.
 - d. The valves shall have pressure taps across the valve for measuring the pressure drop across the valve. The pressure taps shall have ½-inch extensions for accessibility.
 - e. Control valves shall be installed with unions or flanges as necessary for easy removal and replacement.
 - f. Valve Tag shall include the model number, AHU being served, design flow, and maximum flow for that valve.
 - g. The control valves shall be delivered preset to the scheduled design flow and should be capable of reaching 110% of the design flow to allow for field adjustment for capacity changes.
- D. Control Dampers: Ruskin CD-50 or approved equal.
 - 1. Provide dampers with parallel blades for 2- position control.
 - 2. Provide opposed blades for modulating control.
 - 3. Dampers shall be low leakage design with blade and edge seals.
 - 4. Provide multiple sections and operators as required by opening size and sequence of operations, as indicated on the contract drawings.

CONTROL SYSTEMS 230900 - 3 Project No.: CP242241 February 27, 2024

- E. Electric Actuators: Johnson Controls, Bray, Belimo, TAC or approved equal. KMC actuators are not approved. Size electric actuators to operate their appropriate dampers or valves with sufficient reserve power to provide smooth modulating action or 2-position action as specified. If mixed air AHU has return air, exhaust air and outside air dampers that are not mechanically linked then static safety switch must be installed and wired to safety circuit. Spring return actuators should be provided on heat exchanger control valves or dampers or as specified on the drawings. Control signal shall be 0 to 10 VDC unless otherwise specified on drawings. Actuators with integral damper end switch are acceptable. For VAV reheat valves, actuators shall have a manual override capability to aid in system flushing, startup, and balancing.
- F. Air and Hot Water Electronic Temperature Sensors:
 - 1. All electronic temperature sensors shall be compatible with Johnson METASYS systems.
 - Sensors shall be 1,000 ohm platinum, resistance temperature detectors (RTDs) with two
 wire connections. Duct mounted sensors shall be averaging type. Contractor may install
 probe type when field conditions prohibit averaging type, but must receive permission
 from Owner's Representative.
 - 3. Coordinate thermowell manufacturer with RTD manufacturer. Thermowells that are installed by the contractor, but are to have the RTD installed by owner, must be Johnson Controls Inc. series WZ-1000.
- G. Electronic Temperature Sensors and Transmitters:
 - 1. Chilled Water, Tower Water, Heating Hot Water, and Steam Temperature Sensors:
 - a. General: The RTD/Temperature Transmitter/Thermowell assembly shall come as a complete assembly from a single manufacturer. The Assembly shall be suitable for use in the accurate measurement of Chilled/Tower/Hot Water and steam temperatures in a mechanical room environment.
 - b. Calibration: Each RTD must be match calibrated to the Transmitter via NIST traceable calibration standards. Results are to be programmed into the transmitter. Results are to be presented on report as after condition at the specified calibration points. Assembly shall not be approved for installation until Owner has received all factory calibration reports.
 - c. RTD:
 - 1) RTD type: 2-wire or 3-wire 100 ohm platinum class A
 - 2) Outside Diameter: 0.25 inch
 - 3) Tolerance: +/- 0.06% Type A 4) Stability: +/- 0.1 % over one year.
 - 5) TCR: 0.00385 (ohm/ohm/°C).
 - 6) RTD shall be tip sensitive.
 - Resistance vs. Temperature table for the RTD must be provided to the Owner.
 - d. Transmitter:
 - 1) Transmitter shall be match calibrated to the RTD and assembled as a matched pair.
 - 2) Type: 2 wire (loop powered)
 - 3) Input: 2 or 3 wire 100 ohm platinum class A or class B RTD
 - 4) Output: Output shall be a 4-20 mA signal linear to temperature

UNIVERSITY OF MISSOURI

ISSUED FOR BID

5) Calibrated Span:

a) Chilled Water: 30 °F to 130 °F.
 b) Tower Water: 30 °F to 130 °F.
 c) Hot Water: 100 °F to 250 °F.
 d) Steam: 150 °F to 450 °F

- 6) Calibration Accuracy, including total of all errors, of the Transmitter & RTD matched pair over the entire span shall be within +/- 0.2% of the calibrated span or +/- 0.18 °F, whichever is greater.
- 7) Supply Voltage: 24 VDC.
- 8) Ambient Operating Temp.: 32 to 122 °F
- 9) Epoxy potted for moisture resistance.
- 10) Mounting: Transmitter shall be mounted in the RTD connection head.

e. Thermowell

- 1) Thermowell shall be suitable for immersion in chilled/hot water and steam.
- 2) Thermowell shall be reduced tip.
- Thermowell shall be one piece stainless steel machined from solid bar stock.
- 4) Thermowell shall have 1/2" NPT process connection to pipe thred-o-let.
- 5) Thermowell Insertion depth shall be ½ the inside pipe diameter but not to exceed 10".

f. Assembly:

- 1) Assembly configuration: Spring loaded RTD with thermowell-double ended hex-connection head.
- 2) Connection head shall be cast aluminum with chain connecting cap to body, have 1/2" NPT process and 3/4" NPT conduit connections, and a sealing gasket between cap and body.
- g. RTD/Temperature Transmitter/Thermowell assembly shall be the following or approved equal:
 - 1) Manufacturer: Pyromation, Inc.
 - 2) Chilled Water: RAF185L-S4C[length code]08-SL-8HN31,TT440-385U-S(30-130)F with calibration SMC(40,60)F
 - Tower Water: RAF185L-S4C[length code]08-SL-8HN31,TT440-385U-S(5130)F with calibration SMC(55,85)F
 - 4) Hot Water: RAF185L-S4C[length code]08T2-SL-8HN31,TT440-385U-S(100-250)F with calibration SMC(140,180)F
 - 5) Steam: RAT185H-S4C[length code]08T2-SL-8HN31,TT440-385U-S(150-450)F with calibration SMC(300,350)F
- H. Occupant Override: Provide wall mounted occupant override button in locations shown on drawings.

CONTROL SYSTEMS 230900 - 5 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- I. Low Limit Controllers: Provide unit-mounted low limit controllers, of rod-and-tube type, with an adjustable set point and a manual reset. Capillary shall be of adequate length to horizontally traverse face of cooling coil every 12". Multiple low limit controllers may be required for large coils. Controller shall have an extra set of contactors for connection to control panel for alarm status. Locate the thermostat case and bellows where the ambient temperature is always warmer than the set point.
 - 1. Freeze Stats: Johnson Controls model A70HA-1 or approved equal.
- J. Humidistats: Humidistats must be contamination resistant, capable of ±2% RH accuracy, have field adjustable calibration and provide a linear proportional signal.
 - 1. HD20K-T91 or equivalent.
- K. Humidity High Limit
 - 1. Multi-function device that can function as a high limit or proportional override humidity controller, as stand-alone proportional controller, or a stand-alone two-position controller.
 - a. Johnson Controls TRUERH HL-67N5-8N00P or approved equal.
- L. Carbon Dioxide Sensor:
 - 1. Wall Mount: ACI Model ESENSE-R.
 - 2. Duct Mount: ACI Model ESENSE-D.
- M. Fan/Pump Status: Status points for fan or pump motors with a VFD must be connected to the terminal strip of the VFD for status indication. Current switches: Current switches are required for fan and pump statuses that are not connected to a VFD. The switches must have an adjustable trip setpoint with LED indication and be capable of detecting broken belts or couplings. Units shall be powered by monitored line, UL listed and CE certified, and have a five year warranty.
 - 1. Kele, Hawkeye or approved equal.
- N. Relays Used for Fan and Pump Start/Stop: Must have LED indication and be mounted externally of starter enclosure or VFD.
 - 1. Kele, RIBU1C or approved equal.
- O. Power Supply Used to Provide Power to Contractor-Provided Control Devices: Shall have adjustable DC output, screw terminals, overload protection and 24 VAC and 24 VDC output.
 - 1. Kele, DCPA-1.2 or approved equal.
- P. Pressure Differential Switch:
 - 1. Fans: NECC model DP222 or approved equal.

CONTROL SYSTEMS 230900 - 6 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Q. Differential Pressure Transmitter: Provide units with linear analog 4-20mA output proportional to differential pressure, compatible with the Johnson METASYS Systems.
 - 1. Water: Units shall be wet/wet differential pressure capable of a bi-directional pressure range of +/- 50 psid. Accuracy shall be +/- 0.25% full scale with a compensated temperature range of 30 to 150 deg F and a maximum working pressure of 250 psig.
 - 2. Install transmitter in a pre-manufactured assembly with shut off valves, vent valves and a bypass valve.
 - a. Setra model 230 with Kele model 3-VLV, three valve manifold or approved equal.
 - 3. Air: Units shall be capable of measuring a differential pressure of 0 to 5 in. WC. Accuracy shall be +/- 1.0% full scale with a compensated temperature range of 40 to 149 deg F and a maximum working pressure of 250 psig.
 - Setra model 267, or approved equal.
 - b. Shall be installed in control panel and piped 2/3 down the duct unless shown otherwise or approved by owner's representative.
- R. Building Static Pressure: Transducer shall utilize a ceramic capacitive sensing element to provide a stable linear output over the specified range of building static pressure. Transducer shall be housed in a wall-mounted enclosure with LCD display. Transducer shall have the following capabilities:
 - 1. Input Power: 24 VAC
 - 2. Output: 0-10 VDC.
 - 3. Pressure Range: -0.25 to +0.25 inches w.g.
 - 4. Display: 3-1/2 digit LCD, displaying pressure in inches w.g.
 - 5. Accuracy: +/- 1.0% combined linearity and hysteresis.
 - 6. Temperature Effect: 0.05% / deg C.
 - 7. Zero drift (1 year): 2.0% max.
 - 8. Zero Adjust: Push-button auto-zero and digital input.
 - 9. Operating Environment: 0 to 140 deg F, 90% RH (non-condensing).
 - 10. Fittings: Brass barbs, 1/8" O.D.
 - 11. Enclosure: High-impact ABS plastic.
 - 12. Outside Air Sensor Pickup Port: UV stabilized thermoplastic or aluminum "can" enclosure to shield outdoor pressure sensing tube from wind effects. BAPI ZPS-ACC10-rooftop mount, wall mount, or equivalent.
 - 13. Transducer shall be Veris Industries Model PXPLX01S, equivalent from Setra, or approved equal.
- S. High Static Pressure Limit Switch: Provide pressure high limit switch to open contact in fan circuit to shut down the supply fan when the inlet static pressure rises above the set point. Provide with an adjustable set point, a manual reset button, 2 SPST (normally closed) contacts, and ½" compression fittings.
 - 1. Kele model AFS-460-DDS, or approved equal.
- T. Airflow/Temperature Measurement Devices
 - 1. Provide airflow/temperature measurement devices where indicated on the plans. Fan inlet measurement devices shall not be substituted for duct or plenum measurement devices indicated on the plans.

- 2. The measurement device shall consist of one or more sensor probe assemblies and a single, remotely mounted, microprocessor-based transmitter. Each sensor probe assembly shall contain one or more independently wired sensor housings. The airflow and temperature readings calculated for each sensor housing shall be equally weighted and averaged by the transmitter prior to output. Pitot tubes and arrays are not acceptable. Vortex shedding flow meters are not acceptable.
- 3. All Sensor Probe Assemblies:
 - a. Each sensor housing shall be manufactured of a U.L. listed engineered thermoplastic.
 - b. Each sensor housing shall utilize two hermetically sealed, bead-in-glass thermistor probes to determine airflow rate and ambient temperature. Devices that use "chip" or diode case type thermistors are unacceptable. Devices that do not have 2 thermistors in each sensor housing are not acceptable.
 - c. Each sensor housing shall be calibrated at a minimum of 16 airflow rates and have an accuracy of +/-2% of reading over the entire operating airflow range. Each sensor housing shall be calibrated to standards that are traceable to the National Institute of Standards and Technology (NIST).
 - Devices whose accuracy is the combined accuracy of the transmitter and sensor probes must demonstrate that the total accuracy meets the performance requirements of this specification throughout the measurement range.
 - d. The operating temperature range for the sensor probe assembly shall be -20° F to 160 F. The operating humidity range for the sensor probe assembly shall be 0-99% RH (non-condensing).
 - e. Each temperature sensor shall be calibrated at a minimum of 3 temperatures and have an accuracy of +/-0.15°F over the entire operating temperature range. Each temperature sensor shall be calibrated to standards that are traceable to the National Institute of Standards and Technology (NIST).
 - f. Each sensor probe assembly shall have an integral, U.L. listed, plenum rated cable and terminal plug for connection to the remotely mounted transmitter. All terminal plug interconnecting pins shall be gold plated.
 - g. Each sensor assembly shall not require matching to the transmitter in the field.
 - h. A single manufacturer shall provide both the airflow/temperature measuring probe(s) and transmitter at a given measurement location.
- 4. Duct and Plenum Sensor Probe Assemblies:
 - a. Sensor housings shall be mounted in an extruded, gold anodized, 6063 aluminum tube probe assembly. Thermistor probes shall be mounted in sensor housings using a waterproof marine grade epoxy resin. All wires within the aluminum tube shall be Kynar coated.
 - b. The number of sensor housings provided for each location shall be as follows:

1)	Area (sq. ft.)	Sensors
	<2	4
	2 to <4	6
	4 to <8	8
	8 to <16	12
	>=16	16

- c. Probe assembly mounting brackets shall be constructed of 304 stainless steel. Probe assemblies shall be mounted using one of the following options:
 - 1) Insertion mounted through the side or top of the duct.
 - 2) Internally mounted inside the duct or plenum.
 - 3) Standoff mounted inside the plenum.
- d. The operating airflow range shall be 0 to 5,000 FPM unless otherwise indicated on the plans.

5. Fan Inlet Sensor Probe Assemblies:

- a. Sensor housings shall be mounted on 304 stainless steel blocks.
- Mounting rods shall be field adjustable to fit the fan inlet and constructed of nickel plated steel.
- c. Mounting feet shall be constructed of 304 stainless steel.
- d. The operating airflow range shall be 0 to 10,000 FPM unless otherwise indicated on the plans.

6. Transmitters:

- a. The transmitter shall have a 16 character alpha-numeric display capable of displaying airflow, temperature, system status, configuration settings and diagnostics. Configuration settings and diagnostics shall be accessed through a pushbutton interface on the main circuit board. Airflow shall be field configurable to be displayed as a velocity or a volumetric rate.
- b. The transmitter shall be capable of independently monitoring and averaging up to 16 individual airflow and temperature readings. The transmitter shall be capable of displaying the airflow and temperature readings of individual sensors on the LCD display.
- c. The transmitter shall have a power switch and operate on 24 VAC (isolation not required). The transmitter shall use a switching power supply fused and protected from transients and power surges.
- d. All interconnecting pins, headers and connections on the main circuit board, option cards and cable receptacles shall be gold plated.
- e. The operating temperature range for the transmitter shall be -20° F to 120° F. The transmitter shall be protected from weather and water.
- f. The transmitter shall be capable of communicating with the host controls using one of the following interface options:
 - Linear Analog Output Signal: Field selectable, fuse protected and isolated, 0-10VDC and 4-20mA (4-wire).
 - 2) RS-485: Field selectable BACnet-MS/TP, ModBus-RTU and Johnson Controls N2 Bus.
 - 10 Base-T Ethernet: Field selectable BACnet Ethernet, BACnet-IP, ModBus-TCP and TCP/IP.
 - 4) LonWorks Free Topology.
- 7. The measuring device shall be UL listed as an entire assembly.
- 8. The manufacturer's authorized representative shall review and approve placement and operating airflow rates for each measurement location indicated on the plans. A written report shall be submitted to the consulting mechanical engineer if any measurement locations do not meet the manufacturer's placement requirements.

CONTROL SYSTEMS 230900 - 9 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

9. Manufacturer:

- a. Primary flow elements, sensors, meters and transducers shall be EBTRON, Inc. Model GTx116-P and GTx116-F or approved equal.
- b. The naming of any manufacturer does not automatically constitute acceptance of this standard product nor waive their responsibility to comply totally with all requirements of the proceeding specification.
- U. Electrical Requirements: Provide electric-pneumatic switches, electrical devices, and relays that are UL-listed and of type which meet current and voltage characteristics of the project. All devices shall be of industrial/ commercial grade or better. Residential types will be rejected.
 - 1. EP Switches: Landis & Gyr Powers, Inc. Series 265 Junction Box Type or approved equal.
 - Relays: Relays shall have an LED status indicator, voltage transient suppression, Closed-Open-Auto switch, plastic enclosure, and color coded wires. Kele model RIBU1C or approved equal.

PART 3 - EXECUTION

3.1 INSTALLATION OF CONTROL SYSTEMS

A. General: Install systems and materials in accordance with manufacturer's instructions, roughing-in drawings and details shown on drawings.

B. Control Air Piping:

- 1. All control air piping shall be copper. Exception: Flexible Tubing may be used for a maximum of two (2) feet at connections to equipment (except for steam control valves) and inside control cabinets.
- 2. Provide copper tubing with a maximum unsupported length of 3'-0".
- 3. Pressure Test control air piping at 30 psi for 24 hours. Test fails if more than 5 PSI loss occurs.
- 4. Fasten flexible connections bridging cabinets and doors, neatly along hinge side, and protect against abrasion. Tie and support tubing neatly.
- 5. Number-code or color-code tubing, except local individual room control tubing, for future identification and servicing of control system.
- 6. All control tubing at control panel shall be tagged and labeled during installation to assist owner in making termination connections at control panel.
- 7. Provide pressure gages on each output device.
- 8. Paint all exposed control tubing to match existing.
- C. Raceway: Raceway is to be installed in accordance with the National Electric Code. Use of flexible metal conduit or liquidtight flexible conduit is limited to 36" to connect from EMT to devices subject to movement. Flexible raceway is not to be used to compensate for misalignment of raceway during installation.

CONTROL SYSTEMS 230900 - 10 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Control Wiring: Install control wiring in raceway, without splices between terminal points, color-coded. Install in a neat workmanlike manner, securely fastened. Install in accordance with National Electrical Code.
 - 1. Install circuits over 25-volt with color-coded No. 12 stranded wire.
 - 2. Install electronic circuits and circuits under 25-volts with color-coded No. 18 stranded twisted shielded pair type conductor.
 - 3. N2 communications bus wire shall be 18 AWG, plenum rated, stranded twisted shielded, 3 conductor, with blue outer casing, descripted as 18-03 OAS STR PLNM NEON BLU JK distributed by Windy City Wire, constructed by Cable-Tek, or approved equivalent.
 - Metastat wiring shall be minimum 20 AWG, plenum rated, stranded, 8 conductor stranded wire.
 - 4. FC communications bus wire shall be 22 AWG, plenum rated, stranded twisted shielded, 3 conductor, with blue outer casing, descripted as 22-03 OAS STR PLNM NEON BLU JK distributed by Windy City Wire, constructed by Cable-Tek, or approved equivalent.
 - a. Network sensor wiring (SA Bus) shall be 22 gauge plenum rated stranded twisted wire, 4 conductor.
 - All control wiring at control panel shall be tagged and labeled during installation to assist owner in making termination connections at control panel. Label all control wires per bid documents.
- E. All low voltage electrical wiring shall be run as follows:
 - 1. Route electrical wiring in concealed spaces and mechanical rooms whenever possible.
 - 2. Provide EMT conduit and fittings in mechanical rooms and where indicated on drawings.
 - 3. Low voltage electrical wiring routed above acoustical ceiling is not required to be in conduit, but wire must be plenum rated and properly supported to building structure.
 - 4. Provide surface raceway, fittings and boxes in finished areas where wiring cannot be run in concealed spaces. Route on ceiling or along walls as close to ceiling as possible. Run raceway parallel to walls. Diagonal runs are not permitted. Paint raceway and fittings to match existing conditions. Patch/repair/paint any exposed wall penetrations to match existing conditions.
- F. All devices shall be mounted appropriately for the intended service and location.
 - 1. Adjustable thermostats shall be provided with base and covers in occupied areas and mounted 48" above finished floor to the top of the device. Tubing and/or wiring shall be concealed within the wall up to the ceiling wherever possible. Surface raceway may only be used with approval of Owners Representative. Wall mounted sensors such as CO2, RH, and non-adjustable temperature sensors shall be mounted 54" above finished floor. Duct mounted sensors shall be provided with mounting brackets to accommodate insulation. Mounting clips for capillary tubes for averaging sensors are required.
 - 2. All control devices shall be tagged and labeled for future identification and servicing of control system.
 - 3. Preheat and mixed air discharge sensors must be of adequate length and installed with capillary tube horizontally traversing face of coil, covering entire coil every 24 inches bottom to top.
 - 4. All field devices must be accessible or access panels must be installed.

CONTROL SYSTEMS 230900 - 11 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

G. Install magnehelic pressure gage across each air handling unit filter bank. If the air handling unit has a prefilter and a final filter, two magnehelic pressure gages are required.

3.2 ADJUSTING AND START-UP

- A. Start-Up: Temporary control of Air Handling Units shall be allowed only if <u>approved</u> by the owner's representative to protect finishes, etc., AHUs may be run using caution with temporary controls installed by contractor early in the startup process. All safeties including a smoke detector for shut down must be operational. Some means of discharge air control shall be utilized and provided by the contractor such as a temporary temperature sensor and controller located and installed by the Contractor.
- B. The start-up, testing, and adjusting of pneumatic and digital control systems will be conducted by owner. Once all items are completed by the Contractor for each system, Contractor shall allow time in the construction schedule for owner to complete commissioning of controls before project substantial completion. This task should be included in the original schedule and updated to include the allotted time necessary to complete it. As a minimum, the following items are required to be completed by the Contractor for Owner to begin controls commissioning.

1. Process Control Network:

- a. The control boards and enclosures need to be installed in the mechanical rooms.
- b. The fiber optic conduit and box for the process control network needs to be installed. Once in place, Owner needs to be contacted so the length of the owner provided fiber cable can be determined and ordered, if required. Coordinate with Owner to schedule the pull in and termination of the fiber cable. Power should be in place at that time. (Fiber for the process control network is required to allow metering of utilities prior to turn on.)

2. Heating System:

a. Pumps, heat exchangers, steam pressure reducing station, piping, control valves, steam and/or hot water meter, feeder conduit and wire, VFDs, control panels and control wiring installed in the mechanical room. The house keeping pads must be poured before pump operation. All must be in place in working order (pumps aligned, VFDs set up by vendor, motors checked for rotation, steam regulators set to required pressure, condensate pumps operational, heating system ready to circulate (all piping pressure tested, flushed, and insulated) with differential pressure sensors in place.

VAVs-First Pass:

a. Power, (FC or N2 bus), and control wire installed before owner can make first commissioning pass. First pass includes installation of VAV controller, termination of power, control and network communication wiring.

CONTROL SYSTEMS 230900 - 12 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

4. VAVs-Second Pass:

- a. After the air handlers are running and under static pressure control and the heating water system is operating, a second pass can be made on the VAVs to download the control program and commission controllers to verify the VAV dampers, thermostat, and reheat control valves are working properly.
- 5. Exhaust and Energy Recovery Systems:
 - a. Exhaust fans need to be operational and under control before labs can be commissioned.

3.3 CLOSEOUT PROCEDURES

- A. Contractor shall provide complete diagrams of the control system including flow diagrams with each control device labeled, a diagram showing the termination connections, and an explanation of the control sequence. The diagram and sequence shall be framed and protected by glass and mounted next to controller.
- B. Contractor shall provide as built diagram of network bus routing listing all devices on bus, once wiring is complete prior to scope completion.

END OF SECTION 230900

CONTROL SYSTEMS 230900 - 13 Project No.: CP242241



SECTION 232113 - HYDRONIC PIPING

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

Α. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 **SUMMARY**

- This Section includes piping systems for hot water heating and chilled water cooling systems: Α. makeup water for these systems: blow-down drain lines: and condensate drain piping. Piping materials and equipment specified in this Section include the following:
 - 1. Pipes, fittings, and specialties.
 - 2. Special-duty valves.
- В. Related Sections: The following Sections contain requirements that relate to this Section:
 - General Sections "Firestopping" for materials and methods for sealing pipe penetrations 1. through fire and smoke barriers.
 - 2. General Section "Joint Sealants" for materials and methods for sealing pipe penetrations through exterior walls.
 - 3. Division 23 Section "Basic Mechanical Materials and Methods" for general piping materials and installation methods.
 - 4. Division 23 Section "Valves" for gate, globe, ball, butterfly, and check valves.
 - Division 23 Section "Meters and Gages" for thermometers, flow meters, and pressure 5.
 - 6. Division 23 Section "Hangers and Supports" for pipe supports.
 - Division 23 Section "Mechanical Identification" for labeling and identifying hydronic 7. systems.
 - Division 23 Section "HVAC Pumps" for pumps, motors, and accessories for hydronic 8.
 - Division 23 Section "Control Systems" for temperature-control valves and sensors. 9.
 - Division 23 Section "Testing, Adjusting, and Balancing" for hydronic system adjusting and 10. balancing.

1.3 SYSTEM DESCRIPTION

Hydronic systems are chilled water and hot water heating, forced, recirculating systems. Α.

1.4 **SUBMITTALS**

A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections.

HYDRONIC PIPING 232113 - 1 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Product Data including rated capacities of selected models, weights (shipping, installed, and B. operating), furnished specialties, accessories, and installation instructions for each hydronic specialty and special-duty valve specified.
 - 1. Submit flow and pressure drop curves for balancing valves, based on manufacturer's testing.
- Shop Drawings detailing pipe anchors, special pipe support assemblies, alignment guides, and C. expansion joints and loops.
- D. Field test reports indicating and interpreting test results for compliance with performance requirements specified in Part 3 of this Section.
- E. Maintenance data for hydronic specialties and special-duty valves to include in the operation and maintenance manual specified in Division 1.

1.5 **QUALITY ASSURANCE**

- ASME Compliance: Comply with the following provisions: Α.
 - 1. ASME B31.9, "Building Services Piping," for materials, products, and installation. Safety valves and pressure vessels shall bear the appropriate ASME label.
 - 2. Fabricate and stamp air separators and compression tanks to comply with ASME Boiler and Pressure Vessel Code, Section VIII, Division 1.
 - 3. Welding Standards: Qualify welding processes and operators according to ASME Boiler and Pressure Vessel Code, Section IX, "Welding and Brazing Qualifications."

1.6 COORDINATION

- A. Coordinate layout and installation of piping with equipment and with other installations.
- B. Coordinate pipe sleeve installation for foundation wall penetrations.
- C. Coordinate pipe fitting pressure classes with products specified in related Sections.
- D. Coordinate size and location of concrete housekeeping pads. Cast anchor-bolt inserts into pad. Concrete, reinforcement, and formwork requirements are specified in Division 3 Sections.
- E. Coordinate installation of pipe sleeves for penetrations in exterior walls and floor assemblies. Coordinate with requirements for firestopping specified in Division 7 Section "Firestopping" for fire and smoke wall and floor assemblies.

EXTRA MATERIALS 1.7

A. Maintenance Stock: Furnish a sufficient quantity of chemicals for initial system startup and for preventive maintenance for one year from Substantial Completion.

HYDRONIC PIPING 232113 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 2 - PRODUCT

2.1 **MANUFACTURERS**

- Α. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - Balancing Valves: 1.
 - a. Armstrong Pumps, Inc.
 - Nibco. b.
 - Tour & Anderson. C.
 - d. Nexus Valve.

2.2 PIPE AND TUBING MATERIALS

- General: Refer to Part 3 "Pipe Applications" Article for identifying where the following materials Α. are used.
- B. Steel Pipe, 2-1/2-Inch NPS (DN50) and Smaller: All steel pipe shall be ASTM A53, Grade B, Type E. Welded fittings shall be the same material as the pipe.
- C. Steel Pipe, 3- to 12-Inch NPS (DN65 to DN300): All steel pipe shall be ASTM A53, Grade B, Type E. Welded fittings shall be the same material as the pipe.
 - 1. Steel Pipe Nipples: ASTM A 106 or ASTM A 53, Schedule 40, carbon steel, seamless for 2-inch NPS (DN50) and smaller and electric-resistance welded for 2-1/2-inch NPS (DN65) and larger.
- D. Steel pipe, 14- to 18-inch NPS (DN 350 to DN 450): All steel pipe shall be ASTM A53, Grade B, Type E. Welded fittings shall be the same material as the pipe.
- E. Contractor may, at his option, use Drawn-Temper Copper Tubing: ASTM B 88, Type L (ASTM B 88M, Type B) for chilled and hot water heating piping 2-1/2" and below.

2.3 **FITTINGS**

- A. Cast-Iron Threaded Fittings: ASME B16.4; Classes 125.
- B. Malleable-Iron Unions: ASME B16.39: Classes 150, 250, and 300.
- C. Cast-Iron Threaded Flanges: ASME B16.1, Classes 125 and 250; raised ground face, bolt holes spot faced.
- D. Wrought-Steel Fittings: ASTM A 234 (ASTM A 234M), Standard Weight.

HYDRONIC PIPING 232113 - 3 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- E. Wrought-Steel Flanges and Flanged Fittings: ASME B16.5, including bolts, nuts, and gaskets of the following material group, end connections, and facings:
 - 1. Material Group: 1.1.
 - End Connections: Butt welding. 2.
 - Facings: Cast iron with flat faced flanges, 125 lb. valves. 3.
- F. Wrought-Copper Fittings: ASME B16.22.
- G. Wrought-Copper Unions: ASME B16.22.

2.4 JOINING MATERIALS

- Α. Solder Filler Metals: ASTM B 32, 95-5 tin antimony.
- B. Brazing Filler Metals: AWS A5.8, Classification Bag 1 (silver).
- Welding Materials: Comply with Section II, Part C of ASME Boiler and Pressure Vessel Code C. for welding materials appropriate for wall thickness and for chemical analysis of pipe being welded.
- D. Gasket Material: Thickness, material, and type suitable for fluid to be handled; and design temperatures and pressures.
 - 1. Chilled Water: red rubber.
 - 2. Heating Water and Steam: Flexitaulic Flexicarb Style GC or equal.

2.5 **VALVES**

- Gate, globe, check, ball, and butterfly valves are specified in Division 23 Section "Valves." Α.
- В. Refer to Part 3 "Valve Applications" Article for specific uses and applications for each valve specified.
- C. Balancing Valves (2" and Under): 200-psig (860-kPa) working pressure, 250 deg F (121 deg C) maximum operating temperature, bronze body, balancing valve with combination shutoff capability. Balancing valves shall have memory stop and pressure/temperature metering taps, with wheel handle and indicator. Furnish with portable test kit. Quarter turn valves will not be acceptable.
- Safety Relief Valves: Brass or bronze body with brass and rubber, wetted, internal working D. parts; according to ASME Boiler and Pressure Vessel Code, Section IV. See schedule on drawings for sizes.

2.6 HYDRONIC SPECIALTIES

Manual Air Vent: Bronze body and nonferrous internal parts; 150-psig (1035-kPa) working Α. pressure, 225 deg F (107 deg C) operating temperature; ½ ball valve.

HYDRONIC PIPING 232113 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Y-Pattern Strainers: 125-psig (860-kPa) working pressure; cast-iron body (ASTM A 126, Class B), flanged ends for 2-1/2-inch NPS (DN65) and larger, threaded connections for 2-inch NPS (DN50) and smaller, bolted cover, perforated Type 304 stainless-steel basket, and bottom drain connection.

PART 3 - EXECUTION

3.1 PIPE APPLICATIONS

- A. Hot Water: 2-Inch NPS (DN50) and Smaller: Steel pipe with threaded joints.
 - 1. Copper Piping may be utilized.
- B. Hot Water: 2-1/2-Inch NPS (DN65) and Larger: Steel pipe with welded and flanged joints.
- C. Drain Lines: Type L drawn-temper copper tubing with soldered joints.

3.2 VALVE APPLICATIONS

- A. General-Duty Valve Applications: Unless otherwise indicated, use the following valve types:
 - 1. Shutoff Duty: Use ball (up to 2") and butterfly valves (2-1/2" and larger).
 - 2. Throttling Duty: Use balancing valves.
- B. Install shutoff-duty valves at each branch connection to supply mains, at supply connections to each piece of equipment, and elsewhere as indicated.
- C. Install drain valves at low points in mains, risers, branch lines, and elsewhere as required for system drainage.
- D. Install safety relief valves on hot water generators and elsewhere as required by ASME Boiler and Pressure Vessel Code. Pipe discharge to floor without valves. Comply with ASME Boiler and Pressure Vessel Code, Section VIII, Division 1, for installation requirements.

3.3 PIPING INSTALLATIONS

- A. Install piping according to Division 23 Section "Common Work Results for HVAC."
- B. Locate groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- C. Install drains at low points in mains, risers, and branch lines consisting of a tee fitting, 3/4-inch NPS ball valve, and short 3/4-inch NPS threaded nipple and cap. Install manual air vents at all high points.
- D. Reduce pipe sizes using eccentric reducer fitting installed with level side up.

HYDRONIC PIPING 232113 - 5 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- E. Install branch connections to mains using tee fittings in main with takeoff out bottom of main, except for up-feed risers with takeoff out top of main line.
- F. Install unions in pipes 2-inch NPS and smaller, adjacent to each valve, at final connections of each piece of equipment, and elsewhere as indicated. Unions are not required at flanged connections.
- G. Install flanges on valves, apparatus, and equipment having 2-1/2-inch NPS and larger connections.
- H. Install strainers on supply side of each control valve, pressure-reducing valve, pressure-regulating valve, solenoid valve, in-line pump, and elsewhere as indicated. Install 3/4-inch NPS nipple and ball valve in blow-down connection of strainers 2-inch NPS and larger.
- Provide temporary caps and covers over piping to prevent collection of dirt and debris during construction.
- J. Anchor piping as required to ensure proper direction of expansion and contraction.

3.4 HANGERS AND SUPPORTS

- A. General: Hanger, support, and anchor devices are specified in Division 23 Section "Hangers and Supports." Conform to requirements below for maximum spacing of supports.
- B. Install the following pipe attachments:
 - 1. Adjustable steel clevis hangers for individual horizontal runs less than 20 feet (6 m) in length.
 - 2. Adjustable roller hangers and spring hangers for individual horizontal runs 20 feet (6 m) or longer.
 - 3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal runs 20 feet (6 m) or longer, supported on a trapeze.
 - 4. Spring hangers to support vertical runs.
- C. Install hangers for steel piping with the following maximum spacing and minimum rod sizes:
 - 1. NPS 3/4: Maximum span, 7 feet; minimum rod size, 1/4 inch.
 - 2. NPS 1: Maximum span, 7 feet; minimum rod size, 1/4 inch.
 - 3. NPS 1-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
 - 4. NPS 2: Maximum span, 10 feet; minimum rod size, 3/8 inch.
 - 5. NPS 2-1/2: Maximum span, 11 feet; minimum rod size, 3/8 inch.
 - 6. NPS 3: Maximum span, 12 feet; minimum rod size, 3/8 inch.
 - 7. NPS 4: Maximum span, 12 feet; minimum rod size, 1/2 inch.
 - 8. NPS 6: Maximum span, 12 feet; minimum rod size, 1/2 inch.
 - 9. NPS 8: Maximum span, 12 feet; minimum rod size, 5/8 inch.
 - 10. NPS 10: Maximum span, 12 feet; minimum rod size, 3/4 inch.
- D. Install hangers for drawn-temper copper piping with the following maximum spacing and minimum rod sizes:
 - 1. NPS 3/4: Maximum span, 5 feet; minimum rod size, 1/4 inch.

HYDRONIC PIPING 232113 - 6 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. NPS 1: Maximum span, 6 feet; minimum rod size, 1/4 inch.
- 3. NPS 1-1/2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
- 4. NPS 2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
- 5. NPS 2-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
- 6. NPS 3: Maximum span, 10 feet; minimum rod size, 3/8 inch.
- E. Support vertical runs of steel piping at a maximum span of 15 feet.
- F. Support vertical runs of drawn-temper copper piping at a maximum span of 10 feet.

3.5 PIPE JOINT CONSTRUCTION

A. Refer to Division 23 Section " Common Work Results for HVAC " for joint construction requirements for soldered and brazed joints in copper tubing; threaded, welded, and flanged joints in steel piping; and solvent-welded joints for PVC and CPVC piping.

3.6 HYDRONIC SPECIALTIES INSTALLATION

A. Install manual air vents at high points in system, at heat-transfer coils, and elsewhere as required for system air venting.

3.7 FIELD QUALITY CONTROL

- A. Testing Preparation: Prepare hydronic piping according to ASME B31.9 and as follows:
 - 1. Leave joints, including welds, uninsulated and exposed for examination during test.
 - 2. Provide temporary restraints for expansion joints that cannot sustain reactions due to test pressure. If temporary restraints are impractical, isolate expansion joints from testing.
 - 3. Flush system with clean water. Clean strainers.
 - 4. Isolate equipment that is not subjected to test pressure from piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Flanged joints where blinds are inserted to isolate equipment need not be tested.
 - 5. Install relief valve set at a pressure no more than one-third higher than test pressure, to protect against damage by expanding liquid or other source of overpressure during test.

B. Testing: Test hydronic piping as follows:

- Acceptance Testing: Perform hydrostatic tests on the hydronic piping in accordance with ANSI B 31.9 and as follows:
- 2. Notify Owner's Representative 24 hours before required testing. <u>All tests</u> shall be conducted in the presence of the Owner's Representative.
- 3. Flush system with clean water. Clean strainers.
- 4. Minimum test pressure shall be 100 PSIG.
- 5. Pressure gauge shall be min. 4" dia. Face, 0-160 PSIG, and shall be calibrated within 1 year of test date.
- 6. Test pressure shall be held for 1 hour.
- 7. Prepare reports for all tests and required corrective action.

HYDRONIC PIPING 232113 - 7 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 8. Clean and flush hydronic piping systems. Remove, clean, and replace strainer screens. After cleaning and flushing hydronic piping system, but before balancing, remove disposable fine mesh strainers in pump suction diffusers.
- 9. System shall be operated for a minimum of 24 hours to demonstrate to the Owner's Representative that system is complete and operational.

3.8 ADJUSTING AND CLEANING

- After completing system installation, including outlet fittings and devices, inspect finish. A. Remove burrs, dirt, and construction debris, and repair damaged finishes including chips, scratches, and abrasions.
- B. Flush hydronic piping systems with clean water. Remove, clean, and replace strainer screens. After cleaning and flushing hydronic piping system, but before balancing, remove disposable fine-mesh strainers in pump suction diffusers.
- C. Mark calibrated nameplates of pump discharge valves after hydronic system balancing has been completed, to permanently indicate final balanced position.

3.9 **COMMISSIONING**

- Α. Perform these steps before operating the system:
 - 1. Open valves to fully open position. Close coil bypass valves.
 - Check air vents at high points of systems and determine if all are installed and operating 2. freely (automatic type) or bleed air completely (manual type).
 - Set temperature controls so all coils are calling for full flow. 3.
 - Check operation of automatic bypass valves. 4.

END OF SECTION 232113

HYDRONIC PIPING Project No.: CP242241 232113 - 8

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 233113 - METAL DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Single-wall rectangular ducts and fittings.
- 2. Single-wall round and flat-oval ducts and fittings.
- 3. Sheet metal materials.
- 4. Sealants and gaskets.
- 5. Hangers and supports.
- 6. Duct liner

B. Related Sections:

1. Division 23 Section "Air Duct Accessories" for dampers, sound-control devices, duct-mounting access doors and panels, turning vanes, and flexible ducts.

1.3 PERFORMANCE REQUIREMENTS

- A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" and performance requirements and design criteria indicated in "Duct Schedule" Article.
- B. Structural Performance: Duct hangers and supports shall withstand the effects of gravity loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards Metal and Flexible".
- C. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1-2004.

1.4 SUBMITTALS

- A. Product Data: For each type of the following products:
 - 1. Sealants and gaskets.

METAL DUCTS 233113 - 1 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Shop Drawings:

- Fabrication, assembly, and installation, including plans, elevations, sections, 1. components, and attachments to other work.
- 2 Factory- and shop-fabricated ducts and fittings.
- Duct layout indicating sizes, configuration, liner material, and static-pressure classes. 3.
- 4. Elevation of top of ducts.
- 5. Dimensions of main duct runs from building grid lines.
- Fittinas. 6.
- 7. Reinforcement and spacing.
- 8. Seam and joint construction.
- Penetrations through fire-rated and other partitions. 9.
- 10. Equipment installation based on equipment being used on Project.
- Locations for duct accessories, including dampers, turning vanes, and access doors and
- Hangers and supports, including methods for duct and building attachment and vibration 12. isolation.
- C. Coordination Drawings: CAD generated plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
 - 1. Duct installation in congested spaces, indicating coordination with general construction, building components, and other building services. Indicate proposed changes to duct layout.
 - 2. Suspended ceiling components.
 - Structural members to which duct will be attached. 3.
 - Size and location of initial access modules for acoustical tile. 4.
 - Penetrations of smoke barriers and fire-rated construction.
 - Items penetrating finished ceiling including the following: 6.
 - a. Lighting fixtures.
 - b. Air outlets and inlets.
 - Speakers. c.
 - Sprinklers. d.
 - Access panels. e.
 - Perimeter moldings. f.
 - 7. Refer to Section "Common Work Results for HVAC".
- D. Field quality-control reports.

1.5 QUALITY ASSURANCE

- ASHRAE Compliance: Applicable requirements in ASHRAE 62.1-2004, Section 5 "Systems A. and Equipment" and Section 7 - "Construction and System Start-Up."
- В. ASHRAE/IESNA Compliance: Applicable requirements in ASHRAE/IESNA 90.1-2004, Section 6.4.4 - "HVAC System Construction and Insulation."

METAL DUCTS 233113 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 2 - PRODUCTS

2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

- Α. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.
- Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct B. Construction Standards - Metal and Flexible," Figure 1-4, "Transverse (Girth) Joints," for staticpressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 1-5, "Longitudinal Seams - Rectangular Ducts," for static-pressure class, applicable sealing requirements, materials involved, ductsupport intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards -Metal and Flexible."
- Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types D. and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 2, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

SINGLE-WALL ROUND AND FLAT-OVAL DUCTS AND FITTINGS 2.2

- General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on Α. indicated static-pressure class unless otherwise indicated.
- B. Flat-Oval Ducts: Indicated dimensions are the duct width (major dimension) and diameter of the round sides connecting the flat portions of the duct (minor dimension).
- C. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible." Figure 3-2, "Transverse Joints - Round Duct," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
 - Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged. 1.
- Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct D. Construction Standards - Metal and Flexible," Figure 3-1, "Seams - Round Duct and Fittings," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
 - Fabricate round ducts larger than 90 inches in diameter with butt-welded longitudinal 1. seams.

METAL DUCTS 233113 - 3 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Fabricate flat-oval ducts larger than 72 inches in width (major dimension) with buttwelded longitudinal seams.
- Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-4, "90 Degree Tees and Laterals," and Figure 3-5, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

2.3 SHEET METAL MATERIALS

- Α. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards -Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A 653.
 - 1. Galvanized Coating Designation: G90.
 - 2. Finishes for Surfaces Exposed to View: Mill phosphatized.
- C. Carbon-Steel Sheets: Comply with ASTM A 1008, with oiled, matte finish for exposed ducts.
- D. Stainless-Steel Sheets: Comply with ASTM A 480, Type 304 or 316, as indicated in the "Duct Schedule" Article; cold rolled, annealed, sheet. Exposed surface finish shall be No. 2B, No. 2D, No. 3, or No. 4 as indicated in the "Duct Schedule" Article.
- E. Aluminum Sheets: Comply with ASTM B 209 Alloy 3003, H14 temper; with mill finish for concealed ducts, and standard, one-side bright finish for duct surfaces exposed to view.
- F. Reinforcement Shapes and Plates: ASTM A 36, steel plates, shapes, and bars; black and galvanized.
 - 1. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.
- G. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.4 **DUCT LINER**

- Fibrous-Glass Duct Liner: Comply with ASTM C 1071, NFPA 90A, or NFPA 90B; and with Α. NAIMA AH124, "Fibrous Glass Duct Liner Standard".
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CertainTeed Corporation; Insulation Group.
 - Johns Manville. b.
 - Knauf Insulation. c.

METAL DUCTS 233113 - 4 Project No.: CP242241

- Owens Corning. d.
- Maximum Thermal Conductivity: e.
 - 1) Type I, Flexible: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
 - 2) Type II, Rigid: 0.23 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
- 2. Antimicrobial Erosion-Resistant Coating: Apply to the surface of the liner that will form the interior surface of the duct to act as a moisture repellent and erosion-resistant coating. Antimicrobial compound shall be tested for efficacy by an NRTL and registered by the EPA for use in HVAC systems.
- Water-Based Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 3. 916.
 - a. For indoor applications, use adhesive that has a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

Insulation Pins and Washers: B.

- 1. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.106-inch-diameter shank, length to suit depth of insulation indicated with integral 1-1/2-inch galvanized carbon-steel washer.
- 2. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch-thick galvanized steel; with beveled edge sized as required to hold insulation securely in place but not less than 1-1/2 inches in diameter.
- C. Shop Application of Duct Liner: Comply with SMACNA's "HVAC Duct Construction Standards -Metal and Flexible", Figure 2-19, "Flexible Duct Liner Installation".
 - Adherer a single layer of indicated thickness of duct liner with at least 90 percent 1. adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
 - 2. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
 - 3. Butt transverse joints without gaps, and coat joint with adhesive.
 - Fold and compress liner in corners of rectangular ducts or cut and fit to ensure butted0edge overlapping.
 - Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, 5. unless duct size and dimensions of standard liner make longitudinal joints necessary.
 - 6. Apply adhesive coating on longitudinal seams in ducts with air velocity of 2500 fpm.
 - Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.
 - 8. Secure transversely oriented liner edges facing the airstream with metal nosings that have either channel or "z" profiles or are integrally formed from duct wall. Fabricate edge facings at the following locations:
 - Fan discharges. a.
 - Intervals of lined duct preceding unlined duct. b.
 - Upstream edges of transverse joints in ducts where air velocities are higher than C. 2500 fpm or where indicated.

METAL DUCTS 233113 - 5 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

9. Terminate ducts with buildouts attached to fire-damper sleeves, dampers, turning vane assemblies, or other devices. Fabricated buildouts (metal hat sections) or other buildout means are optional; when used, secure buildouts to duct walls with bolts, screws, rivets, or welds.

2.5 SEALANT AND GASKETS

General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and A. gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.

B. Two-Part Tape Sealing System:

- 1. Tape: Woven cotton fiber impregnated with mineral gypsum and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
- 2. Tape Width: 3 inches.
- Sealant: Modified styrene acrylic. 3.
- 4. Water resistant.
- Mold and mildew resistant.
- Maximum Static-Pressure Class: 10-inch wg, positive and negative. 6.
- Service: Indoor and outdoor. 7.
- Service Temperature: Minus 40 to plus 200 deg F. 8.
- Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless 9. steel, or aluminum.
- 10. For indoor applications, use sealant that has a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

C. Water-Based Joint and Seam Sealant:

- 1. Application Method: Brush on.
- 2. Solids Content: Minimum 65 percent.
- Shore A Hardness: Minimum 20. 3.
- 4. Water resistant.
- 5. Mold and mildew resistant.
- 6. VOC: Maximum 75 g/L (less water).
- Maximum Static-Pressure Class: 10-inch wg, positive and negative. 7.
- Service: Indoor or outdoor. 8.
- Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless 9. steel, or aluminum sheets.

D. Solvent-Based Joint and Seam Sealant:

- 1. Application Method: Brush on.
- Base: Synthetic rubber resin. 2.
- 3. Solvent: Toluene and heptane.
- Solids Content: Minimum 60 percent. 4.
- Shore A Hardness: Minimum 60. 5.
- Water resistant. 6.
- 7. Mold and mildew resistant.
- 8. For indoor applications, use sealant that has a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- 9. VOC: Maximum 395 g/L.

METAL DUCTS 233113 - 6 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Maximum Static-Pressure Class: 10-inch wg, positive or negative. 10.
- 11. Service: Indoor or outdoor.
- Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless 12. steel, or aluminum sheets.
- E. Flanged Joint Sealant: Comply with ASTM C 920.
 - General: Single-component, acid-curing, silicone, elastomeric. 1.
 - 2. Type: S.
 - Grade: NS. 3.
 - Class: 25. 4.
 - 5. Use: O.
 - 6. For indoor applications, use sealant that has a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- F. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.
- Round Duct Joint O-Ring Seals: G.
 - Seal shall be rated for 10-inch wg static-pressure class, positive or negative. 1.
 - EPDM O-ring to seal in concave bead in coupling or fitting spigot. 2.
 - 3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

2.6 HANGERS AND SUPPORTS

- Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts. A.
- B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.
- C. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 4-1, "Rectangular Duct Hangers Minimum Size," and Table 4-2, "Minimum Hanger Sizes for Round Duct."
- D. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A603.
- E. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A 492.
- Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and F. bolts designed for duct hanger service; with an automatic-locking and clamping device.
- Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible G. with duct materials.
- Trapeze and Riser Supports: Η.
 - Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates. 1.
 - 2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
 - Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate. 3.

METAL DUCTS 233113 - 7 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 3 - EXECUTION

3.1 **DUCT INSTALLATION**

- Α. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.
- Install ducts according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible" B. unless otherwise indicated.
- C. Install round and flat-oval ducts in maximum practical lengths.
- D. Install ducts with fewest possible joints.
- E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.
- Unless otherwise indicated, install ducts vertically and horizontally, and parallel and F. perpendicular to building lines.
- G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- Install ducts with a clearance of 1 inch, plus allowance for insulation thickness. H.
- Ι. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.
- Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed J. to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. K. Comply with requirements in Division 23 Section "Air Duct Accessories" for fire and smoke dampers.
- L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials. Comply with SMACNA's "Duct Cleanliness for New Construction Guidelines."

INSTALLATION OF EXPOSED DUCTWORK 3.2

- Protect ducts exposed in finished spaces from being dented, scratched, or damaged. Α.
- В. Trim duct sealants flush with metal. Create a smooth and uniform exposed bead. Do not use two-part tape sealing system.

METAL DUCTS 233113 - 8 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Grind welds to provide smooth surface free of burrs, sharp edges, and weld splatter. When welding stainless steel with a No. 3 or 4 finish, grind the welds flush, polish the exposed welds, and treat the welds to remove discoloration caused by welding.
- Maintain consistency, symmetry, and uniformity in the arrangement and fabrication of fittings, D. hangers and supports, duct accessories, and air outlets.
- Repair or replace damaged sections and finished work that does not comply with these E. requirements.

DUCT SEALING 3.3

- Α. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- В. Seal ducts before external insulation is applied. Provide adequate sealing as required to meet duct leakage requirements.

3.4 HANGER AND SUPPORT INSTALLATION

- Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Chapter 4, Α. "Hangers and Supports."
- В. Building Attachments: Concrete inserts or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
 - 1. Where practical, install concrete inserts before placing concrete.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 4-1, "Rectangular Duct Hangers Minimum Size," and Table 4-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.
- D. Hangers Exposed to View: Threaded rod and angle or channel supports.
- E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.
- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.5 CONNECTIONS

Make connections to equipment with flexible connectors complying with Division 23 Section "Air Α. **Duct Accessories."**

METAL DUCTS 233113 - 9 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

3.6 PAINTING

A. Paint interior of metal ducts, for 24 inches length, that are visible through return and exhaust registers and grilles and that do not have duct liner. Apply one coat of flat, black, latex paint over a compatible galvanized-steel primer. Paint materials and application requirements are specified in Division 09 painting Sections.

3.7 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Leakage Tests:
 - Comply with SMACNA's "HVAC Air Duct Leakage Test Manual." Submit a test report for each test.
 - 2. Maximum Allowable Leakage: Duct system leakages shall not exceed 5% of design air flows. When systems are leak tested in section, the total cumulative leakage of the system shall not exceed 5%.
 - 3. Test the following systems:
 - a. All supply air ducts and sections from air handling unit to terminal units.
 - b. All return air ducts and sections from grilles/registers to return/relief air fan.
 - c. 10% of supply air ductwork downstream of boxes, but not less than two systems.
 - d. Two exhaust air duct systems.
 - 4. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
 - 5. Test for leaks before applying external insulation.
 - Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure.
 - 7. Give seven days' advance notice for testing.

C. Duct System Cleanliness Tests:

- 1. Visually inspect duct system to ensure that no visible contaminants are present.
- 2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."
 - a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.
- D. Duct system will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

METAL DUCTS 233113 - 10 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.8 **DUCT CLEANING**

- Clean ductwork that was not continuously sealed from fabrication to post installation before Α. testing, adjusting, and balancing.
- B. Use service openings for entry and inspection.
 - 1. Create new openings and install access panels appropriate for duct static-pressure class if required for cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer. Comply with Division 23 Section "Air Duct Accessories" for access panels and doors.
 - 2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
 - Remove and reinstall ceiling to gain access during the cleaning process. 3.

C. Particulate Collection and Odor Control:

- 1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
- 2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.
- D. Clean the following components by removing surface contaminants and deposits:
 - 1. Air outlets and inlets (registers, grilles, and diffusers).
 - 2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.
 - Air-handling unit internal surfaces and components including mixing box, coil section, air 3. wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
 - 4. Coils and related components.
 - Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and 5. mechanical equipment rooms.
 - 6. Supply-air ducts, dampers, actuators, and turning vanes.
 - 7. Dedicated exhaust and ventilation components and makeup air systems.

E. Mechanical Cleaning Methodology:

- 1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
- 2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
- 3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
- 4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
- 5. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.

METAL DUCTS 233113 - 11 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- Provide drainage and cleanup for wash-down procedures. 6.
- Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus 7. is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

3.9 START UP

Air Balance: Comply with requirements in Division 23 Section "Testing, Adjusting, and A. Balancing for HVAC."

3.10 **DUCT SCHEDULE**

- Fabricate ducts with galvanized sheet steel. A.
- B. Supply Ducts:
 - 1. Downstream of Air Handling Units and Up to Terminal Units:
 - a. Pressure Class: Positive 6-inch wg.
 - 2. From Terminal Units to Outlets:
 - Pressure Class: Positive 1-inch wg.
 - 3. **Ducts Located within Mechanical Equipment Rooms:**
 - a. Pressure Class: Positive 4-inch wg.
- C. Return Ducts:
 - 1. All Ducts:
 - a. Pressure Class: Negative 4-inch wg.
- D. **Exhaust Ducts:**
 - 1. General Exhaust System Ducts:
 - Pressure Class: Negative 4-inch wg. a.
- E. Outdoor-Air Ducts:
 - 1. All Ducts:
 - Pressure Class: Positive or negative 1-inch wg. a.
- F. Intermediate Reinforcement:
 - 1. Galvanized-Steel Ducts: Galvanized steel or carbon steel coated with zinc-chromate primer.

METAL DUCTS 233113 - 12 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

G. Liner:

Return Air Boots and Supply Grille Plenums: Type II, 1 inch thick. 1.

H. Elbow Configuration:

- 1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Elbows."
 - Velocity 1000 fpm or Lower: a.
 - 1) Radius Type RE 1 with minimum 0.5 radius-to-diameter ratio.
 - 2) Mitered Type RE 4 without vanes.
 - Velocity 1000 to 1500 fpm: b.
 - 1) Radius Type RE 1 with minimum 1.0 radius-to-diameter ratio.
 - 2) Radius Type RE 3 with minimum 0.5 radius-to-diameter ratio and two vanes.
 - 3) Mitered Type RE2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-3, "Vanes and Vane Runners," and Figure 2-4, "Vane Support in Elbows."
 - C. Velocity 1500 fpm or Higher:
 - 1) Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio.
 - Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes. 2)
 - Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct 3) Construction Standards - Metal and Flexible," Figure 2-3, "Vanes and Vane Runners," and Figure 2-4, "Vane Support in Elbows."
- 2. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Elbows."
 - Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio. a.
 - Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes. b.
 - Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct C. Construction Standards - Metal and Flexible," Figure 2-3, "Vanes and Vane Runners," and Figure 2-4, "Vane Support in Elbows."
- 3. Round Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-3, "Round Duct Elbows."
 - Minimum Radius-to-Diameter Ratio and Elbow Segments: Comply with SMACNA's a. "HVAC Duct Construction Standards - Metal and Flexible," Table 3-1, "Mitered Elbows." Elbows with less than 90-degree change of direction have proportionately fewer segments.
 - 1) Velocity 1000 fpm or Lower: 0.5 radius-to-diameter ratio and three segments for 90-degree elbow.
 - 2) Velocity 1000 to 1500 fpm: 1.0 radius-to-diameter ratio and four segments for 90-degree elbow.

METAL DUCTS 233113 - 13 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3) Velocity 1500 fpm or Higher: 1.5 radius-to-diameter ratio and five segments for 90-degree elbow.
- Radius-to Diameter Ratio: 1.5. 4)
- Round Elbows, 12 Inches and Smaller in Diameter: Stamped or pleated. b.
- Round Elbows, 14 Inches and Larger in Diameter: Standing seam or Welded. C.

I. **Branch Configuration:**

- Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards Metal 1. and Flexible," Figure 2-6, "Branch Connections."
 - Rectangular Main to Rectangular Branch: 45-degree entry.
 - Rectangular Main to Round Branch: 45-degree square to round. b.
- Round and Flat Oval: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Figure 3-4, "90 Degree Tees and Laterals," and Figure 3-5, "Conical 2. Tees." Saddle taps are permitted in existing duct.
 - Combination Boot Tee. a.
 - 45-degree lateral. b.

END OF SECTION 233113

METAL DUCTS 233113 - 14 Project No.: CP242241

SECTION 233300 - AIR DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Manual volume dampers.
- 2. Fire dampers.
- 3. Flange connectors.
- 4. Turning vanes.
- 5. Duct-mounted access doors.
- 6. Flexible connectors.
- 7. Flexible ducts.
- 8. Duct accessory hardware.

B. Related Sections:

1. Division 28 Section "Fire Detection and Alarm" for duct-mounted fire and smoke detectors.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: For duct accessories. Include plans, elevations, sections, details and attachments to other work.
 - 1. Detail duct accessories fabrication and installation in ducts and other construction. Include dimensions, weights, loads, and required clearances; and method of field assembly into duct systems and other construction. Include the following:
 - a. Special fittings.
 - b. Manual volume damper installations.
 - c. Control damper installations.
 - Fire-damper, smoke-damper, combination fire- and smoke-damper, ceiling, and corridor damper installations, including sleeves; and duct-mounted access doors and remote damper operators.
 - e. Wiring Diagrams: For power, signal, and control wiring.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from Installers of the items involved.
- D. Source quality-control reports.
- E. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

1.4 QUALITY ASSURANCE

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with AMCA 500-D testing for damper rating.

1.5 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Fusible Links: Furnish quantity equal to 10 percent of amount installed, but not less than two.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A 653.
 - 1. Galvanized Coating Designation: G90.
 - 2. Exposed-Surface Finish: Mill phosphatized.
- C. Stainless-Steel Sheets: Comply with ASTM A 480, Type 304, and having a No. 2 finish for concealed ducts and D4 finish for exposed ducts.
- D. Aluminum Sheets: Comply with ASTM B 209, Alloy 3003, Temper H14; with mill finish for concealed ducts and standard, 1-side bright finish for exposed ducts.
- E. Extruded Aluminum: Comply with ASTM B 221, Alloy 6063, Temper T6.
- F. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

G. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.2 MANUAL VOLUME DAMPERS

- A. Standard, Manual Volume Dampers:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Air Balance Inc.; a division of Mestek, Inc.
 - b. American Warming and Ventilating; a division of Mestek, Inc.
 - c. McGill AirFlow LLC.
 - d. METALAIRE, Inc.
 - e. Nailor Industries Inc.
 - f. Ruskin Company.
 - g. Vent Products Company, Inc.
 - 2. Standard leakage rating, with linkage outside airstream.
 - 3. Suitable for horizontal or vertical applications.
 - Frames:
 - a. Hat-shaped, galvanized-steel channels, 0.064-inch minimum thickness, or 0.10 inch aluminum sheet channels.
 - b. Mitered and welded corners.
 - c. Flanges for attaching to walls and flangeless frames for installing in ducts.

5. Blades:

- a. Multiple or single blade.
- b. Parallel- or opposed-blade design.
- c. Stiffen damper blades for stability.
- d. Galvanized-steel, 0.064 inch thick, or roll-formed aluminum 0.10 inch thick.
- 6. Blade Axles: Galvanized steel or Nonferrous metal.
- 7. Bearings:
 - a. Molded synthetic or Stainless-steel sleeve.
 - b. Dampers shall have axles full length of damper blades and bearings at both ends of operating shaft.
- 8. Tie Bars and Brackets: Galvanized steel/Aluminum.

2.3 FLANGE CONNECTORS

- A. Description: Add-on or roll-formed, factory-fabricated, slide-on transverse flange connectors, gaskets, and components.
- B. Material: Galvanized steel.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

C. Gage and Shape: Match connecting ductwork.

2.4 TURNING VANES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Ductmate Industries, Inc.
 - 2. Duro Dyne Inc.
 - 3. METALAIRE, Inc.
 - 4. SEMCO Incorporated.
 - 5. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
- B. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
- C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible"; Figures 2-3, "Vanes and Vane Runners," and 2-4, "Vane Support in Elbows."
- D. Vane Construction: Single wall for ducts up to 48 inches wide and double wall for larger dimensions.

2.5 DUCT-MOUNTED ACCESS DOORS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. American Warming and Ventilating; a division of Mestek, Inc.
 - 2. Cesco Products; a division of Mestek, Inc.
 - 3. Ductmate Industries, Inc.
 - 4. Flexmaster U.S.A., Inc.
 - 5. Greenheck Fan Corporation.
 - 6. McGill AirFlow LLC.
 - 7. Nailor Industries Inc.
 - 8. Ventfabrics, Inc.
 - 9. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
- B. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards Metal and Flexible"; Figures 2-10, "Duct Access Doors and Panels," and 2-11, "Access Panels Round Duct."
 - 1. Door:
 - a. Double wall, rectangular.
 - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
 - c. Vision panel.
 - d. Hinges and Latches: 1-by-1-inch butt or piano hinge and cam latches.
 - e. Fabricate doors airtight and suitable for duct pressure class.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
- 3. Number of Hinges and Locks:
 - Access Doors Less Than 12 Inches Square: Two hinges and one compression latch.
 - b. Access Doors up to 18 Inches Square: Two hinges and two compression latches
 - c. Access Doors up to 24 by 48 Inches: Three hinges and two compression latches with outside and inside handles.
 - d. Access Doors Larger Than 24 by 48 Inches: Four hinges and two compression latches with outside and inside handles.

C. Pressure Relief Access Door:

- 1. Door and Frame Material: Galvanized sheet steel.
- 2. Door: Double wall with insulation fill with metal thickness applicable for duct pressure class.
- Operation: Open outward for positive-pressure ducts and inward for negative-pressure ducts.
- 4. Doors close when pressures are within set-point range.
- 5. Hinge: Continuous piano.
- 6. Latches: Cam.
- 7. Seal: Neoprene or foam rubber.
- 8. Insulation Fill: 1-inch-thick, fibrous-glass or polystyrene-foam board.

2.6 FLEXIBLE CONNECTORS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Ductmate Industries, Inc.
 - 2. Duro Dyne Inc.
 - 3. Ventfabrics, Inc.
 - 4. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
- B. Materials: Flame-retardant or noncombustible fabrics.
- C. Coatings and Adhesives: Comply with UL 181, Class 1.
- D. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to 2 strips of 2-3/4-inch-wide, 0.028-inch-thick, galvanized sheet steel or 0.032-inch-thick aluminum sheets. Provide metal compatible with connected ducts.
- E. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
 - 1. Minimum Weight: 26 oz./sq. yd.
 - 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
 - 3. Service Temperature: Minus 40 to plus 200 deg F.

- F. Thrust Limits: Combination coil spring and elastomeric insert with spring and insert in compression, and with a load stop. Include rod and angle-iron brackets for attaching to fan discharge and duct.
 - 1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
 - Outdoor Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 - 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 - 4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 - 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 - 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
 - 7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

2.7 FLEXIBLE DUCTS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Flexmaster U.S.A., Inc.
 - 2. McGill AirFlow LLC.
 - 3. Thermaflex.
 - 4. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
- B. Insulated, Flexible Duct: UL 181, Class 1, 2-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene or aluminized vapor-barrier film.
 - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 10 to plus 160 deg F.
 - 4. Insulation R-value: Comply with ASHRAE/IESNA 90.1-2004.

C. Flexible Duct Connectors:

- 1. Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action or Nylon strap in sizes 3 through 18 inches, to suit duct size.
- 2. Non-Clamp Connectors: Liquid adhesive plus tape.

2.8 DUCT ACCESSORY HARDWARE

- A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.
- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
 - 1. Install steel volume dampers in steel ducts.
 - 2. Install aluminum volume dampers in aluminum ducts.
- D. Set dampers to fully open position before testing, adjusting, and balancing.
- E. Install test holes at fan inlets and outlets and elsewhere as indicated.
- F. Install fire and smoke dampers according to UL listing.
- G. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
 - 1. On both sides of duct coils.
 - 2. Upstream and downstream from duct filters.
 - 3. At outdoor-air intakes and mixed-air plenums.
 - 4. At drain pans and seals.
 - 5. Downstream from manual volume dampers, control dampers, backdraft dampers, and equipment.
 - 6. Adjacent to and close enough to fire or smoke dampers, to reset or reinstall fusible links.
 - 7. At each change in direction and at maximum 50-foot spacing.
 - 8. Upstream and downstream from turning vanes.
 - 9. Upstream or downstream from duct silencers.
 - 10. Control devices requiring inspection.
 - 11. Elsewhere as indicated.
- H. Install access doors with swing against duct static pressure.
- I. Access Door Sizes:
 - 1. One-Hand or Inspection Access: 8 by 5 inches.
 - 2. Two-Hand Access: 12 by 6 inches.
 - 3. Head and Hand Access: 18 by 10 inches.
 - 4. Head and Shoulders Access: 21 by 14 inches.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 5. Body Access: 25 by 14 inches.
- Body plus Ladder Access: 25 by 17 inches. 6.
- Label access doors according to Division 23 Section "Identification for HVAC Piping and J. Equipment" to indicate the purpose of access door.
- K. Install flexible connectors to connect ducts to equipment.
- For fans developing static pressures of 5-inch wg and more, cover flexible connectors with L. loaded vinyl sheet held in place with metal straps.
- Connect flexible ducts to metal ducts with draw bands and adhesive plus sheet metal screws. M. Do not use flexible ducts through walls, partitions.
- N. Install duct test holes where required for testing and balancing purposes.
- Ο. Install thrust limits at centerline of thrust, symmetrical on both sides of equipment. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop of fans.

3.2 FIELD QUALITY CONTROL

- Α. Tests and Inspections:
 - Operate dampers to verify full range of movement. 1.
 - Inspect locations of access doors and verify that purpose of access door can be 2. performed.
 - 3. Operate fire, smoke, and combination fire and smoke dampers to verify full range of movement and verify that proper heat-response device is installed.
 - Inspect turning vanes for proper and secure installation. 4.
 - Operate remote damper operators to verify full range of movement of operator and 5. damper.

END OF SECTION 233300

AIR DUCT ACCESSORIES

Project No.: CP242241 233300 - 8

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 233600 - AIR TERMINAL UNITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Shutoff, single-duct air terminal units.
 - 2. Shutoff, dual-duct air terminal units.

1.3 SUBMITTALS

- A. Product Data: For each type of the following products, including rated capacities, furnished specialties, sound-power ratings, and accessories.
 - 1. Air terminal units.
 - 2. Liners and adhesives.
 - 3. Sealants and gaskets.
- B. Shop Drawings: For air terminal units. Include plans, elevations, sections, details, and attachments to other work.
 - 1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 2. Wiring Diagrams: For power, signal, and control wiring.
 - 3. Hangers and supports, including methods for duct and building attachment and vibration isolation.
- C. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from Installers of the items involved:
 - 1. Ceiling suspension assembly members.
 - 2. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
- D. Field quality-control reports.

AIR TERMINAL UNITS 233600 - 1 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- E. Operation and Maintenance Data: For air terminal units to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 - 1. Instructions for resetting minimum and maximum air volumes.
 - 2. Instructions for adjusting software set points.

1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1-2010, Section 5 "Systems and Equipment" and Section 7 "Construction and System Start-Up."

PART 2 - PRODUCTS

2.1 TERMINAL UNIT MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - Carnes.
 - 2. METALAIRE, Inc.
 - 3. Price Industries.
 - 4. Titus.
 - 5. Tuttle & Bailey.
 - 6. Nailor²

2.2 SHUTOFF, SINGLE-DUCT AIR TERMINAL UNITS

- A. Furnish and install where shown on drawings, Titus Model DESC-3000 single duct, variable volume terminals units or equivalent meeting these specifications.
- B. All terminals shall have pressure independent DDC control. Control shall be rest for air flow between zero and maximum cataloged cfm. Air flow limiters will not be accepted.
- C. At an inlet velocity of 2000 fpm, the differential static pressure for any size of unit shall not exceed 0.35" wg with a one-row coil, or 50" with a two-row coil.
- D. Discharge sound ratings for the basic unit shall not exceed 23 NC at 1.00" static pressure.
- E. The unit inlet shall be equipped with a cross-shaped flow sensor with amplifying pressure pickup points connected to central averaging chambers. The sensor shall amplify the duct velocity pressure by a factor of 1.75 and shall maintain control accuracy with the same size inlet duct in any configuration.

AIR TERMINAL UNITS 233600 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- F. All units shall be furnished with pressure independent direct digital controls supplied and mounted by the Owner. Contractor shall provide data sheets on all components to be mounted, indicating component dimensions, mounting hardware and methods, as well as wiring and piping diagrams for each application identified by unit tag per the schedule in the drawings, to the terminal unit manufacturer.
- G. The controls shall be compatible with inlet velocity sensors supplied by the terminal manufacturer. The sensor shall be multi-point center averaging type, with a minimum of four measuring ports parallel to the take-off point from the sensor. Sensors with measuring ports in series are not acceptable. The sensor must provide a minimum differential pressure signal of .03" wg at inlet velocities of 500 fpm.
- H. Controls shall be field set by Owner/Balancer for the scheduled minimum and maximum flow rates. Flow measuring taps and flow curves will be supplied with each terminal for field balancing air flow. Each terminal shall be equipped with labeling showing unit location, size, and scheduled cfm.
- I. The Contractor shall provide a Class II 24vac transformer and disconnect switch for DDC controlled VAV boxes. The Owner shall provide and install the damper controllers on the job.
- J. The unit casing shall be 22 gauge galvanized steel, internally lined with engineered closed cell foam insulation which complies with UL 181 and NFPA 90A. Liner shall be 1-1/2" pound density closed cell foam. The linear shall be mechanically fastened to the unit casing.
- K. Damper shall be heavy gauge metal, with shaft rotating in Delrin self-lubricating bearings. Shaft shall be marked on the end to indicate the damper blade position. Unit shall be designed for field conversion from normally open to normally closed, or vice versa, without relocating the actuator, changing parts or adding relays.
- L. The dampers shall have a built-in stop to prevent overstroking and shall seal against a closed-cell foam gasket, to limit close-off leakage.
- A. Each VAV terminal shall be furnished with hot water heating coil. Hot water coil shall be factory mounted in a casing with performance as shown in schedule on drawings. Heaters shall be furnished by the VAV terminal manufacturer as a complete assembly. Construction shall be aluminum plate fins, copper tube serpentine type with sweat connections, tested at 250 psi under water. Coils shall have return bends factory insulated with minimum ½" thick flexible elastomeric insulation. Provide access door between terminal unit discharge and heating coil.

2.3 HANGERS AND SUPPORTS

- A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.
- B. Steel Cables: Galvanized steel complying with ASTM A 603.
- C. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.
- D. Air Terminal Unit Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.

AIR TERMINAL UNITS
233600 - 3
Project No.: CP242241
February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

E. Trapeze and Riser Supports: Steel shapes and plates for units with steel casings; aluminum for units with aluminum casings.

2.4 SOURCE QUALITY CONTROL

- A. Factory Tests: Test assembled air terminal units according to ARI 880.
 - 1. Label each air terminal unit with plan number, nominal airflow, maximum and minimum factory-set airflows, coil type, and ARI certification seal.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install air terminal units according to NFPA 90A, "Standard for the Installation of Air Conditioning and Ventilating Systems."
- B. Install air terminal units level and plumb. Maintain sufficient clearance for normal service and maintenance.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards Metal and Flexible," Chapter 4, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
 - 1. Where practical, install concrete inserts before placing concrete.
- C. Hangers Exposed to View: Threaded rod and angle or channel supports.
- D. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

3.3 CONNECTIONS

- A. Install piping adjacent to air terminal unit to allow service and maintenance.
- B. Hot-Water Piping: In addition to requirements in Division 23 Section "Hydronic Piping," connect heating coils to supply with shutoff valve, strainer, control valve, and union or flange; and to return with balancing valve and union or flange.
- C. Connect ducts to air terminal units according to Division 23 Section "Metal Ducts."

AIR TERMINAL UNITS 233600 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.4 **IDENTIFICATION**

A. Label each air terminal unit with plan number, nominal airflow, and maximum and minimum factory-set airflows. Comply with requirements in Division 23 Section "Identification for HVAC Piping and Equipment" for equipment labels and warning signs and labels.

FIELD QUALITY CONTROL 3.5

- Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, A. test, and adjust components, assemblies, and equipment installations, including connections.
- В. Tests and Inspections:
 - 1. Leak Test: After installation, fill water coils and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- C. Air terminal unit will be considered defective if it does not pass tests and inspections.

3.6 **COMMISSIONING**

- Complete installation and startup checks according to manufacturer's written instructions. A.
- B. Verify that inlet duct connections are as recommended by air terminal unit manufacturer to achieve proper performance.
- C. Verify that controls and control enclosure are accessible.
- D. Verify that control connections are complete.
- E. Verify that nameplate and identification tag are visible.
- F. Verify that controls respond to inputs as specified.

END OF SECTION 233600

AIR TERMINAL UNITS 233600 - 5 Project No.: CP242241



SECTION 233713 - DIFFUSERS, REGISTERS, AND GRILLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Rectangular and square ceiling diffusers.
- 2. Fixed face registers and grilles.

B. Related Sections:

1. Division 23 Section "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers, registers, and grilles.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated, include the following:
 - 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
 - 2. Diffuser, Register, and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.
- B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from Installers of the items involved:
 - 1. Ceiling suspension assembly members.
 - 2. Method of attaching hangers to building structure.
 - 3. Size and location of initial access modules for acoustical tile.
 - 4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
 - 5. Duct access panels.

DIFFUSERS, REGISTERS, AND GRILLES 233713 - 1 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 2 - PRODUCTS

2.1 CEILING DIFFUSERS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Anemostat Products; a Mestek company.
 - 2. Carnes.
 - 3. Krueger.
 - 4. METALAIRE, Inc.
 - 5. Price Industries.
 - 6. Titus.
 - 7. Tuttle & Bailey.
 - 8. Nailor²
- B. Rectangular and Square Ceiling Diffusers:
 - 1. Devices shall be specifically designed for variable-air-volume flows.
 - 2. Material: Steel or Aluminum.
 - 3. Finish: Baked enamel, white unless noted otherwise.
 - 4. Face Size: 24 by 24 inches or 12 by 12 inches.
 - 5. Face Style: Minimum three cone.
 - 6. Mounting: To match ceiling type.
 - 7. Pattern: Adjustable.

2.2 REGISTERS AND GRILLES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Anemostat Products; a Mestek company.
 - 2. Carnes.
 - 3. Krueger.
 - 4. METALAIRE, Inc.
 - 5. Price Industries.
 - 6. Titus.
 - 7. Tuttle & Bailey.

B. Fixed Face Register:

- 1. Material: Steel or Aluminum.
- 2. Finish: Baked enamel, white unless noted otherwise.
- 3. Face Arrangement: 1/2-by-1/2-by-1/2-inch grid.
- 4. Core Construction: Integral.
- 5. Frame: 1 inch wide.
- 6. Mounting: Countersunk screw.
- 7. Damper Type: Adjustable opposed blade for register only.
- 8. Accessory: Filter.

DIFFUSERS, REGISTERS, AND GRILLES 233713 - 2 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.3 SOURCE QUALITY CONTROL

A. Verification of Performance: Rate diffusers, registers, and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas where diffusers, registers, and grilles are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install diffusers, registers, and grilles level and plumb.
- B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
- C. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

3.3 ADJUSTING

A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION 233713

DIFFUSERS, REGISTERS, AND GRILLES 233713 - 3 Project No.: CP242241 February 27, 2024



SECTION 260500 - COMMON WORK RESULTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. MU Division of IT Telecommunications Construction Standards and Specifications apply to this section. The Contractor shall obtain the latest revision of document and install all cables, pathways, boxes, equipment, and hardware in a manner to conform with MU Standards and Specifications.

1.2 SUMMARY

A. Section Includes:

- 1. Electrical equipment coordination and installation.
- 2. Sleeves for raceways and cables.
- 3. Grout.
- 4. Coordination drawings.
- 5. Project record drawings.
- 6. Electrical demolition.
- 7. Common electrical installation requirements.

1.3 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.
- B. NBR: Acrylonitrile-butadiene rubber.

1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. All equipment furnished shall be U.L. Listed and labeled or equivalent approved.
- C. Comply with NFPA 70.
- D. Equipment Selection: Equipment of larger physical dimensions, higher capacities or ratings may be furnished provided such proposed equipment is approved in writing and connecting mechanical/electrical services are appropriately modified. Any additional costs as a result of these modifications shall be borne by the Contractor.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver raceways in clean condition. Store to prevent entrance of dirt, debris and moisture.
- B. Protect stored raceways, wires, and connectors from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, if stored inside.

1.6 INTERPRETATION OF THE DRAWINGS

- A. The drawings indicate diagrammatically the conduit runs and the apparatus served in a general way. No attempt has been made to show exact location of every box, fitting or conduit offset. Such items are to be provided and all wiring connections and home runs are to be made as required. Where conduit runs are shown terminating in arrows, such conduit runs shall be extended to panels/boards or other equipment. Where equipment is specified to be wired, make connections as shown on approved equipment wiring diagrams. Consult equipment approved shop drawings for location of outlets and for miscellaneous controls. Where wire sizes are shown on drawings, the wire size for each circuit shall be for the entire circuit.
- B. Where conduit is shown without wiring symbols, install one (1) hot (phase) wire, one (1) neutral wire, and one (1) ground wire.
- C. Provide full size neutral for each circuit.
- D. No more than three circuits shall be installed in a conduit.

1.7 TEMPORARY POWER

A. The contractor shall make all provisions for and furnish and install all necessary conduit, wire, and distribution equipment for a complete temporary wiring system for use during construction of the building. Temporary wiring shall include a system of temporary lights and power distribution. Refer to Division 01.

1.8 COORDINATION

- A. Coordinate arrangement, mounting, and support of electrical equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
 - 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
 - 3. To allow right of way for piping and conduit installed at required slope.
 - 4. So connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- C. Coordinate location of access panels and doors for electrical items that are behind finished surfaces or otherwise concealed.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping".
- E. Coordinate electrical testing of electrical, mechanical, and architectural items, so equipment and systems that are functionally interdependent are tested to demonstrate successful interoperability.

1.9 LOCATION OF OUTLETS

- A. Outlets are only approximately located on the construction drawings and great care must be used in the actual location of outlets by consulting architectural drawings and details and the various fixture drawings and by securing definite locations from the Architect.
- B. At various places where outlets are shown below exposed pipes or ducts, Contractor shall set outlet box to clear same by at least 12". Where outlets are installed over piping or ducts, outlets shall be moved so as to clear piping and ducts at no additional cost, using approved conduit and condulet fittings.
- C. Switch outlets shall generally be located on lock side of door. Check the latest general drawings on job for door swings before roughing in for switches.
- D. Check height of tile or similar wainscots and set switch outlet boxes so that same will clear top of wainscot or will come entirely within the wainscot.
- E. Wall outlets installed flush shall be provided with device (plaster) covers set to come flush with the finished surface.
- F. For electric water coolers, install box in accordance with manufacturer's shop drawings so that receptacle will be concealed by unit housing.
- G. For other equipment, provide electrical rough-in in accordance with the equipment installation instructions and architectural drawings.
- H. Do not use through-the-wall and back-to-back boxes.

PART 2 - PRODUCTS

2.1 SLEEVES FOR RACEWAYS AND CABLES

- A. Steel Pipe Sleeves: ASTM A 53, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Sleeves for Rectangular Openings: Galvanized sheet steel.
 - 1. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches and no side more than 16 inches, thickness shall be 0.052 inch.
 - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches and 1 or more sides equal to, or more than, 16 inches, thickness shall be 0.138 inch.

2.2 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

2.3 COORDINATION DRAWINGS

- A. The contractor shall prepare CAD generated drawings (min. 1/4" scale) showing following systems/items as a minimum:
 - 1. Electrical equipment locations and clearances required.
 - 2. Routing of main feeders and conduits (3" dia. and larger), cable trays and bus ducts.
 - 3. Locations of items in ceiling such as light fixtures.
- B. The contractor shall submit the CAD generated drawings to the contractor for coordination with other trades. The drawings shall be submitted either in electronic format or printed copies as requested by the contractor.
- C. The contractor shall participate in coordination meetings when requested by the contractor.

2.4 PROJECT RECORD DRAWINGS

- A. Drawings shall be furnished in electronic-media (CD-Rewritable type) and at-least one hard copy prints.
 - 1. Format: Same CAD program, version and operating system as the original contract documents.
 - 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw and add details and notations where applicable.
- B. Identify and date each drawing and include the designation "PROJECT RECORD DRAWING" or "AS-BUILT DRAWING" in a prominent location.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 3 - EXECUTION

3.1 ELECTRICAL DEMOLITION

- A. Refer to Division 02 Section "Selective Demolition" for general demolition requirements and procedures.
- B. Disconnect, demolish, and remove electrical systems, fixtures, devices, and components indicated to be removed. In general, remove all fixtures, raceways, cables, junction boxes, and equipment not utilized in new construction. For circuits disconnects, remove raceways and cables all way to the source. Label breakers/switches from where circuits have been removed as "SPARE".
- C. Protect existing electrical equipment and installation indicated to remain. If damaged or disturbed in the course of the Work, remove damaged portions and install new products of equal capacity, quality, and functionality.
- D. Accessible Work: Remove exposed electrical equipment and installations, indicated to be demolished, in their entirety.
- E. Abandoned Work: Cut and remove buried raceway and wiring, indicated to be abandoned in place, 2 inches below the surface of adjacent construction. Cap raceways and patch surface to match existing finish. Raceways shall not be abandoned within walls.
- F. Remove demolished material from Project site.
- G. Remove, store, clean, reinstall, reconnect, and make operational components indicated for relocation.
- H. Remove equipment to be salvaged, disconnect from power, and deliver to Owner as directed.

3.2 COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION

- A. Comply with NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- D. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- E. Right of Way: Give to piping systems installed at a required slope.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- F. In general install raceways and boxes minimum 8" above hung ceiling. All raceways, boxes and equipment shall be independently supported from structure. Do not support from ductwork or piping.
- G. Where new devices are added to existing circuits, take readings prior to adding new devices, and submit to Architect for review. Do not proceed with new work until approved by Architect.

3.3 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Electrical penetrations occur when raceways, cables, wireways, cable trays, or busways penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- E. Cut sleeves to length for mounting flush with both surfaces of walls.
- F. Extend sleeves installed in floors 2 inches above finished floor level.
- G. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and raceway or cable, unless indicated otherwise.
- H. Seal space outside of sleeves with grout for penetrations of concrete and masonry.
 - 1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- I. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants.".
- J. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping." For communications cable penetrations, comply also with requirements in Division 27 Section "Common Work Results for Communications."
- K. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boot-type flashing units applied in coordination with roofing work.

260500 - 6

Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.4 FIRESTOPPING

A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electrical installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Penetration Firestopping."

END OF SECTION 260500

260500 - 7

Project No.: CP242241 February 27, 2024



SECTION 260505 - ELECTRICAL TESTING

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

Drawings and general provisions of the Contract, including General and Supplementary Α. Conditions and Division 01 Specification Sections, apply to this Section.

1.2 **SUMMARY**

- A. This Section includes general requirements for electrical field testing and inspecting. Detailed requirements are specified in each Section containing components that require testing. General requirements include the following:
 - 1. Suitability of test equipment.
 - 2. Calibration of test instruments.
 - 3. Coordination requirements for testing and inspecting.
 - Reporting requirements for testing and inspecting.
- В. Emergency systems shall be tested as specified herein.

1.3 **QUALITY ASSURANCE**

- The Electrical Contractor shall completely test and inspect all systems in accordance with the Α. specifications and drawings. The Electrical Contractor shall certify that all systems are in complete working order prior to turning over the Owner.
- Except as modified by governing codes and by the contract documents, comply with the latest B. applicable provisions and latest recommendations of the following:
 - 1. NFPA.
 - 2. NEMA.
 - 3. NEC.
 - 4. IEEE.
 - 5. IPCEA.
 - ANSI. 6.
 - 7. UL.
 - 8. NECA.
 - 9. Local Fire Department.

ELECTRICAL TESTING Project No.: CP242241 260505 - 1

UNIVERSITY OF MISSOURI

ISSUED FOR BID

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 GENERAL TESTING

- A. It shall be the responsibility of this Contractor to furnish all testing instruments/equipment, materials and labor necessary to perform the following tests.
 - 1. After wires or cables are in place, but before being connected to devices and equipment, the system shall be tested for shorts, opens, intentional and unintentional grounds by means of wires in conduit that are shorted or unintentionally grounded shall be replaced.
 - 2. Voltage drops for panel and large feeders shall not exceed 3% hence the total voltage drop for a feeder and any branch circuit shall not exceed 5% of the service voltage. The test shall be made under design load or its' equal.
 - 3. Any wiring device or electrical apparatus in this contract, if grounded or shorted on an integral "line" part, shall be removed and the problem rectified.
 - 4. When required, complete test and inspection records shall be made and incorporated into a report for each piece of equipment tested. All readings taken shall be recorded. Four (4) copies shall be submitted to the Architect for approval.
 - 5. Notify the Architect, with minimum seven (7) days notice, about testing schedule.

3.2 WIRING TEST

- A. The wiring and cable tests shall be made before any circuits, main switches, motors, transformers or feeders are energized.
- B. Tests shall be made for continuity, identification and absence of shorts and grounds for each conductor. Both ends of a given conductor shall be identified alike. Before circuit terminal connections are made, continuity and identification of wiring shall be checked by means of a DC test device using a bell, light, meter, or buzzer.
- C. Insulation Resistance (IR) test shall be made using meggers at the following values:
 - 1. 208Y/120 Volt wiring at 500 Volts DC.
- D. Insulation resistance between phase conductors and neutral, phase conductors and ground shall not be less than the minimum requirements of 2000 meg-ohms.
 - 1. Wire terminations shall not be made to equipment (motors, MCCs, but ducts, etc.), until that piece of equipment has been tested and verified as specified in this section.
 - 2. Test motor feeders with motors disconnected, but with circuit breakers, switches or starters in the circuit opened so as to include only that portion of the feeder, required to be tested.
 - 3. Test lighting feeders with the circuit breakers and panelboards connected but with lighting branch circuit breakers or switches open so as to include only the branch circuit to be tested.

ELECTRICAL TESTING 260505 - 2 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

4. Contractor shall correct or replace any circuit which is defective or grounded and shall correct all other problems encountered by these tests. All defects whether due to faulty workmanship or material furnished by the Contractor shall be corrected under this section at the Contractor's expense.

3.3 LIGHTING TEST

- A. Check all lighting fixtures for proper operation. All Contractor supplied fixtures shall be 100% operable at no additional cost to the Owner. Repair cost to Owner-supplied fixtures shall not be the responsibility of the Contractor unless otherwise stated.
- B. Verify operation of Lighting Control Systems. Program time clocks per client's requirements, including holiday setbacks.

3.4 MOTOR TEST

- A. Perform motor tests in coordination with fire suppression, plumbing and HVAC contractors for motors furnished with their equipment.
- B. All 208/120V motors shall be "spot tested" with 500V DC in a similar manner. The minimum resistance to ground shall be 2000 meg-ohm (corrected to 20 degrees C). The Contractor shall record the ambient temperature of the motor and submit this value along with insulation resistance value. For motors from 7-½ to 20 HP, Contractor shall submit Dielectric Absorption Ratios. For motor above 20 HP, the Polarization Indexes of the motor shall also be submitted.
- C. Make the following checks on all motors prior to start up.
 - 1. Check motor nameplates for HP, speed, phase and voltages. Verify proper voltage available for terminal wiring.
 - 2. Check shaft for freedom of rotation.
 - 3. Verify that the motor is properly lubricated prior to energizing.
- D. Contractor shall furnish a proper sized heater for each overload relay.
- E. Make the following tests on all motors during or immediately after start-up:
 - 1. Check for proper shaft rotation.
 - 2. Check motor for smooth operation (vibration).
 - 3. Take a current reading using a clamp-on ammeter. (Record no-load readings and loaded readings).

3.5 PANELBOARD TESTS

A. Test all equipment to be operated on the 208/120V system at 500V DC prior to connecting feeders. A minimum insulation resistance of 2000 meg-ohms shall be obtained between all phases and between phase and neutral, and phase and ground.

ELECTRICAL TESTING 260505 - 3 Project No.: CP242241 February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.6 SPOT TEST

A. "Spot Test" mentioned in this section shall be interpreted as the specific test method of obtaining insulation resistance by applying indicated test voltage for 60 seconds to the equipment or wiring being tested.

3.7 CONTROL WIRING/OUTLET TEST

- A. Control wiring shall perform the function as noted in operation methods and/or included schematics and single line diagrams.
- B. All 120-volt outlets shall be tested with a Daniel Woodhead Cat. No. 1750 and 1760 tester. Minimum acceptable tension is 10 oz. for receptacles.

END OF SECTION 260505

ELECTRICAL TESTING 260505 - 4 Project No.: CP242241 February 27, 2024

SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Building wires and cables rated 600 V and less.
 - 2. Connectors, splices, and terminations rated 600 V and less.
 - 3. Sleeves and sleeve seals for cables.
- B. Related Sections include the following:
 - Division 27 Section "Communications Horizontal Cabling" for cabling used for voice and data circuits.
- C. Pre-wired systems such as type AC (armored cable), type MC (metal-clad and type NM (nonmetallic-sheathed cable) shall not be used. (Exception: MC may be used for lighting fixture whips up to 6'-0" long. They must be dedicated, not daisy chained together).

1.3 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.
- B. NBR: Acrylonitrile-butadiene rubber.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Field quality-control test reports.

1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a member company of the InterNational Electrical Testing Association or is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
 - 1. Testing Agency's Field Supervisor: Person currently certified by the InterNational Electrical Testing Association or the National Institute for Certification in Engineering Technologies to supervise on-site testing specified in Part 3.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with NFPA 70.
- D. All conductors and cables shall be UL labeled.

1.6 COORDINATION

- A. Set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- B. Coordinate layout and installation of conductors and cables with other trades.

1.7 DELIVERY, STORAGE AND HANDLING

- A. Delivery conductors and cables according to NEMA WC 26.
- B. Protect stored conductors and cables from moisture and dirt. Do not store outside, exposed to elements. Elevate above grade. Do not exceed structural capacity of floor, when stored inside.

PART 2 - PRODUCTS

2.1 CONDUCTORS AND CABLES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Encore Wire and Cable.
 - 2. Senator Wire & Cable Company.
 - 3. Southwire Company.
 - 4. Cerro Wire.
- B. Copper Conductors: Comply with NEMA WC 70.
- C. Conductor Insulation: Comply with NEMA WC 70 for Types THHN-THWN and XHHW.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

D. Multiconductor Cable: Comply with NEMA WC 70 for metal-clad cable, Type MC or mineral-insulated, metal-sheathed cable, Type MI with ground wire.

2.2 CONNECTORS AND SPLICES

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. AFC Cable Systems, Inc.
 - 2. AMP Incorporated/Tyco International.
 - 3. Hubbell Power Systems, Inc.
 - 4. O-Z/Gedney; EGS Electrical Group LLC.
 - 5. 3M; Electrical Products Division.
 - 6. Panduit Corporation.
 - 7. Tyco Electronics Corp.
- B. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

2.3 SLEEVES FOR CABLES

- A. Steel Pipe Sleeves: ASTM A 53, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- C. Sleeves for Rectangular Openings: Galvanized sheet steel with minimum 0.052- or 0.138-inch thickness as indicated and of length to suit application.
- D. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL AND SIZE APPLICATIONS

- A. Feeders: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- B. Branch Circuits: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- C. Conductors smaller than No. 12 AWG shall not be utilized anywhere, unless specifically noted on drawings.
- D. The minimum conductor size for branch circuits shall be #12 AWG copper. To compensate for voltage drop, where branch circuit lengths are between 100 and 150 feet, use #10 AWG copper. For branch circuit lengths exceeding 150 feet, use #8 AWG copper.

E. Wire size ampacity shall equal or exceed its overload protective device. Where wire sizes shown on the drawings are greater than the apparent ampacity requirements, the size shown shall prevail to compensate for voltage drop. In no instance shall conductors be installed that are less than required by NEC.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Service Entrance: Type THWN, single conductors in raceway or Type XHHW, single conductors in raceway. Mineral-insulated, metal-sheathed cable, Type MI where specifically indicated on drawings.
- B. Exposed Feeders: Type THHN-THWN, single conductors in raceway.
- C. Feeders Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN-THWN, single conductors in raceway.
- D. Feeders at all other locations: Type THHN-THWN, single conductors in raceway.
- E. Exposed Branch Circuits, Including in Crawlspaces: Type THHN-THWN, single conductors in raceway.
- F. Branch Circuits below Slabs-on-Grade, and Underground: Type THHN-THWN, single conductors in raceway.
- G. Branch Circuits at all other locations: Type THHN-THWN, single conductors in raceway.
- H. Class 1 Control Circuits: Type THHN-THWN, in raceway.
- I. Class 2 Control Circuits: Type THHN-THWN, in raceway.
- J. Fire Alarm Circuits: Refer to Section 280513 "Conductors and Cables for Electronic Safety and Security".

3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Conceal conduits in finished walls, and above ceilings, unless otherwise indicated.
- B. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- C. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- D. Install exposed conduits parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- E. Support conduits according to Division 26 Section "Hangers and Supports for Electrical Systems."

UNIVERSITY OF MISSOURI

ISSUED FOR BID

F. Identify and factory color-code conductors and cables according to Division 26 Section "Identification for Electrical Systems."

3.4 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torquetightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- B. Make splices and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
 - 1. Use oxide inhibitor in each splice and tap conductor for aluminum conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches of slack.

3.5 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Rectangular Sleeve Minimum Metal Thickness:
 - 1. For sleeve rectangle perimeter less than 50 inches and no side greater than 16 inches, thickness shall be 0.052 inch.
 - 2. For sleeve rectangle perimeter equal to, or greater than, 50 inches and 1 or more sides equal to, or greater than, 16 inches, thickness shall be 0.138 inch.
- E. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- F. Cut sleeves to length for mounting flush with both wall surfaces.
- G. Extend sleeves installed in floors 2 inches above finished floor level.
- H. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and cable.
- I. Seal space outside of sleeves with grout for penetrations of concrete and masonry and with approved joint compound for gypsum board assemblies.
- J. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and cable, using joint sealant appropriate for size, depth, and location of joint according to Division 07 Section "Joint Sealants."

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

K. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at cable penetrations. Install sleeves and seal with firestop materials according to Division 07 Section "Penetration Firestopping."

3.6 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Division 07 Section "Penetration Firestopping."

3.7 FIELD QUALITY CONTROL

- A. Perform tests and inspections and prepare test reports.
- B. Tests and Inspections:
 - After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors, and branch circuit conductors for compliance with requirements.
 - 2. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
 - 3. Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each splice in cables and conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner.
 - Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each splice 11 months after date of final acceptance.
 - Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - c. Record of Infrared Scanning: Prepare a certified report that identifies splices checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
- C. Test Reports: Prepare a written report to record the following:
 - 1. Test procedures used.
 - 2. Test results that comply with requirements.
 - 3. Test results that do not comply with requirements and corrective action taken to achieve compliance with requirements.
- D. Remove and replace malfunctioning units and retest as specified above.

END OF SECTION 260519

SECTION 260526 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. MU Division of IT Telecommunications Construction Standards and Specifications apply to this section. The Contractor shall obtain the latest revision of document and install all cables, pathways, boxes, equipment, and hardware in a manner to conform with MU Standards and Specifications.

1.2 SUMMARY

- A. This Section includes methods and materials for grounding systems and equipment.
- B. This Section includes grounding of electrical systems and equipment and basic requirements for grounding for protection of life, equipment, circuits, and systems. Grounding requirements specified in this Section may be supplemented in other Sections of these Specifications.
- C. Related Sections include the following:
 - 1. Division 26 Section 260519 "Low-Voltage Electrical Power Conductors and Cables" for requirements for grounding conductors.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Field quality-control test reports.
- C. Operation and Maintenance Data: For grounding to include the following in operation and maintenance manuals:
 - 1. Instructions for periodic testing and inspection of grounding features at grounding connections for separately derived systems based on NFPA 70B.
 - Tests shall be to determine if ground resistance or impedance values remain within specified maximums, and instructions shall recommend corrective action if they do not.
 - b. Include recommended testing intervals.

1.4 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a member company of the InterNational Electrical Testing Association or is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
 - 1. Testing Agency's Field Supervisor: Person currently certified by the InterNational Electrical Testing Association to supervise on-site testing specified in Part 3.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with UL 467 for grounding and bonding materials and equipment.
- D. Communications Grounding shall comply with BICSI Telecommunications Distribution Methods Manual (TDMM) and BICSI Information Transport Systems Installation Methods Manual, latest editions.

PART 2 - PRODUCTS

2.1 CONDUCTORS

- A. Insulated Conductors: Copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.
- B. Bare Copper Conductors:
 - 1. Solid Conductors: ASTM B 3.
 - 2. Stranded Conductors: ASTM B 8.
 - 3. Bonding Cable: 28 kcmil, 14 strands of No. 17 AWG conductor, 1/4 inch in diameter.
 - 4. Bonding Conductor: No. 4 or No. 6 AWG, stranded conductor.
 - 5. Bonding Jumper: Copper tape, braided conductors, terminated with copper ferrules; 1-5/8 inches wide and 1/16 inch thick.
- C. Grounding Bus: Rectangular bars of annealed copper, 1/4 by 2 inches in cross section, unless otherwise indicated; with insulators.
 - 1. Telecommunications Ground Busbar (TGB) shall have industry-standard 2-hole pattern, and be 4 inches wide, as manufactured by CPI # 40153-012 or approved equivalent.

2.2 CONNECTORS

A. Listed and labeled by a nationally recognized testing laboratory acceptable to authorities having jurisdiction for applications in which used, and for specific types, sizes, and combinations of conductors and other items connected.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Bolted Connectors for Conductors and Pipes: Copper or copper alloy, bolted pressure-type, with at least two bolts.
 - 1. Pipe Connectors: Clamp type, sized for pipe.
 - 2. Telecommunications Grounding Connector Lugs: Irreversible compression type, 2-hole lug, for connection to TGBs. Approved manufacturers: Burndy, Panduit, Thomas & Betts.
- C. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions. All concealed terminations to the grounding electrode shall be made using exothermic welds.

PART 3 - EXECUTION

3.1 APPLICATIONS

- A. Conductors: Install solid conductor for No. 10 AWG and smaller, and stranded conductors for No. 8 AWG and larger, unless otherwise indicated.
- B. Conductor Terminations and Connections:
 - 1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.

3.2 EQUIPMENT GROUNDING

- A. Install insulated equipment grounding conductors with all feeders and branch circuits.
- B. Install insulated equipment grounding conductors with the following items, in addition to those required by NFPA 70:
 - 1. Feeders and branch circuits.
 - 2. Lighting circuits.
 - 3. Receptacle circuits.
 - 4. Single-phase motor and appliance branch circuits.
 - 5. Three-phase motor and appliance branch circuits.
 - 6. Flexible raceway runs.
 - 7. Armored and metal-clad cable runs.
- C. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install a separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.

3.3 INSTALLATION

A. Ground electrical systems and equipment according to NEC requirements, except where Drawings or Specifications exceed NEC requirements.

- B. Grounding Conductors: Route along shortest and straightest paths possible, minimizing direction changes and utilizing wide-radius bends where direction changes are necessary, unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
- C. Common Ground Bonding with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest point to electrical service grounding electrode. Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.
- D. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance, except where routed through short lengths of conduit.
 - 1. Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate any adjacent parts.
 - 2. Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install so vibration is not transmitted to rigidly mounted equipment.
 - 3. Use exothermic-welded connectors for outdoor locations, but if a disconnect-type connection is required, use a bolted clamp.

E. Grounding and Bonding for Piping:

- Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes, using a bolted clamp connector or by bolting a lug-type connector to a pipe flange, using one of the lug bolts of the flange. Where a dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
- 2. Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with a bolted connector.
- 3. Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.
- F. Bonding Interior Metal Ducts: Bond metal air ducts to equipment grounding conductors of associated fans, blowers, electric heaters, and air cleaners. Install tinned bonding jumper to bond across flexible duct connections to achieve continuity.
- G. The complete metal conduit system shall be used for the equipment grounding system. Conduit systems and associated fittings and terminations shall be made mechanically tight to provide a continuous electrical path to ground and shall be safely grounded at all equipment by bonding all metallic conduit to the equipment enclosures with locknuts cutting thru paint of enclosures. Bond all conduits entering primary switchgear, unit substations and secondary switchboards with a ground wire connecting the grounding type bushings to the equipment ground bar. Conductors shall be sized per NEC.
- H. In addition to using the conduit system for grounding, a complete auxiliary green wire equipment grounding system shall be installed, continuous from main ground, through distribution and branch circuit panelboards and paralleling all feeders and branch circuit wiring. The minimum size shall be #12 copper except #14 on control circuits. This shall apply to all circuits rated 100 volts or more above ground potential.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- I. Bond all communications conduit systems to ground.
- J. Connect ground terminal on wiring devices to auxiliary green wire equipment grounding system.
- K. Motor frames shall be bonded to the equipment grounding system by an independent green wire, sized as shown.
- L. System neutral connections shall be insulated from metal enclosures except at the neutral of the service entrance equipment. Connections to the main switchboard enclosure shall be by means of bonding jumpers.
- M. The building neutral shall be identified throughout with white conductors.
- N. Metal covers on pull boxes and junction boxes shall be effectively grounded.
- O. Wiring devices shall be connected with grounding jumper from ground pole on device to grounding screw in the outlet box.

3.4 CONNECTIONS

- A. General: Make connections so possibility of galvanic action or electrolysis is minimized. Select connectors, connection hardware, and connection methods so metals in direct contact will be galvanically compatible.
 - 1. Use electroplated or hot-tin-coated materials to assure high conductivity and to make contact points closer in order pf galvanic series.
 - 2. Make connections with clean, bare metal at points of contact.
 - 3. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.
- B. Exothermic-Welded Connections: Use for connections to structural steel and for underground connections, except those at test wells. Complete with manufacturer's written instructions. Welds that are puffed up or that show convex surfaces indicating improper cleaning are not acceptable.
- C. Equipment Grounding-Wire Terminations: For No. 8 AWG and larger, use pressure-type grounding lugs. No. 10 AWG and smaller grounding conductors may be terminated with winged pressure-type connectors.
- D. Noncontact Metal Raceway Terminations: Where metallic raceways terminate at metal housings without mechanical and electrical connection to housing, terminate each conduit with a grounding bushing. Connect grounding bushings with a bare grounding conductor to grounding bus or terminal in housing. Bond electrically noncontinuous conduits at both entrances and exits with grounding bushings and bare grounding conductors, except as otherwise indicated.
- E. Tighten screws and bolts for grounding and bonding connectors and terminals according to manufacturer's published torque-tightening values. Where these requirements are not available, use those specified in UL 486A and UL 486B.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

- F. Compression-Type Connections: use hydraulic compression tools to provide correct circumferential pressure for compression connectors. Use tools and dies recommended by manufacturer of connectors. Provide embossing die code or other standard method to make a visible indication that a connector has been adequately compressed on grounding conductor.
- G. Moisture Protection: Where insulated grounding conductors are connected to grounding rods or grounding buses, insulate entire area of connection and seal against moisture penetration of insulation and cable.

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing and inspecting agency to perform the following field tests and inspections and prepare test reports:
- B. Perform the following tests and inspections and prepare test reports:
 - 1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
 - 2. Test completed grounding system. The maximum ground-resistance level shall not exceed 5 ohms.
 - a. Measure ground resistance not less than two full days after last trace of precipitation and without soil being moistened by any means other than natural drainage or seepage and without chemical treatment or other artificial means of reducing natural ground resistance.
 - b. Perform tests by fall-of-potential method according to IEEE 81.
 - 3. Prepare dimensioned drawings locating each test well, ground rod and ground rod assembly, and other grounding electrodes. Identify each by letter in alphabetical order, and key to the record of tests and observations. Include the number of rods driven and their depth at each location, and include observations of weather and other phenomena that may affect test results. Describe measures taken to improve test results.
- C. Report measured ground resistances that exceed the following values:
 - 1. Power and Lighting Equipment or System: 5 ohms.
- D. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Architect promptly and include recommendations to reduce ground resistance.

END OF SECTION 260526

SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Hangers and supports for electrical equipment and systems.
 - 2. Construction requirements for concrete bases.
- B. Related Sections include the following:
 - 1. Division 26 Section "Vibration and Seismic Controls For Electrical Systems" for products and installation requirements necessary for compliance with criteria.
- C. All conduit shall be supported from the building. Attachment to other pipes, conduits, ductwork, etc. will not be allowed.

1.3 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. IMC: Intermediate metal conduit.
- C. RMC: Rigid metal conduit.

1.4 PERFORMANCE REQUIREMENTS

- A. Design supports for multiple raceways capable of supporting combined weight of supported systems and its contents.
- B. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
- C. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed for this Project, with a minimum structural safety factor of five times the applied force.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.5 SUBMITTALS

- A. Product Data: For the following:
 - 1. Steel slotted support systems.
 - 2. Nonmetallic slotted support systems.
- B. Shop Drawings: Show fabrication and installation details and include calculations for the following:
 - 1. Trapeze hangers. Include Product Data for components.
 - 2. Steel slotted channel systems. Include Product Data for components.
 - 3. Nonmetallic slotted channel systems. Include Product Data for components.
 - 4. Equipment supports.
- C. Welding certificates.

1.6 QUALITY ASSURANCE

- A. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- B. Comply with NFPA 70.

1.7 COORDINATION

A. Coordinate size and location of concrete bases.

PART 2 - PRODUCTS

2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Comply with MFMA-4, factory-fabricated components for field assembly.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allied Tube & Conduit.
 - b. Cooper B-Line, Inc.; a division of Cooper Industries.
 - c. ERICO International Corporation.
 - d. GS Metals Corp.
 - e. Thomas & Betts Corporation.
 - f. Unistrut; Tyco International, Ltd.
 - 2. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
 - 3. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.

- 4. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
- 5. Channel Dimensions: Selected for applicable load criteria.
- B. Nonmetallic Slotted Support Systems: Structural-grade, factory-formed, glass-fiber-resin channels and angles with 9/16-inch-diameter holes at a maximum of 8 inches o.c., in at least 1 surface.
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allied Tube & Conduit.
 - b. Cooper B-Line, Inc.; a division of Cooper Industries.
 - c. Fabco Plastics Wholesale Limited.
 - d. Seasafe, Inc.
 - 2. Fittings and Accessories: Products of channel and angle manufacturer and designed for use with those items.
 - 3. Fitting and Accessory Materials: Same as channels and angles, except metal items may be stainless steel.
 - 4. Rated Strength: Selected to suit applicable load criteria.
- C. Raceway and Cable Supports: As described in NECA 1 and NECA 101.
- D. Conduit and Cable Support Devices: Steel and malleable-iron hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- E. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for non-armored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be malleable iron.
- F. Structural Steel for Fabricated Supports and Restraints: ASTM A 36, steel plates, shapes, and bars; black and galvanized.
- G. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
 - 1. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened Portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
 - a. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1) Cooper B-Line, Inc.; a division of Cooper Industries.
 - 2) Empire Tool and Manufacturing Co., Inc.
 - 3) Hilti Inc.
 - 4) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
 - 5) MKT Fastening, LLC.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Concrete Inserts: Steel or malleable-iron, slotted support system units similar to MSS Type 18; complying with MFMA-4 or MSS SP-58.
- 3. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
- 4. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
- 5. Toggle Bolts: All-steel springhead type.
- 6. Hanger Rods: Threaded steel.

2.2 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems except if requirements in this Section are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMT, IMC, and RMC as scheduled in NECA 1, where its Table 1 lists maximum spacings less than stated in NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- C. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted or other support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
 - 1. Secure raceways and cables to these supports with two-bolt conduit clamps.
- D. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch and smaller raceways serving branch circuits and communication systems above suspended ceilings and for fastening raceways to trapeze supports.

3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this Article.
- B. Raceway Support Methods: In addition to methods described in NECA 1, EMT, IMC, and RMC may be supported by openings through structure members, as permitted in NFPA 70.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
 - 1. To Wood: Fasten with lag screws or through bolts.
 - 2. To New Concrete: Bolt to concrete inserts.
 - 3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 4. To Existing Concrete: Expansion anchor fasteners.
 - 5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches thick.
 - 6. To Steel: Beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69.
 - 7. To Light Steel: Sheet metal screws.
 - 8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate.
- E. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- B. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 PAINTING

- A. Touchup: Comply with requirements in Division 09 painting Sections for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 260529



SECTION 260533 - RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. MU Division of IT Telecommunications Construction Standards and Specifications apply to this section. The Contractor shall obtain the latest revision of document and install all cables, pathways, boxes, equipment, and hardware in a manner to conform with MU Standards and Specifications.

1.2 SUMMARY

- A. This Section includes raceways, fittings, boxes, enclosures, and cabinets for electrical wiring.
- B. All empty conduit shall be furnished with a pull string.

1.3 DEFINITIONS

- A. EMT: Electrical metallic tubing.
- B. ENT: Electrical nonmetallic tubing.
- C. FMC: Flexible metal conduit.
- D. IMC: Intermediate metal conduit.
- E. LFMC: Liquidtight flexible metal conduit.
- F. LFNC: Liquidtight flexible nonmetallic conduit.
- G. RNC: Rigid nonmetallic conduit.
- H. RMC: Rigid metal conduit (rigid steel conduit).

1.4 SUBMITTALS

A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Shop Drawings: For the following raceway components. Include plans, elevations, sections, details, and attachments to other work.
 - Custom enclosures and cabinets.
- C. Coordination Drawings: Conduit routing plans, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
 - 1. Structural members in the paths of conduit groups with common supports.
 - 2. HVAC and plumbing items and architectural features in the paths of conduit groups with common supports.

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 METAL CONDUIT AND TUBING

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Allied Tube & Conduit; a Tyco International Ltd. Co.
 - 2. Republic Conduit.
 - 3. Western Tube and Conduit.
 - Wheatland Tube Company.
- B. Rigid Steel Conduit: ANSI C80.1.
- C. IMC: ANSI C80.6.
- D. PVC-Coated Steel Conduit: PVC-coated rigid steel conduit.
 - 1. Comply with NEMA RN 1.
 - 2. Coating Thickness: 0.040 inch, minimum.
- E. EMT: ANSI C80.3.
- F. FMC: Zinc-coated steel.
- G. LFMC: Flexible steel conduit with PVC jacket.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- H. Fittings for Conduit (Including all Types and Flexible and Liquidtight), EMT, and Cable: NEMA FB 1; listed for type and size raceway with which used, and for application and environment in which installed.
 - 1. Fittings for EMT: Steel or die-cast, compression type, and rated for ground connection.
 - 2. Coating for Fittings for PVC-Coated Conduit: Minimum thickness, 0.040 inch, with overlapping sleeves protecting threaded joints.
- Joint Compound for Rigid Steel Conduit or IMC: Listed for use in cable connector assemblies, and compounded for use to lubricate and protect threaded raceway joints from corrosion and enhance their conductivity.

2.2 NONMETALLIC CONDUIT AND TUBING

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. AFC Cable Systems, Inc.
 - 2. Anamet Electrical, Inc.; Anaconda Metal Hose.
 - 3. CANTEX Inc.
 - 4. CertainTeed Corp.; Pipe & Plastics Group.
 - 5. Condux International, Inc.
 - 6. Lamson & Sessions; Carlon Electrical Products.
 - 7. Manhattan/CDT/Cole-Flex.
 - 8. RACO; a Hubbell Company.
 - 9. Thomas & Betts Corporation.
- B. ENT: NEMA TC 13.
- C. RNC: NEMA TC 2, Type EPC-40-PVC, unless otherwise indicated.
- D. LFNC: UL 1660.
- E. Fittings for ENT and RNC: NEMA TC 3; match to conduit or tubing type and material.
- F. Fittings for LFNC: UL 514B.

2.3 METAL WIREWAYS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Cooper B-Line, Inc.
 - 2. Hoffman.
 - 3. Keystone/Rees Inc.
 - Square D; Schneider Electric.
- B. Description: Sheet metal sized and shaped as indicated, NEMA 250, Type 3R, unless otherwise indicated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Fittings and Accessories: Include couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- D. Wireway Covers: Screw-cover type. Flanged-and-gasketed type where shown on drawings.
- E. Finish: Manufacturer's standard enamel finish.

2.4 BOXES, ENCLOSURES, AND CABINETS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Cooper Crouse-Hinds; Div. of Cooper Industries, Inc.
 - 2. EGS/Appleton Electric.
 - 3. Erickson Electrical Equipment Company.
 - 4. Hoffman.
 - 5. Hubbell Incorporated; Killark Electric Manufacturing Co. Division.
 - 6. O-Z/Gedney; a unit of General Signal.
 - 7. RACO; a Hubbell Company.
 - 8. Thomas & Betts Corporation.
 - 9. Walker Systems, Inc.; Wiremold Company (The).
- B. Pull and junction boxes shall be minimum 4" x 4".
- C. Communications back-boxes for outlets shall be 4" x 4", 2-1/2" depth, with 2" x 4" single-gang reducer for single-gang faceplate mounting. Joint/shared boxes for power and Communications are not allowed.
- D. Sheet Metal Outlet and Device Boxes: NEMA OS 1.
- E. Cast-Metal Outlet and Device Boxes: NEMA FB 1, Type FD, with gasketed cover.
- F. Nonmetallic Outlet and Device Boxes: NEMA OS 2.
- G. Metal Floor Boxes: Cast or sheet metal, fully adjustable, rectangular.
- H. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- I. Cast-Metal Access, Pull, and Junction Boxes: NEMA FB 1, with gasketed cover.
- J. Hinged-Cover Enclosures: NEMA 250, Type 1, with continuous-hinge cover with flush latch, unless otherwise indicated.
 - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
 - 2. Nonmetallic Enclosures: Plastic, finished inside with radio-frequency-resistant paint.

K. Cabinets:

1. NEMA 250, Type 1, galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. Hinged door in front cover with flush latch and concealed hinge.
- 3. Key latch to match panelboards.
- 4. Metal barriers to separate wiring of different systems and voltage.
- 5. Accessory feet where required for freestanding equipment.

2.5 SLEEVES FOR RACEWAYS

- A. Steel Pipe Sleeves: ASTM A 53, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- C. Sleeves for Rectangular Openings: Galvanized sheet steel with minimum 0.052- or 0.138-inch thickness as indicated and of length to suit application.
- D. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."

PART 3 - EXECUTION

3.1 RACEWAY APPLICATION

- A. Comply with the following indoor applications, unless otherwise indicated:
 - 1. Exposed, Not Subject to Physical Damage: EMT.
 - 2. Exposed and Subject to Physical Damage: Rigid steel conduit or IMC. Includes raceways in the following locations:
 - a. Loading dock.
 - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
 - c. Mechanical rooms.
 - d. Electrical rooms.
 - e. Stairwells.
 - f. Within block or masonry walls.
 - Concealed Above Hung Ceilings and Within Interior Sheet Rock Walls and Partitions: EMT.
 - 4. Underground Conduit: Rigid steel conduit or IMC, below concrete. Conduit is not allowed within poured concrete.
 - 5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations. Length not to exceed 6 ft.
 - 6. Damp or Wet Locations: Rigid steel conduit.
 - 7. Raceways for Optical Fiber or Communications Cable in Spaces Used for Environmental Air: Plenum-type, optical fiber/communications cable raceway or EMT.
 - 8. Raceways for Optical Fiber or Communications Cable Risers in Vertical Shafts: EMT.
 - 9. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4, nonmetallic in damp or wet locations.

- B. Concealed: FMC ½" inch only in specific locations, in existing areas, within existing walls to remain. Utilize only between box in wall to junction box above ceiling. Junction box shall be located within 12" above hung ceiling. FMC, within walls, not acceptable in other locations.
- C. Minimum Raceway Size: 3/4-inch trade size, except for Communications cabling which shall be minimum raceway size 1-inch.
- D. Raceway Fittings: Compatible with raceways and suitable for use and location.
 - 1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings, unless otherwise indicated.
 - 2. PVC Externally Coated, Rigid Steel Conduits: Use only fittings listed for use with that material. Patch and seal all joints, nicks, and scrapes in PVC coating after installing conduits and fittings. Use sealant recommended by fitting manufacturer.
- E. Install raceways underground or below floor only for locations indicated on drawings.

3.2 INSTALLATION

- A. Comply with NECA 1 for installation requirements applicable to products specified in Part 2 except where requirements on Drawings or in this Article are stricter.
- B. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping. Do not install horizontal raceway directly and parallel under cold water or chilled water pipes. In general, install raceways as high as possible, closer to underside of structure. Install horizontal raceways minimum 8 inches above ceilings.
- C. Complete raceway installation before starting conductor installation.
- D. Support raceways as specified in Division 26 Section "Hangers and Supports for Electrical Systems."
- E. Install temporary closures to prevent foreign matter entering the raceways.
- F. Arrange stub-ups so curved portions of bends are not visible above the finished slab.
- G. Install no more than the equivalent of three 90-degree bends in any conduit run.
- H. Conceal conduit and EMT within finished walls and ceilings, unless otherwise indicated.
- I. Install exposed raceways parallel or at right angles to nearby surfaces or structural members and follow surface contours as much as possible.
 - 1. Run parallel or banked raceways together on common supports.
 - 2. Make parallel bends in parallel or banked runs. Use factory elbows only where elbows can be installed parallel; otherwise, provide field bends for parallel raceways.
- J. Join raceways with fittings designed and approved for that purpose and make joints tight.
 - 1. Use insulating bushings to protect conductors.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- K. Utilize compression fittings only with suitable tools.
- L. Raceways embedded in slabs is not allowed.
- M. Arrange raceways to cross building expansion joints at right angles with expansion fittings.
- N. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- O. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors, including conductors smaller than No. 4 AWG.
- P. Terminations: Where raceways are terminated with locknuts and bushings, align raceways to enter squarely and install locknuts with dished part against the box. Where terminations are not secure with one (1) locknut, use two (2) locknuts: one (1) inside and one (1) outside the box.
- Q. Where raceways are terminated with threaded hubs, screw raceways or fittings tightly into the hub so the end bears against the wire protection shoulder. Where chase nipples are used, align raceways so the coupling is square to the box and tighten the chase nipple so no threads are exposed.
- R. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire.
- S. Raceways for Optical Fiber and Communications Cable: Install raceways, metallic and nonmetallic, rigid and flexible, as follows:
 - 1. Raceway shall be sized to include minimum 33% spare cable capacity for future adds.
 - 2. 1-Inch Trade Size and Larger:
 - a. Install raceways in maximum lengths of 150 feet.
 - b. Install with a maximum of three 90-degree bends or equivalent for each length of raceway unless Drawings show stricter requirements.
 - c. Separate lengths with pull or junction boxes or terminations at distribution frames or cabinets where necessary to comply with these requirements.
 - 3. Conduits shall not be daisy-chained together.
 - 4. Conduit inside bend radius must be:
 - a. 2" Trade size and smaller conduit: minimum bend radius of six times the conduit inside diameter.
 - b. Larger than 2" Trade size conduit: minimum bend radius of 10 times the conduit inside diameter.
 - 5. Conduit fill limits in terms of maximum number of Category 6 cables shall be as follows:

a. 1" Conduit: 5 cablesb. 1-1/4" Conduit: 8 cablesc. 1-1/2" Conduit: 11 cables

UNIVERSITY OF MISSOURI

ISSUED FOR BID

d. 2" Conduit: 20 cablese. 3" Conduit: 47 cablesf. 4" Conduit: 84 cables

- 6. Maintain following minimum clearances from cable pathways, to avoid electromagnetic interference, from the following:
 - a. Motors and transformers: 4-feet
 - b. Conduit and cables used for electrical power distribution: 1-foot
 - c. Fluorescent lighting: 5-inches
- 7. Pull boxes shall be placed directly after a bend where possible, or sized accordingly if the pull box is located at the bend.
- 8. 1-inch minimum conduit shall extend from outlet backbox, to above accessible ceiling with minimum 12-inches clearance above ceiling, turn 90-degrees, and be reamed and installed with a nylon insulated bushing to avoid damage to cables. This conduit must terminate before passing through a fire rated wall.
- 9. When using architect- and owner- approved surface mount raceway, a Wiremold # 5744S outlet box or approved equal shall be provided. Dual channel raceway such as Wiremold 4000 shall use a V/G4007C-1 device plate.
- T. Install raceway sealing fittings at suitable, approved, and accessible locations and fill them with listed sealing compound. For concealed raceways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install raceway sealing fittings at the following points:
 - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
 - 2. Where otherwise required by NFPA 70.
- U. Expansion-Joint Fittings: Install UL approved expansion fittings in each run of aboveground conduit that is located at building expansion joint. Length of fittings shall not exceed 6 inches.
- V. Flexible Conduit Connections: Use maximum of 72 inches of flexible conduit from junction boxes to recessed and semirecessed lighting fixtures, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.
 - 1. Use LFMC in damp or wet locations subject to severe physical damage.
 - 2. Flexible conduit from light fixture to lighting fixture not allowed.
- W. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall.
- X. Set metal floor boxes level and flush with finished floor surface.
- Y. Set nonmetallic floor boxes level. Trim after installation to fit flush with finished floor surface.
- Z. All raceways terminating a junction boxes, located above ceiling shall be provided with color coded vinyl tape indicating the service. Color coding tape shall be applied next to the junction box. Tape color shall match junction box cover color.

AA. The height of the center of outlets above the finished floor, if not otherwise specified or shown on drawings, shall be as following:

Lighting Brackets	As indicated on drawings	
Switch Outlets		
Convenience Receptacle		*
Telephone Outlet		*
Data Outlet		*
Wall Telephone Outlet	3'-10" to centerline	**
Fire Alarm Manual Pull Stations	3'-10" to centerline	
Audio /Visual Alarms	6'-8" to bottom of device	***

- * Minimum height of 1'-3" to meet ADA Standards
- ** Mount at 5'-6" in Mechanical Rooms
- *** Maximum of 6' below finished ceiling whichever is least unless shown or indicated otherwise

Note: Where receptacles are shown installed above countertops, mount receptacles no less than 6" centerline above tops of splash back. See architectural elevations case work shop drawings for determining exact heights.

3.3 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Rectangular Sleeve Minimum Metal Thickness:
 - 1. For sleeve cross-section rectangle perimeter less than 50 inches and no side greater than 16 inches, thickness shall be 0.052 inch.
 - 2. For sleeve cross-section rectangle perimeter equal to, or greater than, 50 inches and 1 or more sides equal to, or greater than, 16 inches, thickness shall be 0.138 inch.
- E. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- F. Cut sleeves to length for mounting flush with both surfaces of walls.
- G. Extend sleeves installed in floors 2 inches above finished floor level.
- H. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and raceway unless sleeve seal is to be installed.
- I. Seal space outside of sleeves with grout for penetrations of concrete and masonry and with approved joint compound for gypsum board assemblies.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- J. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway, using joint sealant appropriate for size, depth, and location of joint. Refer to Division 07 Section "Joint Sealants" for materials and installation.
- K. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway penetrations. Install sleeves and seal with firestop materials. Comply with Division 07 Section "Penetration Firestopping."

3.4 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Penetration Firestopping."

3.5 PROTECTION

- A. Provide final protection and maintain conditions that ensure coatings, finishes, and cabinets are without damage or deterioration at time of Substantial Completion.
 - Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
 - Repair damage to PVC or paint finishes with matching touchup coating recommended by manufacturer.

3.6 CLEANING

A. After completing installation of exposed, factory-finished raceways and boxes, inspect exposed finishes and repair damaged finishes. Remove burrs, dirt, and construction debris.

END OF SECTION 260533

RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

260533 - 10

Project No.: CP242241 February 27, 2024

SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Identification for raceways.
- 2. Identification of power and control cables.
- 3. Identification for conductors.
- 4. Underground-line warning tape.
- 5. Warning labels and signs.
- 6. Instruction signs.
- 7. Equipment identification labels.
- 8. Miscellaneous identification products.

1.3 SUBMITTALS

- A. Product Data: For each electrical identification product indicated.
- B. Identification Schedule: An index of nomenclature of electrical equipment and system components used in identification signs and labels.

1.4 QUALITY ASSURANCE

- A. Comply with ANSI A13.1.
- B. Comply with NFPA 70.
- C. Comply with 29 CFR 1910.144 and 29 CFR 1910.145.
- D. Comply with ANSI Z535.4 for safety signs and labels.
- E. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.5 COORDINATION

- A. Coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual; and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.
- B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- C. Coordinate installation of identifying devices with location of access panels and doors.
- D. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 POWER RACEWAY IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each raceway size.
- B. Colors for Raceways Carrying Circuits at 600 V or Less:
 - 1. Black letters on an orange field.
 - 2. Legend: Indicate voltage and system or service type.
- C. Self-Adhesive Vinyl Labels for Raceways Carrying Circuits at 600 V or Less: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound adhesive tape for securing ends of legend label.

2.2 ARMORED AND METAL-CLAD CABLE IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each raceway and cable size.
- B. Colors for Raceways Carrying Circuits at 600 V and Less:
 - 1. Black letters on an orange field.
 - 2. Legend: Indicate voltage and system or service type.
- C. Self-Adhesive Vinyl Labels: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound adhesive tape for securing ends of legend label.

2.3 POWER AND CONTROL CABLE IDENTIFICATION MATERIALS

A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each raceway and cable size.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

B. Self-Adhesive Vinyl Labels: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound adhesive tape for securing ends of legend label.

2.4 CONDUCTOR IDENTIFICATION MATERIALS

- A. Color-Coding of Conductor Tape: All service, feeder and branch circuit conductors, rated for 600V or less shall be factory color-coded as specified herein. Field applied labels, tapes or bands not acceptable.
- B. Self-Adhesive Vinyl Labels: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound adhesive tape for securing ends of legend label.

2.5 FLOOR MARKING TAPE

A. 2-inch-wide, 5-mil pressure-sensitive vinyl tape, with black and white stripes and clear vinyl overlay.

2.6 WARNING LABELS AND SIGNS

- A. Comply with NFPA 70 and 29 CFR 1910.145.
- B. Self-Adhesive Warning Labels: Factory-printed, multicolor, pressure-sensitive adhesive labels, configured for display on front cover, door, or other access to equipment unless otherwise indicated.
- C. Baked-Enamel Warning Signs:
 - 1. Preprinted aluminum signs, punched or drilled for fasteners, with colors, legend, and size required for application.
 - 2. 1/4-inch grommets in corners for mounting.
 - 3. Nominal size, 7 by 10 inches.
- D. Warning label and sign shall include, but are not limited to, the following legends:
 - 1. Workspace Clearance Warning: "WARNING OSHA REGULATION AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 36 INCHES."

2.7 INSTRUCTION SIGNS

- A. Engraved, laminated acrylic or melamine plastic, minimum 1/16 inch thick for signs up to 20 sq. inches and 1/8 inch thick for larger sizes.
 - 1. Engraved legend with black letters on white face.
 - 2. Punched or drilled for mechanical fasteners.
 - 3. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.

IDENTIFICATION FOR ELECTRICAL SYSTEMS

260553 - 3

2.8 EQUIPMENT IDENTIFICATION LABELS

A. Self-Adhesive, Engraved, Laminated Acrylic or Melamine Label: Minimum 0.0625 inch thick adhesive backed, with white letters on a black background. Minimum letter height shall be 3/8 inch.

2.9 JUNCTION/PULL BOX COVER IDENTIFICATION

- A. Paint all junction and pull box covers to identify service and voltage as follows:
 - 1. 120V Normal power Green.
 - 2. Fire alarm System Red.
- B. All covers shall identify circuit numbers, panel designation, voltage and service. Identification shall be done by black magic markers.

2.10 CABLE TIES

- A. General-Purpose Cable Ties: Fungus inert, self extinguishing, one piece, self locking, Type 6/6 nylon.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 12,000 psi.
 - 3. Temperature Range: Minus 40 to plus 185 deg F.
 - 4. Color: Black except where used for color-coding.
- B. Plenum-Rated Cable Ties: Self extinguishing, UV stabilized, one piece, self locking.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 7000 psi.
 - 3. UL 94 Flame Rating: 94V-0.
 - 4. Temperature Range: Minus 50 to plus 284 deg F.
 - 5. Color: Black.

2.11 MISCELLANEOUS IDENTIFICATION PRODUCTS

- A. Paint: Comply with requirements in Division 09 painting Sections for paint materials and application requirements. Select paint system applicable for surface material and location (exterior or interior).
- B. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Verify identity of each item before installing identification products.
- B. Location: Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.
- C. Apply identification devices to surfaces that require finish after completing finish work.
- D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.
- E. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
- F. System Identification Color-Coding Bands for Raceways and Cables: Each color-coding band shall completely encircle cable or conduit. Place adjacent bands of two-color markings in contact, side by side. Locate bands at changes in direction, at penetrations of walls and floors, at 50-foot maximum intervals in straight runs, and at 25-foot maximum intervals in congested areas, within mechanical rooms, chiller rooms and boiler rooms.
- G. Cable Ties: For attaching tags. Use general-purpose type, except as listed below:
 - 1. Outdoors: UV-stabilized nylon.
 - 2. In Spaces Handling Environmental Air: Plenum rated.
- H. Painted Identification: Comply with requirements in Division 09 painting Sections for surface preparation and paint application.

3.2 IDENTIFICATION SCHEDULE

- A. Accessible Raceways and Metal-Clad Cables, 600 V or Less, for All Service, All Feeder, and Branch Circuits More Than 30 A, and 120 V to ground: Identify with self-adhesive vinyl label or self-adhesive vinyl tape applied in bands. Install labels at 20-foot maximum intervals. The identification will include source board/panel and target board/panel. Use black letters on orange background.
- B. Accessible Raceways and Cables within Buildings: Identify the covers of each junction and pull box as specified herein.
- C. Power-Circuit Conductor Identification, 600 V or Less: Factory color-code conductors as listed below:
 - 1. Colors for 208/120-V Circuits:
 - a. Phase A: Black.
 - b. Phase B: Red.
 - c. Phase C: Blue.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- d. Neutral: White.e. Ground: Green.f. Switch Legs: Pink.
- D. Install instructional sign including the color-code for grounded and ungrounded conductors using adhesive-film-type labels.
- E. Conductors to Be Extended in the Future: Attach marker tape to conductors and list source.
- F. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.
 - 1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
 - 2. Use system of marker tape designations that is uniform and consistent with system used by manufacturer for factory-installed connections.
 - 3. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual.
- G. Workspace Indication: Install floor marking tape to show working clearances in the direction of access to live parts. Workspace shall be as required by NFPA 70 and 29 CFR 1926.403 unless otherwise indicated. Do not install at flush-mounted panelboards and similar equipment in finished spaces.
- H. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Self-adhesive warning labels or Baked-enamel warning signs or Metal-backed, butyrate warning signs.
 - 1. Comply with 29 CFR 1910.145.
 - 2. Identify system voltage with black letters on an orange background.
 - 3. Apply to exterior of door, cover, or other access.
 - 4. For equipment with multiple power or control sources, apply to door or cover of equipment including, but not limited to, the following:
 - a. Power transfer switches.
 - b. Controls with external control power connections.
- I. Operating Instruction Signs: Install instruction signs to facilitate proper operation and maintenance of electrical systems and items to which they connect. Install instruction signs with approved legend where instructions are needed for system or equipment operation.
- J. Emergency Operating Instruction Signs: Install instruction signs with white legend on a red background with minimum 3/8-inch-high letters for emergency instructions at equipment used for power transfer.

IDENTIFICATION FOR ELECTRICAL SYSTEMS

260553 - 6

K. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and the Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.

1. Labeling Instructions:

- a. Indoor Equipment: Self-adhesive, engraved, laminated acrylic or melamine label or Engraved, laminated acrylic or melamine label. Unless otherwise indicated, provide a single line of text with 1/2-inch-high letters on 1-1/2-inch-high label; where two lines of text are required, use labels 2 inches high.
- b. Outdoor Equipment: Engraved, laminated acrylic or melamine label 4 inches high.
- c. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.
- d. Unless provided with self-adhesive means of attachment, fasten labels with
- e. Use appropriate mechanical fasteners that do not change the NEMA or NRTL rating of the enclosure.
- f. The label shall include voltage, phases, number of wires, and board/switchgear/equipment served from. (Example: Panelboard BL-20-LN; 120/208 volts, 3 phase, 4 wire, served from board DP-B1-HN).

2. Equipment to Be Labeled:

- a. Panelboards: Typewritten directory of circuits in the location provided by panelboard manufacturer. Panelboard identification shall be self-adhesive, engraved, laminated acrylic or melamine label.
- b. Enclosures and electrical cabinets.
- c. Access doors and panels for concealed electrical items.
- d. Switchboards.
- e. Enclosed switches.
- f. Enclosed circuit breakers.
- g. Enclosed controllers.
- h. Push-button stations.
- i. Contactors.
- j. Remote-controlled switches, dimmer modules, and control devices.
- k. Battery-inverter units.
- I. Monitoring and control equipment.

END OF SECTION 260553

IDENTIFICATION FOR ELECTRICAL SYSTEMS

260553 - 7



SECTION 260573 - OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY AND ARC FLASH HAZARD ANALYSIS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes computer-based, fault-current and overcurrent protective device coordination studies. Protective devices shall be set based on results of the protective device coordination study. The study shall include short circuit evaluation, device evaluation, device coordination and arc flash evaluation.
- B. The Owner shall be furnished short-circuit and protective device coordination studies as prepared by contractor.
- C. Contractor shall furnish an Arc Flash Hazard Analysis Study per the requirements set forth in the current issue of NFPA 70E Standard for Electrical Safety in the Workplace. The arc flash hazard analysis shall be performed according to the IEEE Standard 1584 2002, the IEEE Guide for Performing Arc-Flash Calculations.
- D. The scope of the studies shall include the new electrical distribution equipment and feeder equipment shown on the plans. New equipment on sheet EP100 shall be added to existing SKM model provided by owner and labeled accordingly.

E. Feeder Circuits:

1. All three (3) phase feeder circuit protective devices installed with a rating equal to or greater than 30 amps.

F. Branch Circuits:

- 1. All three (3) phase branch circuit overcurrent protective devices installed with a rating equal to or greater than 30 amps.
- 2. All motor circuit overcurrent protective devices for motors with a rating equal to or greater than 10 horsepower.

1.3 SUBMITTALS

A. Product Data: For computer software program to be used for studies.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Product Certificates: For coordination-study and fault-current-study computer software programs, certifying compliance with IEEE 399.
- C. Qualification Data: For coordination-study specialist.
- D. The studies shall be submitted to the Owner and Engineer for review and approval prior to final completion.
- E. A preliminary Arc Flash Hazard Analysis shall be submitted to the Owner's Representative and Engineer with new electrical equipment submittals. **Equipment submittals will not be reviewed without the study specified herein.**
- F. The results of the short-circuit, protective device coordination and arc flash hazard analysis studies shall be summarized in a final report. A minimum of two (2) bound color copies of the complete final report shall be submitted. Electronic PDF copies of the report shall be provided. Two (2) CDs containing all study files, including all device curves shall be provided (use the SKM "Project-Backup" command).
- G. The report shall include the following sections:
 - Executive Summary including introduction, Scope of Work and Results / Recommendations.
 - 2. Short-Circuit Methodology, Analysis Results and Recommendations.
 - 3. Short-Circuit Device Evaluation Table.
 - 4. Protective Device Coordination Methodology Analysis Results and Recommendations.
 - 5. Protective Device Settings Table.
 - 6. Time-Current Coordination Graphs and Recommendations.
 - 7. Arc Flash Hazard Methodology Analysis Results and Recommendations including the details of the incident energy and flash protection boundary calculations, along with Arc Flash boundary distances, working distances, Incident Energy levels and Personal Protection Equipment levels.
 - 8. Arc Flashing Labeling section showing types of labels to be provided. Section will contain descriptive information as well as typical label images.
 - 9. One-line system diagram that shall be computer generated and will clearly identify individual equipment buses, bus numbers used in the short-circuit analysis, cable and bus connections between the equipment, calculated maximum short-circuit current at each bus location, devices numbers used in the time-current coordination analysis, and other information pertinent to the computer analysis.
- H. Other Action Submittals: The following submittals shall be made after the approval process for system protective devices has been completed. Submittals shall be in digital form.
 - 1. Coordination-study input data, including completed computer program input data sheets.
 - 2. Study and Equipment Evaluation Reports.
 - 3. Coordination-Study Report.
 - 4. Setting report.
 - 5. Arc flash calculations and report.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.4 QUALITY ASSURANCE

- A. Studies shall use computer programs that are distributed nationally and are in wide use. Software algorithms shall comply with requirements of standards and guides specified in this Section. Manual calculations are not acceptable.
- B. Coordination-Study Specialist Qualifications: An entity experienced in the application of computer software used for studies, having performed successful studies of similar magnitude on electrical distribution systems using similar devices.
 - 1. Professional engineer, licensed in the state where Project is located, shall be responsible for the study. All elements of the study shall be performed under the direct supervision and control of engineer. Submitted study shall bear the seal of the professional engineer.
- C. The Registered Professional Electrical Engineer shall be an employee of the approved firm providing the study.
- D. The Registered Professional Electrical Engineer shall have a minimum of five (5) years of experience in performing power system studies.
- E. The approved firm shall demonstrate experience with Arc Flash Hazard Analysis by submitting names of at least ten actual arc flash hazard analyses it has performed in the past year.
- F. The engineering firm shall have a minimum of ten (10) years of experience in performing power system studies.
- G. The study shall include the stamp or seal and signature of the preparing engineer and shall be reviewed and approved by the Engineer of Record.
- H. Comply with IEEE 242 for short-circuit currents and coordination time intervals.
- I. Comply with IEEE 399 for general study procedures.

PART 2 - PRODUCTS

2.1 COMPUTER SOFTWARE DEVELOPERS

A. Acceptable Computer Software Developers: Subject to compliance with requirements, provide products by SKM Systems Analysis, Inc. only. The study shall be performed using SKM Systems Analysis Power Tools of Windows (PTW 32).

2.2 COMPUTER SOFTWARE PROGRAM REQUIREMENTS

- A. Comply with IEEE 399.
- B. Analytical features of fault-current-study computer software program shall include "mandatory," "very desirable," and "desirable" features as listed in IEEE 399.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Computer software program shall be capable of plotting and diagramming time-current-characteristic curves as part of its output. Computer software program shall report device settings and ratings of all overcurrent protective devices and shall demonstrate selective coordination by computer-generated, time-current coordination plots.
 - 1. Optional Features:
 - Arcing faults.
 - b. Simultaneous faults.
 - c. Explicit negative sequence.
 - d. Mutual coupling in zero sequence.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine Project overcurrent protective device submittals for compliance with electrical distribution system coordination requirements and other conditions affecting performance.
- B. Proceed with coordination study only after relevant equipment submittals have been assembled.

3.2 POWER SYSTEM DATA

- A. Gather and tabulate the following input data to support coordination study:
 - Product Data for overcurrent protective devices specified in other Division 26 Sections and involved in overcurrent protective device coordination studies. Use equipment designation tags that are consistent with electrical distribution system diagrams, overcurrent protective device submittals, input and output data, and recommended device settings.
 - 2. Impedance of utility service entrance.
 - 3. Electrical Distribution System Diagram: In two (2) hard-copy and two (2) CD electronic-copy formats, PDF submittals, showing the following (use SKM "project Backup" command):
 - a. Circuit-breaker and fuse-current ratings and types.
 - b. Relays and associated power and current transformer ratings and ratios.
 - c. Transformer kilovolt amperes, primary and secondary voltages, connection type, impedance, and X/R ratios.
 - d. Cables: Indicate conduit material, sizes of conductors, conductor material, insulation, and length.
 - e. Motor horsepower and code letter designation according to NEMA MG 1.
 - 4. Data sheets to supplement electrical distribution system diagram, cross-referenced with tag numbers on diagram, showing the following:
 - a. Special load considerations, including starting inrush currents and frequent starting and stopping.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- b. Transformer characteristics, including primary protective device, magnetic inrush current, and overload capability.
- c. Motor full-load current, locked rotor current, service factor, starting time, type of start, and thermal-damage curve.
- d. Ratings, types, and settings of utility company's overcurrent protective devices.
- e. Special overcurrent protective device settings or types stipulated by utility company.
- f. Time-current-characteristic curves of devices indicated to be coordinated.
- g. Manufacturer, frame size, interrupting rating in amperes rms symmetrical, ampere or current sensor rating, long-time adjustment range, short-time adjustment range, and instantaneous adjustment range for circuit breakers.
- h. Manufacturer and type, ampere-tap adjustment range, time-delay adjustment range, instantaneous attachment adjustment range, and current transformer ratio for overcurrent relays.
- i. Panelboards, switchboards, motor-control center ampacity, and interrupting rating in amperes rms symmetrical.

3.3 FAULT-CURRENT STUDY

- A. Calculate the maximum available short-circuit current in amperes rms symmetrical at circuit-breaker positions of the electrical power distribution system. The calculation shall be for a current immediately after initiation and for a three-phase bolted short circuit at each of the following:
 - 1. Switchgear and switchboard bus.
 - 2. Motor-control center and starters.
 - 3. Distribution panelboard.
 - 4. Branch circuit panelboard.
- B. Study electrical distribution system from normal and alternate power sources throughout electrical distribution system for Project. Utilize approved computer software program. Include studies of system-switching configurations and alternate operations that could result in maximum fault including arcing fault conditions.
- C. Calculate momentary and interrupting duties on the basis of maximum available fault current.
- D. Calculations to verify interrupting ratings of overcurrent protective devices shall comply with IEEE 141 and IEEE 242.
 - 1. Transformers:
 - a. ANSI C57.12.10.
 - b. ANSI C57.12.22.
 - c. ANSI C57.12.40.
 - d. IEEE C57.12.00.
 - e. IEEE C57.96.
 - 2. Medium-Voltage Circuit Breakers: IEEE C37.010.
 - 3. Low-Voltage Circuit Breakers: IEEE 1015 and IEEE C37.20.1.
 - Low-Voltage Fuses: IEEE C37.46.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

E. Study Report:

- 1. Show calculated X/R ratios and equipment interrupting rating (1/2-cycle) fault currents on electrical distribution system diagram.
- 2. Show momentary (1/2 cycle), interrupting (5-cycle), 30-cycle fault-current values for 3-phase, 2-phase and phase-to-ground faults and time-delayed currents (6 cycles and above) on medium-voltage breakers as needed to set relays and assess the sensitivity of overcurrent relays.

F. Equipment Evaluation Report:

- 1. For 600-V overcurrent protective devices, ensure that interrupting ratings are equal to or higher than calculated 1/2-cycle symmetrical fault current.
- 2. For devices and equipment rated for asymmetrical fault current, apply multiplication factors listed in the standards to 1/2-cycle symmetrical fault current.
- 3. Verify adequacy of phase conductors at maximum three-phase bolted fault currents; verify adequacy of equipment grounding conductors and grounding electrode conductors at maximum ground-fault currents. Ensure that short-circuit withstand ratings are equal to or higher than calculated 1/2-cycle symmetrical fault current.

3.4 COORDINATION STUDY

- A. Perform coordination study using approved computer software program. Prepare a written report using results of fault-current study. Comply with IEEE 399.
 - 1. Calculate the maximum and minimum 1/2-cycle short-circuit currents.
 - Calculate the maximum and minimum interrupting duty (5 cycles to 2 seconds) shortcircuit currents.
 - 3. Calculate the maximum and minimum ground-fault currents.
- B. Protective device coordination time-current curves (TCC) shall be displayed on log-log scale graphs.
- C. Include on each TCC graph, a complete title with descriptive device names.
- D. Terminate device characteristic curves at a point reflecting maximum symmetrical or asymmetrical fault current to which the device is exposed.
- E. Identify the device associated with each curve by manufacturer type, function, and if applicable, tap, time delay, and instantaneous settings recommended.
- F. Plot the following characteristics on the TCC graphs, where applicable.
 - 1. Electric utility's overcurrent protective device.
 - 2. Low voltage fuses including manufacturer's minimum melt, total clearing, tolerance, and damage bands.
 - Low voltage equipment circuit breaker trip devices, including manufacturer's tolerance bands.
 - 4. Transformer full-load current, magnetizing inrush current, and ANSI through-fault protection curves.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

- 5. Ground fault protective devices, as applicable.
- 6. Pertinent motor starting characteristics and motor damage points, where applicable.
- 7. The largest feeder circuit breaker in each motor control center and applicable panelboard.
- G. Provide adequate time margins between device characteristics such that selective operation is provided, while providing proper protection.
- H. Provide the following:
 - A one-line diagram shall be provided which clearly identified individual equipment buses, bus numbers, device identification numbers and the maximum available short-circuit current at each bus.
 - 2. A sufficient number of log-log plots shall be provided to indicate the degree of system protection and coordination by displaying the time-current characteristics of series connected overcurrent devices and other pertinent system parameters.
 - Computer printouts shall accompany the log-log plots and will contain descriptions for each of the devices shown, settings of the adjustable devices, and device identification numbers to aid in locating the devices on the log-log plots and the system one-line diagram.
 - 4. The study shall include a separate, tabular printout containing the recommended settings of all adjustable overcurrent protective devices, the equipment designation where the device is located, and the device number corresponding to the device on the system one-line diagram
 - 5. A discussion section which evaluates the degree of system protection and service continuity with overcurrent devices, along with recommendations as required for addressing system protection or device coordination deficiencies.
 - 6. Contractor shall notify Owner in writing of any significant deficiencies in protection and/or coordination. Provide recommendations for improvements.
- I. Comply with IEEE 141 and IEEE 242 recommendations for fault currents and time intervals.
- J. Transformer Primary Overcurrent Protective Devices:
 - 1. Device shall not operate in response to the following:
 - a. Inrush current when first energized.
 - b. Self-cooled, full-load current or forced-air-cooled, full-load current, whichever is specified for that transformer.
 - c. Permissible transformer overloads according to IEEE C57.96 if required by unusual loading or emergency conditions.
 - 2. Device settings shall protect transformers according to IEEE C57.12.00, for fault currents.
- K. Conductor Protection: Protect cables against damage from fault currents according to ICEA P-32-382, ICEA P-45-482, and conductor melting curves in IEEE 242. Demonstrate that equipment withstands the maximum short-circuit current for a time equivalent to the tripping time of the primary relay protection or total clearing time of the fuse. To determine temperatures that damage insulation, use curves from cable manufacturers or from listed standards indicating conductor size and short-circuit current.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- L. The protective device settings must address the need to minimize arc flash hazards while maintaining proper coordination.
- M. Coordination-Study Report: Prepare a written report indicating the following results of coordination study:
 - 1. Tabular Format of Settings Selected for Overcurrent Protective Devices:
 - a. Device tag.
 - b. Relay-current transformer ratios; and tap, time-dial, and instantaneous-pickup values.
 - c. Circuit-breaker sensor rating; and long-time, short-time, and instantaneous settings.
 - d. Fuse-current rating and type.
 - e. Ground-fault relay-pickup and time-delay settings.
 - 2. Coordination Curves: Prepared to determine settings of overcurrent protective devices to achieve selective coordination. Graphically illustrate that adequate time separation exists between devices installed in series, including power utility company's upstream devices. Prepare separate sets of curves for the switching schemes and for emergency periods where the power source is local generation. Show the following information:
 - a. Device tag.
 - b. Voltage and current ratio for curves.
 - c. Three-phase and single-phase damage points for each transformer.
 - d. No damage, melting, and clearing curves for fuses.
 - e. Cable damage curves.
 - f. Transformer inrush points.
 - g. Maximum fault-current cutoff point.
- N. Completed data sheets for setting of overcurrent protective devices.
- O. Main service entrance switch shall be set to coordinate with utility company.

3.5 OVERCURRENT PROTECTIVE DEVICE SETTING

- A. Manufacturer's Field Service: Engage a factory-authorized service representative, of electrical distribution equipment being set and adjusted, to assist in setting of overcurrent protective devices within equipment.
- B. Testing: Perform the following device setting and prepare reports:
 - 1. After installing overcurrent protective devices and during energizing process of electrical distribution system, perform the following:
 - a. Verify that overcurrent protective devices meet parameters used in studies.
 - b. Adjust devices to values listed in study results.
 - 2. Adjust devices according to recommendations in Chapter 7, "Inspection and Test Procedures", and Tables 10.7 and 10.8 in NETA ATS.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

3.6 ARC FLASH HAZARD ANALYSIS

- A. The arc flash hazard analysis shall be performed according to the IEEE 1584 equations that are presented in NFPA 70E-2009, Annex D. The arc flash hazard analysis shall be performed in conjunction with the short-circuit analysis and the protective device time-current coordination analysis.
- B. The flash protection boundary and the incident energy shall be calculated at significant locations in the electrical distribution system (switchboards, switchgear, motor-control centers, starters, panelboards) where work could be performed on energized parts.
- C. The analysis shall be based on the specific devices installed and include (but not be limited to) the following:
 - 1. Service Entrance Equipment:
 - a. All overcurrent protective devices installed in service entrance panels.
 - 2. Feeder Circuits:
 - a. All three (3) phase feeder circuit overcurrent protective devices installed with a rating equal to or greater than 30 amps.
 - 3. Branch Circuits:
 - a. All three (3) phase feeder circuit overcurrent protective devices installed with a rating equal to or greater than 30 amps.
 - b. All motor circuit overcurrent protective devices for motors with a rating equal to or greater than 10 horsepower.
 - 4. Motor Control Centers:
 - a. All motor circuit overcurrent protective devices for motors with a rating equal to or greater than 10 horsepower.
- D. Working distances shall be based on IEEE 1685. The calculated arc flash protection boundary shall be determined using those working distances.
- E. When appropriate, the short circuit calculations and the clearing times of the phase overcurrent devices will be retrieved from the short-circuit and coordination study model. Ground overcurrent relays should not be taken into consideration when determining the clearing time when performing incident energy calculations.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

- F. The short-circuited calculations and the corresponding incident energy calculations for multiple system scenarios must be compared and the greatest incident energy must be uniquely reported for each equipment location in a single table. Calculations must be performed to represent the maximum and minimum contributions of fault current magnitude for normal and emergency operating conditions. The minimum calculation will assume that the utility contribution is at a minimum. Conversely, the maximum calculation will assume a maximum contribution from the utility. Calculations shall take into consideration the parallel operation of synchronous generators with the electric utility, where applicable as well as any stand-by generator applications.
 - 1. The Arc-Flash Hazard Analysis shall be performed utilizing mutually agreed upon facility operational conditions, and the final report shall describe, when applicable, how these conditions differ from worst-case bolted fault conditions.
- G. The incident energy calculations must consider the accumulation of energy over time when performing arc flash calculations on buses with multiple sources. Alterative calculations must take into account the changing current contributions, as the sources are interrupted or decremented with time. Fault coordination from motors should be decremented as follows:
 - 1. Fault contribution from induction motors should not be considered beyond 5 cycles.
- H. For each piece of ANSI rated equipment with an enclosed main device, two calculations shall be made. A calculation shall be made for the main cubicle, sides, or rear, and shall be based on a device located upstream of the equipment to clear the arcing fault. A second calculation shall be made for the front cubicles and shall be based on the equipment's main device to clear the arcing fault. For all other non-ANSI rated equipment, only one calculation shall be required and it shall be based on a device located upstream of the equipment to clear the arcing fault.
- I. When performing incident energy calculations on the line side of a main breaker (as required per above), the line side and load side contributions must be included in the fault calculation.
- J. Mis-coordination should be checked amongst all devices within the branch containing the immediate protective device upstream of the calculation location and the calculation should utilize the fastest device to complete the incident energy for the corresponding location.
- K. Arc Flash calculations shall be based on actual overcurrent protective device clearing time. A maximum clearing time of 2 seconds will be used based on IEEE 1584-2002 Section B.1.2. Where it is not physically possible to move outside of the flash protection boundary in less than 2 seconds during an arc flash event, a maximum clearing time based on the specific location shall be utilized.

L. Provide the following:

- 1. Results of the Arc-Flash Hazard Analysis shall be submitted in tabular form, and shall include device or bus name, bolted and arcing fault current levels, flash protection boundary distances, working distances, personal-protective equipment classes and AFIE (Arc Flash Incident Energy) levels.
- 2. The Arc-Flash Hazard Analysis shall report incident energy values based on recommended device settings for equipment within the scope of the study.
- 3. The Arc-Flash Hazard Analysis may include recommendations to reduce AFIE levels and enhance worker safety.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.7 FIELD ADJUSTMENT

- A. The contractor shall adjust relay and protective device settings according to the recommended setting table provided by the coordination study.
- B. The contractor shall make modifications to equipment as required to accomplish conformances with short circuit and protective device coordination studies.
- C. The Arc Flash Hazard Analysis shall be reviewed and updated to reflect any changes and corrections to conductor length within one week of the final electrical walk through for punch list.

3.8 ARC FLASH LABELS

- A. Contractor shall provide a 4.0 in. x 4.0 inc. thermal transfer type label of high adhesion polyester for each work location analyzed. The labels shall be waterproof.
- B. The labels shall be designated according to the following standards:
 - 1. UL969 Standard for Marking and Labeling Systems.
 - 2. ANSI Z535.4 Product Safety Signs and Labels.
 - 3. NFPA 70 (National Electric Coe) Article 110.16.
- C. The label shall include the following information:
 - 1. System Voltage.
 - 2. Location.
 - 3. Source Protective device name.
 - 4. Flash protection boundary.
 - 5. Arc-Flash Incident energy value (cal/cm²).
 - a. For incident energy values less than or equal to 40 cal/cm2, label shall indicate "WARNING" using black lettering on orange background.
 - b. For incident energy values greater than 40 cal/cm2, label shall indicate "DANGER" using white lettering with red background.
 - 6. Limited, restricted and prohibited Approach Boundaries.
 - 7. Study report number and issue date.
- D. Labels shall be printed by a thermal transfer type printer, with no field markings.
- E. Arc flash labels shall be provided for equipment as identified in the study and the respective equipment access areas per the following:
 - Floor Standing Equipment: Labels shall be provided on the front of each individual section. Equipment requiring rear and/or side access shall have labels provided on each individual section access area. Equipment line-ups containing sections with multiple incident energy and flash protection boundaries shall be labeled as identified in the Arc Flash Analysis table.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

- 2. Wall Mounted Equipment: Labels shall be provided on the front cover or a nearby adjacent surface, depending upon equipment configuration.
 - a. General Use Safety labels shall be installed on equipment in coordination with the Arc Flash labels. The General Use Safety labels shall warn of general electrical hazards associated with shock, arc flash, and explosions, and instruct workers to turn off power prior to work
- F. Owner and engineer approved Arc Flash Hazard warning labels shall be furnished and installed by the contractor prior to project completion.
 - 1. Contractor shall provide preliminary Arc Flash label for owner's review prior to installation.

END OF SECTION 260573

SECTION 260923 - LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following lighting control devices:
 - 1. Indoor occupancy sensors.
 - 2. Digital Lighting/Receptacle Control System.
 - 3. Emergency shunt relays.
- B. Related Sections include the following:
 - 1. Division 26 Section "Wiring Devices" for wall-box dimmers, wall-switch occupancy sensors, and manual light switches.

1.3 DEFINITIONS

- A. LED: Light-emitting diode.
- B. PIR: Passive infrared.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Show installation details for occupancy and light-level sensors.
 - 1. Interconnection diagrams showing field-installed wiring.
- C. Field quality-control test reports.
- D. Operation and Maintenance Data: For each type of product to include in emergency, operation, and maintenance manuals.

1.5 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1.6 COORDINATION

A. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression system, and partition assemblies.

PART 2 - PRODUCTS

2.1 INDOOR OCCUPANCY SENSORS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Watt Stopper (The).
- B. General Description: Wall- or ceiling-mounting, solid-state units with a separate relay unit.
 - 1. Operation: Unless otherwise indicated, turn lights on when covered area is occupied and off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
 - 2. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A. Sensor shall be powered from the relay unit.
 - 3. Relay Unit: Dry contacts rated for 20-A ballast load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Power supply to sensor shall be 24-V dc, 150-mA, Class 2 power source as defined by NFPA 70.
 - 4. Mounting:
 - a. Sensor: Suitable for mounting in any position on a standard outlet box.
 - b. Relay: Externally mounted through a 1/2-inch knockout in a standard electrical enclosure.
 - c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged
 - 5. Indicator: LED, to show when motion is being detected during testing and normal operation of the sensor.
 - 6. Bypass Switch: Override the on function in case of sensor failure.
 - 7. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc; keep lighting off when selected lighting level is present.

- C. PIR Type: Ceiling mounting; detect occupancy by sensing a combination of heat and movement in area of coverage.
 - 1. Detector Sensitivity: Detect occurrences of 6-inch-minimum movement of any portion of a human body that presents a target of not less than 36 sq. in.
 - 2. Detection Coverage (Room): Detect occupancy anywhere in a circular area of 1000 sq. ft. when mounted on a 96-inch-high ceiling.
 - 3. Detection Coverage (Corridor): Detect occupancy within 90 feet when mounted on a 10-foot-high ceiling.
- D. Ultrasonic Type: Ceiling mounting; detect occupancy by sensing a change in pattern of reflected ultrasonic energy in area of coverage.
 - 1. Detector Sensitivity: Detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
 - 2. Detection Coverage (Small Room): Detect occupancy anywhere within a circular area of 600 sq. ft. when mounted on a 96-inch-high ceiling.
 - 3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. when mounted on a 96-inch-high ceiling.
 - 4. Detection Coverage (Large Room): Detect occupancy anywhere within a circular area of 2000 sq. ft. when mounted on a 96-inch-high ceiling.
 - 5. Detection Coverage (Corridor): Detect occupancy anywhere within 90 feet when mounted on a 10-foot-high ceiling in a corridor not wider than 14 feet.
- E. Dual-Technology Type: Ceiling mounting; detect occupancy by using a combination of PIR and ultrasonic detection methods in area of coverage. Particular technology or combination of technologies that controls on-off functions shall be selectable in the field by operating controls on unit.
 - 1. Sensitivity Adjustment: Separate for each sensing technology.
 - 2. Detector Sensitivity: Detect occurrences of 6-inch-minimum movement of any portion of a human body that presents a target of not less than 36 sq. in., and detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
 - 3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. when mounted on a 96-inch-high ceiling.
- 2.2 Digital Lighting/Receptacle Control System
 - A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Legrand, Wattstopper.
 - B. Description: Intelligent, distributed lighting control system with components that operate on a free-topology local network.
 - 1. Room Controller: Low-voltage, digital, controller for light(s) in a single area or room with the following features.
 - a. 120/277-volt input designed for LED lighting loads.
 - b. One (1) or two (2) relays rated 20 amps as indicated on drawings.

- c. 0-10V dimming capability as indicated on drawings.
- d. Inputs for occupancy sensor and low-voltage wall switch(es).
- 2. Occupancy Sensor: Low-voltage, digital, dual-technology ceiling-mount occupancy sensor with the following features.
 - a. 24 VDC input from digital network.
 - b. LCD display and pushbuttons for setting sensor and system parameters.
 - c. Two (2) RJ45 digital network ports.
 - d. Passive infrared (PIR) and ultrasonic technologies.
 - e. Infrared (IR) transceiver.
- 3. Wall Switch: Low-voltage, digital, push-button wall control station, with number of button(s) indicated on plans, and the following features.
 - a. 24 VDC input from digital network.
 - b. Two (2) RJ45 digital network ports.
 - c. Infrared (IR) transceiver.
- 4. Partition Interface and Wall Switch: Low-voltage, digital interface for movable room partition walls and push-button control station, with number of button(s) indicated on plans, and the following features.
 - a. 24 VDC input from digital network.
 - b. Four (4) input terminals for inputs from limit switches on movable walls.
 - c. Two (2) RJ45 digital network ports.
 - d. Infrared (IR) transceiver.
- 5. Plug Load Controller: Low-voltage, digital interface for control of receptacles with the following features.
 - a. 24 VDC input from digital network.
 - b. One (1) 120-volt, 20-amp relay for on/off control of load.
 - c. Three (3) RJ45 digital network ports.
- C. BAS and Security System Interface: Provide hardware interface to enable the BAS or Security System to control room or plug-load controllers.

2.3 EMERGENCY SHUNT RELAY

- A. Description: Normally closed, electrically held relay, arranged for wiring in parallel with manual or automatic switching contacts; complying with UL 924.
 - 1. Coil Rating: 120 or 277 V.

2.4 CONDUCTORS AND CABLES

A. Power Wiring to Supply Side of Remote-Control Power Sources: Not smaller than No. 12 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- B. Classes 2 and 3 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 18 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."
- C. Class 1 Control Cable: Multiconductor cable with stranded-copper conductors not smaller than No. 14 AWG. Comply with requirements in Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

PART 3 - EXECUTION

3.1 SENSOR INSTALLATION

A. Install and aim sensors in locations to achieve not less than 90 percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's written instructions.

3.2 WIRING INSTALLATION

- A. Wiring Method: Comply with Division 26 Section "Low-Voltage Electrical Power Conductors and Cables". Minimum conduit size shall be 3/4 inch.
- B. Wiring within Enclosures: Comply with NECA 1. Separate power-limited and nonpower-limited conductors according to conductor manufacturer's written instructions.
- C. Size conductors according to lighting control device manufacturer's written instructions, unless otherwise indicated.
- D. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.

3.3 IDENTIFICATION

- A. Identify components and power and control wiring according to Division 26 Section "Identification for Electrical Systems".
- B. Label time switches and contactors with a unique designation.

3.4 FIELD QUALITY CONTROL

- A. Perform the following field tests and inspections and prepare test reports:
 - 1. After installing time switches and sensors, and after electrical circuitry has been energized, adjust and test for compliance with requirements.
 - 2. Operational Test: Verify operation of each lighting control device and adjust time delays.
- B. Lighting control devices that fail tests and inspections are defective work.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.5 ADJUSTING

A. Occupancy Adjustments: When requested within 12 months of date of final acceptance by Owner, provide on-site assistance in adjusting sensors to suit occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.

3.6 DEMONSTRATION

- A. Coordinate demonstration of products specified in this Section with demonstration requirements for low-voltage, programmable lighting control system specified in Division 26 Section "Network Lighting Controls".
- B. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain lighting control devices. Refer to Division 01 Section "Demonstration and Training".

END OF SECTION 260923

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 262726 - WIRING DEVICES

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

Drawings and general provisions of the Contract, including General and Supplementary Α. Conditions and Division 01 Specification Sections, apply to this Section.

1.2 **SUMMARY**

- A. This Section includes the following:
 - 1. Receptacles, receptacles with integral GFCI, and associated device plates.
 - 2. Wall-box motion sensors.
 - 3. Wall-box dimmers.
 - Wall-switch and exterior occupancy sensors. 4.
 - Floor service outlets, poke-through assemblies, service poles, and multioutlet 5. assemblies.
- В. Related Sections include the following:
 - Division 27 Section "Communications Horizontal Cabling" for workstation outlets. 1.

1.3 **DEFINITIONS**

- A. EMI: Electromagnetic interference.
- B. GFCI: Ground-fault circuit interrupter.
- C. Pigtail: Short lead used to connect a device to a branch-circuit conductor.
- D. RFI: Radio-frequency interference.
- E. TVSS: Transient voltage surge suppressor.
- F. UTP: Unshielded twisted pair.

1.4 **SUBMITTALS**

- Product Data: For each type of product indicated. Α.
- Shop Drawings: List of legends and description of materials and process used for premarking B. wall plates.
- Field quality-control test reports. C.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

D. Operation and Maintenance Data: For wiring devices to include in all manufacturers' packing label warnings and instruction manuals that include labeling conditions.

1.5 QUALITY ASSURANCE

- Source Limitations: Obtain each type of wiring device and associated wall plate through one A. source from a single manufacturer. Insofar as they are available, obtain all wiring devices and associated wall plates from a single manufacturer and one source.
- Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, B. Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with NFPA 70.

1.6 COORDINATION

- Α. Receptacles for Owner-Furnished Equipment: Match plug configurations.
 - 1. Cord and Plug Sets: Match equipment requirements.

EXTRA MATERIALS 1.7

- A. Furnish extra materials described in subparagraphs below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Floor Service Outlet Assemblies: One for every 10 installed, but no fewer than one.
 - Receptacles: One for every 20 installed, but no fewer than two. 2.
 - Snap Switches: One for every 20 installed, but no fewer than two. 3.

PART 2 - PRODUCTS

2.1 **MANUFACTURERS**

- A. Acceptable Manufacturers' Names: Subject to compliance with requirements, provide products by one of the following:
 - 1. Wiring Devices (Receptacles, Switches):
 - Cooper Wiring Devices. a.
 - Hubbell Incorporated; Wiring Device-Kellems. b.
 - Leviton Mfg. Company Inc. C.
 - Pass & Seymour/Legrand; Wiring Devices Div. d.

WIRING DEVICES 262726 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2. Occupancy Sensors:

- Cooper Industries, Inc. a.
- Hubbell Incorporated. b.
- Leviton Mfg. Company, Inc. C.
- Pass & Seymour/Legrand. d.
- e. The Watt Stopper.

3. Poke-Through and Floor Service Outlets:

- Hubbell Incorporated: Wiring Device-Kellems.
- Pass & Seymour/Legrand; Wiring Devices Div. b.
- Square D/Groupe Schneider NA. C.
- Thomas & Betts Corporation. d.
- Wiremold Company (The). e.

4. Multioutlet Assemblies:

- Hubbell Incorporated; Wiring Device-Kellems. a.
- Wiremold Company (The). b.

2.2 STRAIGHT BLADE RECEPTACLES

- Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 configuration A. 5-20R, UL 498, and FS W-C-596.
 - 1. Description: Grounding system shall be all brass and integral to the wrap around mounting strap (single-piece with no rivets or mechanical connections in the primary path between the point of ground wire termination and ground blades). NOTE: specific catalog numbers are not listed below. This product description (or similar verbiage) must be highlighted in the submittal documents to confirm this performance requirement has been satisfied.

2.3 **GFCI RECEPTACLES**

- General Description: Straight blade, feed-through type. Comply with NEMA WD 1, NEMA WD 6, Α. UL 498, and UL 943, Class A, and include indicator light that is lighted when device is tripped.
- В. Duplex GFCI Convenience Receptacles, 125 V, 20 A.

2.4 WALL-BOX DIMMERS

- Dimmer Switches: Modular, full-wave, solid-state units with integral, guiet on-off switches, with Α. audible frequency and EMI/RFI suppression filters.
- В. Control: Continuously adjustable slider; with single-pole or three-way switching. Comply with UL 1472.

WIRING DEVICES 262726 - 3 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Incandescent Lamp Dimmers: 120 V; control shall follow square-law dimming curve. On-off switch positions shall bypass dimmer module.
 - 1. 600 W; dimmers shall require no derating when ganged with other devices. Illuminated when "OFF."
- D. Fluorescent Lamp Dimmer Switches: Modular; compatible with dimmer ballasts; trim potentiometer to adjust low-end dimming; dimmer-ballast combination capable of consistent dimming with low end not greater than 20 percent of full brightness.

OCCUPANCY SENSORS 2.5

A. Wall-Switch Sensors:

Description: Passive-infrared type, 120/277 V, adjustable time delay up to 30 minutes, 1. 180-degree field of view, with a minimum coverage area of 900 sq. ft.

Wall-Switch Sensors: B.

1. Description: Adaptive-technology type, 120/277 V, adjustable time delay up to 20 minutes, 180-degree field of view, with a minimum coverage area of 900 sq. ft.

C. Long-Range Wall-Switch Sensors:

Description: Passive-infrared type, 120/277 V, adjustable time delay up to 30 minutes, 1. 110-degree field of view, with a minimum coverage area of 1200 sq. ft.

D. Long-Range Wall-Switch Sensors:

1. Description: Dual technology, with both passive-infrared- and ultrasonic-type sensing, 120/277 V, adjustable time delay up to 30 minutes, 110-degree field of view, and a minimum coverage area of 1200 sq. ft.

E. Wide-Range Wall-Switch Sensors:

Description: Passive-infrared type, 120/277 V, adjustable time delay up to 30 minutes, 1. 150-degree field of view, with a minimum coverage area of 1200 sq. ft.

F. **Exterior Occupancy Sensors:**

1. Description: Passive-infrared type, 120/277 V, weatherproof, adjustable time delay up to 15 minutes, 180-degree field of view, and 110-foot detection range. Minimum switch rating: 1000-W incandescent, 500-VA fluorescent.

2.6 WALL PLATES

- A. Single and combination types to match corresponding wiring devices.
 - 1. Plate-Securing Screws: Metal with head color to match plate finish.
 - 2. Material for Finished Spaces: Smooth, high-impact thermoplastic.

WIRING DEVICES 262726 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3. Material for Unfinished Spaces: Smooth, high-impact thermoplastic.
- 4. Material for Damp Locations: Cast aluminum with spring-loaded lift cover, and listed and labeled for use in "wet locations."
- Wet-Location, Weatherproof Cover Plates: NEMA 250, complying with type 3R weather-B. resistant, die-cast aluminum with lockable cover.

2.7 FLOOR SERVICE FITTINGS

- Α. Type: Modular, flush-type, dual-service units suitable for wiring method used.
- В. Compartments: Barrier separates power from voice and data communication cabling.
- C. Service Plate: Round, die-cast aluminum with satin finish.
- D. Power Receptacle: NEMA WD 6 configuration 5-20R, gray finish, unless otherwise indicated.
- E. Voice and Data Communication Outlet: Two modular, keyed, color-coded, RJ-45 Category 5e jacks for UTP cable.

2.8 POKE-THROUGH ASSEMBLIES

- A. Description: Factory-fabricated and -wired assembly of below-floor junction box with multichanneled, through-floor raceway/firestop unit and detachable matching floor service outlet assembly.
 - 1. Service Outlet Assembly: Pedestal type with services indicated or Flush type with two simplex receptacles and space for two RJ-45 jacks.
 - Size: Selected to fit nominal 3-inch cored holes in floor and matched to floor thickness. 2.
 - Fire Rating: Unit is listed and labeled for fire rating of floor-ceiling assembly.
 - Closure Plug: Arranged to close unused 3-inch cored openings and reestablish fire rating 4. of floor.
 - 5. Wiring Raceways and Compartments: For a minimum of four No. 12 AWG conductors and a minimum of two, 4-pair, Category 5e voice and data communication cables.

2.9 MULTIOUTLET ASSEMBLIES

- Components of Assemblies: Products from a single manufacturer designed for use as a A. complete, matching assembly of raceways and receptacles.
- B. Raceway Material: Metal, with manufacturer's standard finish.
- C. Wire: No. 12 AWG.
- D. Number of Circuits: As indicated on drawings.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.10 **FINISHES**

- A. Color: Wiring device catalog numbers in Section Text do not designate device color.
 - 1. Wiring Devices: Ivory or White or As selected by Architect, unless otherwise indicated or required by NFPA 70 or device listing.

PART 3 - EXECUTION

3.1 **APPLICATION**

- Wiring devices, on emergency power circuits, shall be red in color. Α.
- В. All wall plates within a room or area shall be same type - thermoplastic. Mix matching of wall plates shall not be acceptable.

3.2 INSTALLATION

- Comply with NECA 1, including the mounting heights listed in that standard, unless otherwise A.
- В. Coordination with Other Trades:
 - 1. Take steps to insure that devices and their boxes are protected. Do not place wall finish materials over device boxes and do not cut holes for boxes with routers that are guided by riding against outside of the boxes.
 - 2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
 - 3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
 - 4. Install wiring devices after all wall preparation, including painting, is complete.

Conductors: C.

- 1. Do not strip insulation from conductors until just before they are spliced or terminated on devices.
- 2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
- 3. The length of free conductors at outlets for devices shall meet provisions of NFPA 70. Article 300, without pigtails.
- **Existing Conductors:** 4.
 - Cut back and pigtail, or replace all damaged conductors. a.
 - b. Straighten conductors that remain and remove corrosion and foreign matter.
 - Pigtailing existing conductors is permitted provided the outlet box is large enough.

WIRING DEVICES 262726 - 6 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

D. Device Installation:

- Replace all devices that have been in temporary use during construction or that show 1. signs that they were installed before building finishing operations were complete.
- 2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
- 3. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
- 4. Connect devices to branch circuits using pigtails that are not less than 6 inches in length.
- When there is a choice, use side wiring with binding-head screw terminals. Wrap solid 5. conductor tightly clockwise, 2/3 to 3/4 of the way around terminal screw.
- 6. Use a torque screwdriver when a torque is recommended or required by the manufacturer.
- 7. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
- 8. Tighten unused terminal screws on the device.
- When mounting into metal boxes, remove the fiber or plastic washers used to hold device 9. mounting screws in vokes, allowing metal-to-metal contact.
- 10. Install devices and assemblies level, plumb and square with building lines.

E. Receptacle Orientation:

- 1. Install ground pin of vertically mounted receptacles at top, and on horizontally mounted receptacles to the right.
- 2. Install ground pin of vertically mounted receptacles, located more than 60" above floor, at bottom.
- F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.

G. Dimmers:

- 1. Install dimmers within terms of their listing.
- Verify that dimmers used for fan speed control are listed for that application. 2.
- Install unshared neutral conductors on line and load side of dimmers according to 3. manufacturers' device listing conditions in the written instructions.
- H. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.
- I. Adjust locations of floor service outlets and service poles to suit arrangement of partitions and furnishings.
- Install GFCI receptacles as shown on drawings and within 60 inches of water source. J.

WIRING DEVICES 262726 - 7 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.3 IDENTIFICATION

- A. Comply with Division 26 Section "Identification for Electrical Systems."
 - 1. Receptacles and Switch Wall Plates: Identify panelboard and circuit number from which served. Use engraved machine printing with black-filled lettering on face of plate, and durable wire markers or tags inside outlet boxes.

3.4 FIELD QUALITY CONTROL

- A. Perform tests and inspections and prepare test reports.
 - 1. Test Instruments: Use instruments that comply with UL 1436.
 - 2. Test Instrument for Convenience Receptacles: Digital wiring analyzer with digital readout or illuminated LED indicators of measurement.
- B. Tests for Convenience Receptacles:
 - 1. Line Voltage: Acceptable range is 105 to 132 V.
 - 2. Percent Voltage Drop under 15-A Load: A value of 5 percent or higher is not acceptable.
 - 3. Ground Impedance: Values of up to 2 ohms are acceptable.
 - 4. GFCI Trip: Test for tripping values specified in UL 1436 and UL 943.
 - 5. Using the test plug, verify that the device and its outlet box are securely mounted.
 - 6. The tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.

END OF SECTION 262726

WIRING DEVICES 262726 - 8 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

SECTION 265100 - INTERIOR LIGHTING

PART 1 - GENERAL

1.1 **RELATED DOCUMENTS**

Drawings and general provisions of the Contract, including General and Supplementary Α. Conditions and Division 01 Specification Sections, apply to this Section.

1.2 **SUMMARY**

- A. This Section includes the following:
 - 1. Interior lighting fixtures, LED modules, and drivers.
 - 2. Exit signs.
 - 3. Lighting fixture supports.
- Related Sections include the following: В.
 - 1. Division 26 Section "Lighting Control Devices".
 - Division 26 Section "Wiring Devices". 2.

1.3 **DEFINITIONS**

- Α. BF: Ballast factor.
- B. CRI: Color-rendering index.
- C. CU: Coefficient of utilization.
- D. LER: Luminaire efficacy rating.
- E. Luminaire: Complete lighting fixture, including ballast housing if provided.
- F. RCR: Room cavity ratio.

1.4 **SUBMITTALS**

- Product Data: For each type of lighting fixture, arranged in order of fixture designation. Include A. data on features, accessories, finishes, and the following:
 - Physical description of lighting fixture including dimensions. 1.
 - LED driver. 2.
 - 3. Energy-efficiency data.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 4. Photometric data, in IESNA format, based on laboratory tests of each lighting fixture type, outfitted with LEDs and drivers identical to those indicated for the lighting fixture as applied in this Project.
 - For indicated fixtures, photometric data shall be certified by a qualified a. independent testing agency. Photometric data for remaining fixtures shall be certified by the manufacturer.
 - b. Photometric data shall be certified by a manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program (NVLAP) for Energy Efficient Lighting Products.
- В. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
 - Lighting fixtures. 1.
 - Suspended ceiling components. 2.
 - 3. Structural members to which suspension systems for lighting fixtures will be attached.
- C. Field quality-control test reports.
- D. Operation and Maintenance Data: For lighting equipment and fixtures to include in emergency, operation, and maintenance manuals.
- E. Warranties: Special warranties specified in this Section.

QUALITY ASSURANCE 1.5

- Luminaire Photometric Data Testing Laboratory Qualifications: Provided by manufacturers' Α. laboratories that are accredited under the National Volunteer Laboratory Accreditation Program for Energy Efficient Lighting Products.
- В. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with NFPA 70.

1.6 COORDINATION

A. Coordinate layout and installation of lighting fixtures and suspension system with other construction that penetrates ceilings or is supported by them, including HVAC equipment, firesuppression system, and partition assemblies.

INTERIOR LIGHTING 265100 - 2 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.7 WARRANTY

- A. Special Warranty for LED Drivers: Manufacturer's standard form in which drivers manufacturer agrees to repair or replace drivers that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period for Electronic Drivers: Five years from date of final acceptance by Owner.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
- B. In Interior Lighting Fixture Schedule where titles below are column or row headings that introduce lists, the following requirements apply to product selection:
 - 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.
 - 2. Troffers:
 - a. Columbia Lighting; Division of Hubbell Lighting.
 - b. H.E. Williams, Inc.
 - c. Lithonia Lighting.
 - d. LSI Midwest Lighting.
 - e. Metalux.
 - 3. Strip Fixtures:
 - a. Columbia Lighting; Division of Hubbell Lighting.
 - b. H.E. Williams, Inc.
 - c. Lithonia Lighting.
 - d. LSI Midwest Lighting.
 - e. Metalux.
 - 4. Under Cabinet Fixtures:
 - a. ALKCO; Division of JJI Lighting Group Co.
 - b. Columbia Lighting.
 - c. H.E. Williams, Inc.
 - d. Lithonia Lighting.
 - e. LSI Midwest Lighting.
 - f. Metalux.
 - g. Nulite Limited.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 5. Exit Signs and Emergency Lighting:
 - Dual-Lite; Division of Hubbell Lighting. a.
 - Emergi-lite: Division of Thomas and Betts. b.
 - Failsafe: Division of Cooper Lighting. C.
 - H.E. Williams, Inc. d.
 - e. Hubbell Lighting, Inc.
 - f. Lithonia Lighting.
 - Prescolite; Division of Hubbell Lighting. g.
 - h. Surelite: division of Cooper Lighting.
- 6. Downlighting (Recessed, Surface, HID):
 - Edison Price Lighting. a.
 - Halo; Division of Cooper Lighting. b.
 - H.E. Williams, Inc. C.
 - d. Hubbell Lighting, Inc.
 - e. Infinity Lighting.
 - f. The Kirlin Company.
 - Kurt Versen Co. g.
 - h. Lithonia Lighting.
 - Lightolier; Division of Genlyte Thomas Co. i.
 - Prescolite: division of Hubbell Lighting. j.
 - Rambusch Lighting. k.
- C. In order to create a controlled, competitive bidding climate, the Lighting Fixture Schedule, as indicated on the drawings, was developed around the manufacturer listed in the schedule. Equal products from the manufacturers listed will be acceptable. In limited circumstances, for various reasons, certain fixtures were deemed to be proprietary. In these cases, the language, "No substitutions", is intended to provide the electrical distributors bidding the job with the ability to assembly the most competitive lump sum price for the lighting fixture/lamp package. The electrical distributor, therefore, has the authority to require unit pricing from the manufacturer's representatives for those products so specified.
- Light Fixture Schedule as indicated on drawings. D.

2.2 LIGHTING FIXTURES AND COMPONENTS, GENERAL REQUIREMENTS

- Α. Recessed Fixtures: Comply with NEMA LE 4 for ceiling compatibility for recessed fixtures.
- B. Metal Parts: Free of burrs and sharp corners and edges.
- Sheet Metal Components: Steel, unless otherwise indicated. Form and support to prevent C. warping and sagging.
- D. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

INTERIOR LIGHTING 265100 - 4 Project No.: CP242241

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- E. Reflecting surfaces shall have minimum reflectance as follows, unless otherwise indicated:
 - 1. White Surfaces: 85 percent.
 - Specular Surfaces: 83 percent. 2.
 - Diffusing Specular Surfaces: 75 percent. 3.
 - Laminated Silver Metallized Film: 90 percent. 4.
- F. Plastic Diffusers, Covers, and Globes:
 - 1. Acrylic Lighting Diffusers: 100 percent virgin acrylic plastic. High resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
 - Lens Thickness: At least 0.125 inch minimum unless different thickness is indicated.
 - b. UV stabilized.
 - 2. Glass: Annealed crystal glass, unless otherwise indicated.
- G. Electromagnetic-Interference Filters: Factory installed to suppress conducted electromagneticinterference as required by MIL-STD-461E. Fabricate lighting fixtures with one filter on each ballast indicated to require a filter.

2.3 LED MODULES AND DRIVERS

- A. Comply with LM-79, LM-80 and TM-21 standards for the following:
 - Color Rendering Index (CRI): Minimum 80. 1.
 - Color Corrected Temperature (CCT): As noted in Light Fixture Schedule. 2.
 - Lumen Output: As noted in Light Fixture Schedule. 3.
 - Lifetime: L70 minimum 50,000 hours.
- B. Dimming: Drivers shall be dimmable down to 1% standard, unless noted otherwise in Light Fixture Schedule, and flicker-free.
- C. Control Voltage: As noted in Light Fixture Schedule.
 - 1. Ballast Manufacturer Certification: Indicated by label.

EXIT SIGNS 2.4

- Description: Comply with UL 924; for sign colors, visibility, luminance, and lettering size, comply Α. with authorities having jurisdiction.
- В. Internally Lighted Signs:
 - 1. Lamps for AC Operation: LEDs, 70,000 hours minimum rated lamp life.

INTERIOR LIGHTING 265100 - 5 Project No.: CP242241

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.5 LIGHTING FIXTURE SUPPORT COMPONENTS

- Α. Comply with Division 26 Section "Hangers and Supports for Electrical Systems" for channeland angle-iron supports and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch steel tubing with swivel ball fittings and ceiling canopy. Finish same as fixture.
- Twin-Stem Hangers: Two, 1/2-inch steel tubes with single canopy designed to mount a single C. fixture. Finish same as fixture.
- D. Wires: ASTM A 641/A 641M, Class 3, soft temper, zinc-coated steel, 12 gauge.
- E. Wires for Humid Spaces: ASTM A 580/A 580M, Composition 302 or 304, annealed stainless steel, 12 gage.
- F. Rod Hangers: 3/16-inch minimum diameter, cadmium-plated, threaded steel rod.
- Hook Hangers: Integrated assembly matched to fixture and line voltage and equipped with G. threaded attachment, cord, and locking-type plug.

2.6 DIMMING CONTROL DEVICES

Dimming Controls: Sliding-handle type with on/off control; compatible with LED driver and Α. having light output and energy input over the full dimming range.

PART 3 - EXECUTION

3.1 **INSTALLATION**

- Α. Lighting fixtures: Set level, plumb, and square with ceilings and walls. Install lamps in each fixture.
- B. Support for Lighting Fixtures in or on Grid-Type Suspended Ceilings: Use grid as a support element.
 - Install a minimum of four ceiling support system rods or wires for each fixture. Locate not 1. more than 6 inches from lighting fixture corners.
 - 2. Support Clips: Fasten to lighting fixtures and to ceiling grid members at or near each fixture corner with clips that are UL listed for the application.
 - 3. Fixtures of Sizes Less Than Ceiling Grid: Install as indicated on reflected ceiling plans or center in acoustical panel, and support fixtures independently with at least two 3/4-inch metal channels spanning and secured to ceiling tees.
 - Install at least two independent support rods or wires from structure to a tab on lighting 4. fixture. Wire or rod shall have breaking strength of the weight of fixture at a safety factor of 3.

INTERIOR LIGHTING 265100 - 6 Project No.: CP242241

February 27, 2024

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Suspended Lighting Fixture Support:
 - 1. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
 - 2. Stem-Mounted, Single-Unit Fixtures: Suspend with twin-stem hangers.
 - 3. Continuous Rows: Use tubing or stem for wiring at one point and tubing or rod for suspension for each unit length of fixture chassis, including one at each end.
- D. Adjust aimable lighting fixtures to provide required light intensities.
- E. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables".

3.2 FIELD QUALITY CONTROL

A. Prepare a written report of tests, inspections, observations, and verifications indicating and interpreting results. If adjustments are made to lighting system, retest to demonstrate compliance with standards.

END OF SECTION 265100

INTERIOR LIGHTING 265100 - 7 Project No.: CP242241

February 27, 2024



SECTION 270500 - COMMON WORK RESULTS FOR COMMUNICATIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. MU Division of IT Telecommunications Construction Standards and Specifications apply to this section. The Contractor shall obtain the latest revision of document and install all cables, pathways, boxes, equipment, and hardware in a manner to conform with MU Standards and Specifications.

1.2 SUMMARY

A. Section Includes:

- 1. Communications equipment coordination and installation.
- 2. Sleeves for pathways and cables.
- 3. Grout.
- 4. Common communications installation requirements.

1.3 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.
- B. NBR: Acrylonitrile-butadiene rubber.

1.4 SUBMITTALS

A. Product Data: For pre-manufactured sleeves, and for sleeve seals.

1.5 COORDINATION

- A. Coordinate arrangement, mounting, and support of communications equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
 - To provide for ease of disconnecting the equipment with minimum interference to other installations.
 - 3. To allow right of way for piping and conduit installed at required slope.
 - 4. So connecting pathways, cables, wireways and cable trays will be clear of obstructions and of the working and access space of other equipment.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

- B. Coordinate installation of required supporting devices and other structural components as they are constructed.
- Coordinate location of access panels and doors for communications items that are behind finished surfaces or otherwise concealed.
- D. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."

1.6 SCHEDULING AND PHASING

A. All Communications work shall be scheduled to meet project completion date. All work shall be phased for projects requiring phasing work. Install additional conduit, junction-boxes, pull-boxes, devices, cables as required to support phasing. Refer to phasing schedule on drawings.

PART 2 - PRODUCTS

2.1 SLEEVES FOR PATHWAYS AND CABLES

- A. Pre-manufactured fire-stop sleeves: STI EZ-Path Series 44. Provide in quantity to match cable fill capacity to fill capacity of adjacent cable tray, where tray path crosses fire- and/or smokerated walls.
- B. Steel Pipe Sleeves: ASTM A 53, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- C. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- D. Sleeves for Rectangular Openings: Galvanized sheet steel.
 - 1. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches and no side more than 16 inches, thickness shall be 0.052 inch.
 - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches and 1 or more sides equal to, or more than, 16 inches, thickness shall be 0.138 inch.

2.2 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.3 COORDINATION DRAWINGS

- A. The contractor shall prepare CAD generated drawings (min. 1/4" scale) showing following systems/items as a minimum:
 - 1. Equipment locations and clearances required.
 - 2. Locations of items in ceilings such as lights, etc.
- B. The contractor shall submit the CAD generated drawings for coordination with other trades. The drawings shall be submitted either in electronic format or printed copies as requested by the contractor.
- C. The contractor shall participate in coordination meetings when requested.

2.4 PROJECT RECORD DRAWINGS

- A. Drawings shall be furnished in electronic-media (CD-Rewritable type) and at-least one hard copy prints.
 - 1. Format: Same CAD program, version and operating system as the original contract documents.
 - 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw and add details and notations where applicable.
- B. Identify and date each drawing and include the designation "PROJECT RECORD DRAWING" or "AS-BUILT DRAWING" in a prominent location, with contractor's name below it.

PART 3 - EXECUTION

3.1 DEMOLITION

- A. Refer to Division 02 Section "Selective Demolition" for general demolition requirements and procedures.
- B. Disconnect, demolish, and remove communication systems, fixtures, devices, and components indicated to be removed. In general, remove all fixtures, raceways, cables, junction boxes, and equipment not utilized in new construction. For devices disconnected, remove raceways and cables all way to the source.
- C. Protect existing communication equipment and installation indicated to remain. If damaged or disturbed in the course of the Work, remove damaged portions and install new products of equal capacity, quality, and functionality.
- D. Accessible Work: Remove exposed communication equipment and installations, indicated to be demolished, in their entirety.
- E. Remove demolished material from Project site.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- F. Remove, store, clean, reinstall, reconnect, and make operational components indicated for relocation.
- G. Remove equipment to be salvaged, disconnect from power, and deliver to Owner as directed.

3.2 COMMON REQUIREMENTS FOR COMMUNICATIONS INSTALLATION

- A. Comply with NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- D. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both communications equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- E. Right of Way: Give to piping systems installed at a required slope.
- F. In general install raceways and boxes minimum 8" above hung ceiling. All raceways, boxes and equipment shall be independently supported from structure. Do not support from ductwork or piping.
- G. Maintain following minimum clearances from J-hooks and all cable pathways, to avoid electromagnetic interference, from the following:
 - 1. Motors and transformers: 4-feet
 - 2. Conduit and cables used for electrical power distribution: 1-foot
 - 3. Fluorescent lighting: 5-inches

3.3 SLEEVE INSTALLATION FOR COMMUNICATIONS PENETRATIONS

- A. Communications penetrations occur when pathways, cables, wireways, or cable trays penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- E. Cut sleeves to length for mounting to extend three inches past both surfaces of walls.
- F. Extend sleeves installed in floors four inches above finished floor level.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- G. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and pathway or cable, unless indicated otherwise.
- H. Seal space outside of sleeves with grout for penetrations of concrete and masonry.
 - Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- I. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and pathway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants".
- J. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pathway and cable penetrations. Install sleeves and seal pathway and cable penetration sleeves with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping."

3.4 FIRESTOPPING

A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for communications installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Penetration Firestopping."

END OF SECTION 270500

COMMON WORK RESULTS FOR COMMUNICATIONS

270500 - 5

Project No.: CP242241 February 27, 2024



SECTION 271500 - COMMUNICATIONS HORIZONTAL CABLING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. MU Division of IT Telecommunications Construction Standards and Specifications apply to this section. The Contractor shall obtain the latest revision of document and install all cables, pathways, boxes, equipment, and hardware in a manner to conform with MU Standards and Specifications.

1.2 SUMMARY

A. Section Includes:

- 1. Pathways.
- 2. UTP cabling.
- 3. Coaxial cable.
- 4. Cabling system identification products.
- Cable management system.

B. Related Sections:

1. Division 28 Section "Conductors and Cables for Electronic Safety and Security" for voice and data cabling associated with system panels and devices.

C. System Description:

- 1. The Owner will furnish, terminate, label, and test all telephone, data and television cable for installation by the Contractor. The Contractor shall install all Owner-provided horizontal cables in a manner acceptable to the Owner.
- 2. All backbone cabling and telephone, data and television distribution equipment will be furnished, installed, terminated, labeled, and tested by the Owner.
- 3. Equipment racks and overhead ladder runways in Telecom Rooms shall be furnished and installed by Owner. Owner will bond these items to Contractor-provided busbars within the Telecom Rooms.
- 4. All work shall be coordinated with the Owner.
- 5. Cabling shall be supported with cable tray and with J-hooks in accessible ceiling areas. Cable tray layout is shown on the plans, J-Hook methodology on the drawing details, and shall be furnished and installed by the Contractor. Install cabling in EMT conduit with capacity equaling adjacent cable tray in areas where ceilings are not accessible.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.3 DEFINITIONS

- A. Basket Cable Tray: A fabricated structure consisting of wire mesh bottom and side rails.
- B. BICSI: Building Industry Consulting Service International.
- C. Channel Cable Tray: A fabricated structure consisting of a one-piece, ventilated-bottom or solid-bottom channel.
- D. Consolidation Point: A location for interconnection between horizontal cables extending from building pathways and horizontal cables extending into furniture pathways.
- E. Cross-Connect: A facility enabling the termination of cable elements and their interconnection or cross-connection.
- F. EMI: Electromagnetic interference.
- G. IDC: Insulation displacement connector.
- H. Ladder Cable Tray: A fabricated structure consisting of two longitudinal side rails connected by individual transverse members (rungs).
- LAN: Local area network.
- J. MUTOA: Multiuser telecommunications outlet assembly, a grouping in one location of several telecommunications outlet/connectors.
- K. Outlet/Connectors: A connecting device in the work area on which horizontal cable or outlet cable terminates.
- L. RCDD: Registered Communications Distribution Designer.
- M. Solid-Bottom or Nonventilated Cable Tray: A fabricated structure consisting of longitudinal side rails and a bottom without ventilation openings.
- N. Trough or Ventilated Cable Tray: A fabricated structure consisting of longitudinal side rails and a bottom having openings for the passage of air.
- O. UTP: Unshielded twisted pair.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
 - 1. J-hooks.
 - 2. Telecommunications Grounding busbars, conductors and bonding connectors.
- B. Qualification Data: For qualified layout technician and installation supervisor.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
 - 1. Installation Supervision: Installation shall be under the direct supervision of a BICSI Level 2 Installer, who shall be present at all times when Work of this Section is performed at Project site.
- B. All testing shall be performed by Owner. Contractor shall re-pull all cables that fail testing.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. Telecommunications Pathways and Spaces: Comply with ANSI/TIA-569-B.
- E. Grounding: Comply with ANSI-J-STD-607-A.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. The Owner will deliver all cables to the job site. The Contractor shall store cables to prevent entrance of dirt, debris and moisture.
- B. Protect stored cables from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, if stored inside.

1.7 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.8 COORDINATION

- A. Coordinate layout and installation of telecommunications pathways and cabling with Owner's telecommunications and LAN equipment and service suppliers.
- B. Coordinate telecommunications outlet/connector locations with location of power receptacles at each work area.

COMMUNICATIONS HORIZONTAL CABLING 271500 - 3

Project No.: CP242241 February 27, 2024

PART 2 - PRODUCTS

2.1 PATHWAYS

- A. Cable Support: NRTL labeled for support of Category 6A cabling, designed to prevent degradation of cable performance and pinch points that could damage cable.
 - 1. J-hooks with fastening devices to maintain cable bundles within j-hooks.
 - 2. J-hooks shall be plenum rated, and as manufactured by B-Line, Erico/Caddy, or Panduit.
 - 3. J-hooks shall be sized to allow for minimum 40% spare cable capacity, with a minimum support diameter of 2 inches.
 - 4. Cable bundles in J-hooks shall not exceed fifty (50) cables.
- B. Conduit and Boxes: Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems." Flexible metal conduit shall not be used.
 - 1. Outlet boxes shall be no smaller than 4 inches wide, 4 inches high, and 2-1/2 inches deep, with plaster ring to accommodate a 2 inch by 4 inch faceplate, unless noted otherwise on the plans.
 - 2. Conduit stub-ups from outlet boxes to above accessible ceiling, shall be 1 inch diameter minimum, shall turn 90-degrees at a minimum 12" above ceiling, and shall be reamed and have insulated bushings installed to avoid cable damage.

2.2 GROUNDING

- A. Comply with requirements per drawing notes and details, and in Division 26 Section "Grounding and Bonding for Electrical Systems" for grounding conductors and connectors.
- B. Bonding connectors shall be 2-hole irreversible compression type, as manufactured by Panduit or Burndy.
- C. Comply with ANSI-J-STD-607-A.

PART 3 - EXECUTION

3.1 CABLE INSTALLATION REQUIREMENTS

- A. Install voice, data and television cable as supplied by the Owner.
- B. Furnish all required installation tools to facilitate cable pulling without damage to cable jacket.
- C. During pulling operation adequate number of workers shall be present to allow cable observation at all points of raceway entry and exit, as well as to feed cable and operate pulling machinery.

- D. Pull cables in accordance with cable manufacturer's recommendations and ANSI/IEEE C2 Standards. Recommended pulling tensions and pulling bending radius shall not be exceeded. Any cables bent or kinked to radius less than recommended dimension are not allowed and shall be replaced at no expense to Owner.
 - 1. Category 6A cables shall be installed with minimum bend radius of six times the outside cable diameter.
- E. Pull all cable by hand unless installation conditions require mechanical assistance. Where mechanical assistance is used, care shall be taken to insure that maximum tensile load for cable as defined by these specifications is not exceeded. This may be in the form of continuous monitoring of pulling tension, use of "break-away" or other approved method.
- F. Install cable in conduit cable trays or J-hooks in accessible ceiling areas. Anchor all cable supports independently to building structure. All routing shall be kept clear of other trades' work. D-rings and bridal rings are not acceptable.
- G. J-hook cable supports shall be installed in accordance with manufacturers' installation requirements. Spacing of J-hook cable supports shall be maximum every 5 ft. or in accordance with cable manufacturers' specifications, whichever distance is shorter.
- H. Size all cable pathways to allow for minimum 40% spare cable fill capacity.
 - Maximum number of Category 6A cables allowed to be installed in conduit according to conduit trade sizes shall be as follows:

a. 1" Conduit: 3 cables

b. 1-1/4" Conduit: 4 cables

c. 1-1/2" Conduit: 6 cables

d. 2" Conduit: 12 cables

e. 3" Conduit: 20 cables

- I. Cable bundles in j-hooks shall not exceed a maximum of 50 cables.
- J. Eliminate cable stress caused by tension in suspended cable runs. Cables must exhibit some sag in hanging between supports.
- K. Cable routing in telecom closet shall be routed and supported on Owner-furnished Owner-installed ladder runway. Coordinate installation and lengths required with the Owner as required for the Owner to land cables on the equipment furnished and installed by them. Provide minimum 10-feet of slack past termination location in every cable in Telecom Room, based on coordination with Owner, per requirements in the UMC Division of IT Telecommunications Construction Standards and Specifications.
- L. Provide minimum 12-inches of cable slack in outlet back-boxes, and 3-feet of cable slack in service loop above each outlet conduit stub-up.
- M. Contractor shall be responsible for identifying and reporting to Construction Manager any existing damage to walls, flooring, tiles and furnishings in work area prior to start of work. Repair damage to interior spaces caused by installation of cable, raceway or other hardware. Repairs must match pre-existing color and finish of walls, floors and ceilings. Replace any contractor-damaged ceiling tiles to match color, size, style and texture.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- N. Avoid abrasion and other damage to cables during installation.
- O. Pulling lubricant may be used to ease pulling tensions. Lubricant shall be of type that is non-injurious to cable jacket and other materials used. Lubricant shall not harden or become adhesive with age.
- P. Provide pull cord (200 lb. minimum) installed with cable installed in each conduit 11/4" and larger.
- Q. Provide to Engineer, prior to installation, submittals drawings showing proposed installation for approval.
- R. Install cables with no splices unless otherwise specified. Damaged or broken cables must be completely replaced at no additional cost to Owner.
- S. Cabling shall be neatly laced, dressed, and supported. Plenum-rated cable ties shall be utilized in plenum spaces. Velcro-type cable ties shall be utilized in Telecom Rooms, on maximum spacing of 36" between ties. Cable ties shall be hand-applied, never applied with a tool, and shall remain loose around cable bundles such that the ties can be rotated by hand after installation.
- T. Grounding and Bonding:
 - 1. Contractor to coordinate system grounding and bonding requirements where provided.
 - 2. Comply with Division 26 Section "Grounding and Bonding for Electrical Systems."
 - 3. Install bonding connectors on conductors via manufacturer-approved irreversible compression tool.
- U. Voice and data system cables shall be placed within cable trays where shown on floor plans, and in J-hooks where cables are not in cable trays and are above accessible ceilings. Support J-hooks on maximum 60-inch spans, from wall or structure above accessible ceilings. Furnish and install all-thread, Unistrut or other support structure as required to support J-hooks and cables.
- V. Maintain 8" minimum clearance from bottom of J-hooks to ceilings.
- W. Maintain following minimum clearances from J-hooks and all cable pathways, to avoid electromagnetic interference, from the following:
 - 1. Motors and transformers: 4-feet
 - 2. Conduit and cables used for electrical power distribution: 1-foot
 - 3. Fluorescent lighting: 5-inches
- X. Cable pathways shall be installed in such a way as to facilitate ongoing maintenance, additions, and relocations.
- Y. All pathway devices and support hardware shall have smooth edges, with no sharp edges coming in contact with cables.
- Z. Pathways and cabling shall be installed such that no Communications cable length exceeds 295-feet total from Telecom Room termination location to outlet termination location.
- AA. Cable routing, support, and sealing of penetrations shall meet applicable MU codes.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.2 TESTING

- A. Owner shall be responsible for cable testing and qualified personnel to conduct acceptance tests
- B. If Owners' tests fail to meet industry specifications, the Contractor shall replace and make changes as are necessary and then Owner will repeat tests, which disclose fault or defective material, equipment or installation method. Provide labor and materials at no additional cost to Owner.

END OF SECTION 271500

COMMUNICATIONS HORIZONTAL CABLING 271500 - 7

Project No.: CP242241 February 27, 2024



SECTION 280500 - COMMON WORK RESULTS FOR ELECTRONIC SAFETY AND SECURITY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Electronic safety and security equipment coordination and installation.
- 2. Sleeves for raceways and cables.
- 3. Grout.
- 4. Coordination drawings.
- 5. Project record drawings.
- 6. Electronic safety and security demolition.
- 7. Common electronic safety and security installation requirements.

1.3 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.
- B. NBR: Acrylonitrile-butadiene rubber.

1.4 SUBMITTALS

A. Product Data: For sleeve seals.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Delivery raceways in clean condition. Store to prevent entrance of dirt, debris and moisture.
- B. Protect stored raceways, cables, and connectors from moisture and dirt. Elevate above grade. Do not exceed structural capacity of floor, if stored inside.

1.6 COORDINATION

- A. Coordinate arrangement, mounting, and support of electronic safety and security equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
- 3. To allow right of way for piping and conduit installed at required slope.
- 4. So connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- C. Coordinate location of access panels and doors for electronic safety and security items that are behind finished surfaces or otherwise concealed.
- D. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."

1.7 SCHEDULING AND PHASING

A. All electronic safety and security work shall be scheduled to meet project completion date. All work shall be phased for projects requiring phasing of work. Install additional conduit, junction-boxes, pull-boxes, devices as required to support phasing. Refer to phasing schedule on drawings.

PART 2 - PRODUCTS

2.1 SLEEVES FOR RACEWAYS AND CABLES

- A. Steel Pipe Sleeves: ASTM A 53, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- C. Sleeves for Rectangular Openings: Galvanized sheet steel.
 - 1. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches and no side more than 16 inches, thickness shall be 0.052 inch.
 - b. For sleeve cross-section rectangle perimeter equal to, or more than, 50 inches and 1 or more sides equal to, or more than, 16 inches, thickness shall be 0.138 inch.

2.2 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

2.3 COORDINATION DRAWINGS

- A. The contractor shall prepare CAD generated drawings (min. 1/4" scale) showing following systems/items as a minimum:
 - 1. Main equipment locations and clearances required.
 - 2. Locations of items in ceiling such as cameras, smoke detectors, heat detectors, etc.
- B. The contractor shall submit the CAD generated drawings to the contractor for coordination with other trades. The drawings shall be submitted either in electronic format or printed copies as requested by the contractor.
- C. The contractor shall participate in coordination meetings when requested by the contractor.

2.4 PROJECT RECORD DRAWINGS

- A. Drawings shall be furnished in electronic-media (CD-Rewritable type) and at-least one hard copy prints.
 - 1. Format: Same CAD program, version and operating system as the original contract documents.
 - 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw and add details and notations where applicable.
- B. Identify and date each drawing and include the designation "PROJECT RECORD DRAWING" or "AS-BUILT DRAWING" in a prominent location, with contractor's name below it.

PART 3 - EXECUTION

3.1 COMMON REQUIREMENTS FOR ELECTRONIC SAFETY AND SECURITY INSTALLATION

- A. Comply with NECA 1.
- B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- D. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electronic safety and security equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- E. Right of Way: Give to piping systems installed at a required slope.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

Project No.: CP242241

February 27, 2024

3.2 SLEEVE INSTALLATION FOR ELECTRONIC SAFETY AND SECURITY PENETRATIONS

- A. Electronic safety and security penetrations occur when raceways, pathways, cables, wireways, or cable trays penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- E. Cut sleeves to length for mounting flush with both surfaces of walls.
- F. Extend sleeves installed in floors 2 inches above finished floor level.
- G. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and raceway or cable, unless indicated otherwise.
- H. Seal space outside of sleeves with grout for penetrations of concrete and masonry
 - 1. Promptly pack grout solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect grout while curing.
- I. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants."
- J. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials. Comply with requirements in Division 07 Section "Penetration Firestopping."

3.3 FIRESTOPPING

A. Apply firestopping to penetrations of fire-rated floor and wall assemblies for electronic safety and security installations to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Penetration Firestopping."

END OF SECTION 280500

SECTION 280513 - CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. UTP cabling.
 - 2. 50/125-micrometer, multimode optical fiber cabling.
 - Coaxial cabling.
 - 4. RS-232 cabling.
 - 5. RS-485 cabling.
 - 6. Low-voltage control cabling.
 - 7. Control-circuit conductors.
 - 8. Fire alarm wire and cable.
 - 9. Identification products.
- B. All fire alarm system wiring shall be installed in a dedicated raceway. Raceway may be EMT, RMC, FMC and LFMC (flexible type limited by NEC).

1.3 DEFINITIONS

- A. Basket Cable Tray: A fabricated structure consisting of wire mesh bottom and side rails.
- B. BICSI: Building Industry Consulting Service International.
- C. Channel Cable Tray: A fabricated structure consisting of a one-piece, ventilated-bottom or solid-bottom channel section.
- D. EMI: Electromagnetic interference.
- E. IDC: Insulation displacement connector.
- F. Ladder Cable Tray: A fabricated structure consisting of two longitudinal side rails connected by individual transverse members (rungs).
- G. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control and signaling power-limited circuits.
- H. Open Cabling: Passing telecommunications cabling through open space (e.g., between the studs of a wall cavity).

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- I. RCDD: Registered Communications Distribution Designer.
- J. Solid-Bottom or Nonventilated Cable Tray: A fabricated structure consisting of integral or separate longitudinal side rails, and a bottom without ventilation openings.
- K. Trough or Ventilated Cable Tray: A fabricated structure consisting of integral or separate longitudinal rails and a bottom having openings sufficient for the passage of air and using 75 percent or less of the plan area of the surface to support cables.
- L. UTP: Unshielded twisted pair.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
 - 1. For fire alarm wiring and cable, include the following installation data for each type used:
 - a. Nominal OD.
 - b. Minimum bending radius.
 - c. Maximum pulling tension.
- B. Shop Drawings: Cable tray layout, showing cable tray route to scale, with relationship between the tray and adjacent structural, electrical, and mechanical elements. Include the following:
 - 1. Vertical and horizontal offsets and transitions.
 - 2. Clearances for access above and to side of cable trays.
 - 3. Vertical elevation of cable trays above the floor or bottom of ceiling structure.
 - 4. Load calculations to show dead and live loads as not exceeding manufacturer's rating for tray and its support elements.
- C. Qualification Data: For qualified layout technician, installation supervisor, and field inspector.
- D. Field quality-control reports.
- E. Maintenance Data: For wire and cable to include in maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E 84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 25 or less.
 - 2. Smoke-Developed Index: 50 or less.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

1.6 DELIVERY, STORAGE, AND HANDLING

A. Test cables upon receipt at Project site.

1.7 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install UTP, optical fiber, and coaxial cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 PATHWAYS

- A. All fire alarm system wiring shall be installed in a dedicated raceway. Raceway may be EMT, RMC, FMC, LFMC (flexible type limited by NEC), and surface raceway (only in areas where not subject to damage).
- B. Support of Open Cabling: NRTL labeled for support of Category 5e/Category 6 cabling, designed to prevent degradation of cable performance and pinch points that could damage cable.
 - 1. Support brackets with cable tie slots for fastening cable ties to brackets.
 - 2. Lacing bars, spools, J-hooks, and D-rings.
 - 3. Straps and other devices.

C. Cable Trays:

- 1. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Cable Management Solutions, Inc.
 - b. Cablofil Inc.
 - c. Chalfant Manufacturing Co.
 - d. Cooper B-Line, Inc.
 - e. Cope Tyco/Allied Tube & Conduit.
 - f. GS Metals Corp.
 - g. MONO-SYSTEMS, Inc.
 - h. MP Husky.
 - i. FW Industries.
- 2. Cable Tray Materials: Metal, suitable for indoors, and protected against corrosion by electroplated zinc galvanizing, complying with ASTM B 633, Type 1, not less than 0.000472 inch.
 - a. Basket Cable Trays: 6 inches wide and 2 inches. Wire mesh spacing shall not exceed 2 by 4 inches.
 - b. Trough Cable Trays: Nominally 6 inches wide.

- c. Ladder Cable Trays: Nominally 18 inches wide, and a rung spacing of 12 inches.
- d. Channel Cable Trays: One-piece construction, nominally 4 inches wide. Slot spacing shall not exceed 4-1/2 inches o.c.
- e. Solid-Bottom Cable Trays: One-piece construction, nominally 12 inches wide. Provide without solid covers.
- D. Conduit and Boxes: Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems." Flexible metal conduit shall not be used.
 - 1. Outlet boxes shall be no smaller than 2 inches wide, 3 inches high, and 2-1/2 inches deep.

2.2 BACKBOARDS

A. Backboards: Plywood, fire-retardant treated, 3/4 by 48 by 96 inches. Comply with requirements for plywood backing panels in Division 06 Section "Rough Carpentry".

2.3 UTP CABLE

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Belden CDT Inc.; Electronics Division.
 - 2. Berk-Tek; a Nexans company.
 - 3. Genesis Cable Products; Honeywell International, Inc.
 - KRONE Incorporated.
 - 5. Mohawk; a division of Belden CDT.
 - 6. Nordex/CDT; a subsidiary of Cable Design Technologies.
 - 7. Superior Essex Inc.
 - 8. 3M.
 - 9. Tyco Electronics/AMP Netconnect; Tyco International Ltd.
- B. Description: 100-ohm, 4-pair UTP, formed into 25-pair binder groups covered with a blue thermoplastic jacket.
 - 1. Comply with ICEA S-90-661 for mechanical properties.
 - 2. Comply with TIA/EIA-568-B.1 for performance specifications.
 - 3. Comply with TIA/EIA-568-B.2, Category 5e or Category 6.
 - 4. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
 - a. Communications, General Purpose: Type CM or CMG.
 - b. Communications, Plenum Rated: Type CMP, complying with NFPA 262.
 - c. Communications, Riser Rated: Type CMR, complying with UL 1666.
 - d. Communications, Limited Purpose: Type CMX.
 - e. Multipurpose: Type MP or MPG.
 - f. Multipurpose, Plenum Rated: Type MPP, complying with NFPA 262.
 - g. Multipurpose, Riser Rated: Type MPR, complying with UL 1666.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

2.4 UTP CABLE HARDWARE

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. American Technology Systems Industries, Inc.
 - 2. Hubbell Premise Wiring.
 - 3. KRONE Incorporated.
 - 4. Leviton Voice & Data Division.
 - 5. Nordex/CDT; a subsidiary of Cable Design Technologies.
 - 6. Panduit Corp.
 - 7. Siemon Co. (The).
 - 8. Tyco Electronics/AMP Netconnect; Tyco International Ltd.
- B. UTP Cable Connecting Hardware: IDC type, using modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of the same category or higher.
- C. Connecting Blocks: 110-style for Category 5e/110-style for Category 6. Provide blocks for the number of cables terminated on the block, plus 25 percent spare. Integral with connector bodies, including plugs and jacks where indicated.

2.5 OPTICAL FIBER CABLE

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Berk-Tek; a Nexans company.
 - 2. Corning Cable Systems.
 - 3. General Cable Technologies Corporation.
 - Mohawk: a division of Belden CDT.
 - 5. Nordex/CDT; a subsidiary of Cable Design Technologies.
 - 6. Optical Connectivity Solutions Division; Emerson Network Power.
 - 7. Superior Essex Inc.
 - 8. 3M
 - 9. Tyco Electronics/AMP Netconnect; Tyco International Ltd.
- B. Description: Multimode, 50/125-micrometer, 24-fiber, nonconductive, tight buffer, optical fiber cable.
 - 1. Comply with ICEA S-83-596 for mechanical properties.
 - 2. Comply with TIA/EIA-568-B.3 for performance specifications.
 - 3. Comply with TIA/EIA-492AAAA-B for detailed specifications.
 - 4. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444, UL 1651, and NFPA 70 for the following types:
 - a. General Purpose, Nonconductive: Type OFN or OFNG.
 - b. Plenum Rated, Nonconductive: Type OFNP, complying with NFPA 262.
 - c. Riser Rated, Nonconductive: Type OFNR, complying with UL 1666.
 - d. General Purpose, Conductive: Type OFC or OFCG.
 - e. Plenum Rated, Conductive: Type OFCP, complying with NFPA 262.
 - f. Riser Rated, Conductive: Type OFCR, complying with UL 1666.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 5. Conductive cable shall be steel armored type.
- 6. Maximum Attenuation: 3.50 dB/km at 850 nm; 1.5 dB/km at 1300 nm.
- 7. Minimum Modal Bandwidth: 160 MHz-km at 850 nm; 500 MHz-km at 1300 nm.

C. Jacket:

- 1. Jacket Color: Agua for 50/125-micrometer cable.
- 2. Cable cordage jacket, fiber, unit, and group color shall be according to TIA/EIA-598-B.
- 3. Imprinted with fiber count, fiber type, and aggregate length at regular intervals not to exceed 40 inches.

2.6 OPTICAL FIBER CABLE HARDWARE

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. ADC.
 - 2. American Technology Systems Industries, Inc.
 - 3. Berk-Tek; a Nexans company.
 - 4. Corning Cable Systems.
 - 5. Hubbell Premise Wiring.
 - 6. Nordex/CDT; a subsidiary of Cable Design Technologies.
 - 7. Optical Connectivity Solutions Division; Emerson Network Power.
 - 8. Siemon Co. (The).
- B. Cable Connecting Hardware: Meet the Optical Fiber Connector Intermateability Standards (FOCIS) specifications of TIA/EIA-604-2, TIA/EIA-604-3-A, and TIA/EIA-604-12. Comply with TIA/EIA-568-B.3.
 - Quick-connect, simplex and duplex, Type SC/Type ST connectors. Insertion loss not more than 0.75 dB.
 - 2. Type SFF connectors may be used in termination racks, panels, and equipment packages.

2.7 RS-232 CABLE

- A. Standard Cable: NFPA 70, Type CM.
 - 1. Paired, 2 pairs, No. 22 AWG, stranded (7x30) tinned copper conductors.
 - 2. Polypropylene insulation.
 - 3. Individual aluminum foil-polyester tape shielded pairs with 100 percent shield coverage.
 - 4. PVC jacket.
 - 5. Pairs are cabled on common axis with No. 24 AWG, stranded (7x32) tinned copper drain wire.
 - 6. Flame Resistance: Comply with UL 1581.
- B. Plenum-Rated Cable: NFPA 70, Type CMP.
 - 1. Paired, 2 pairs, No. 22 AWG, stranded (7x30) tinned copper conductors.
 - 2. Plastic insulation.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 3. Individual aluminum foil-polyester tape shielded pairs with 100 percent shield coverage.
- 4. Plastic jacket.
- 5. Pairs are cabled on common axis with No. 24 AWG, stranded (7x32) tinned copper drain wire.
- 6. Flame Resistance: Comply with NFPA 262.

2.8 RS-485 CABLE

- A. Standard Cable: NFPA 70, Type CM or CMG.
 - 1. Paired, 2 pairs, twisted, No. 22 AWG, stranded (7x30) tinned copper conductors.
 - 2. PVC insulation.
 - Unshielded.
 - 4. PVC jacket.
 - 5. Flame Resistance: Comply with UL 1581.
- B. Plenum-Rated Cable: NFPA 70, Type CMP.
 - 1. Paired, 2 pairs, No. 22 AWG, stranded (7x30) tinned copper conductors.
 - 2. Fluorinated ethylene propylene insulation.
 - 3. Unshielded.
 - 4. Fluorinated ethylene propylene jacket.
 - 5. Flame Resistance: NFPA 262, Flame Test.

2.9 LOW-VOLTAGE CONTROL CABLE

- A. Paired Lock Cable: NFPA 70, Type CMG.
 - 1. 1 pair, twisted, No. 16 AWG, stranded (19x29) tinned copper conductors.
 - 2. PVC insulation.
 - Unshielded.
 - 4. PVC jacket.
 - 5. Flame Resistance: Comply with UL 1581.
- B. Plenum-Rated, Paired Lock Cable: NFPA 70, Type CMP.
 - 1. 1 pair, twisted, No. 16 AWG, stranded (19x29) tinned copper conductors.
 - 2. PVC insulation.
 - 3. Unshielded.
 - 4. PVC jacket.
 - 5. Flame Resistance: Comply with NFPA 262.
- C. Paired Lock Cable: NFPA 70, Type CMG.
 - 1. 1 pair, twisted, No. 18 AWG, stranded (19x30) tinned copper conductors.
 - 2. PVC insulation.
 - 3. Unshielded.
 - 4. PVC jacket.
 - 5. Flame Resistance: Comply with UL 1581.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- D. Plenum-Rated, Paired Lock Cable: NFPA 70, Type CMP.
 - 1. 1 pair, twisted, No. 18 AWG, stranded (19x30) tinned copper conductors.
 - 2. Fluorinated ethylene propylene insulation.
 - 3. Unshielded.
 - 4. Plastic jacket.
 - 5. Flame Resistance: NFPA 262, Flame Test.

2.10 CONTROL-CIRCUIT CONDUCTORS

- A. Class 1 Control Circuits: Stranded copper, Type THHN-THWN, in raceway complying with UL 83
- B. Class 2 Control Circuits: Stranded copper, Type THHN-THWN, in raceway complying with UL 83.
- C. Class 3 Remote-Control and Signal Circuits: Stranded copper, Type TW or TF, complying with UL 83.

2.11 FIRE ALARM WIRE AND CABLE

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Comtran Corp.
 - 2. Genesis Cable Products; Honeywell International, Inc.
 - 3. Rockbestos-Suprenant Cable Corporation.
 - 4. West Penn Wire/CDT; a division of Cable Design Technologies.
- B. General Wire and Cable Requirements: NRTL listed and labeled as complying with NFPA 70, Article 760.
- C. Wiring shall be U.L. listed as fire alarm protection signaling circuit cable per NEC. Wire for notification circuits shall be a minimum #14 AWG, type KF-2 or KFF-2. Cable type may vary if recommended by the system manufacturer for compatibility with system warranty or design.

2.12 IDENTIFICATION PRODUCTS

- A. Acceptable Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Brady Corporation
 - 2. HellermannTyton.
 - 3. Kroy LLC.
 - 4. Panduit Corp.
- B. Comply with UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

C. Comply with requirements in Division 26 Section "Identification for Electrical Systems."

2.13 SOURCE QUALITY CONTROL

- A. Factory test UTP and optical fiber cables on reels according to TIA/EIA-568-B.1.
- B. Factory test UTP cables according to TIA/EIA-568-B.2.
- C. Factory test multimode optical fiber cables according to TIA/EIA-526-14-A and TIA/EIA-568-B.3.
- D. Factory sweep test coaxial cables at frequencies from 5 MHz to 1 GHz. Sweep test shall test the frequency response, or attenuation over frequency, of a cable by generating a voltage whose frequency is varied through the specified frequency range and graphing the results.
- E. Cable will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 INSTALLATION OF PATHWAYS

- A. Cable Trays: Comply with NEMA VE 2 and TIA/EIA-569-A-7.
- B. Comply with TIA/EIA-569-A for pull-box sizing and length of conduit and number of bends between pull points.
- C. Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems." for installation of conduits and wireways.
- D. Install manufactured conduit sweeps and long-radius elbows whenever possible.
- E. Pathway Installation in Equipment Rooms:
 - 1. Position conduit ends adjacent to a corner on backboard where a single piece of plywood is installed or in the corner of room where multiple sheets of plywood are installed around perimeter walls of room.
 - 2. Install cable trays to route cables if conduits cannot be located in these positions.
 - 3. Secure conduits to backboard when entering room from overhead.
 - 4. Extend conduits 3 inches above finished floor.
 - 5. Install metal conduits with grounding bushings and connect with grounding conductor to grounding system.
- F. Backboards: Install backboards with 96-inch dimension vertical. Butt adjacent sheets tightly, and form smooth gap-free corners and joints.

3.2 INSTALLATION OF CONDUCTORS AND CABLES

- A. Comply with NECA 1.
- B. General Requirements for Cabling:
 - 1. Comply with TIA/EIA-568-B.1.
 - 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
 - 3. Install 110-style IDC termination hardware unless otherwise indicated.
 - 4. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, and cross-connect and patch panels.
 - 5. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
 - 6. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM, "Cabling Termination Practices" Chapter. Install lacing bars and distribution spools.
 - 7. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
 - 8. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
 - Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.

C. UTP Cable Installation:

- 1. Comply with TIA/EIA-568-B.2.
- 2. Do not untwist UTP cables more than 1/2 inch from the point of termination to maintain cable geometry.
- D. Optical Fiber Cable Installation:
 - 1. Comply with TIA/EIA-568-B.3.
 - 2. Cable shall be terminated on connecting hardware that is rack or cabinet mounted.
- E. Open-Cable Installation:
 - 1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
 - 2. Suspend copper cable not in a wireway or pathway a minimum of 8 inches above ceilings by cable supports not more than 60 inches apart.
 - 3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.
- F. Installation of Cable Routed Exposed under Raised Floors:
 - 1. Install plenum-rated cable only.
 - 2. Install cabling after the flooring system has been installed in raised floor areas.
 - 3. Coil cable 72 inches long shall be neatly coiled not less than 12 inches in diameter below each feed point.

G. Outdoor Coaxial Cable Installation:

- 1. Install outdoor connections in enclosures complying with NEMA 250, Type 4X. Install corrosion-resistant connectors with properly designed O-rings to keep out moisture.
- 2. Attach antenna lead-in cable to support structure at intervals not exceeding 36 inches.

H. Separation from EMI Sources:

- 1. Comply with BICSI TDMM and TIA/EIA-569-A recommendations for separating unshielded copper voice and data communication cable from potential EMI sources, including electrical power lines and equipment.
- 2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.
- 3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
- 4. Separation between communications cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
- 5. Separation between Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.
- 6. Separation between Cables and Fluorescent Fixtures: A minimum of 5 inches.

3.3 FIRE ALARM WIRING INSTALLATION

- A. Comply with NECA 1 and NFPA 72.
- B. Wiring Method: Install wiring in metal raceway according to Division 26 Section "Raceway and Boxes for Electrical Systems."
 - 1. Fire alarm circuits and equipment control wiring associated with the fire alarm system shall be installed in a dedicated raceway system. This system shall not be used for any other wire or cable.

C. Wiring Method:

- 1. Cables and raceways used for fire alarm circuits, and equipment control wiring associated with the fire alarm system, may not contain any other wire or cable.
- D. Wiring within Enclosures: Separate power-limited and non-power-limited conductors as recommended by manufacturer. Install conductors parallel with or at right angles to sides and back of the enclosure. Bundle, lace, and train conductors to terminal points with no excess. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with the fire alarm system to terminal blocks. Mark each terminal according to the system's wiring diagrams. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.
- E. Cable Taps: Use numbered terminal strips in junction, pull, and outlet boxes, cabinets, or equipment enclosures where circuit connections are made.
- F. Color-Coding: Color-code fire alarm conductors differently from the normal building power wiring. Use one color-code for alarm circuit wiring and another for supervisory circuits. Color-code audible alarm-indicating circuits differently from alarm-initiating circuits. Use different colors for visible alarm-indicating devices. Paint fire alarm system junction boxes and covers red.
- G. Risers: Install at least two vertical cable risers to serve the fire alarm system. Separate risers in close proximity to each other with a minimum one-hour-rated wall, so the loss of one riser does not prevent the receipt or transmission of signals from other floors or zones.
- H. Wiring to Remote Alarm Transmitting Device: 1-inch conduit between the fire alarm control panel and the transmitter. Install number of conductors and electrical supervision for connecting wiring as needed to suit monitoring function.

3.4 CONTROL-CIRCUIT CONDUCTORS

- A. Minimum Conductor Sizes:
 - 1. Class 1 remote-control and signal circuits, No. 14 AWG.
 - 2. Class 2 low-energy, remote-control and signal circuits, No. 16 AWG.
 - 3. Class 3 low-energy, remote-control, alarm and signal circuits, No. 12 AWG.

3.5 FIRESTOPPING

- A. Comply with requirements in Division 07 Section "Penetration Firestopping."
- B. Comply with TIA/EIA-569-A, "Firestopping" Annex A.
- C. Comply with BICSI TDMM, "Firestopping Systems" Article.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

3.6 GROUNDING

- A. For communications wiring, comply with ANSI-J-STD-607-A and with BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. For low-voltage wiring and cabling, comply with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems."

3.7 IDENTIFICATION

A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."

3.8 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
 - 1. Visually inspect UTP and optical fiber cable jacket materials for UL or third-party certification markings. Inspect cabling terminations to confirm color-coding for pin assignments, and inspect cabling connections to confirm compliance with TIA/EIA-568-B.1.
 - 2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
 - 3. Test UTP cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross connection.
 - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-B.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.

4. Optical Fiber Cable Tests:

- a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-B.1. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
- b. Link End-to-End Attenuation Tests:
 - 1) Multimode Link Measurements: Test at 850 or 1300 nm in 1 direction according to TIA/EIA-526-14-A, Method B, One Reference Jumper.
 - 2) Attenuation test results for links shall be less than 2.0 dB. Attenuation test results shall be less than that calculated according to equation in TIA/EIA-568-B.1.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- C. Document data for each measurement. Print data for submittals in a summary report that is formatted using Table 10.1 in BICSI TDMM as a guide, or transfer the data from the instrument to the computer, save as text files, print, and submit.
- D. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

END OF SECTION 280513

Project No.: CP242241 February 27, 2024

SECTION 283111 - DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Fire-alarm control unit.
- Manual fire-alarm boxes.
- 3. System smoke detectors.
- 4. Heat detectors.
- 5. Notification appliances.
- 6. Magnetic door holders.
- 7. Remote annunciator.
- 8. Addressable interface device.
- 9. Digital alarm communicator transmitter.
- 10. System printer.
- B. All devices, equipment and installation are to be provided by a single source who assumes responsibility for the entire system per NFPA 72. Non-addressable devices do not have to be of the same brand as the main system, but must meet the manufacturer's requirements and UL ratings for the system installed.

1.3 DEFINITIONS

- A. LED: Light-emitting diode.
- B. NICET: National Institute for Certification in Engineering Technologies.

1.4 SYSTEM DESCRIPTION

A. Noncoded, UL-certified addressable system, with multiplexed signal transmission, dedicated to fire-alarm service only.

1.5 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Fire-alarm control unit and raceways shall withstand the effects of earthquake motions determined according to SEI/ASCE 7.
 - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event".

1.6 SUBMITTALS

- A. General Submittal Requirements:
 - Submittals shall be approved by authorities having jurisdiction prior to submitting them to Architect
 - 2. Shop Drawings shall be prepared by persons with the following qualifications:
 - a. Trained and certified by manufacturer in fire-alarm system design.
 - b. NICET-certified fire-alarm technician, Level III minimum.
 - c. Licensed or certified by authorities having jurisdiction.
- B. Product Data: For each type of product indicated.
- C. Shop Drawings: For fire-alarm system. Include plans, elevations, sections, details, and attachments to other work.
 - 1. Comply with recommendations in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72.
 - 2. Current draw on each notification circuit with allowance for 20% expansion.
 - 3. Include voltage drop calculations for all notification appliance circuits.
 - 4. Include battery-size calculations for entire system including any power expanders.
 - 5. Include performance parameters and installation details for each detector, verifying that each detector is listed for complete range of air velocity, temperature, and humidity possible when air-handling system is operating.
 - 6. Include plans, sections, and elevations of heating, ventilating, and air-conditioning ducts, drawn to scale and coordinating installation of duct smoke detectors and access to them. Show critical dimensions that relate to placement and support of sampling tubes, detector housing, and remote status and alarm indicators. Locate detectors according to manufacturer's written recommendations.
 - 7. Include floor plans to indicate all final outlet locations showing address of each addressable device. Show size and route of cable and conduits.
 - 8. Include a matrix showing alarm and initiation devices with associated actions.
 - 9. Power Calculations:
 - a. Battery Capacity Calculations: Battery size shall be a minimum of 125% of the calculated requirement. Batteries must be capable of operating the panel in normal mode for 24 hours with sufficient capacity to operate the panel in alarm mode for 15 minutes at the end of that 24 hour period.
 - b. Supervisory power requirements for all equipment.

- c. Alarm power requirements for all equipment.
- d. Power supply rating justification showing power requirements for each of the system power supplies. Power supplies shall be sized to furnish the total connected load in a worst-case condition.
- 10. Complete manufacturer's catalog data on all devices, modules, bases, etc.
- 11. Submit panel and annunicator panel configuration showing layout including the following as applicable:
 - a. Circuit interface panels including all modules.
 - b. Power supplies, batteries and battery chargers.
 - c. Pre-amplifiers, and tone generators.
 - d. Equipment enclosures.
 - e. Alarm monitoring modules, and supervised control modules.
 - f. Initiation loop must be capable of supporting at least 60 devices of any type. If the loop supports different numbers of different type devices, it must be capable of supporting at least 60 devices of each type.
 - g. Alarm notification circuits must be capable of 1.5 amps per circuit at 24vdc. Panels capable of allowing varying current draws per circuit, but allowing an average of 1.5 amps average may be allowed if the engineer designs the circuits appropriately. In that case each circuit must still have .3 amp minimum allowed for future in addition to the designed load.
- 12. The latest version of software for programming the fire alarm system. A programming manual shall accompany the submitted program and shall be adequate to allow understanding, operation and editing by the system.
- D. Qualification Data: For qualified Installer.
- E. Proposed vendors must be able to show the ability to respond to requests for service within 24 hours and the ability to supply replacement parts for the system within 48 hours relative to the site where the system is to be installed.
- F. Seismic Qualification Certificates: For fire-alarm control unit, accessories, and components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- G. Field quality-control reports.
- H. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 - 1. Comply with the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
 - 2. Provide "Record of Completion Documents" according to NFPA 72 article "Permanent Records" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter.

- 3. Record copy of site-specific software.
- 4. Provide "Maintenance, Inspection and Testing Records" according to NFPA 72 article of the same name and include the following:
 - a. Frequency of testing of installed components.
 - b. Frequency of inspection of installed components.
 - c. Requirements and recommendations related to results of maintenance.
 - d. Manufacturer's user training manuals.
- 5. Manufacturer's required maintenance related to system warranty requirements.
- 6. Abbreviated operating instructions for mounting at fire-alarm control unit.
- 7. Copy of NFPA 72.
- I. Software and Firmware Operational Documentation:
 - 1. Software operating and upgrade manuals.
 - 2. Program Software Backup: On magnetic media or compact disk, complete with data files.
 - 3. Device address list.
 - 4. Printout of software application and graphic screens.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: Personnel shall be trained and certified by manufacturer for installation of units required for this Project.
- B. Installer Qualifications: Installation shall be by personnel certified by NICET as fire-alarm Level III technician.
- C. Source Limitations for Fire-Alarm System and Components: Obtain fire-alarm system from single source from single manufacturer. Components shall be compatible with, and operate as, an extension of existing system.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- E. NFPA Certification: Obtain certification according to NFPA 72 by a UL-listed alarm company.

1.8 PROJECT CONDITIONS

- A. Interruption of Existing Fire-Alarm Service: Do not interrupt fire-alarm service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary guard service according to requirements indicated:
 - 1. Notify Architect no fewer than seven (7) days in advance of proposed interruption of firealarm service.
 - 2. Do not proceed with interruption of fire-alarm service without Architect's written permission.

1.9 SOFTWARE SERVICE AGREEMENT

- A. Comply with UL 864.
- B. Technical Support: Beginning with final acceptance by Owner, provide software support for two years.
- C. Upgrade Service: Update software to latest version at Project completion. Install and program software upgrades that become available within two years from date of final acceptance by Owner. Upgrading software shall include operating system. Upgrade shall include new or revised licenses for use of software.
 - 1. Provide 30 days' notice to Owner to allow scheduling and access to system and to allow Owner to upgrade computer equipment if necessary.

1.10 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Lamps for Remote Indicating Lamp Units: Quantity equal to 10 percent of amount installed, but no fewer than 1 unit.
 - Lamps for Strobe Units: Quantity equal to 10 percent of amount installed, but no fewer than 1 unit.
 - 3. Smoke Detectors, Fire Detectors: Quantity equal to 10 percent of amount of each type installed, but no fewer than 1 unit of each type.
 - 4. Detector Bases: Quantity equal to 2 percent of amount of each type installed, but no fewer than 1 unit of each type.
 - 5. Keys and Tools: One extra set for access to locked and tamperproofed components.
 - 6. Audible and Visual Notification Appliances: One of each type installed.
 - 7. Fuses: Two of each type installed in the system.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products which coordinate with existing system.

2.2 SYSTEMS OPERATIONAL DESCRIPTION

- A. Fire-alarm signal initiation shall be by one or more of the following devices:
 - 1. Manual stations.
 - 2. Heat detectors.
 - 3. Flame detectors.
 - 4. Smoke detectors.
 - 5. Verified automatic alarm operation of smoke detectors.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 6. Automatic sprinkler system water flow.
- 7. Heat detectors in elevator shaft and pit.
- 8. Fire-extinguishing system operation.
- 9. Fire standpipe system.
- B. Fire-alarm signal shall initiate the following actions:
 - 1. Continuously operate alarm notification appliances.
 - 2. Identify alarm at fire-alarm control unit and remote annunciators where indicated.
 - 3. Transmit an alarm signal to the remote alarm receiving station.
 - 4. Unlock electric door locks in designated egress paths.
 - 5. Release fire and smoke doors held open by magnetic door holders.
 - 6. Switch heating, ventilating, and air-conditioning equipment controls to fire-alarm mode.
 - 7. Close smoke dampers in air ducts of designated air-conditioning duct systems.
 - 8. Recall elevators to primary or alternate recall floors.
 - 9. Record events in the system memory.
 - 10. Record events by the system printer.
- C. Supervisory signal initiation shall be by one or more of the following devices and actions:
 - 1. Valve supervisory switch.
 - 2. Low-air-pressure switch of a dry-pipe sprinkler system.
 - 3. Elevator shunt-trip supervision.
 - 4. Duct smoke detectors.
 - 5. Fire pump power failure, phase reversal, and fire pump running.
- D. System trouble signal initiation shall be by one or more of the following devices and actions:
 - 1. Open circuits, shorts, and grounds in designated circuits.
 - 2. Opening, tampering with, or removing alarm-initiating and supervisory signal-initiating devices.
 - 3. Loss of primary power at fire-alarm control unit.
 - 4. Ground or a single break in fire-alarm control unit internal circuits.
 - 5. Abnormal ac voltage at fire-alarm control unit.
 - 6. Break in standby battery circuitry.
 - 7. Failure of battery charging.
 - 8. Abnormal position of any switch at fire-alarm control unit or annunciator.
- E. System Trouble and Supervisory Signal Actions: Initiate notification appliance and annunciate at fire-alarm control unit and remote annunciators. Record the event on system printer.

2.3 SYSTEM SMOKE DETECTORS

- A. General Requirements for System Smoke Detectors:
 - 1. Comply with UL 268; operating at 24-V dc, nominal.
 - 2. Detectors shall be four-wire type.
 - 3. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.
 - 4. Base Mounting: Detector and associated electronic components shall be mounted in a twist-lock module that connects to a fixed base. Provide terminals in the fixed base for connection to building wiring.

- 5. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
- 6. Integral Visual-Indicating Light: LED type indicating detector has operated and power-on status.
 - a. Provide multiple levels of detection sensitivity for each sensor.
- 7. Any initiating device installed above a suspended ceiling shall have an indicator showing below the ceiling the location of the device.

B. Photoelectric Smoke Detectors:

- 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
- 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).

2.4 NOTIFICATION APPLIANCES

- A. General Requirements for Notification Appliances: Individually addressed, connected to a signaling line circuit, equipped for mounting as indicated and with screw terminals for system connections.
- B. General Requirements for Notification Appliances: Connected to notification appliance signal circuits, zoned as indicated, equipped for mounting as indicated and with screw terminals for system connections.
 - Combination Devices: Factory-integrated audible and visible devices in a single-mounting assembly, equipped for mounting as indicated and with screw terminals for system connections.
- C. Visible Notification Appliances: Xenon strobe lights comply with UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch high letters on the lens.

2.5 ADDRESSABLE INTERFACE DEVICE

- A. Description: Microelectronic monitor module, NRTL listed for use in providing a system address for alarm-initiating devices for wired applications with normally open contacts.
- B. Integral Relay: Capable of providing a direct signal to elevator controller to initiate elevator recall.

PART 3 - EXECUTION

3.1 EQUIPMENT INSTALLATION

- A. Comply with NFPA 72 for installation of fire-alarm equipment.
- B. Smoke- or Heat-Detector Spacing:
 - 1. Comply with NFPA 72, "Smoke-Sensing Fire Detectors" Section in the "Initiating Devices" Chapter, for smoke-detector spacing.
 - 2. Comply with NFPA 72, "Heat-Sensing Fire Detectors" Section in the "Initiating Devices" Chapter, for heat-detector spacing.
 - 3. Smooth ceiling spacing shall not exceed 30 feet.
 - 4. Spacing of detectors for irregular areas, for irregular ceiling construction, and for high ceiling areas shall be determined according to Appendix A in NFPA 72.
 - 5. HVAC: Locate detectors not closer than 3 feet from air-supply diffuser or return-air opening.
 - 6. Lighting Fixtures: Locate detectors not closer than 12 inches from any part of a lighting fixture.
- C. Duct Smoke Detectors: Comply with NFPA 72 and NFPA 90A. Install sampling tubes so they extend the full width of duct.
- D. Remote Status and Alarm Indicators: Install near each smoke detector and each sprinkler water-flow switch and valve-tamper switch that is not readily visible from normal viewing position.
- E. Audible Alarm-Indicating Devices: Install not less than 6 inches below the ceiling. Install on flush-mounted back boxes with the device-operating mechanism concealed behind a grille.
- F. Visible Alarm-Indicating Devices: Install adjacent to each alarm speaker and at least 6 inches below the ceiling.
- G. Device Location-Indicating Lights: Locate in public space near the device they monitor.

3.2 CONNECTIONS

- A. Connect hardware and devices to fire-alarm system.
 - Verify that hardware and devices are NRTL listed for use with fire-alarm system in this Section before making connections.
- B. Make addressable connections with a supervised interface device to the following devices and systems. Install the interface device less than 3 feet from the device controlled. Make an addressable confirmation connection when such feedback is available at the device or system being controlled.
 - 1. Smoke dampers in air ducts of designated air-conditioning duct systems.
 - 2. Alarm-initiating connection to elevator recall system and components.

- 3. Supervisory connections at valve supervisory switches.
- 4. Supervisory connections at elevator shunt trip breaker.

3.3 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
- B. Install framed instructions in a location visible from fire-alarm control unit.

3.4 GROUNDING

A. Ground fire alarm equipment, conductors, and cable shields per NFPA and manufacturer.

3.5 FIELD QUALITY CONTROL

- A. Field tests shall be witnessed by authorities having jurisdiction.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

D. Tests and Inspections:

- 1. Visual Inspection: Conduct visual inspection prior to testing.
 - a. Inspection shall be based on completed Record Drawings and system documentation that is required by NFPA 72 in its "Completion Documents, Preparation" Table in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter.
 - b. Comply with "Visual Inspection Frequencies" Table in the "Inspection" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72; retain the "Initial/Reacceptance" column and list only the installed components.
- 2. System Testing: Comply with "Test Methods" Table in the "Testing" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
- 3. Test audible appliances for the public operating mode according to manufacturer's written instructions. Perform the test using a portable sound-level meter complying with Type 2 requirements in ANSI S1.4.
- 4. Test audible appliances for the private operating mode according to manufacturer's written instructions.
- 5. Test visible appliances for the public operating mode according to manufacturer's written instructions.

UNIVERSITY OF MISSOURI

ISSUED FOR BID

- 6. Factory-authorized service representative shall prepare the "Fire Alarm System Record of Completion" in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72 and the "Inspection and Testing Form" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
- E. Reacceptance Testing: Perform reacceptance testing to verify the proper operation of added or replaced devices and appliances.
- F. Fire-alarm system will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.
- H. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.
- I. Annual Test and Inspection: One year after date of final acceptance by Owner, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

3.6 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system.

END OF SECTION 283111

DIGITAL, ADDRESSABLE FIRE ALARM SYSTEM

283111 - 10

Project No.: CP242241 February 27, 2024